Preventa™
Machine Safety Products

Catalog
2014

Schneider Electric™

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

ven Engineering, Inc. - (800) 253-9210 - sales@[illegible] - [illegible]

Preventa™
Machine safety products

Safety functions 1

Safety automation system solutions 2

Safety relays 3

Safety interlock and limit switches 4

Light curtains 5

Cable pull switches 6

International safety standards 7

US safety standards 8

Technical information 9

Product reference index 10

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Go online to www.schneider-electric.com for information about Preventa™ products listed in this catalog, including:

1 Go to: www.schneider-electric.com and select "Products" on the "Products and Services" tab.



2 On the "Products" page, find the "Machine Safety Products" icon and select "All Machine Safety Products".



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3 **On the “Machine Safety Products” page, select the product you are interested in, for example: “Safety Relays - Preventa XPS - Safety Modules”.**



4 **Explore the product page you have selected, including the “Product Information” tabs: “Documents & Downloads” and “Support”.**



Save time and money with our Preventa™ machine safety solutions offer



Safety-related signal transmission

Acquiring information…

- Safety interlock devices used as part of safeguarding systems to control access, under specific conditions of reduced risk.
- Light curtains to detect approach to dangerous and limited areas.
- Emergency stop buttons and cable pull switches for emergency shut down.

Monitoring and processing…

- Safety relay modules with specific safety functions – to monitor input signals from safety-related devices, and to interface with contactors and drives – by switching off output safety contacts.
- Safety Controller: configurable safety device capable of centralizing a range of safety monitoring functions.
- Safety PLCs: programmable electronic systems to carry out safety or non-safety related tasks for machinery and equipment.
- "As-interface safety at work": safety field bus network certified to work with safety-related devices to provide safety functions.

Safety interlocks

Light curtains

Emergency stop

Cable pull switch

Safety relays

Safety Controller

Safety PLCs

As-interface safety at work

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com



Stopping the machine…

- Contactors to cut-off the electrical power supply to motors – with mechanically linked or mirrored auxiliary contacts – integrated for feedback loop diagnosis of safety relay modules, safety controllers, or safety PLCs.
- Variable speed drives and servo drives with integrated safety functions…control stopping of dangerous movements.

Up to 50%
better space optimization
Compact components have smaller footprint

Save up to 30%
on installation time
Reduce installation time with quick and easy wiring

Variable speed drives

Servo drives

Contactors

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions

Selection of protective functions *1/2*

Selection of Preventa™ safety solutions *1/4*

Selection of Preventa safety products *1/6*

Emergency stop function and principal protective functions:

Guards without locking device *1/8*

Guards with locking device *1/8*

Coded magnetic safety interlock and system *1/9*

Light curtains *1/9*

Two-hand control system *1/10*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions
Selection of protective functions

On the basis of the risk estimation established, the designer will select one or more protective functions that will meet the needs.

The standards classify these functions into two distinct groups.

Emergency stops

This function, required on all machines, is not considered as a principal method of risk reduction. It supplements other protective measures (standard EN/ISO 12100).

Depending on the type of stop, the standard recognizes three categories (see details below):

- emergency stop categories 0 or 1,
- controlled stop categories 1 or 2, generally used with variable speed drives (please refer to our specific Variable Speed Drive catalogs).

Selection of safety function families

	Emergency stop			Protective solutions	
				Protective functions	
				Control of access to hazardous zones	
	Stop category 0	Stop category 1	Stop category 2	Interlocking Guard	
				Without guard locking	With guard locking
					
Access to hazardous zones:					
■ Free, frequent to continuous	-	-		-	-
■ Occasional (e.g.: once per shift) or frequent	-	-		X	X
Protection for all personnel	-	-		X	X
Stopping time of a dangerous movement:					
■ Short	X	-		X	-
■ Long (high inertia)	-	X		-	X
■ Long (high inertia); power is maintained on actuators	-	-	X	-	-

X	: The function provides the solution as long as the recommended use limits are complied with.
(X)	: The use of this function is possible but is not recommended.
-	: The function does not provide the solution.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions
Selection of protective functions

Protection methods

The functions selected, as shown in the chart below, are based on two criteria:

1 Persons may occasionally enter the hazardous zones or may work continuously within a hazardous zone.
2 Methods adopted to reduce the risks involve the use of defined functions.

Selection of safety function families (continued)

Protective solutions (continued)

Protective functions (continued)

Control of access to hazardous zones (continued)				Starting and enabling of dangerous movements	
Coded magnetic switch	Light curtains		Safety mats	Two-hand control	Enabling switch
	ESPE	ESPE with muting function			
					
-	X	X	X	X	-
X	(X)	(X)	(X)	(X)	X
X	X	X	X	X	X
X	X	X	X	X	X
-	-	-	-	-	-
-	-	-	-	-	-

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions
Selection of Preventa™ safety solutions

The table below indicates the associated control solutions for each safety function.
The Schneider Electric range of safety control solutions consists of four product families:

- dedicated safety relay modules with one or two safety functions,
- configurable controllers managing several safety functions,
- safety monitors and interfaces dedicated to the AS-Interface system, allowing use of a single medium for control and safety,
- safety PLCs used within complex safety systems.



		Product families		
		Safety relay modules	Configurable safety controllers	
Architecture		Simple machines	Machines with several safety functions	
Setting-up		Wired link	Configurable by push buttons	Configurable by software
Diagnostics		LED	LED	LED
		-	-	PC
		Solid-state outputs	Solid-state outputs	Modbus™ serial link (RTU), CANopen, Profibus™ DP
Functions	Emergency stop monitoring	XPSAC, XPSAF, XPSAK, XPSAR, XPSAXE	**X**	**X**
	Monitoring of emergency stop and of a guard with timer	XPSATE, XPSAV, XPSABV	**X**	**X**
	Monitoring of a guard with safety switch	XPSAC, XPSAF, XPSAK, XPSAR, XPSAXE	**X**	**X**
	Monitoring of a guard with coded magnetic switch	XPSDMB, XPSDME	**X**	**X**
	Monitoring of safety mats and sensitive edges	XPSAK	**X**	**X**
	Two-hand control (type IIIC acc. EN 574)	XPSBCE, XPSBF	-	**X**
	Two-hand control (type IIIA acc. EN 574)	XPSBAE	-	-
	Monitoring of type 4 light curtains, solid-state outputs and test function	XPSAFL, XPSAR, XPSAK	**X**	**X**
	Monitoring of single-beam photo-electric sensors (transmitter + receiver) with test input and built-in muting function	XPSCM	-	-
	Monitoring of a type 4 light curtain with relay output	-	-	**X**
	Monitoring muting function of 2 light curtains with transistor outputs	XPS LCM	-	-
	Monitoring of an enabling switch	-	**X**	**X**
	Zero speed detection on motor	XPSVNE	-	**X**
	Dynamic valve monitoring on linear hydraulic presses	XPSPVT	-	**X**
	Dynamic monitoring of double-bodied solenoid valves	XPSPVK	-	**X**
	Safety stop at top dead center with automatic overtravel monitoring on eccentric presses	XPSOT	-	**X**
	Foot switch	-	-	**X**

XPSAC, XPSAF, etc. : The product family provides the function.
X : The product family provides the function after programming (by means of push button or software, depending on the product).
- : The product family does not provide the function.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions
Selection of Preventa™ safety solutions

AS-Interface™ "safety at work" safety interfaces and monitors			Safety PLCs
Machines using AS-Interface			Communication network
Interface to be connected	Built-in interfaces	Monitor library configurable by software	Programmable by software
-	-	LED	LED
-	-	PC	PC
-	-	AS-Interface	Modbus™ serial link (RTU), Modbus™ TCP/IP, Profibus™ DP
ASISSLB4, ASISSLE4, ASISSLE5	ASISEA1C, ASISSK1C, ASISSLE4, ASISSLE5	X	X
-	-	-	X
ASISSLC1, ASISSLC2, ASISSLLS	-	X	X
ASISSLC1, ASISSLC2, ASISSLLS	-	X	X
-	-	X	X
2 x ASISSLC2	-	X	X
-	-	X	X
-	-	X	X
-	-	-	-
ASISSLC1, ASISSLC2, ASISSLLS	-	X	X
-	-	-	-
-	-	-	X
-	-	-	X
-	-	-	X
-	-	-	X
-	-	-	X
ASISSLC1, ASISSLC2, ASISSLLS	-	X	X

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions
Selection of Preventa™ safety products

This selection table indicates which safety products to select, according to the required safety functions.

Final selection will be made by consulting the specific catalog pages for each of these products.

			Safety control solution						
			Emergency stop		Prevention functions				
					Control of access to hazardous zones				
			Stop category 0	**Stop category 0+1**	**Interlocking guard with and without guard locking**	**Coded magnetic switch**	**ESPE light curtains**	**ESPE light curtains with muting function**	**Safety mats**
									
	EN/ISO 13849	**EN/IEC 62061**							
Safety relay modules *One safety function, Hard wired.*	max. Category 1, PL = b	SIL 1	-	-	-	-	-	-	-
	max. Category 2, PL = c	SIL 1	-	-	-	-	XPSCM	XPSCM	-
	max. Category 3, PL = d	SIL 2	XPSAC, XPSAFL	XPSATE (cat. 1 stop) , XPSABV	XPSAC	XPSDMB, XPSDME	XPSAFL	-	XPSAK
	max. Category 4, PL = e	SIL 3	XPSAF, XPSAK, XPSAR , XPSAXE	XPSATE (cat. 0 stop), XPSABV, XPSAV	XPSAF, XPSAK, XPSAR , XPSAXE	XPSDMB, XPSDME	XPSAFL, if OSSDs are tested by ESPE	XPSCM, XPSLCM	-
Configurable safety *Several safety functions controllers, Hard wired, Fieldbus for diagnostics (only for XPSMC).*	max. Category 1, PL = b	SIL 1	-	-	-	-	-	-	-
	max. Category 2, PL = c	SIL 1	-	-	-	-	-	-	-
	max. Category 3, PL = d	SIL 2	-	-	-	-	-	-	-
	max. Category 4, PL = e	SIL 3	XPSMP, XPSMC	XPSMC	XPSMP, XPSMC	XPSMP, XPSMC	XPSMP, XPSMC	XPSMC	XPSMP, XPSMC
AS-Interface™ "safety at work" safety monitors and interfaces *Several safety functions, Safety Network, Fieldbus for diagnostics.*	max. Category 1, PL = b	SIL 1	-	-	-	-	-	-	-
	max. Category 2, PL = c	SIL 1	-	-	-	-	-	-	-
	max. Category 3, PL = d	SIL 2	-	-	-	-	-	-	-
	max. Category 4, PL = e	SIL 3	X	X	X	X	X	-	-
Safety PLCs *Several safety functions, Safety Network, Fieldbus for diagnostics.*	max. Category 1, PL = b	SIL 1	X	X	X	X	X	X	X
	max. Category 2, PL = c	SIL 1	X	X	X	X	X	X	X
	max. Category 3, PL = d	SIL 2	X	X	X	X	X	X	X
	max. Category 4, PL = e	SIL 3	X	X	X	X	X	X	X

XPSAC, etc. : The solution is specifically provided by the products indicated.
X : The solution is provided by the products.
- : The solution is not provided by the products.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions

Selection of Preventa™ safety products

Starting and enabling of dangerous movements		Safety monitoring functions				Functions for specific machines	
Two-hand control	**Enabling switch**	**Zero speed detection (remanent voltage)**	**Zero speed detection/safety speed reduction**	**Safety timer**	**Increasing the number of safety contacts**	**Safety valve monitoring**	**Safety function for presses**
							
XPSBAE	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-
-	-	XPSVNE	-	XPSTSA XPSTSW	-	-	-
XPSBCE, XPSBF	-	-	-	-	XPSECME, XPSECPE	XPSPVT, XPSPVK	XPSOT
XPSBAE	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-
XPSMC	XPSMP, XPSMC	-	XPSMC	XPSMC	-	XPSMC	XPSMC
-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-
X	-	-	-	**X**	-	-	-
X	**X**	-	**X**	**X**	**X**	**X**	**X**
X	**X**	-	**X**	**X**	**X**	**X**	**X**
X	**X**	-	**X**	**X**	**X**	**X**	**X**
X	**X**	-	**X**	**X**	**X**	**X**	**X**

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions

Emergency stop function and Principal protective functions

Guards without guard locking device

Guards with guard locking device



Stop category 0



Stop category 1

Emergency stop function



Sub-elements of the emergency stop function



Guard without guard locking device



Guard with guard locking device



System with two safety limit switches



Combination of actuator operated guard switches and safety limit switches



Combination of actuator operated guard switches with guard locking and safety limit switches

Emergency stop function

International standard EN/ISO 13850 (which replaces standard EN 418) specifies the functional requirements and design principles of emergency stop devices.
It applies to all machines, whatever type of energy is used to control this function.
NFPA 79 (US) also has very similar electrical requirements for emergency stop functions.

When the emergency stop instruction ceases, the effect must be maintained until it is reset. Manual resetting must only be possible in the location where the instruction was given.
Resetting must not start the machine, but simply enable the starting cycle.
Restarting of the machine must not be possible until the emergency stop has been reset.

The standard allows two types of stop:
-- category 0 : stopping by immediate cutting-off of power or mechanical disconnection between the dangerous components,
-- category 1 stop: controlled stopping with power maintained to the actuator to achieve stopping (braking for example), then cut-off of power when standstill is reached.
The choice between these two stopping methods is determined by an evaluation of the machine-related risks.

This function includes several sub-functions but is generally represented by the drawings to the left.

The operator interface may be:
-- a push button equipped with a mushroom head,
-- a cable actuated switch,
-- a foot switch.

Guards without guard locking device

On a large number of potentially dangerous machines, the operator must be kept at a distance during operation, but needs to take action when the machine is stopped to position a part, remove a product or adjust a tool.

An effective means of protection is to install a guard which, according to the type of installation, will cut-off the power to the motor if an attempt is made to open it during the machine operating phase.
In all cases, it must not be possible to restart the machine until the guard is closed.

Depending on the level of protection required, the system will consist of two safety limit switches (safety interlock switches) or a combination of protected, actuator operated guard switches to prevent tampering.

Guards with guard locking device

This type of guard is necessary for potentially dangerous machines with high inertia (long rundown time).
The guard is interlocked (by a solenoid for example); it cannot be opened until the machine has come to a complete standstill.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions

Principal protective functions

Coded magnetic safety interlock and system Light curtains



Coded magnetic safety interlock



Functions of coded magnetic safety interlocks



Functions of a coded magnetic safety interlock system

Coded magnetic safety interlock and system

A coded magnetic solution is often used on industrial machines fitted with a door or guards with imprecise guiding.
It is particularly suitable for machines subjected to frequent washing or splashing of liquids as well as small machines with a single guard for self-contained systems.

Depending on the models used, the sensing distance will be between 0.19 and 0.30 in. (5 and 10 mm).

The reed contacts used for the coded magnetic safety interlock switches (coded magnetic switches) cannot withstand short-circuits and the switches always incorporate a resistor in series. Their operation can therefore only be guaranteed with the associated processing module (for example: safety relay or safety controller).

The Hall-effect self-contained systems with integral processing do not require any further processing of the signal (XCSDM3 and XCSDM4).

The illustrations to the left show the functions of coded magnetic safety interlocks and of a system.



Light curtain



Light curtains

Light curtains are electro-sensitive systems (Electro-Sensitive Protective Equipment - also referred to as ESPE) designed to protect persons working in the vicinity of machinery, by stopping dangerous movements when a light beam is broken.

The absence of a door or guard reduces loading, inspection or tool changing times.

This type of system, defined by standards EN/IEC 61496-1 and EN/IEC 61496-2, is frequently used with machines such as:

- presses,
- machine tools,
- assembly lines, etc.

The machine must be designed so that a person cannot gain access to dangerous movements without breaking one or more of the light beams.
In addition, the movement must be stopped whatever the entry speed of the operator into the hazardous zone.

The diagram to the left illustrates the operation of a light curtain.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com



Two-hand control system



Functions of a two-hand control system



Functional diagram of a two-hand control system

Two-hand control system

Standards ISO 13851 and EN 574 define this type of system.
It requires simultaneous operation by both hands in order to start and maintain operation of a machine.
It therefore provides protection exclusively for the person operating it.

A diagram representing the function is given to the left; it must meet the following requirements:

- concurrent, maintained operation of the two input controls for the same period of time
- synchronous operation; the delay between the two signals must not exceed 0.5 s
- prevention of accidental operation (mechanical guard)
- protection against tampering

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Preventa™ safety PLCs, XPSMF

Selection guide: Preventa safety PLCs, XPSMF *2/2*

Preventa safety compact PLCs, XPSMF40 . . . . . *2/4*

Preventa safety compact PLCs, XPSMF31/30/35 . . . . . *2/18*

Preventa safety modular PLC, XPSMF60:

Rack, power supply and central processing unit *2/34*
- "In rack" analog input card *2/50*
- "In rack" analog output card *2/52*
- "In rack" mixed card: counting inputs/digital outputs *2/54*
- "In rack" digital input card (24 digital inputs) *2/56*
- "In rack" digital input card (32 digital inputs) *2/58*
- "In rack" digital I/O card *2/60*
- "In rack" relay output card *2/62*

Communication on network and bus *2/64*

Programming software XPSMFWIN for Preventa safety compact and modular safety PLCs, XPSMF *2/68*

Selection guide: Safety remote input/output modules, XPSMF1/2/3 . . . . . *2/74*

Safety remote input modules, XPSMF1 . . . . . *2/76*

Safety remote output modules, XPSMF2 . . . . . *2/80*

Safety remote mixed I/O modules, XPSMF3 . . . . . *2/90*

Preventa safety controllers, XPSMP and XPSMC

Selection guide: Preventa safety controllers *2/104*

Controllers with pre-defined functions, XPSMP *2/106*

Configurable controllers, XPSMC *2/118*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact and modular, XPSMF

2

Introduction

*Products referenced **XPSMF31222, XPSMF3022** and **XPSMF35●●** are marked **HIMatrix® F31, HIMatrix® F30** and **HIMatrix® F35** (manufactured by Hima, sold by Schneider Electric).*

Compact PLCs:
- Designed for use with numerous machine safety functions and for the protection of personnel.
- Designed for use in safety related parts of control systems up to category 4 conforming to EN 954-1, up to performance level "e" conforming to EN/ISO 13849-1, and up to SIL 3 conforming to EN/IEC 61508.

User memory	Application	250 kB			
	Data	250 kB			
Response time		Depending on size of application			
Maximum power consumption		8 A			9 A
Supply		External ⎓ 24 V supply (with separate protection conforming to EN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)			
Inputs **Digital**	Number of channels	**24**, configurable, not electrically isolated	**20**, not electrically isolated		**24**, not electrically isolated
	Current at state 0	1.5 mA max. at ⎓ 24 V	1.5 mA max., 1.25 mA at 5 V		
	Current at state 1	3.5 mA at ⎓ 24 V 4.5 mA at ⎓ 30 V	≥ 2 mA at ⎓ 15 V	> 2 mA at ⎓ 15 V	3.5 mA at ⎓ 24 V 4.5 mA at ⎓ 30 V
Analog	Number of channels	–	–	–	**8**, single-pole
	Range: voltage/current	–	–	–	0…10 V/0…20 mA *(1)*
Counting	Number of channels	–	–	–	**2**
	Current	–	–	–	1.4 mA at ⎓ 5 V, 6.5 mA at ⎓ 24 V
Outputs Digital	Number of channels	**24**, configurable, not electrically isolated	**8** *(2)*, not electrically isolated		**8**, not electrically isolated
	Output current	Chnls. 1 to 3, 5 to 7, 9 to 11, 13 to 15, 17 to 19, 21 to 23: 0.5 A at 140°F (60°C) Channels 4, 8, 12, 16, 20 and 24: 1 A at 140 °F (60 °C), 2 A at 122°F (50°C)	Channels 1 to 3 and 5 to 7: 0.5 A at 140 °F (60 °C) Channels 4 and 8: 1 A at 140°F (60 °C), 2 A at 122°F (50 °C)		
Analog	Number of channels	–	–	–	–
	Range: voltage/current	–	–	–	–
Relay	Number	–	–	–	–
	Switching voltage	–	–	–	–
Line control		**2 x 4**	*(2)*	*(2)*	–
Input/output connections		Removable screw terminals are provided with all Safety compact PLCs Reference **XPSMF40●●** is also provided with cage clamp terminal			
Communication on Ethernet network		**By integrated RJ45 switched Ethernet communication ports**			
■ **Safe communication** using SafeEthernet protocol		yes	yes	yes	yes
■ **Non safe communication** using Modbus™ TCP/IP protocol, server (slave)		yes (**XPSMF4002/4022/4042**)	yes (**XPSMF31222**)	yes (**XPSMF3022**)	yes (**XPSMF3502/ MF3522/MF3542**)
Communication on fieldbus					
Non safety using Modbus RTU protocol, slave (RS 485)		yes (**XPSMF4020/4022**)	–	yes (**XPSMF3022**)	yes (**XPSMF3522**)
Non safety using PROFIBUS DP protocol, (V0 slave)		yes (**XPSMF4040/4042**	–	–	yes (**XPSMF3542**)
Safety PLC type		**XPSMF400●/MF402●/ MF404●**	**XPSMF31222**	**XPSMF3022**	**XPSMF3502/ MF3522/MF3542**
See page		2/12	2/27	2/27	2/27
"In rack" card type		–	–	–	–
See page		–	–	–	–

(1) With 500 Ω jumper. (2) The digital outputs can be configured as line control outputs.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular, XPSMF

Modular PLC XPSMF60: metal rack **XPSMFGEH01** with slots for power supply module **XPSMFPS01**, central processing unit **XPSMFCPU22** and six "in rack" I/O cards.
- Designed for use with numerous machine safety functions and for the protection of personnel.
- Designed for use in safety related parts of control systems up to category 4 conforming to EN 954-1, up to performance level "e" conforming to EN/ISO 13849-1, and up to SIL 3 conforming to EN/IEC 61508.

500 kB						
500 kB						
Depending on size of application						
30 A max., 32 A external fuse						
External ⎓ 24 V supply (with separate protection conforming to EN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)						
–	–	–	**24**, electrically isolated	**32** *(2)*, electrically isolated	**24** *(2)*, electrically isolated	–
–	–	–	–	1 mA at 5 V	1 mA at 5 V	–
–	–	–	⩾ 2.2 mA at 79 V	2 mA at ⎓ 10 V, 5 mA at ⎓ 24 V	2 mA at ⎓ 10 V, 5 mA at ⎓ 24 V	–
8 single-pole or **4** 2-pole, configurable, electrically isolated	–	–	–	–	–	–
- 10…+ 10 V/0…20 mA *(1)*	–	–	–	–	–	–
–		**2**	–	–	–	–
–	–	0.8 A at ⎓ 3.3 V 0.1 A at ⎓ 5 V 0.1 A + output current at ⎓ 24 V	–	–	–	–
–	–	**4**	–	–	**16** *(3)*, electrically isolated	–
–	–	0.5 A per channel, 2 A max. per "in rack" card	–	–	2 A per channel at 86 °F (30 °C), 8 A max. at 86 °F (30 °C) per "in rack" card	–
–	**8**, electrically isolated	–	–	–	–	–
–	- 10…10 V / 0…20 mA	–	–	–	–	–
–	–	–	–	–	–	**8**
–	–	–	–	–	–	≂ 6…250 V
–	–	–	–	–	*(3)*	–
Removable screw terminals are provided with "in rack" I/O cards and Power supply module						
By integrated RJ45 switched Ethernet communication ports						
yes						
yes						
yes						
yes						

XPSMFGEH01 (rack) + XPSMFPS01 (power supply) + XPSMFCPU22 (central processing unit) + "in rack" I/O cards (to be selected from below)

2/44

XPSMFAI801	XPSMFAO801	XPSMFCIO2401	XPSMFDI2401	XPSMFDI3201	XPSMFDIO241601	XPSMFDO801
2/51	2/53	2/55	2/57	2/59	2/61	2/63

(1) With 250 Ω or 500 Ω jumper. (2) Digital inputs can be supplied by the line control outputs of the same I/O card. (3) The digital outputs (n° 1… n° 16) can be configured as line control outputs.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact, XPSMF40

Introduction

Preventa™ compact safety PLCs **XPSMF40●●** enable the monitoring of simple to complex safety functions for all industrial applications relating to the protection of personnel and machine safety.

Designed for use with numerous machine safety functions, these compact safety PLCs are intended for use in safety related parts of control systems.
They can manage up to:

- category 4 conforming to EN 954-1,
- performance level “e” conforming to EN/ISO 13849-1,
- SIL 3 (safety integrity level) conforming to EN/IEC 61508.

The compact safety PLC range **XPSMF40●●** consists of 6 versions that are differentiated by their non safety related communication protocols.

Compact PLCs	Digital Inputs/Outputs	Line control outputs	Communication		
			On Ethernet network		On fieldbus
			Safety protocol	Non safety protocol	
XPSMF4000	24, configurable	8	SafeEthernet	–	–
XPSMF4002	24, configurable	8	SafeEthernet	Modbus™ TCP/IP Server	–
XPSMF4020	24, configurable	8	SafeEthernet	–	Modbus serial Slave (RTU)
XPSMF4022	24, configurable	8	SafeEthernet	Modbus TCP/IP Server	Modbus serial Slave (RTU)
XPSMF4040	24, configurable	8	SafeEthernet	–	PROFIBUS DP V0 slave
XPSMF4042	24, configurable	8	SafeEthernet	Modbus TCP/IP Server	PROFIBUS DP V0 slave

Safety PLCs

In order to meet safety requirements, the compact safety PLCs **XPSMF40●●** incorporate two essential functions (**Redundancy** and **Self-monitoring)** complying to category 4 conforming to EN 954-1 and performance level “e” conforming to EN/ISO 13849-1 in addition to the SafeEthernet safety communication protocol between the safety PLCs and the safety remote I/O modules (**Special Switch**).

■ **Redundancy**: the triple processor integrated in the compact safety PLCs analyzes and compares the data received from the safety inputs and outputs. The incoming and outgoing data (programmed values and received values) are received in parallel by the three processors and compared in real-time.
■ **Self-monitoring (“Watchdog”)**: the compact safety PLCs continuously monitor the data processing cycle and the execution of tasks, and intervenes if the cycle time does not conform to the predefined value.
■ **The integrated switch (Special Switch)** stores for a very short time and sends at very high speed the data provided by the inputs and outputs of the safety PLCs on the Ethernet network, while avoiding signal collisions and excessive amounts of data on the network.

Functional diagrams

Compact safety PLCs XPS4000/MF4002



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact, XPSMF40

Functional diagrams *(continued)*

Compact safety PLCs XPSMF4020/MF4022



Compact safety PLCs XPSMF4040/MF4042



Line control for safety PLCs XPSMF40●●

Line control is a means of short-circuit and line break monitoring.
Using line control outputs enables SIL 3 (EN/IEC 61508) and category 4 (EN 954-1) safety to be achieved. The line control outputs send a high signal with a very short low signal, thus enabling a wiring anomaly (short-circuit, line break) to be seen at the inputs of the safety PLCs.

The line control outputs 1 to 8 are connected to the digital inputs of the same circuit.

Example: Emergency stop pushbutton with two normally closed (N.C.) contacts that are supplied by two different line control outputs connected via these two normally closed contacts and fed into the inputs of the safety PLCs

Programming automated safety functions

Software **XPSMFWIN** (reference SSV1XPSMFWIN) running on a PC enables the programming of all safety remote I/O modules and safety PLCs, as well as configuration of the communication settings.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact, XPSMF40

Compact safety PLCs **XPSMF40●●** incorporate:
- ■ 24 configurable I/O channels
- □ digital inputs
- □ or digital outputs
- ■ and 8 (2 x 4) line control output channels.

Digital inputs

Compact safety PLCs **XPSMF40●●** incorporate up to 24 digital inputs for the connection of safety related input devices, such as emergency stop contacts, magnetic switches, and light curtains.

Compact PLCs	Digital inputs		
	N°	Safety detection	Safety dialog
XPSMF4000	24	Limit switches, Guard switches, with reset and with actuator, Light curtains type 2 and type 4, Safety mats and sensing edges	Mushroom head Emergency stops, Enclosures for control and signalling units, Two-hand control stations
XPSMF4002	24		
XPSMF4020	24		
XPSMF4022	24		
XPSMF4040	24		
XPSMF4042	24		

Digital outputs

Compact safety PLCs **XPSMF40●●** incorporate up to 24 digital outputs for the connection of safety related output devices, such as contactors, illuminated beacons, and sirens.

Compact PLCs	Digital outputs		
	N°	Safety actuators	Safety dialog
XPSMF4000	24	Contactors-motors, Contactors-reversing, Variable speed drives	Beacons and indicator banks, Rotating mirror beacons, Sirens
XPSMF4002	24		
XPSMF4020	24		
XPSMF4022	24		
XPSMF4040	24		
XPSMF4042	24		

Line control outputs

Compact PLCs	Line control outputs	
	N°	
XPSMF4000	8 (2 x 4)	Short-circuit and line break monitoring
XPSMF4002		
XPSMF4020		
XPSMF4022		
XPSMF4040		
XPSMF4042		

Remote inputs and outputs

In addition to the inputs/outputs integrated as standard, compact safety PLCs **XPSMF40●●** can be connected to safety remote input modules **XPSMF1** and/or safety remote output modules **XPSMF2** and/or safety remote mixed I/O modules **XPSMF3**.
The safety remote input, output and mixed I/O modules can be located within the vicinity of the machines to be monitored, thus reducing cabling.

Communication between these safety remote I/O modules and safety PLCs **XPSMF40●●** is performed on an Ethernet network using the SafeEthernet safety protocol, via the integrated RJ45 switched Ethernet communications ports.

Integrating safety PLCs XPSMF40 on a Premium™ automation platform

Designed for mechanical integration on a Premium automation platform, safety PLCs **XPSMF40●●** occupy 2 slots on the Premium rack **TSX RKY**.
There is interaction between the two programming environments (Unity and XPSMFWIN): the variables defined using software **XPSMFWIN** can be retrieved by Unity (platform programming software) by using a tool included in Safety Suite V2.



*Example of mechanical integration of a compact safety PLC **XPSMF40** on a Premium™ automation platform.*

1 *Premium rack*
2 *Power supply module*
3 *Premium processor module*
4 *Other Premium modules (communication, I/O)*
5 *Compact safety **PLC XPSMF40***

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety communication on Ethernet network

Communication between the PC, Magelis™ graphic terminals or automation platform (Premium™) and the compact safety PLCs **XPSMF40●●** is achieved by **Ethernet** network connection via the integrated RJ45 switched Ethernet communication ports of the compact PLCs.



1 Premium™ automation platform: Modbus™ TCP/IP client.
2 Graphic terminal **XBTGT**: Modbus TCP/IP client.
3 Safety PLCs **XPSMF40●●**: Modbus TCP/IP servers.
4 Safety remote I/O modules **XPSMF1/2/3**. They communicate with safety PLCs **XPSMF40●2** using the SafeEthernet protocol.

Communication on Modbus serial (RTU) and PROFIBUS DP fieldbus

■ On **Modbus serial (RTU)**, safety PLCs **XPSMF4020** and **XPSMF4022** are slaves of the Premium™ automation platform and Magelis graphic terminal.
They are connected to the Modbus serial network via their RJ45 connector.



1 Graphic terminal **XBTGT**: Modbus serial (RTU) master.
2 Premium™ automation platform: Modbus serial (RTU) master.
3 Safety PLCs **XPSMF402●**: Modbus serial (RTU) slave, Modbus TCP/IP server.
4 Safety remote I/O modules **XPSMF1/2/3**. They communicate with safety PLCs **XPSMF402●** using the SafeEthernet protocol.
5 Graphic terminal **XBTGT**: Modbus serial (RTU) client.

■ On **PROFIBUS DP**, safety PLCs **XPSMF4040** and **XPSMF4042** are slaves of the Premium™ automation platform and Magelis graphic terminal.
They are connected to the PROFIBUS DP network via their SUB-D 9-pin connector.



1 Premium™ automation platform: PROFIBUS DP master.
2 Graphic terminal **XBTGT**: PROFIBUS DP master.
3 Safety PLC **XPSMF404●**: PROFIBUS DP slave, Modbus TCP/IP server.
4 Graphic terminal **XBTGT**: Modbus TCP/IP client.
5 Safety remote I/O modules **XPSMF1/2/3**. They communicate with safety PLCs **XPSMF404●** using the SafeEthernet protocol.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact, XPSMF40



Description

Safety PLCs XPSMF4000/MF4002

On the front cover of the enclosure:

1 One terminal block *(1)* for ⎓ 24 V supply.
2 Two integrated RJ45 (type 10BASE-T/100BASE-TX) switched ports for programming, and for Safety and non-safety related communication on Ethernet (safety related using SafeEthernet protocol and Non-safety related using Modbus TCP/IP server protocol).
3 Process status LEDs.
4 One “Reset” button.
5 Six terminal blocks *(1)* for connection of configurable digital I/Os.
6 Two terminal blocks *(1)* for connection of line control outputs.
7 On the rear face: one removable plate with spring mounting for mounting on 35 mm DIN rail.



Safety PLCs XPSMF4020/MF4022

On the front cover of the enclosure:

1 One terminal block *(1)* for ⎓ 24 V supply.
2 Two integrated RJ45 (type 10BASE-T/100BASE-TX) switched ports for programming, and for Safety and non-safety related communication on Ethernet (safety related using SafeEthernet protocol and Non-safety related using Modbus server protocol).
3 Process status LEDs.
4 One “Reset” button.
5 Six terminal blocks *(1)* for connection of configurable digital I/Os.
6 Two terminal blocks *(1)* for connection of line control outputs.
7 One RJ45 connector for connection on Modbus serial (RTU), with 2 process status LEDs.
8 On the rear face: one removable plate with spring mounting for mounting on 35 mm DIN rail.



Safety PLCs XPSMF4040/MF4042

On the front cover of the enclosure:

1 One terminal block *(1)* for ⎓ 24 V supply.
2 Two integrated RJ45 (type 10BASE-T/100BASE-TX) switched ports for programming, and for Safety and non-safety related communication on Ethernet (safety related using SafeEthernet protocol and Non-safety related using Modbus TCP/IP server protocol).
3 Process status LEDs.
4 One “Reset” button.
5 Six terminal blocks *(1)* for connection of configurable digital I/Os.
6 Two terminal blocks *(1)* for connection of line control outputs.
7 One SUB-D (9-pin female) connector for connection on PROFIBUS DP, with 2 process status LEDs.
8 On the rear face: one removable plate with spring mounting for mounting on 35 mm DIN rail.

*(1) Removable Screw and Cage clamp terminals are provided with compact safety PLCs **XPSMF40**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Process status LEDs



1 *Internal Ethernet LED*
2 *External Ethernet LEDs*

Modbus serial (RTU) LEDs

PROFIBUS DP LEDs

LED details

Process status LEDs on safety PLCs XPSMF40●●

LED	Color	Status	Meaning
1…24	Green	On	Channels configured as inputs: input signal being received. Channels configured as outputs: output signal being sent.
T1…T8	Green	On	Line control outputs active.
PWR	Green	On	⎓ 24 V voltage present.
		Off	No voltage.
PG	Yellow	On	The CPU is being loaded with a new configuration.
		Flashing	The FLASH ROM is being loaded with a new operating system.
		Off	No loading of configuration or operating system.
ERR	Red	On	Software error or hardware anomaly detected by the CPU.
			The monitoring program (Watchdog) has triggered the STOP state of the process because the programmed cycle time has been exceeded.
			The CPU has stopped the execution of the user application, ended all hardware and software tests and all outputs have been reset.
			The process can only be started again from the PC.
		Off	No errors detected.
FAU	Orange	On	Error display for line control.
			The user application has caused an error.
			The system configuration is defective.
			The loading of a new operating system was defective and the operating system is corrupt.
		Flashing	An error has occurred while writing to FLASH ROM memory (during updating of the operating system).
			One or more I/O errors have occurred.
		Off	None of the above errors have occurred.
RUN	Green	On	Normal service mode, loaded program running, the PLC receives I/O messages, communication and hardware/software tests carried out.
		Flashing	The CPU is in STOP and is not executing any user application. All the outputs are reset to a safe, de-energized state.
		Off	The CPU is in “ERROR” state (see ERR).
FOR	Green	On	The CPU is in RUN mode and force is active.
		Flashing	The system is not processing (STOP), but force is prepared and is activated if the triple processor is started.
		Off	Force mode not activated.
OSL	Orange	Flashing	Emergency loading of the operating system is active.
BL	Orange	Flashing	COM in INIT_Fail state.

Ethernet LEDs on safety PLCs XPSMF40●●

LK/ACT external	Green	Off	No connection/link established.
		On	Connection established/link established.
		Flashing	External data exchange (speed 10…100 Mbps).
LK/ACT internal	Green	Off	No connection/link established.
		On	Connection established/link established.
		Flashing	Internal data exchange (speed 10…100 Mbps).

Modbus™ serial (RTU) LEDs on safety PLCs XPSMF4020/MF4022

COM	Yellow	Off	No bus network signals being received or transmitted.
		On	Bus network signals being received or transmitted.
RDY	Green	Off	Transmission power not available.
		On	Equipment on.

PROFIBUS DP LEDs on safety PLCs XPSMF4040/MF4042

RUN	Green	Off	Equipment not connected or not operational.
		On	Equipment operational.
ERR	Red	Off	Transmission power not available or the slave is exchanging data.
		On	Connection to other equipment is established but no data exchange is possible. Bus disconnected or bus Master not available.
		Flashing	A configuration error has occurred and no data exchange is possible.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact, XPSMF40

Environment			
Compact safety PLC type			**XPSMF4000/4002, XPSMF4020/4022, XPSMF4040/4042**
Products designed for max. use in safety related parts of control systems (conforming to EN 954-1, EN/ISO 13849-1 and EN/IEC 61508)			Category 4 (EN 954-1), Performance level "e" (EN/ISO 13849-1), Safety integrity level: SIL 3 (EN/IEC 61508)
Product certifications			IEC 61511 part 1-3: 2004, DIN VDE 0116: 1989, EN 50156-1: 2004, EN 12067-2: 2004, EN 298: 2003, EN 230: 2005, NFPA 85: 2001, EN/IEC 61131-2: 2003, EN 61000-6-2: 2001, EN 61000-6-4: 2001
Ambient air temperature conforming to EN/IEC 61131-2	Operating	**°F (°C)**	+32… + 140 (0…+ 60)
	Storage	**°F (°C)**	-40… + 185 (- 40…+ 85)
Relative humidity			95% (supply not connected)
Degree of protection	Enclosure		IP 20
Pollution			Degree of pollution II
Altitude			6560 ft. (2,000 m)
Protection class			Class II, conforming to EN/IEC 61131-2
Electromagnetic compatibility			Conforming to EN/IEC 61131-2
Vibration resistance conforming to EN/IEC 61131-2	Operating		1 g, frequency 9…150 Hz
Shock resistance conforming to EN/IEC 61131-2	Operating		15 g (duration 11 ms), unit test while operating, 2 cycles per axis
Resistance to electrostatic discharges conforming to EN/IEC 61000-4-2		**kV**	4 contact, 8 air discharge
Immunity to high frequency interference conforming to EN/IEC 61000-4-3		**V/m**	10 (80 MHz…2 GHz), amplitude modulation 80%
Electrical specifications			
Supply	Voltage	**V**	⎓ 24 (external supply with separate protection conforming to EN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)
	Voltage limits		- 15…+ 20 %
Maximum power consumption		**A**	8
Idle current		**A**	0.5
Immunity to momentary supply interruptions		**ms**	10
Protection			Internal fuse, 10 A
Response time		**ms**	Depending on size of application
Clock			Supplied by backup capacitor for 1 week following loss of supply
User memory	Application	**kB**	250
	Data	**kB**	250
LED display			Yes
Digital inputs			
Number	Inputs not electrically isolated		24, configurable channels
Permissible current	At state 0	**mA**	1.5 max. at ⎓ 24 V
	At state 1	**mA**	3.5 at ⎓ 24 V, 4.5 at ⎓ 30 V
Input supply			3 x ⎓ 20 V/100 mA (on 24 V)
Input resistance		**kΩ**	< 7
Overvoltage protection		**V**	- 10, + 35
LED display			Yes, see page 2/9
Maximum distance of equipment			984 ft. (300 m)
Digital outputs			
Number	Outputs not electrically isolated		24, configurable channels
Output voltage		**V**	⎓ 24 ± 2
Output current	Channels 1 to 3, 5 to 7, 9 to 11, 13 to 15, 17 to 19, 21 to 23	**A**	0.5 at 140 °F (60 °C)
	Channels 4, 8, 12, 16, 20 and 24	**A**	1 at 140 °F (60 °C), 2 at 122 °F (50 °C)
Minimum load		**mA**	2 per channel
Leakage current at state 0		**mA**	1 max. at 2 V
Response to overload			Shutdown of outputs concerned with cyclic reconnection
Total output current		**A**	7 max., shutdown of all outputs if exceeded with cyclic reconnection
LED display			Yes
Maximum distance of equipment			984 ft. (300 m)
Line control outputs			
Number	Outputs not electrically isolated		8 (2 x 4)
Output voltage		**V**	20, depending on the supply voltage
Output current		**mA**	60
Minimum load		**mA**	None
Response to overload			4 x ⩾ 19.2 V/60 mA (on 24 V), short-circuit current
LED display			Yes

Introduction: page 2/4 | Specifications: page 2/10 | References: page 2/12 | Dimensions, mounting: page 2/15 | Connections: page 2/16

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Communication

Ethernet network

Safety communication using SafeEthernet safety protocol

Compatibility			**XPSMF4000/MF4002, XPSMF4020/MF4022, XPSMF4040/MF4042**
Transmission	Communication ports		Integrated 2 RJ45 switched Ethernet communications ports
	Baud rate	**Mbps**	100 Half duplex, 10 Full duplex, Autonegotiation
Structure			10BASE-T/100BASE-TX
Medium			Dual twisted pair cable, category 5D or better (Ethernet)

Non safety communication using Modbus™ TCP/IP protocol

Compatibility			**XPSMF4002, XPSMF4022, XPSMF4042**
Connection ports	Number and type		Integrated 2 RJ45 switched Ethernet communications ports
	Baud rate	**Mbps**	100 Half duplex, 10 Full duplex, Autonegotiation
	Master/Slave		Server (slave)
Structure			10BASE-T/100BASE-TX
Medium			Dual twisted pair cable, category 5D or better (Ethernet)
Transparent Ready™ service	Class		A10
	Standard Ethernet TCP/IP communication services (supported by compact safety PLCs XPSMF40)		Modbus TCP/IP server.
			Modbus TCP/IP messaging (reading/writing of data words) Modbus identification requests
	TCP port		Standard 502
	Max. number of Modbus TCP/IP connections		1 to 20

Modbus serial (RTU)

Compatibility			**XPSMF4020, XPSMF4022**
Serial link ports	Number and type		1 x RJ45
	Master/Slave		Slave, V0
Addressing			122 slave addresses
Physical layer			RS 485
Medium			Shielded dual twisted pair cable

PROFIBUS DP

Compatibility			**XPSMF4040, XPSMF4042**
Serial link ports	Number and type		1 x SUB-D 9-pin female
	Master/Slave		Slave, V0
Physical layer			RS 485
Medium			Shielded dual twisted pair cable

Connections *(1)*

Type of connection			**Removable screw clamp terminal blocks** *(2)*	**Removable spring terminal blocks** *(2)*
Supply connection	Number of terminal blocks		1	1
	For 1 cable without cable end		Solid or flexible AWG 24-12 (0.2…2.5 mm^2)	–
	For 1 flexible cable with or without plastic cable end		AWG 24-14 (0.25…2.5 mm^2)	–
	For 2 cables of same diameter, without cable end		–	Solid or flexible AWG 24-12 (0.2…2.5 mm^2)
	For 2 cables of same diameter, flexible without cable end		–	AWG 24-12 (0.25…2.5 mm^2)
	For 2 cables of same diameter, flexible with plastic cable end		–	AWG 24-12 (0.25…2.5 mm^2)
Cable connection	Tightening torque		4.43 lb-in (0.5 Nm)	–
	Bared length		0.39" (10 mm)	0.35" (9 mm)
Connection to digital input channels, digital output channels, line control output channels	Number of terminal blocks		8	8
	For 1 cable without cable end		Solid or flexible AWG 24-16 (0.14…1.5 mm^2)	–
	For 1 flexible cable without cable end		AWG 24-16 (0.25…1.5 mm^2)	–
	For 1 flexible cable with plastic cable end		AWG 24-20 (0.25…0.5 mm^2)	–
	For 2 cables of same diameter, without cable end		–	Solid or flexible AWG 26-16 (0.14…1.5 mm^2)
	For 2 cables of same diameter, flexible without cable end		–	AWG 22 (0.25…0.34 mm^2)
	For 2 cables of same diameter, flexible with plastic cable end		–	AWG 20 (0.5 mm^2)
Cable connection	Tightening torque		1.95...2.21 lb-in (0.22...0.25 Nm)	–
	Bared length		0.35" (9mm)	0.35" (9mm)

(1) AWG: American Wire Gauge.
*(2) Removable Screw and Cage Clamp terminals provided with safety PLCs **XPSMF40●●**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact, XPSMF40

XPSMF4000
XPSMF4002

XPSMF4020
XPSMF4022

XPSMF4040
XPSMF4042

Compact safety PLCs

⎓ **24 V supply**

Digital Inputs or Outputs	Line control outputs	Communication on Ethernet network SafeEthernet protocol	Modbus TCP/IP protocol	Modbus™ serial (RTU)	PROFIBUS DP	Reference	Weight oz (kg)
0…24 configurable channels	2 x 4	Yes	–	–	–	**XPSMF4000**	35.273 (1.000)
			Yes, server	–	–	**XPSMF4002**	35.273 (1.000)
			–	Yes, slave	–	**XPSMF4020**	35.273 (1.000)
			Yes, server	Yes, slave	–	**XPSMF4022**	35.273 (1.000)
			–	–	Yes, slave	**XPSMF4040**	35.273 (1.000)
			Yes, server	–	Yes, slave	**XPSMF4042**	35.273 (1.000)

Configuration software

■ Reference **SSV1XPSMFWIN** contains the full version of the programming software XPSMFWIN software for the XPSMF Safety PLCs. The XPSMFWIN is part of our Safety Suite and is not available separately.

Description	Operating system	Details	Languages	Reference	Weight oz (kg)
Configuration software XPSMFWIN for programming compact safety PLCs CD-ROM + user manual	Windows® 2000, Windows® XP	Software available on Safety Suite V2 software pack	English, German, French	**SSV1XPSMFWIN**	18.342 (0.520)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact, XPSMF40

ABL8RPS24050

ABL1REM24025

XBTGT2130, XBTGT2330

XBTGT4330

XBTGT5●30

XBTGT6330

XBTGT7340

Phaseo™ regulated switch mode power supplies

Mains input voltage	Output voltage	Nominal power	Nominal current	Auto-protect reset	Conformity to standard IEC EN 61000-3-2 and IEC EN 60950	Reference	Weight
V	⎓ V	W	A				oz (kg)
Universal range, single-phase (N-L1) **or 2-phase** (L1-L2) **connection**							
∿ **100…120 V/200...500** - 15%, + 10% 50/60 Hz	24...28.8	72	3	Auto/Manual	Yes	**ABL8RPS24030**	10.582 (0.300)
		120	5	Auto/Manual	Yes	**ABL8RPS24050**	24.692 (0.700)
		240	10	Auto/Manual	Yes	**ABL8RPS24100**	35.273 (1.000)
Dedicated range, single-phase connection							
∿ **100…240** *(1)* wide range, 47…63 Hz	12	60	5	Auto	No	**ABL1REM12050**	15.521 (0.440)
	24	60	2.5	Auto	No	**ABL1REM24025**	15.521 (0.440)
∿ **100...120/200...240** *(2)*	24	240	10	Auto	No	**ABL1REM24100**	31.041 (0.880)

Magelis™ multifunction graphic terminals with touch sensitive screen and on-board Ethernet *(1) (2)*

Supply voltage ⎓ 24 V

Description		Ports: serial and communication (type of link)	Application memory	Reference	Weight oz (kg)
5.7"	Monochrome black and white STN	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 1 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	16 Mb	**XBTGT2130**	35.273 (1.000)
	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 1 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	16 Mb	**XBTGT2330**	35.273 (1.000)
7.5"	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 1 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT4330**	63.493 (1.800)
10.4"	Color STN	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT5230**	105.822 (3.000)
	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT5330**	105.822 (3.000)
12.1"	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT6330**	105.822 (3.000)
15"	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT7340**	197.534 (5.600)

(1) Service instructions, USB connectors locking device and mounting kit included.
(2) Other operator dialog terminals, industrial PCs: please refer to our "Human Machine Interface" catalog.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

490NTW000●●

Connecting cables for network and bus

Connection to Ethernet network

Description	Pre-fitted connectors	Length ft. (m)	Reference	Weight oz (kg)
Shielded twisted pair cables, straight through	2 RJ45 connectors For connection to DTE (Data Terminal Equipment)	6.56 (2)	**490NTW00002***(1)*	–
		16.40 (5)	**490NTW00005***(1)*	–
		39.37 (12)	**490NTW00012***(1)*	–
		131.23 (40)	**490NTW00040***(1)*	–
		262.47 (80)	**490NTW00080***(1)*	–
Shielded twisted pair cables, crossed wires	2 RJ45 connectors For connection between hubs, switches and transceivers	16.40 (5)	**490NTC00005***(1)*	–
		49.21 (15)	**490NTC00015***(1)*	–
		131.23 (40)	**490NTC00040***(1)*	–
		262.47 (80)	**490NTC00080***(1)*	–

Connection to Modbus™ serial link

Description	Use		Length ft. (m)	Reference	Weight lb (kg)
	From	To			
Trunk cables, shielded dual twisted pair, RS 485	Compact safety PLCs XPSMF4020/MF4022 (RJ45)	Modbus splitter box LU9 GC3 (RJ45)	328 (100)	**TSXCSA100**	12.522 (5.680)
			656 (200)	**TSXCSA200**	24.030 (10.920)
			1640 (500)	**TSXCSA500**	66.139 (30.000)
	Graphic terminals XBTGT (SUB-D 9-pin)	Modbus splitter box LU9 GC3 (RJ45)	8.2 (2.5)	**XBTZ938***(2)*	0.474 (0.210)
Adaptor for cable XBTZ938	SUB-D 9-pin (XBTGT)	XBTZ938 (SUB-D 25-pin)	0.66 (0.2)	**XBTZG909**	–



Description	Specifications	Sold in lots of	Unit reference	Weight oz (kg)
End of line adaptors For RJ45 connector	R = 120 Ω, C = 1 nF	2	**VW3A8306RC**	7.055 (0.200)
	R = 150 Ω	2	**VW3A8306R**	0.353 (0.010)

PROFIBUS DP bus connection components

Description	Profile	Services	Reference	Weight oz (kg)
PROFIBUS DP module set for Premium™ PLCs	Master, 12 Mbps	Class 1 and Class 2 master V0 functions, see specifications. PROFIBUS FMS messaging not supported	**TSXPBY100**	30.688 (0.870)

Description	Use	Reference	Weight oz (kg)
Remote inputs/outputs on PROFIBUS DP bus	Advantys™ STB network interface module	**STBNDP2112**	4.938 (0.140)
	Momentum™ communication module	**170DTN11000**	–
Connectors for remote I/O communication module	Line terminators	**490NAD91103**	–
	Intermediate connection	**490NAD91104**	–
	Intermediate connection and terminal port	**490NAD91105**	–

TSXPBY100

Description	Length ft. (m)	Reference	Weight oz (kg)
PROFIBUS DP connecting cables	328 (100)	**TSXPBSCA100**	–
	1312 (400)	**TSXPBSCA400**	–

490NAD91103

Description	Reference	Weight oz (kg)
Replacement parts	Main bus junction box	**490NAE91100**	–
	PCMCIA card	**467NHP81100**	–

*(1) Cable conforming to standard EIA/TIA-568 category 5 and IEC 1180/EN 50 173 class D. For UL and CSA 22.1 approved cables, add the letter **U** to the end of the reference.*
*(2) Requires adaptor **XBTZG909**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Dimensions

XPSMF40●●



(1) 6.02 in (153 mm) with screw terminal block, 5.96 in (151.4 mm) with spring terminal block.
(2) Removable plate with spring mounting for mounting on 1.38 (35 mm) DIN rail.

Mounting

Mounting precautions relating to connectors

Access to Ethernet network	Access to Modbus™ serial link (RTU)	Access to Profibus DP bus
RJ45 socket (SafeEthernet protocol, Modbus TCP/IP server protocol)	RJ45 socket	Connector 490 NAD 911 03 in SUB-D 9-pin socket



r = 22.5 min.

r = 22.5 min.

Dual Dimensions: INCHES / Millimeters

Mounting in panel or enclosure



(1) Minimum recommended value.
(2) Prefabricated electrical ducting for passage of cables.

Mounting on Premium™ rack

Mechanical mounting only, without connection to either the back plane bus or to the Premium™ platform supply



1 Premium™ rack
2 Premium™ supply
3 Premium™ CPU
4 Premium™ I/O module
5 Safety PLC **XPSMF40●●** (occupies 2 slots)
6 Premium™ As-interface master

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact, XPSMF40

Connections



XPSMF4000/MF4002

XPSMF4000/MF4002, XPSMF4020/MF4022, XPSMF4040/MF4042

Item	Connection	Connector	Screw	Function
A	**Supply**	Supply	24 V	⎓ 24 V
			0 V	⎓ 24 V (reference pole)
			FE	Ground *(1)*
B	**Digital Inputs or Outputs**	Connector 1	S+	Supply to Inputs 1 to 4
			1	Input/Output 1
			2	Input/Output 2
			3	Input/Output 3
			4	Input/Output 4
			L-	Inputs/Outputs 1 to 4 common
		Connector 2	S+	Supply to Inputs 5 to 8
			5	Input/Output 5
			6	Input/Output 6
			7	Input/Output 7
			8	Input/Output 8
			L-	Inputs/Outputs 5 to 8 common
		Connector 3	S+	Supply to Inputs 9 to 12
			9	Input/Output 9
			10	Input/Output 10
			11	Input/Output 11
			12	Input/Output 12
			L-	Inputs/Outputs 9 to 12 common
		Connector 5	S+	Supply to Inputs 13 to 16
			13	Input/Output 13
			14	Input/Output 14
			15	Input/Output 15
			16	Input/Output 16
			L-	Inputs/Outputs 13 to 16 common
		Connector 6	S+	Supply to Inputs 17 to 20
			17	Input/Output 17
			18	Input/Output 18
			19	Input/Output 19
			20	Input/Output 20
			L-	Inputs/Outputs 17 to 20 common
		Connector 7	S+	Supply to Inputs 21 to 24
			21	Input/Output 21
			22	Input/Output 22
			23	Input/Output 23
			24	Input/Output 24
			L-	Inputs/Outputs 21 to 24 common
C	**Line control outputs**	Connector 4	L-	Outputs 1 to 4 common
			1	Line control Output 1 (T1)
			2	Line control Output 2 (T2)
			3	Line control Output 3 (T3)
			4	Line control Output 4 (T4)
			L-	Outputs 1 to 4 common
		Connector 8	L-	Outputs 5 to 8 common
			5	Line control Output 5 (T5)
			6	Line control Output 6 (T6)
			7	Line control Output 7 (T7)
			8	Line control Output 8 (T8)
			L-	Outputs 5 to 8 common

(1) Grounded when mounting on plate or rail.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Connections *(continuous)*



XPSMF4020/MF4022



XPSMF4040/MF4042

XPSMF4000/MF4002, XPSMF4020/MF4022, XPSMF4040/MF4042

Item	Connection	Type	Function
D	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and the programming terminal in a point to point or via an Ethernet network for programming, or setting an IP address.
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.
	Non-Safe Communication available with references: XPSMF4002, XPSMF4022, XPSMF4042		Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other non- safety related components (e.g HMI Magelis™, standard PLCs, and Scada systems) this can be established in a point to point way or via an Ethernet network.
XPSMF4020/MF4022			
E	**Communication**	RJ45 (Modbus™)	**XPSMF4020/MF4022**: slaves on Modbus serial (RTU)
XPSMF4040/MF4042			
F	**Communication**	SUB-D 9-pin female (Profibus)	**XPSMF4040/MF4042**: slaves on PROFIBUS DP

Connections examples

Actuator connections to the outputs



Emergency stop connections (line control)



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact, XPSMF31/30/35

XPSMF31222

XPSMF3022

XPSMF35●●

*Products referenced **XPSMF31222, XPSMF3022** and **XPSMF35●●** are marked **HIMatrix® F31**, **HIMatrix® F30** and **HIMatrix® F35** (manufactured by Hima, sold by Schneider Electric).*

Introduction

Preventa™ compact safety PLCs **XPSMF31/30/35** enable the monitoring of simple to complex safety functions for all industrial applications relating to the protection of personnel and machine safety.

Designed for use with numerous machine safety functions, these compact safety PLCs are intended for use in safety related parts of control systems.
They can manage up to:
- category 4 conforming to EN 954-1,
- performance level “e” conforming to EN/ISO 13849-1,
- SIL 3 (safety integrity level) conforming to EN/IEC 61508.

The compact safety PLC range **XPSMF31/30/35** comprises 5 versions that are differentiated by their specifications, detailed below.

Compact PLCs	Inputs			Outputs Digital	Communication	
	Digital	Analog	Counter		On Ethernet network	On fieldbus
XPSMF31222	20	–	–	8 *(1)*	For all compact PLCs XPSMF31/30/35 using SafeEthernet safety protocol, and with non safety protocol Modbus™ TCP/IP server	–
XPSMF3022	20	–	–	8 *(1)*		Modbus serial Slave (RTU)
XPSMF3502	24	8	2	8		–
XPSMF3522	24	8	2	8		Modbus serial Slave (RTU)
XPSMF3542	24	8	2	8		PROFIBUS DP V0 slave

Safety PLCs

In order to meet safety requirements, the compact safety PLCs **XPSMF31/30/35** incorporate two essential functions (**Redundancy** and **Self-monitoring)** complying to category 4 conforming to EN 954-1 and performance level “e” conforming to EN/ISO 13849-1 in addition to the SafeEthernet safety communication protocol between the safety PLCs and the safety remote I/O modules (**Special Switch**).

■ **Redundancy**: the dual processor integrated in the compact safety PLCs analyzes and compares the data received from the safety inputs and outputs.
The incoming and outgoing data (programmed values and received values) are received in parallel by the two processors and compared in real-time.

■ **Self-monitoring (“Watchdog”)**: the compact safety PLCs continuously monitor the data processing cycle and the execution of tasks, and intervenes if the cycle time does not conform to the predefined value.

■ **The integrated switch (Special Switch)** stores for a very short time and sends at very high speed the data provided by the inputs and outputs of the safety PLCs on the Ethernet network, while avoiding signal collisions and excessive amounts of data on the network.

Functional diagrams

Compact safety PLC XPSMF31222



(1) Digital outputs can be configured for line control.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact, XPSMF31/30/35

Functional diagrams *(continued)*

Compact safety PLC XPSMF3022



Compact safety PLCs XPSMF35●●



Line control for XPSMF31222 and XPSMF3022

Line control is a means of short-circuit and line break monitoring.
Using line control outputs enables SIL 3 (EN/IEC 61508) and category 4 (EN 954-1) safety to be achieved. The line control outputs send a high signal with a very short low signal, thus enabling a wiring anomaly (short-circuit, line break) to be seen at the inputs of the safety PLC inputs.

Digital outputs 1 to 8 are connected to the digital inputs of the same circuit.

Example: Emergency stop pushbutton with two normally closed (N.C.) contacts that are supplied by two different line control outputs connected via these two normally closed contacts and fed into the inputs of the safety PLCs.

Programming automated safety functions

Software **XPSMFWIN** (reference SSV1XPSMFWIN) running on a PC enables the programming of all safety remote I/O modules and safety PLCs, as well as configuration of the communication settings.

(1) Digital outputs can be configured for line control.
(2) FB1 and FB2 not used.
*(3) FB3 not available on safety PLC **XPSMF3502**.*
(4) Depending on model.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact, XPSMF31/30/35

Digital inputs

Compact safety PLCs **XPSMF3●●●●** incorporate up to 24 digital inputs for the connection of safety related input devices.

Compact PLCs	Digital inputs		
	N°	Safety detection	Safety dialog
XPSMF31222	20	Limit switches, Guard switches, with reset and with actuator, Light curtains type 2 and type 4, Safety mats and sensing edges	Mushroom head Emergency stops, Enclosures for control and signalling units, Two-hand control stations
XPSMF3022	20		
XPSMF3502	24		
XPSMF3522	24		
XPSMF3542	24		

Analog inputs

Compact safety PLCs **XPSMF35●●** incorporate 8 analog measuring inputs that receive analog safety related signals from the machines to be monitored *(1)*.

Compact PLCs	Analog inputs with transmitter supply	
	N°	Functions
XPSMF3502	8	Closed circuit scanning of input channels, Single-pole measuring of 0 to 10 V voltages, Measuring 0 to 20 mA currents using jumper
XPSMF3522	8	
XPSMF3542	8	

Counter inputs

Compact safety PLCs **XPSMF35●●** incorporate 2 independent and configurable counting channels:

- as a counting function, independent to the direction of counting,
- as a counting function, dependent to the direction of counting,
- or as a counting function via an absolute encoder with Gray code.

Compact PLCs	Counting inputs		
	N°	⎓ 5 V	⎓ 24 V
XPSMF3502	2	Incremental encoders	Sensors, 2/3-wire PNP/NPN
XPSMF3522	2		
XPSMF3542	2		

Digital outputs

All compact safety PLCs **XPSMF●●●●** incorporate 8 digital outputs for connection to signalling equipment and machines to be controlled *(1)*.

Compact PLCs	Digital outputs		
	N°	Safety actuators	Safety dialog
XPSMF31222	8	Contactors-motors, Control relays, Variable speed drives.	Beacons and indicator banks, Rotating mirror beacons, Sirens
XPSMF3022	8		
XPSMF3502	8		
XPSMF3522	8		
XPSMF3542	8		

Remote inputs and outputs

In addition to the inputs/outputs integrated as standard, compact safety PLCs **XPSMF31/30/35** can be connected to safety remote input modules **XPSMF1** and/or safety remote output modules **XPSMF2** and/or safety remote mixed I/O modules **XPSMF3**.
The safety remote input, output and mixed I/O modules can be located within the vicinity of the machines to be monitored, thus reducing cabling.
Communication between these safety remote I/O modules and compact safety PLCs **XPSMF31/30/35** is performed on an Ethernet network using the SafeEthernet safety protocol, via the Integrated RJ45 switched Ethernet communications ports.

(1) Use shielded dual twisted pair cables, maximum length 984.2 ft (300 m), short-circuit unused analog inputs.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety communication on Ethernet network

Communication between the PC, Magelis™ graphic terminal or automation platform (Premium™) and the compact safety PLCs is achieved by **Ethernet** network connection via the Integrated RJ45 switched Ethernet communications ports of compact PLCs **XPSMF31/30/35**.



1 Premium™ automation platform: Modbus™ TCP/IP client.
2 Graphic terminal **XBTGT**: Modbus TCP/IP client.
3 Safety PLC **XPSMF31/30/35**: Modbus TCP/IP server.
4 Safety remote I/O modules **XPSMF1/2/3**. They communicate with safety PLCs **XPSMF31/30/35** using the SafeEthernet protocol.

Communication on Modbus serial (RTU) and PROFIBUS DP fieldbus

■ On **Modbus serial (RTU)**, safety PLCs **XPSMF3022** and **XPSMF3522** are slaves of the Premium™ automation platform and Magelis graphic terminals.
They are connected to the Modbus serial network via their SUB-D 9-pin connector (FB3).



1 Graphic terminal **XBTGT**: Modbus serial (RTU) master.
2 Premium™ automation platform: Modbus serial (RTU) master.
3 Graphic terminal **XBTGT**: Modbus serial (RTU) client.
4 Safety PLC **XPSMF3022** or **XPSMF3522**: Modbus serial (RTU) slave, Modbus TCP/IP server.
5 Safety remote I/O modules **XPSMF1/2/3**. They communicate with safety PLCs **XPSMF3●●2** using the SafeEthernet protocol.

■ On **PROFIBUS DP**, safety PLC **XPSMF3542** is a slave of the Premium™ automation platform and Magelis™ graphic terminal.
It is connected to the PROFIBUS DP network via its SUB-D 9-pin connector (FB3).



1 Premium™ automation platform: PROFIBUS DP master.
2 Graphic terminal **XBTGT**: PROFIBUS DP master.
3 Safety PLC **XPSMF3542**: PROFIBUS DP slave, Modbus TCP/IP server.
4 Safety remote I/O modules **XPSMF1/2/3**. They communicate with safety PLC **XPSMF3542** using the SafeEthernet protocol.
5 Graphic terminal **XBTGT**: Modbus TCP/IP client.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact, XPSMF31/30/35



Description

Safety PLCs XPSMF31222 and XPSMF3022

On the front cover of the metal enclosure:

1 One terminal block *(1)* for ⎓ 24 V supply.
2 Two terminal blocks *(1)* for connection of digital outputs, with output status LED (four LEDs per terminal block).
3 Five terminal blocks *(1)* for connection of digital inputs, with input status LED (four LEDs per terminal block).
4 Eight process status LEDs.
5 Four integrated RJ45 (type 10BASE-T/100BASE-TX) switched ports for programming, and for Safety and non-safety related communication on Ethernet (safety related using SafeEthernet protocol and Non-safety related using Modbus™ TCP/IP server protocol).
6 On **XPSMF3022** only: two unused SUB-D connectors (FB1 and FB2).
7 On **XPSMF3022** only: one SUB-D 9-pin connector for connection on Modbus serial (RTU) (FB3).
8 One ground connection screw.
9 On the top: one “Reset” button.
10 On the rear face: one spring operated mounting device for mounting on 35 mm DIN rail.



Safety PLCs XPSMF35●●

On the front cover of the metal enclosure:

1 One terminal block *(1)* for ⎓ 24 V supply.
2 One terminal block *(1)* for connection of digital outputs, with four digital output status LEDs.
3 Three terminal blocks *(1)* for connection of digital inputs, with input status LED (eight LEDs per terminal block).
4 One terminal block *(1)* for connection of 2 counting input channels.
5 Four terminal blocks *(1)* for connection of analog inputs.
6 One plate for securing shielded analog input connection cables.
7 Eight process status LEDs.
8 Two unused SUB-D connectors (FB1 and FB2).
9 Four integrated RJ45 (type 10BASE-T/100BASE-TX) switched ports for programming, and for Safety and non-safety related communication on Ethernet (safety related using SafeEthernet protocol and Non-safety related using Modbus TCP/IP server protocol).
10 One type SUB-D 9-pin connector (FB3) for connection on PROFIBUS DP (**XPSMF3542**) or Modbus serial (RTU) (**XPSMF3522**).
11 One ground connection screw.
12 On the top: one “Reset” button.
13 On the rear face: one spring operated mounting device for mounting on 35 mm DIN rail.

*(1) Removable screw terminals are provided with compact safety PLCs **XPSMF31/30/35**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Status LED details

Compact safety PLCs XPSMF31222, XPSMF3022 and XPSMF35●●

LED	Color	Status	Meaning
FB1, FB2	–	–	Not used.
FB3	Orange	On	Communication on Modbus™ serial or PROFIBUS DP *(1)* active.
Inputs 1 to 20	Orange	On	Inputs active.
Outputs 1 to 8	Orange	On	Outputs active.
24 VDC	Green	On	⎓ 24 V voltage present.
		Off	No voltage.
RUN	Green	On	Normal service mode, loaded program running, the PLC receives I/O messages, communication and hardware/software tests carried out.
		Flashing	The CPU is in STOP and is not executing any user application. All the outputs are reset to a safe, de-energized state.
		Off	The CPU is in "ERROR" state (see ERROR).
ERROR	Red	On	Software error or hardware anomaly detected by the CPU.
			The monitoring program (Watchdog) has triggered the STOP state of the process because the programmed cycle time has been exceeded.
			The CPU has stopped the execution of the user application, ended all hardware and software tests and all outputs have been reset.
			The process can only be started again from the PC.
		Off	No errors detected.
PROG	Orange	On	The CPU is being loaded with a new configuration.
		Flashing	The FLASH ROM is being loaded with a new operating system.
		Off	No loading of configuration or operating system.
FORCE	Orange	On	The CPU is in RUN mode and force is active.
		Flashing	The system is not processing (STOP), but force is prepared and is activated if the dual processor is started.
		Off	Force mode not activated.
FAULT	Orange	On	Error display for line control.
			The user application has caused an error.
			The system configuration is defective.
			The loading of a new operating system was defective and the operating system is corrupt.
		Flashing	An error has occurred while writing to FLASH ROM memory (during updating of the operating system).
			One or more I/O errors have occurred.
		Off	None of the above errors have occurred.
OSL	Orange	Flashing	Emergency loading of the operating system is active.
BL	Orange	Flashing	COM in INIT_Fail state.
RJ45	Green	On	Full duplex mode operation.
		Flashing	Signal collision.
		Off	Half duplex mode operation, no collision.
	Yellow	On	Connection established.
		Flashing	Interface active.

(1) Depending on PLC model.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact, XPSMF31/30/35

Environment

Compact safety PLC type			XPSMF31222	XPSMF3022	XPSMF3502, XPSMF3522, XPSMF3542
Products designed for max. use in safety related parts of control systems (conforming to EN 954-1, EN/ISO 13849-1 and EN/IEC 61508)			Category 4 (EN 954-1), Performance level "e" (EN/ISO 13849-1), Safety integrity level: SIL 3 (EN/IEC 61508)		
Product certifications			IEC 61511: 2004, DIN VDE 0116: 1989, EN 50156-1: 2004, EN 12067-2: 2004, EN 298: 2003, EN 230: 1990, NFPA 85: 2001, EN/IEC 61131-2: 2003, EN 61000-6-2: 2001, EN 61000-6-4: 2001		IEC 61511: 2004, DIN VDE 0116: 1989, EN 50156-1: 2004, EN 12067-2: 2004, EN 298: 2003, EN 230: 1990, NFPA 85: 2001, EN/IEC 61131-2: 2003, EN 61000-6-2: 2001, EN 61000-6-4: 2001, EN 54-2: 1997, NFPA 72: 2002
Ambient air temperature conforming to EN 61131-2	For operation	**°F(°C)**	+32… + 140 (0…+ 60)		
	For storage	**°F(°C)**	-40… + 185 (- 40…+ 85)		
Relative humidity			95% (supply not connected)		
Degree of protection	Enclosure		IP 20		
Pollution			Degree of pollution II		
Altitude			6560 ft (2000 m)		
Protection class			Class II, conforming to EN/IEC 61131-2		
Electromagnetic compatibility			Conforming to IEC 61131-2		
Vibration resistance conforming to EN 61131-2	Operating		1 g, frequency 9…150 Hz		
Shock resistance conforming to EN 61131-2	Operating		15 g (duration 11 ms), unit test while operating, 2 cycles per axis		
Resistance to electrostatic discharges conforming to EN/IEC 61000-4-2		**kV**	4 contact, 8 air discharge		
Immunity to high frequency interference conforming to EN/IEC 61000-4-3		**V/m**	10 (80 MHz…2 GHz), amplitude modulation 80%		

Electrical specifications

Supply	Voltage	**V**	⎓ 24 (external supply with separate protection conforming to EN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)		
	Voltage limits		- 15…+ 20%		
Maximum power consumption		**A**	8	8	9
Idle current		**A**	0.4	0.5	0.75
Immunity to momentary supply interruptions		**ms**	10		
Protection			Internal fuse		
Response time		**ms**	Depending on size of application		
Clock			Supplied by backup capacitor for 1 week following loss of supply		
User memory	Application	**kB**	250		
	Data	**kB**	250		
LED display			Yes		
Digital inputs					
Number	Inputs not electrically isolated		20		24
Permissible current	At state 0	**mA**	1.5 max., 1 mA at 5 V	1.5 max., 1.25 mA at 5 V	1.5 max., 1 mA at 5 V
	At state 1	**mA**	≥ 2 at ⎓ 15 V	> 2 at ⎓ 15 V	Approx. 3.5 at ⎓ 24 V Approx. 4.5 at ⎓ 30 V
Input supply			5 x 20 V/100 mA (on 24 V)		20 V/100 mA
Input protection			Protected against short-circuits, short-circuits to ground		
Overvoltage protection		**V**	500, conforming to IEC 61000-4-5		
Switching point		**V**	Typically 7.5		–
Current		**mA**	> 2 (⎓ 15 V)		–
LED display			Yes		
Maximum distance of equipment			328 ft (100 m)		
Digital outputs					
Number	Outputs not electrically isolated		8, configurable for line control		8
Output voltage		**V**	⎓ 24 ± 2		
Output current	Channels 1 to 3 and 5 to 7	**A**	0.5 at 140 °F (60 °C)		
	Channels 4 and 8	**A**	1 at 140 °F (60 °C), 2 at 122 °F (50 °C)		
Minimum load		**mA**	2 per channel		
Leakage current at state 0		**mA**	1 max. at 2 V		
Response to overload			Shutdown of outputs concerned with cyclic reconnection		
Total output current		**A**	7 max., shutdown of all outputs if exceeded with cyclic reconnection		
LED display			Yes		
Maximum distance of equipment			328 ft (100 m)		

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Electrical specifications *(continued)*

Compact safety PLC type			XPSMF3502, XPSMF3522, XPSMF3542		
Analog inputs					
Number	Inputs not electrically isolated		8, single-pole		
External jumper		Ω	250 or 500 depending on application		
Input values	Nominal value	**V**	⎓ 0…10		
		mA	0…20, with 500 Ω jumper		
	Service value	**V**	⎓ 0.1…11.5		
		mA	0/4…23, with 500 Ω jumper		
Input impedance		**MΩ**	1		
Maximum distance of equipment		**m**	300		
Internal resistance of signal source		Ω	⩽ 500		
Overvoltage protection		**V**	+ 15, - 4		
Resolution (A/D converter)			12-bit		
Safety accuracy			± 2%		
LED display			Yes		
Counting inputs					
Number	Counter		2, not electrically isolated		
	Inputs		3 on each pole (A, B, Z)		
Input voltages	High threshold 5 V	**V**	4…6		
	High threshold 24 V	**V**	13…33		
	Low threshold 5 V	**V**	0…0.5		
	Low threshold 24 V	**V**	- 3…5		
Input currents		**mA**	1.4 at 5 V 6.5 at 24 V		
Input impedance		**kΩ**	3.7		
Maximum distance of equipment			1640 ft (500 m), with shielded dual twisted pair cable		
Up/down counting resolution			24-bit		
Input frequency		**kHz**	100, at 5 and 24 V		
Triggering			On falling edge		
Edge steepness		**V/µs**	1		
LED display			Yes		

Communication

Compatibility			XPSMF31222	XPSMF3022	XPSMF3502, XPSMF3522, XPSMF3542
Ethernet network: safety communication using SafeEthernet protocol					
Transmission	Communication ports		Integrated 4 RJ45 switched Ethernet communications ports		
	Baud rate	**Mbps**	100 Half duplex, 10 Full duplex, Autonegotiation		
Structure			10BASE-T/100BASE-TX		
Medium			Dual twisted pair cable, category 5D or better (Ethernet)		
Ethernet network: Non-safety related communication using Modbus™ TCP/IP protocol					
Connection Ports	Number and type		Integrated 4 RJ45 switched Ethernet communication ports		
	Baud rate	**Mbps**	100 Half Duplex, 10 Full Duplex, Autonegotiation		
	Master/Slave		Server (slave)		
Structure			10BASE-T/100BASE-TX		
Medium			Dual twisted pair cable, category 5D or better (Ethernet)		
Transparent Ready™ Services	Class		A10		
	Standard Ethernet TCP/IP communication services		Modbus TCP/IP Server		
			Modbus TCP/IP messaging (reading/writing of data words)		
			Modbus identification request		
	TCP port		Standard 502		
	Max. number of Modbus TCP/IP connections		1 to 20		
Modbus serial (RTU)					
Serial link ports	Number and type		–	1 x SUB-D 9-pin female (FB3)	
	Master/Slave		–	Slave	
Addressing			–	122 slave addresses	
Physical layer			–	RS 485	
Medium			–	Shielded dual twisted pair cable	
PROFIBUS DP					
Serial link ports	Number and type		–	–	1 x SUB-D 9-pin female
	Master/Slave		–	–	Slave, V0
Physical layer			–	–	RS 485
Medium			–	–	Shielded dual twisted pair cable

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Connections *(1)*

Safety PLC type			XPSMF31222	XPSMF3022	XPSMF3502, XPSMF3522, XPSMF3542
Type of connection			Screw clamp terminal blocks *(2)*		
Supply connection	Number of terminal blocks		1		
	For 1 cable without cable end		Solid or flexible AWG 24-12 (0.2…2.5 mm^2)		
	For 1 flexible cable with or without plastic cable end		AWG 22-16 (0.25…2.5 mm^2)		
	For 2 cables of same diameter, without cable end		Solid or flexible AWG 24-12 (0.2…1.5 mm^2)		
	For 2 cables of same diameter, flexible without cable end		AWG 22-18 (0.25…1.0 mm^2)		
	For 2 cables of same diameter, flexible with plastic cable end		AWG 22-16 (0.5…1.5 mm^2)		
Digital input channel and output channel connection	Number of terminal blocks		5 (inputs) and 2 (outputs)	5 (inputs) and 2 (outputs)	3 (inputs) and 1 (output)
	For 1 cable without cable end		Solid or flexible AWG 28-16 (0.14…1.5 mm^2)		
	For 1 flexible cable without cable end		AWG 22-16 (0.25…1.5 mm^2)		
	For 1 flexible cable with plastic cable end		AWG 22-20 (0.25…0.5 mm^2)		
	For 2 cables of same diameter, without cable end		Solid: AWG 28-20 (0.14…0.5 mm^2) Flexible: AWG 28-18 (0.14…0.75 mm^2)		
	For 2 cables of same diameter, flexible without cable end		AWG 22 (0.25…0.34 mm^2)		
	For 2 cables of same diameter, flexible with plastic cable end		AWG 20 (0.5 mm^2)		
Analog input channel connection	Number of terminal blocks		–	–	4
	For 1 cable without cable end		–	–	Solid or flexible AWG 28-16 (0.14…1.5 mm^2)
	For 1 flexible cable without cable end		–	–	AWG 22-16 (0.25…1.5 mm^2)
	For 1 flexible cable with plastic cable end		–	–	AWG 22-20 (0.25…0.5 mm^2)
	For 2 cables of same diameter, without cable end		–	–	Solid: AWG 28-20 (0.14…0.5 mm^2) Flexible: AWG 28-18 (0.14…0.75 mm^2)
	For 2 cables of same diameter, flexible without cable end		–	–	AWG 22 (0.25…0.34 mm^2)
	For 2 cables of same diameter, flexible with plastic cable end		–	–	AWG 20 (0.5 mm^2)
Counting channel connection	Number of terminal blocks		–	–	1
	For 1 cable without cable end		–	–	Solid or flexible AWG 28-16 (0.14…1.5 mm^2)
	For 1 flexible cable without cable end		–	–	AWG 22-16 (0.25…1.5 mm^2)
	For 1 flexible cable with plastic cable end		–	–	AWG 22-20 (0.25…0.5 mm^2)
	For 2 cables of same diameter, without cable end		–	–	Solid: AWG 28-20 (0.14…0.5 mm^2) Flexible: AWG 28-18 (0.14…0.75 mm^2)
	For 2 cables of same diameter, flexible without cable end		–	–	AWG 22 (0.25…0.34 mm^2)
	For 2 cables of same diameter, flexible with plastic cable end		–	–	AWG 20 (0.5 mm^2)
Cable connection	Tightening torque		1.9…2.2 lb-in (0.22…0.25 Nm)		
	Bared length		0.35 in. (9 mm)		

(1) AWG: American Wire Gauge.
*(2) Removable screw terminals are provided with compact safety PLCs **XPSMF31/30/35**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact, XPSMF31/30/35

XPSMF31222

XPSMF3022

XPSMF35●●

*Products referenced **XPSMF31222, XPSMF3022** and **XPSMF35●●** are marked **HIMatrix® F31**, **HIMatrix® F30** and **HIMatrix® F35** (manufactured by Hima, sold by Schneider Electric).*

Compact safety PLCs

⎓ **24 V supply**

Inputs			Outputs Digital	Communication on				Reference	Weight oz (kg)
				Ethernet network		Modbus™ serial (RTU)	PROFIBUS DP		
Digital	Analog	Counting		Safe Ethernet protocol	Modbus TCP/IP server protocol				
20	–	–	8	Yes	Yes	–	–	**XPSMF31222**	35.273 (1.000)
						Yes Slave	–	**XPSMF3022**	42.328 (1.200)
24	8	2	8	Yes	Yes	–	–	**XPSMF3502**	42.328 (1.200)
						Yes Slave	–	**XPSMF3522**	42.328 (1.200)
						–	Yes slave	**XPSMF3542**	42.328 (1.200)

Configuration software

■ Reference **SSV1XPSMFWIN contains the full version of the programming software XPSMFWIN software for the XPSMF Safety PLCs. The XPSMFWIN is part of our Safety Suite and is not available seperately.**

Description	Operating system	Details	Languages	Reference	Weight oz (kg)
Configuration software XPSMFWIN for programming compact safety PLCs CD-ROM + user manual	Windows® 2000, Windows® XP	Software available on Safety Suite V2 software pack	English, German, French	**SSV1XPSMFWIN**	18.342 (0.520)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact, XPSMF31/30/35

ABL8RPS24050

ABL1REM24025

XBTGT2130, XBTGT2330

XBTGT4330

XBTGT5●30

XBTGT6330

XBTGT7340

Phaseo™ regulated switch mode power supplies

Mains input voltage	Output voltage	Nominal power	Nominal current	Auto-protect reset	Conformity to standard IEC EN 61000-3-2 and IEC EN 60950	Reference	Weight
V	⎓ V	W	A				oz (kg)
Universal range, single-phase (N-L1) **or 2-phase** (L1-L2) **connection**							
∿ **100…120 V/200...500** - 15%, + 10% 50/60 Hz	24...28.8	72	3	Auto/Manual	Yes	**ABL8RPS24030**	10.582 (0.300)
		120	5	Auto/Manual	Yes	**ABL8RPS24050**	24.692 (0.700)
		240	10	Auto/Manual	Yes	**ABL8RPS24100**	35.273 (1.000)
Dedicated range, single-phase connection							
∿ **100…240** *(1)* wide range, 47…63 Hz	12	60	5	Auto	No	**ABL1REM12050**	15.521 (0.440)
	24	60	2,5	Auto	No	**ABL1REM24025**	15.521 (0.440)
∿ **100...120/200...240** *(2)*	24	240	10	Auto	No	**ABL1REM24100**	31.041 (0.880)

Magelis™ multifunction graphic terminals with touch sensitive screen and on-board Ethernet *(1) (2)*

Supply voltage ⎓ 24 V

Description		Ports: serial and communication (type of link)	Application memory	Reference	Weight oz (kg)
5.7"	Monochrome black and white STN	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 1 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	16 Mb	**XBTGT2130**	35.273 (1.000)
	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 1 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	16 Mb	**XBTGT2330**	35.273 (1.000)
7.5"	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 1 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT4330**	63.493 (1.800)
10.4"	Color STN	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT5230**	105.822 (3.000)
	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT5330**	105.822 (3.000)
12.1"	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT6330**	105.822 (3.000)
15"	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT7340**	197.534 (5.600)

(1) Service instructions, USB connectors locking device and mounting kit included.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

490 NTW 000●●

Connecting cables for network and bus

Connection to Ethernet network

Description	Pre-fitted connectors	Length ft (m)	Reference	Weight oz (kg)
Shielded twisted pair cables, straight through	2 RJ45 connectors For connection to DTE (Data Terminal Equipment)	6.6 (2)	**490NTW00002***(1)*	–
		16.4 (5)	**490NTW00005***(1)*	–
		39.4 (12)	**490NTW00012***(1)*	–
		131.2 (40)	**490NTW00040***(1)*	–
		262.5 (80)	**490NTW00080***(1)*	–
Shielded twisted pair cables, crossed wires	2 RJ45 connectors For connection between hubs, switches and transceivers	16.4 (5)	**490NTC00005***(1)*	–
		49.2 (15)	**490NTC00015***(1)*	–
		131.2 (40)	**490NTC00040***(1)*	–
		262.5 (80)	**490NTC00080***(1)*	–

Connection to Modbus™ serial link

Description	Use		Length ft. (m)	Reference	Weight oz (kg)
	From	To			
Modbus serial link connecting cables	Compact PLCs XPSMF3022/3522 + adaptor XPSMFADAPT (RJ45)	Modbus splitter box LU9 GC3 (RJ45)	1.0 (0.3)	**VW3A8306R03**	0.882 (0.025)
			3.28 (1)	**VW3A8306R10**	2.116 (0.060)
			9.84 (3)	**VW3A8306R30**	74.640 (1.130)
		Premium™ module TSX SCY 21601 (SUB-D 25-pin)	1.0 (0.3)	**XPSMCSCY**	–
	Graphic terminals XBTGT (SUB-D 9-pin)	Modbus splitter box LU9 GC3 (RJ45)	8.2 (2.5)	**XBTZ938***(2)*	7.408 (0.210)
Adaptor for cable XBTZ938	SUB-D 9-pin (XBTGT)	XBTZ938 (SUB-D 25-pin)	0.66 (0.2)	**XBTZG909**	–
Adaptor SUB-D 9-pin/RJ45	Compact PLCs (SUB-D 9-pin)	Connecting cables for Modbus serial link (RJ45)	–	**XPSMFADAPT**	–



TSX PBY 100

Description	Specifications	Sold in lots of	Unit reference	Weight oz (kg)
End of line adaptors For RJ45 connector	R = 120 Ω, C = 1 nF	2	**VW3A8306RC**	7.055 (0.200)
	R = 150 Ω	2	**VW3A8306R**	0.353 (0.010)

PROFIBUS DP bus connection components

Description	Profile	Services	Reference	Weight oz (kg)
PROFIBUS DP module set for Premium™ PLCs	Master, 12 Mbps	Class 1 and Class 2 master V0 functions, see specifications. Profibus FMS messaging not supported	**TSXPBY100**	30.688 (0.870)

Description	Use	Reference	Weight oz (kg)
Remote inputs/outputs on PROFIBUS DP bus	Advantys™ STB network interface module	**STBNDP2112**	4.938 (0.140)
	Momentum™ communication module	**170DTN11000**	–
Connectors for remote I/O communication module	Line terminators	**490NAD91103**	–
	Intermediate connection	**490NAD91104**	–
	Intermediate connection and terminal port	**490NAD91105**	–

Description	Length (m)	Reference	Weight oz (kg)
PROFIBUS DP connecting cables	100	**TSXPBSCA100**	–
	400	**TSXPBSCA400**	–

490 NAD 911 03

Description		Reference	Weight oz (kg)
Replacement parts	Main bus junction box	**490NAE91100**	–
	PCMCIA card	**467NHP81100**	–

*(1) Cable conforming to standard EIA/TIA-568 category 5 and IEC 1180/EN 50 173 class D. For UL and CSA 22.1 approved cables, add the letter **U** to the end of the reference.*
(2) Requires adaptor XBTZG909.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Dimensions

XPSMF31222



*(1) Removable screw terminals are provided with compact safety PLC **XPSMF31222**.*

XPSMF3022



*(1) Removable screw terminals are provided with compact safety PLC **XPSMF3022**.*

XPSMF35●●



Dual Dimensions: INCHES / Millimieters

*(1) Removable screw terminals are provided with compact safety PLC **XPSMF35●●**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Mounting

Mounting precautions relating to connectors

Access to Modbus™ serial link (RTU)

SUB-D 9-pin connector



Adaptor XPSMFADAPT



Access to PROFIBUS DP

Connector 490NAD91103



Access to Ethernet network

RJ45 socket (SafeEthernet protocol, Modbus TCP/IP server protocol)



Dual Dimensions: INCHES
Millimieters

Mounting in panel or enclosure





(1) Prefabricated electrical ducting for passage of cables.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact, XPSMF31/30/35

Connections

XPSMF31222, XPSMF3022



Item	Connection	Screw N°	Screw	Function
A1	**Supply**	–	L+	⎓ 24 V
			L+	⎓ 24 V
			L-	⎓ 24 V (reference pole)
			L-	⎓ 24 V (reference pole)
A2	**Ground**		⏚	Ground
B	**Outputs Digital**	1	L-	Outputs common
		2	1	Output 1
		3	2	Output 2
		4	3	Output 3
		5	4	Output 4 (for increased load)
		6	L-	Outputs common
C	**Outputs Digital**	7	L-	Outputs common
		8	5	Output 5
		9	6	Output 6
		10	7	Output 7
		11	8	Output 8 (for increased load)
		12	L-	Outputs common
D	**Inputs Digital**	13	LS+	Sensor supply for inputs 1 to 4
		14	1	Digital input 1
		15	2	Digital input 2
		16	3	Digital input 3
		17	4	Digital input 4
		18	L-	Inputs common
E	**Inputs Digital**	19	LS+	Sensor supply for inputs 5 to 8
		20	5	Digital input 5
		21	6	Digital input 6
		22	7	Digital input 7
		23	8	Digital input 8
		24	L-	Inputs common
F	**Inputs Digital**	25	LS+	Sensor supply for inputs 9 to 12
		26	9	Digital input 9
		27	10	Digital input 10
		28	11	Digital input 11
		29	12	Digital input 12
		30	L-	Inputs common

Item	Connection	Screw N°	Screw	Function
G	**Inputs Digital**	31	LS+	Sensor supply for inputs 13 to 16
		32	13	Digital input 13
		33	14	Digital input 14
		34	15	Digital input 15
		35	16	Digital input 16
		36	L-	Inputs common
H	**Inputs Digital**	37	LS+	Sensor supply for inputs 17 to 20
		38	17	Digital input 17
		39	18	Digital input 18
		40	19	Digital input 19
		41	20	Digital input 20
		42	L-	Inputs common

Item	Connection	Type	Function
K	**Communication**	SUB-D 9-pin (FB3)	**XPSMF3022**: slave on Modbus™ serial (RTU)
J	**Programming**	Integrated 4 RJ45 switched Ethernet Communication ports	Either of the four switched Ethernet ports can be used to create a connection between the safety PLC and the programming terminal in a point to point or via an Ethernet network for programming, or setting an IP address.
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the four switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.
	Non-Safe Communication available with references: XPSMF3022, and XPSMF31222		Either of the four switched Ethernet ports can be used to create a connection between the safety PLC and other non- safety related components (e.g HMI Magelis™, standard PLCs, and Scada systems) this can be established in a point to point way or via an Ethernet network.

Connection examples

Actuator connections to the outputs



Emergency stop connections (line control)



Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Connections

XPSMF35●●



Item	Connection	Screw N°	Screw	Function
A1	**Supply**	–	L+	⎓ 24 V
			L+	⎓ 24 V
			L-	⎓ 24 V (reference pole)
			L-	⎓ 24 V (reference pole)
A2	**Ground**	–	⏚	Ground
B	**Outputs - Digital**	1	L-	Outputs common
		2	1	Digital output 1
		3	2	Digital output 2
		4	3	Digital output 3
		5	4	Digital output 4 (for increased load)
		6	5	Digital output 5
		7	6	Digital output 6
		8	7	Digital output 7
		9	8	Digital output 8 (for increased load)
		10	L-	Outputs common
C	**Inputs - Digital**	11	LS+	Sensor supply for inputs 1 to 8
		12	1	Digital input 1
		13	2	Digital input 2
		14	3	Digital input 3
		15	4	Digital input 4
		16	5	Digital input 5
		17	6	Digital input 6
		18	7	Digital input 7
		19	8	Digital input 8
		20	L-	Inputs common
D	**Inputs - Digital**	21	LS+	Sensor supply for inputs 9 to 16
		22	9	Digital input 9
		23	10	Digital input 10
		24	11	Digital input 11
		25	12	Digital input 12
		26	13	Digital input 13
		27	14	Digital input 14
		28	15	Digital input 15
		29	16	Digital input 16
		30	L-	Inputs common
E	**Inputs - Digital**	31	LS+	Sensor supply for inputs 17 to 24
		32	17	Digital input 17
		33	18	Digital input 18
		34	19	Digital input 19
		35	20	Digital input 20
		36	21	Digital input 21
		37	22	Digital input 22
		38	23	Digital input 23
		39	24	Digital input 24
		40	L-	Inputs common

Item (cont.)	Connection	Screw N°	Screw	Function
F	**Inputs - Analog**	41	T1	Transmitter supply 1
		42	I1	Analog input 1
		43	L-	Inputs common
		44	T2	Transmitter supply 2
		45	I2	Analog input 2
		46	L-	Inputs common
G	**Inputs - Analog**	47	T3	Transmitter supply 3
		48	I3	Analog input 3
		49	L-	Inputs common
		50	T4	Transmitter supply 4
		51	I4	Analog input 4
		52	L-	Inputs common
H	**Inputs - Analog**	53	T5	Transmitter supply 5
		54	I5	Analog input 5
		55	L-	Inputs common
		56	T6	Transmitter supply 6
		57	I6	Analog input 6
		58	L-	Inputs common
I	**Inputs - Analog**	59	T7	Transmitter supply 7
		60	I7	Analog input 7
		61	L-	Inputs common
		62	T8	Transmitter supply 8
		63	I8	Analog input 8
		64	L-	Inputs common
J	**Inputs - Counter**	65	A1	Input A1 or bit 0 (LSB)
		66	B1	Input B1 or bit 1
		67	Z1	Input Z1 or bit 2 (MSB)
		68	L-	Inputs common
		69	A2	Input A2 or bit 0 (LSB)
		70	B2	Input B2 or bit 1
		71	Z2	Input Z2 or bit 2 (MSB)
		72	L-	Inputs common

Item	Connection	Type	Function
K	**Communication**	SUB-D 9-pin (FB3)	**XPS3522**: slave on Modbus™ serial (RTU) **XPS3542**: slave V0 on PROFIBUS DP
L	**Programming**	Integrated 4 RJ45 switched Ethernet Communication ports	Either of the four switched Ethernet ports can be used to create a connection between the safety PLC and the programming terminal in a point to point or via an Ethernet network for programming, or setting an IP address.
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the four switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.
	Non-Safe Communication available with references: XPSMF3502, XPSMF3522 and XPSMF3542		Either of the four switched Ethernet ports can be used to create a connection between the safety PLC and other non- safety related components (e.g HMI Magelis™, standard PLCs, and Scada systems) this can be established in a point to point way or via an Ethernet network.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU



Modular safety PLC XPSMF60, fitted with 6 different "in rack" I/O cards

Introduction

Safety PLC **XPSMF60** offers a modular solution for monitoring simple to complex safety functions for all industrial applications relating to the protection of personnel and machine safety.

Designed for use with numerous machine safety functions, this modular safety PLC is intended for use in safety related parts of control systems.
It can manage up to:

- category 4 conforming to EN 954-1,
- performance level "e" conforming to EN/ISO 13849-1,
- SIL 3 (safety integrity level) conforming to EN/IEC 61508.

Modularity

The safety PLC **XPSMF60** is a modular system consisting of a metal housing or rack, fitted with a power supply module, a CPU and "in rack" I/O cards.

■ Various types of "in rack" I/O cards are catalog listed and are selected according to the application.

■ Mounting the "in rack" cards is a simple operation using the guide rails (6 slots). Electrical connection is automatic and assured by the back plane bus of the rack.

■ The mounting order of the "in rack" I/O cards is open to the user, but the order, however, must correspond to the programming software.

■ The removal of the "in rack" cards, performed with the supply switched-off, is facilitated by a grip at the base of the cards.

■ Covering plates for unused "in rack" I/O card slots are available to protect the system in polluted environments.

Composition of the modular safety PLC XPSMF60

Minimum basic equipment	Optional "in rack" I/O cards	
	Type	Details
Metal rack XPSMFGEH01 with back plane bus assuring electrical connection of components installed + metal securing plate for shielded cables (EMC), two cooling fans **+** **a power supply module (⎓ 24 V) XPSMFPS01**, **+** **a central processing unit XPSMFCPU22** with 4 x RJ45 integrated switched Ethernet ports for Programming, and for Safety and non-safety related communication on Ethernet (safety related using SafeEthernet protocol and Non-safety related using Modbus™ TCP/IP server protocol) and in addition a SUB-D (FB2) connector for communication on Modbus serial (RTU)	XPSMFAI801	8 single-pole analog inputs or 4 2-pole analog inputs
	XPSMFAO801	8 analog outputs
	XPSMFCIO2401	2 counting inputs, 4 digital outputs
	XPSMFDI2401	24 digital inputs (⎓ 110 V / ∿ 127 V)
	XPSMFDI3201	32 digital inputs
	XPSMFDIO241601	24 digital inputs, 16 digital outputs
	XPSMFDO801	8 relay outputs (∿ 6…250 V)

Safety PLCs

In order to meet safety requirements, the modular safety PLC **XPSMF60** incorporates two essential functions (**Redundancy** and **Self-monitoring)** complying to category 4 conforming to EN 954-1 and performance level "e" conforming to EN/ISO 13849-1 in addition to the SafeEthernet safety communication protocol between the safety PLCs and the safety remote I/O modules (**Special Switch**).

■ **Redundancy**: the 2 processors integrated in the modular safety PLC analyze and compare the data received from the safety inputs and outputs.
The incoming and outgoing data (programmed values and received values) are received in parallel by the two processors and compared in real-time.

■ **Self-monitoring ("Watchdog")**: the modular safety PLC continuously monitors the data processing cycle and the execution of tasks, and intervenes if the cycle time does not conform to the predefined value.

■ **The integrated switch (Special Switch)** stores for a very short time and sends at very high speed the data provided by the inputs and outputs of the safety PLC on the Ethernet network, while avoiding signal collisions and excessive amounts of data on the network.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU

Functional diagrams

Central processing unit XPSMFCPU22



Power supply module XPSMFPS01



Line control for "in rack" I/O card XPSMFDIO241601 and "in rack" input card XPSMFDI3201

Line control is a means of short-circuit and line break monitoring.
Using line control outputs enables SIL 3 (EN/IEC 61508) and category 4 (EN 954-1) safety to be achieved. The line control outputs send a high signal with a very short low signal, thus enabling a wiring anomaly (short-circuit, line break) to be seen at the inputs of the safety PLCs.
The digital outputs 1 to 16 of card **XPSMFDIO241601** are connected to the digital inputs of the same card or to the digital inputs of card **XPSMFDI3201**.

(1) FB1 not used.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU

XPSMFDI2401

XPSMFDI3201

XPSMFAI801

Safety inputs and outputs (continued)

Programming automated safety functions

Software **XPSMFWIN** (reference SSV1XPSMFWIN) running on a PC enables the programming of all safety remote I/O modules and the modular safety PLCs, as well as configuration of the communication settings.

Safety inputs and outputs

The modularity of the PLC **XPSMF60** allows the user to select and install, in the six slots of the rack, various input, output and input/output cards to alter the number and type of safety inputs and/or outputs to be monitored.
6 identical cards can be installed in the same rack.
The cards listed (see below and next page) indicate the number of inputs and outputs available for connection to the machines to be monitored.

Digital input cards *(1)*

Cards	Digital inputs		
	Nº	Type	
		Safety detection	Safety dialog
XPSMFDI2401	24	Limit switches, Guard switches, with reset and with actuator, Light curtains type 2 and type 4, Safety mats and sensing edges	Mushroom head emergency stops, Enclosures for control and signalling units, Two-hand control stations
XPSMFDI3201	32		

Analog input card *(1) (2)*

Card	Analog measuring inputs	
	N°	Functions
XPSMFAI801	8 single-pole or 4 2-pole	Closed circuit scanning of input channels, Single-pole measuring of 0 to 10 V voltages, 2-pole measuring of -10 to +10 V voltages, Single-pole measuring of 0 to 20 mA currents

(1) Removable screw terminal blocks are provided with the power supply and "in rack" I/O cards.
(2) Use shielded dual twisted pair cables, maximum length 984 ft (300m), short-circuit unused analog inputs.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU

XPSMFCIO2401

XPSMFDIO241601

XPSMFAO801

XPSMFDO801

Safety inputs and outputs *(continued)*

Mixed I/O cards *(1)*

Card	Counting inputs			Digital outputs	
	N°	⎓ 5 V	⎓ 24 V	N°	Type
XPSMFCIO2401	2	Incremental encoders	Sensors 2/3-wire PNP/NPN	4	**Safety actuators** Contactors-motors, Control relays, Variable speed drives. **Safety dialog** Beacons and indicator banks, Rotating mirror beacons, Sirens
		Independent and configurable counting inputs (one channel for counting and one channel for increasing or decreasing counting direction)			

Card	Digital inputs		Digital outputs	
	N°	Type	N°	Type
XPSMFDIO241601	24	**Safety detection** Limit switches, Guard switches, with reset and with actuator, Light curtains type 2 and type 4, Safety mats and sensing edges **Safety dialog** Mushroom head Emergency stops, Enclosures for control and signalling units, Two-hand control stations	16	**Safety actuators** Contactors-motors, Control relays, Variable speed drives. **Safety dialog** Beacons and indicator banks, Rotating mirror beacons, Sirens

Analog output card *(1) (2)*

Card	Analog outputs	
	N°	Functions
XPSMFAO801	8	Closed circuit scanning of output channels, Single-pole measuring of 0 to 10 V voltages, Measuring, using jumper, 0/4 to 20 mA currents (with 500 Ω external resistor)

Relay output card *(1) (2)*

Card	Relay outputs	
	N°	Type
XPSMFDO801	8	**Safety actuators** Contactors-motors, Control relays, Variable speed drives. **Safety dialog** Beacons and indicator banks, Rotating mirror beacons, Sirens

Remote inputs and outputs

In addition to the inputs/outputs available as standard on the optional “in rack” cards, the modular safety PLC **XPSMF60** can be connected to safety remote input modules **XPSMF1** and/or safety remote output modules **XPSMF2** and/or safety remote mixed I/O modules **XPSMF3**.
The safety remote input, output and mixed I/O modules can be located within the vicinity of the machines to be monitored, thus reducing cabling.
Communication between these safety modules and the safety PLC **XPSMF60** is performed on an Ethernet network using the SafeEthernet safety protocol, via the integrated RJ45 switched Ethernet communications ports.

(1) Removable screw terminal blocks are provided with the power supply and “in rack” I/O cards.
(2) Use shielded dual twisted pair cables, maximum length 984 ft (300 m), short-circuit unused analog inputs.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU

Communication

Safety communication on Ethernet network

Communication between the PC, Magelis™ graphic terminals or automation platform (Premium™) and the modular safety PLC is achieved by the **Ethernet** network connection via the integrated RJ45 switched Ethernet communications ports of the modular safety PLC.

Modular PLC	Communication protocols	
	safety	non safety
XPSCPU22	SafeEthernet	Modbus™ TCP/IP server (slave)



1 Premium™ automation platform: Modbus™ TCP/IP client.
2 Graphic terminal **XBTGT**: Modbus TCP/IP client.
3 Modular safety PLC: Modbus TCP/IP server.
4 Safety remote I/O modules **XPSMF1/2/3**. They communicate with compact and modular safety PLCs using the SafeEthernet protocol.
5 Compact safety PLC **XPSMF31/30**: Modbus TCP/IP server.
6 Compact safety PLC **XPSMF35●●**: Modbus TCP/IP server.

Communication on Modbus serial (RTU) fieldbus

On Modbus serial (RTU), the modular safety PLC is a slave of the Premium™ automation platform and Magelis graphic terminal.
It is connected to the Modbus serial network via its SUB-D 9-pin connector (FB2).



1 Graphic terminal **XBTGT**: Modbus serial (RTU) master.
2 Premium™ automation platform: Modbus serial (RTU) master.
3 Modular safety PLC: Modbus serial (RTU) slave, Modbus TCP/IP server.
4 Safety remote I/O modules **XPSMF1/2/3**. They communicate with the modular safety PLC using the SafeEthernet protocol.
5 Graphic terminal **XBTGT**: Modbus serial (RTU) client.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU



Description

Modular safety PLC

Modular assembly consisting of:

1 A metal rack **XPSMFGEH01**.
2 A ⎓ 24 V power supply module **XPSMFPS01**.
3 A central processing unit **XPSMFCPU22**.
4 Six optional “in rack” I/O cards (back plane bus assures the electrical connection of “in rack” cards installed, the power supply module and the CPU).
5 A metal plate for securing shielded analog input connection cables (EMC),
6 One ground connection screw.
7 Two cooling fans (beneath the metal rack).
8 Four Ø 0.55 in (14 mm) elongated holes for mounting the rack on a vertical support.



Power supply module XPSMFPS01 and Central processing unit XPSMFCPU22 consisting of:

1 Four voltage status LEDs (FAULT, 24 V, 3.3 V or 5 V).
2 A RESTART button (accessible using fine pointed tool).
3 A 3-pole terminal block (3 captive screws) for “Fault contact” function *(1)*.
4 A ⎓ 24 V supply terminal block, including ground connection *(2)*.
5 A grip to assist installation/removal of the power supply module.
6 Seven process status LEDs.
7 Four integrated RJ45 (type 10BASE-T/100BASE-TX) switched ports for Programming, and for Safety and non-safety related communication on Ethernet. (safety related using SafeEthernet protocol and Non-safety related using Modbus™ TCP server protocol).
8 Two process status LEDs.
9 A SUB-D 9-pin connector (FB2) for connection on Modbus serial (RTU) (FB1 not used), with process status LED.
10 A grip to assist installation/removal of the CPU.

*(1) “**Fault contact**” function: the power supply module incorporates a volt-free changeover contact. Operating errors occurring in the system are read and displayed by the LEDs. The errors are analyzed on the programming PC:*



Contact positions	Status
1-2 closed (2-3 open)	Normal operation of the PLC.
1-2 open (2-3 closed)	Absence of supply to the PLC or the CPU is in ERROR STOP mode.

(2) Removable screw terminal blocks are provided with the power supply and “in rack” I/O cards.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com



LED details

Power supply module XPSMFPS01

LED	Color	Status	Meaning
24 VDC	Green	On	⎓ 24 V voltage present.
		Off	No voltage.
3.3 VDC	Green	On	⎓ 3.3 V voltage present.
		Off	No voltage.
5 VDC	Green	On	⎓ 5 V voltage present.
		Off	No voltage.
FAULT	Orange	On	Operating error.
			The user application has caused an error.
			The system configuration is defective.
			Replace module.
		Off	None of the above errors have occurred.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU



LED details *(continued)*

Central processing unit XPSMFCPU22

LED	Color	Status	Meaning
RUN	Green	On	Program in operation: CPU in STOP or RUN mode.
		Flashing	A new programming system will be downloaded.
		Off	The CPU is in “ERROR” state (see ERROR).
ERR	Red	On	Software error or hardware anomaly detected by the CPU. The monitoring program (Watchdog) has triggered the STOP state of the process because the programmed cycle time has been exceeded. The CPU has stopped the execution of the user application, ended all hardware and software tests and all outputs have been reset. The process can only be started again from the PC.
		Flashing	In the event of all the LEDs being on, restarting has detected a system error, a new operating system (OS) must be loaded.
		Off	No error detected.
FB1	–	–	Not used.
FB2	Orange	On	Communication on Modbus™ serial link active.
RUN	Green	On	Normal service mode, loaded program running, the PLC receives I/O messages, communication and hardware/ software tests carried out.
		Off	The CPU is in “ERROR” state (see ERROR).
STOP	Red	On	The CPU is in STOP mode and no program can be executed.
			The outputs are in the waiting state for the correct supply.
			The CPU has stopped the execution of the user application, ended all hardware and software tests and all outputs have been reset.
			The process can only be started again from the terminal.
		Off	CPU operating. A new programming system will be downloaded.
PROG	Orange	On	The CPU is being loaded with a new configuration.
		Flashing	CPU changing from INIT state to STOP state. The FLASH ROM is being loaded with a new operating system.
		Off	No loading of configuration or operating system.
FAULT	Orange	On	Program error.
			The loading of a new operating system was defective and the operating system is corrupt.
		Flashing	An error has occurred while writing to FLASH ROM memory (during updating of the operating system).
			One or more I/O errors have occurred.
		Off	None of the above errors have occurred.
FORCE	Orange	On	CPU in RUN mode and force is active.
		Flashing	Program in STOP mode, but force is prepared and activated if the program restarts.
		Off	Force not activated.
OSL	Orange	Flashing	Operating system and backup loading active.
BL	Orange	Flashing	COM in INIT_Fail state.
RJ45	Green	On	Full duplex mode operation.
		Flashing	Signal collision.
		Off	Half duplex mode operation, no collision.
	Yellow	On	Connection established.
		Flashing	Interface active.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU

Environment

Modular safety PLC			Rack XPSMFGEH01 + power supply module XPSMFPS01 and central processing unit XPSMFCPU22
Products designed for max. use in safety related parts of control systems (conforming to EN 954-1, EN/ISO 13849-1 and EN/IEC 61508)			Category 4 (EN 954-1), Performance level “e” (EN/ISO 13849-1), Safety integrity level: SIL 3 (EN/IEC 61508)
Product certifications			EN/IEC 61508, part 1-7: 2000, IEC 61511 part 1-3: 2004, DIN VDE 0116: 1989, EN 50156-1: 2004, EN 12067-2: 2004, EN 298: 2003, EN 230: 1990, NFPA 85: 2001, EN/IEC 61131-2: 2003, EN 61000-6-2: 2001, EN 61000-6-4: 2001 EN 54-2: 1997, NFPA 72: 2002
Ambient air temperature conforming to EN 61131-2	Operating	**°F (°C)**	Rack, power supply module and CPU: +32… + 140 (0…+ 60)
	Storage	**°F (°C)**	■ Rack **XPSMFGEH01**: -40… + 185 (- 40…+ 85), ■ Power supply module **XPSMFPS01**: □ -40… + 185 (- 40…+ 85), without backup battery □ -22… + 185 (- 30…+ 85), with backup battery ■ Central processing unit **XPSMFCPU22**: -40… + 185 (- 40…+ 85)
Relative humidity			95% (supply not connected)
Degree of protection	Enclosure		IP 20 with covering plate on unused “in rack” I/O card slots
Pollution			Degree of pollution II
Altitude			6560 ft (2000 m)
Protection class			Class II, conforming to EN/IEC 61131-2
Electromagnetic compatibility			Conforming to EN/IEC 61131-2
Vibration resistance conforming to EN 61131-2	Operating		1 g, frequency 10…150 Hz, unit test while operating, 10 cycles per axis
Shock resistance conforming to EN 61131-2	Operating		15 g (duration 11 ms), unit test while operating, 2 cycles per axis
Resistance to electrostatic discharges conforming to EN/IEC 61000-4-2		**kV**	4 contact, 8 air discharge
Immunity to high frequency interference conforming to EN/IEC 61000-4-3		**V/m**	10 (26 MHz…1 GHz)
Rack material			Metal alloy

Electrical specifications

Supply	Voltage	**V**	⎓ 24 (External supply with separate protection conforming to EN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)
	Voltage limits		- 15… + 20% (power supply module) - 20… + 25%
Output voltage of power supply module		**V**	⎓ 3.3 / 10 A
		V	⎓ 5 / 2 A
Maximum power consumption		**A**	30 max., 32 A external fuse
Immunity to momentary supply interruptions		**ms**	10
Protection			Internal fuse
Response time		**ms**	Depending on size of application
Backup capacitor			Approximately 1 week for diagnostics and time information Program is not effected
Clock			Yes
Operational data of CPU			⎓ 3.3 V/1.5 A
			⎓ 5 V/1 A
User memory	Application	**kB**	500
	Data	**kB**	500
LED display			Yes

Communication

Ethernet network: safety communication using SafeEthernet protocol

Compatibility			Central processing unit XPSMFCPU22
Transmission	Communication ports		Integrated 4 RJ45 switched Ethernet communications ports
	Baud rate	**Mbps**	100 Half duplex, 10 Full duplex, Autonegotiation
Structure			10BASE-T/100BASE-TX
Medium			Dual twisted pair cable, category 5D or better (Ethernet)
Functions	Control of:		Transmitted data: duplication, loss, bit changing. Addressing of transmitted and received messages. Data sequence: repetition, loss of data, change. Data reception time: delay, repetition, echo
	Diagnostics on:		CPU, user program, communication, operating voltage and temperature, inputs & outputs

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Communication *(continuous)*			
Compatibility			**Central processing unit XPSMFCPU22**
Ethernet network: Non-safety related communication using Modbus™ TCP/IP protocol			
Connection Ports	Number and type		Integrated 4 RJ45 switched Ethernet communication ports
	Baud rate	**Mbps**	100 Half duplex, 10 Full duplex, Autonegotiation
	Master/Slave		Server (slave)
Structure			10BASE-T/100BASE-TX
Medium			Dual twisted pair cable, category 5D or better (Ethernet)
Transparent Ready™ Services	Class		A10
	Standard Ethernet TCP/IP communication services		Modbus TCP/IP Server
			Modbus TCP/IP messaging (reading/writing of data words)
			Modbus identification requests
	TCP port		standard 502
	Max. number of Modbus TCP/IP connections		1 to 20
Modbus serial (RTU)			
Serial link ports	Number and type		1 x SUB-D 9-pin female (FB2)
	Master/Slave		Slave
Addressing			122 slave addresses
Physical layer			RS 485
Connections *(1)*			
Power supply module			**XPSMFPS01**
Type of connection			Removable screw terminal blocks *(2)*
Supply connection	Number of terminal blocks		1
	For 1 cable without cable end		Solid or flexible AWG 20 (0.75…16 mm^2)
	For 1 flexible cable with or without plastic cable end		AWG 20 (0.5…16 mm^2)
	For 2 cables of same diameter, without cable end		Solid or flexible AWG 20 (0.75…6 mm^2)
	For 2 cables of same diameter, flexible without cable end		AWG 20 (0.5…4 mm^2)
	For 2 cables of same diameter, flexible with plastic cable end		AWG 20 (0.5…6 mm^2)
"In rack" I/O card			**XPSMFAI801, XPSMFAO801, XPSMFCIO2401, XPSMFDI2401, XPSMFDI3201, XPSMFDIO241601, XPSMFDO801**
Type of connection			Removable screw terminal blocks *(2)*
Digital input channel and output channel connection	Number of terminal blocks		Depending on "in rack" I/O card type
	For 1 cable without cable end		Solid or flexible: AWG 28-16 (0.14…1.5 mm^2)
	For 1 flexible cable without cable end		AWG 22-16 (0.25…1.5 mm^2)
	For 1 flexible cable with plastic cable end		AWG 22-20 (0.25…0.5 mm^2)
	For 2 cables of same diameter, without cable end		Solid: AWG 28-20 (0.14…0.5 mm^2) Flexible: AWG 28-18 (0.14…0.75 mm^2)
	For 2 cables of same diameter, flexible without cable end		AWG 22 (0.25…0.34 mm^2)
	For 2 cables of same diameter, flexible with plastic cable end		AWG 20 (0.5 mm^2)
Analog input channel and output channel connection	Number of terminal blocks		Depending on "in rack" I/O card type
	For 1 cable without cable end		Solid or flexible: AWG 28-16 (0.14…1.5 mm^2)
	For 1 flexible cable without cable end		AWG 22-16 (0.25…1.5 mm^2)
	For 1 flexible cable with plastic cable end		AWG 22-20 (0.25…0.5 mm^2)
	For 2 cables of same diameter, without cable end		Solid: AWG 28-20 (0.14…0.5 mm^2) Flexible: AWG 28-18 (0.14…0.75 mm^2)
	For 2 cables of same diameter, flexible without cable end		AWG 22 (0.25…0.34 mm^2)
	For 2 cables of same diameter, flexible with plastic cable end		AWG 20 (0.5 mm^2)
Counting channel connection	Number of terminal blocks		Depending on "in rack" I/O card type
	For 1 cable without cable end		Solid or flexible: AWG 28-16 (0.14…1.5 mm^2)
	For 1 flexible cable without cable end		AWG 22-16 (0.25…1.5 mm^2)
	For 1 flexible cable with plastic cable end		AWG 22-20 (0.25…0.5 mm^2)
	For 2 cables of same diameter, without cable end		Solid: AWG 28-20 (0.14…0.5 mm^2) Flexible: AWG 28-18 (0.14…0.75 mm^2)
	For 2 cables of same diameter, flexible without cable end		AWG 22 (0.25…0.34 mm^2)
	For 2 cables of same diameter, flexible with plastic cable end		AWG 20 (0.5 mm^2)
Cable connection	Tightening torque		1.9…2.2 lb-in (0.22…0.25 Nm)
	Bared length		0.35 in (9mm)

(1) AWG: American Wire Gauge.
(2) Removable screw terminal blocks are provided with the power supply and "in rack" I/O cards.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU



Modular PLC (⎓ 24 V supply)

Minimum basic equipment

Description	Reference	Weight oz (kg)
Metal rack *(1)* **fitted with:** □ a back plane bus, assuring electrical connection of components installed: power supply module, CPU and "in rack" cards □ two cooling fans □ a metal securing plate for shielded cables (EMC)	**XPSMFGEH01**	–
⎓ **24 V power supply module** *(1)*	**XPSMFPS01**	28.925 (0.820)
CPU *(1)* **fitted with:** □ 4 x integrated RJ45 (type 10BASE-T/100BASE-TX) switched ports for Programming, and for Safety and non-safety related communication on Ethernet. (safety related using SafeEthernet protocol and Non-safety related using Modbus™ TCP/IP server protocol □ 1 x SUB-D 9-pin port (FB2) for access to Modbus serial (RTU)	**XPSMFCPU22**	9.877 (0.280)

Optional "in rack" I/O cards

Description	Functions		Reference	Weight oz (kg)
	Inputs	Outputs		
"In rack" I/O card *(1)*	Analog: 8 single-pole or 4 2-pole, configurable	–	**XPSMFAI801**	8.466 (0.240)
	–	8 analog	**XPSMFAO801**	9.877 (0.280)
	2 counting	4 digital	**XPSMFCIO2401**	9.171 (0.260)
	24 digital (⎓ 110 V / ∿ 127 V)	–	**XPSMFDI2401**	9.171 (0.260)
	32 digital	–	**XPSMFDI3201**	9.171 (0.260)
	24 digital	16 digital *(2)*	**XPSMFDIO241601**	9.171 (0.260)
	–	8 relay ≂ 6…250 V	**XPSMFDO801**	21.164 (0.600)

(1) Removable screw terminal blocks are provided with the power supply and "in rack" I/O cards.
(2) Configurable for line control.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Configuration software

■ Reference **SSV1XPSMFWIN** contains the full version of the programming software XPSMFWIN software for the XPSMF Safety PLCs. The XPSMFWIN is part of our Safety Suite and is not available seperately.

Description	Operating system	Details	Languages	Reference	Weight oz (kg)
Configuration software XPSMFWIN for programming modular safety PLCs CD-ROM + user manual	Windows® 2000, Windows® XP	Software available on Safety Suite V2 software pack	English, German, French	**SSV1XPSMFWIN**	18.342 (0.520)

Accessories for modular PLC

Description	For use with	Reference	Weight oz (kg)
Covering plate	Unused “in rack” I/O card slots	**XPSMFBLK**	–

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU

ABL8RPS24050

Phaseo™ regulated switch mode power supplies

Mains input voltage	Output voltage	Nominal power	Nominal current	Auto-protect reset	Conformity to standard IEC EN 61000-3-2 and IEC EN 60950	Reference	Weight
V	⎓ V	W	A				oz (kg)
Universal range, single-phase (N-L1) **or 2-phase** (L1-L2) **connection**							
∿ **100…120 V/200...500** - 15%, + 10% 50/60 Hz	24...28.8	72	3	Auto/Manual	Yes	**ABL8RPS24030**	10.582 (0.300)
		120	5	Auto/Manual	Yes	**ABL8RPS24050**	24.692 (0.700)
		240	10	Auto/Manual	Yes	**ABL8RPS24100**	35.273 (1.000)
Dedicated range, single-phase connection							
∿ **100…240** *(1)* wide range, 47…63 Hz	12	60	5	Auto	No	**ABL1REM12050**	15.521 (0.440)
	24	60	2.5	Auto	No	**ABL1REM24025**	15.521 (0.440)
∿ **100...120/200...240** *(2)*	24	240	10	Auto	No	**ABL1REM24100**	31.041 (0.880)

ABL1REM24025

Magelis™ multifunction graphic terminals with touch sensitive screen and on-board Ethernet *(1)*

Supply voltage ⎓ 24 V

Description		Ports: serial and communication (type of link)	Application memory	Reference	Weight oz (kg)
5.7"	Monochrome black and white STN	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 1 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	16 Mb	**XBTGT2130**	35.273 (1.000)
	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 1 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	16 Mb	**XBTGT2330**	35.273 (1.000)
7.5"	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 1 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT4330**	63.493 (1.800)
10.4"	Color STN	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT5230**	105.822 (3.000)
	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT5330**	105.822 (3.000)
12.1"	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT6330**	105.822 (3.000)
15"	Color TFT	1 x SUB-D 9-pin (RS 232C or RS 422/485 serial link to PLCs) 1 x RJ45 (RS 485 serial link) 2 x USB (peripheral connection and application transfer) 1 x RJ45 (Ethernet TCP/IP, 10BASE-T/100BASE-TX)	32 Mb	**XBTGT7340**	197.534 (5.600)

XBTGT2130, XBTGT2330

XBTGT4330

XBTGT5●30

XBTGT6330

XBTGT7340

(1) Service instructions, USB connectors locking device and mounting kit included.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU

490NTW000●●

Connecting cables for network and bus

Connection to Ethernet network

Description	Pre-fitted connectors	Length ft (m)	Reference	Weight oz (kg)
Shielded twisted pair cables, straight through	2 RJ45 connectors For connection to DTE (Data Terminal Equipment)	6.6 (2)	**490NTW00002***(1)*	–
		16.4 (5)	**490NTW00005***(1)*	–
		39.4 (12)	**490NTW00012***(1)*	–
		131.2 (40)	**490NTW00040***(1)*	–
		262.5 (80)	**490NTW00080***(1)*	–
Shielded twisted pair cables, crossed wires	2 RJ45 connectors For connection between hubs, switches and transceivers	16.4 (5)	**490NTC00005***(1)*	–
		49.2 (15)	**490NTC00015***(1)*	–
		131.2 (40)	**490NTC00040***(1)*	–
		262.5 (80)	**490NTC00080***(1)*	–

Connection to Modbus™ serial link

Description	Use		Length ft. (m)	Reference	Weight lb (kg)
	From	To			
Trunk cables, shielded dual twisted pair, RS 485	Compact safety PLCs XPSMF4020/MF4022 (RJ45)	Modbus splitter box LU9 GC3 (RJ45)	328 (100)	**TSXCSA100**	12.522 (5.680)
			656 (200)	**TSXCSA200**	24.074 (10.920)
			1640 (500)	**TSXCSA500**	66.139 (30.000)
	Graphic terminals XBTGT (SUB-D 9-pin)	Modbus splitter box LU9 GC3 (RJ45)	8.2 (2.5)	**XBTZ938***(2)*	0.441 (0.210)
Adaptor for cable XBTZ938	SUB-D 9-pin (XBTGT)	XBTZ938 (SUB-D 25-pin)	0.66 (0.2)	**XBTZG909**	–
Adaptor SUB-D 9-pin/RJ45	Compact PLCs (SUB-D 9-pin)	Connecting cables for Modbus serial link (RJ45)	–	**XPSMFADAPT**	–



Description	Specifications	Sold in lots of	Unit reference	Weight oz (kg)
End of line adaptors For RJ45 connector	R = 120 Ω, C = 1 nF	2	**VW3A8306RC**	7.055 (0.200)
	R = 150 Ω	2	**VW3A8306R**	0.353 (0.010)

PROFIBUS DP bus connection components

Description	Profile	Services	Reference	Weight oz (kg)
PROFIBUS DP module set for Premium™ PLCs	Master, 12 Mbps	Class 1 and Class 2 master V0 functions, see specifications. PROFIBUS FMS messaging not supported	**TSXPBY100**	30.688 (0.870)

Description	Use	Reference	Weight oz (kg)
Remote inputs/outputs on PROFIBUS DP bus	Advantys™ STB network interface module	**STBNDP2112**	4.938 (0.140)
	Momentum™ communication module	**170DTN11000**	–
Connectors for remote I/O communication module	Line terminators	**490NAD91103**	–
	Intermediate connection	**490NAD91104**	–
	Intermediate connection and terminal port	**490NAD91105**	–

TSXPBY100

Description	Length ft (m)	Reference	Weight oz (kg)
PROFIBUS DP connecting cables	328 (100)	**TSXPBSCA100**	–
	1312 (400)	**TSXPBSCA400**	–

Description	Reference	Weight oz (kg)
Replacement parts	Main bus junction box	**490NAE91100**	–
	PCMCIA card	**467NHP81100**	–

490NAD91103

*(1) Cable conforming to standard EIA/TIA-568 category 5 and IEC 1180/EN 50 173 class D. For UL and CSA 22.1 approved cables, add the letter **U** to the end of the reference.*
(2) Requires adaptor XBTZG909.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU

Dimensions

XPSMF60



Dual Dimensions: INCHES / Millimeters

(1) Removable screw terminal blocks are provided with the power supply and "in rack" I/O cards.

Mounting precautions relating to connectors

Access to Modbus™ serial link (RTU) and Ethernet network

4 RJ45 connectors: access to Ethernet network (SafeEthernet protocol, Modbus TCP/IP server protocol)



SUB-D 9-pin connector: access to Modbus serial link (RTU)



Adaptor XPSMFADAPT: access to Modbus serial link (RTU)



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
Rack, power supply and CPU

Connections

Power supply module and CPU



Item	Connection	Screw	Function
A	**Supply**	L+	⎓ 24 V
		L-	⎓ 24 V (reference pole)
		⏚	Ground

Item	Connection	Type	Function
B	**Communication**	SUB-D 9-pin female (FB2)	**XPSMFCPU22**: slave on Modbus™ serial (RTU)
C	**Programming**	Integrated 4 RJ45 switched Ethernet Communication ports	Either of the four switched Ethernet ports can be used to create a connection between the safety PLC and the programming terminal in a point to point or via an Ethernet network for programming, and setting an IP address.
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the four switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.
	Non-Safe Communication available with: XPSMF60 (reference XPSMFCPU22		Either of the four switched Ethernet ports can be used to create a connection between the safety PLC and other non- safety related components (e.g HMI Magelis™, standard PLCs, and Scada systems) this can be established in a point to point way or via an Ethernet network.

Connection examples

Actuator connections to the outputs



Emergency stop connections (line control)



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
"In rack" analog input card



Introduction

The "in rack" analog input card **XPSMFAI801** is designed to manage up to:
- category 4 conforming to EN 954-1,
- performance level "e" conforming to EN/ISO 13849-1,
- SIL 3 (safety integrity level) conforming to EN/IEC 61508.

■ It incorporates 8 analog inputs:
□ electrically isolated from the back plane bus of rack **XPSMFGEH01**,
□ configured by choice of connection for managing eight single-pole or four 2-pole functions.

■ The card can be installed in rack **XPSMFGEH01** as many times as required in the six slots available.

Input values *(1)*

Number	Type	Voltage	Current	Value range	Example
8 inputs	Single-pole	± 10 V	–	± 1000	Single-pole measuring of 0 to 10 V voltages
		–	0...20 mA	0...1000 *(2)* 0...2000 *(3)*	Measuring 0 to 20 mA currents using jumper
4 inputs	2-pole	± 10 V	–	± 1000	Closed circuit scanning of input channels

Functional diagram



Description

On the front cover of the card:
1 Two process status LEDs (RUN, ERR).
2 Two removable screw terminal blocks (9 terminals per block) for connection of inputs *(4)*.
3 Grip to assist installation/removal.
4 On the rear: terminals for automatic electrical connection to the back plane bus of rack **XPSMFGEH01**.

LED details

LED	Color	Status	Meaning
RUN	Green	On	Voltage present.
		Off	No voltage.
ERR	Red	On	Card defect or external error, diagnostics response.
		Off	No error regarding the card or on the channels.

(1) The unused input channels must be short-circuited on the reference pole (L-).
(2) With 250 Ω external jumper.
(3) With 500 Ω external jumper.
*(4) Removable screw terminals are provided with the "in rack" card **XPSMFAI801**.*

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
"In rack" analog input card

Specifications

Card type			XPSMFAI801
Number of analog inputs			8 single-pole inputs (± 10 V / 0…20 mA) or 4 2-pole inputs (± 10 V), electrically isolated, configurable by choice of connection
Supply	Voltage	**V**	⎓ 24, supplied by rack XPSMFGEH01 incorporating power supply module XPSMFPS01
	Voltage limits		- 15…+ 20%
Signal	Usable range	**V**	± 10.25
		mA	0...+ 20.5 (with jumper)
	Nominal value	**V**	± 10
		mA	0...+ 20 (with jumper)
Maximum input signal		**V**	± 10.7
Jumper for current measurement		Ω	250 or 500
Overvoltage protection		**V**	⎓ - 15…+ 15 (30 V range)
Input resistance	d.c.	**MΩ**	1
Operational data			⎓ 24 V/380 mA ⎓ 3.3 V/150 mA
Ambient air temperature conforming to EN 61131-2	Operating	**°F (°C)**	+32… + 140 (0…+ 60)
	Storage	**°F (°C)**	- 40… + 185 (- 40…+ 85)
Resolution	Effective		9-bit
	Maximum		12-bit
Output voltage			± 1% max.
Safety accuracy			± 1% max.
Transient deviation			± 1% max.
Value acquisition renewal			Once per CPU cycle
Processing time			Approximately 45 µs
Connections			See page 2/43

References

Description	Number of channels	Voltage Current	Reference	Weight oz (kg)
Analog input card	8 single-pole	± 10 V 0...20 mA *(1)*	**XPSMFAI801**	8.466 (0.240)
	4 2-pole	± 10 V		

XPSMFAI801

Connections

Item	Connection	Screw N°	Screw	Function
A	**Analog inputs**	01	L1+	Analog input 1
		02	L-	Input 1 (reference pole)
		03	L2+	Analog input 2
		04	L-	Input 2 (reference pole)
		05	L3+	Analog input 3
		06	L-	Input 3 (reference pole)
		07	L4+	Analog input 4
		08	L-	Input 4 (reference pole)
		09	⏚	Ground/Shielding
B	**Analog inputs**	10	L5+/L1-	Analog input 5
		11	L-	Input 5 (reference pole)
		12	L6+/L2-	Analog input 6
		13	L-	Input 6 (reference pole)
		14	L7+/L3-	Analog input 7
		15	L-	Input 7 (reference pole)
		16	L8+/L4-	Analog input 8
		17	L-	Input 8 (reference pole)
		18	⏚	Ground/Shielding

Configuration of analog inputs

Connection	…	with	…	Connection	…	with	…
8 single-pole inputs	L1+		L-	**4 2-pole inputs**	L1+		L5+/L1-
	L2+		L-		L2+		L6+/L2-
	L3+		L-		L3+		L7+/L3-
	L4+		L-		L4+		L8+/L4-
	L5+/L1-		L-				
	L6+/L2-		L-				
	L7+/L3-		L-				
	L8+/L4-		L-				

(1) With a 250 Ω or 500 Ω external jumper.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
"In rack" analog output card



Introduction

The analog output card **XPSMFAO801** is designed to manage up to:
- category 4 conforming to EN 954-1,
- performance level "e" conforming to EN/ISO 13849-1,
- SIL 3 (safety integrity level) conforming to EN/IEC 61508.

■ It incorporates 8 configurable analog outputs (0…20 mA, 0…+ 10 V or - 10…+ 10 V):

□ For selection of the type of voltage/current measurement: a switch enables selection of 6 functions for each output channel.

Switch position	Outputs	
	Voltage ± 10 V	Current 0…+ 20 mA
1	–	On
2	–	On
3	–	On
4	On	–
5	On	–
6	On	–

□ Selection of measuring scale using software **XPSMFWIN**: the "Properties" sub-menu displays the scale options in the "Type" window (…FS1000 or …FS2000).

Configurable output values				
Type	Voltage	Current	Value range	
			Half scale (version FS1000)	Full scale (version FS2000)
8 analog outputs	–	0…20 mA	0...+ 1000	0...+ 2000
	0…+ 10 V	–	0...+ 1000	0…+ 2000
	- 10...+ 10 V	–	- 1000...+ 1000	- 2000...+ 2000

■ The card can be installed in rack **XPSMFGEH01** as many times as required in the six slots available.

Functional diagram



Description

On the front cover of the card:

1 Two process status LEDs (RUN, ERR).
2 Two removable screw terminal blocks (9 terminals per block) for connection of outputs *(1)*.
3 Grip to assist installation/removal.
4 On the rear: terminals for automatic electrical connection to the back plane bus of rack **XPSMFGEH01**.

LED details

LED	Color	Status	Meaning
RUN	Green	On	Voltage present.
		Off	No voltage.
ERR	Red	On	Card defect or external error, diagnostics response.
		Off	No error regarding the card or on the channels.

*(1) Removable screw terminals are provided with the "in rack" card **XPSMFAO801**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
“In rack” analog output card

Specifications

Card type			XPSMFAO801
Number of outputs			8 analog outputs
Supply	Voltage	**V**	⎓ 24 (supplied by rack XPSMFGEH01 incorporating power supply module XPSMFPS01)
	Voltage limits		- 15…+ 20%
Nominal output values		**V**	± 10 (- 10…+ 10)
		mA	0...+ 20
Maximum output value		**V**	± 10.25
		mA	0...+ 21
Overvoltage protection		**V**	24
Output resistance	Current	Ω	≤ 600
	Voltage	**k**Ω	> 1
Operational data			3.3 V/130 mA 5 V/280 mA 24 V/630 mA
Ambient air temperature conforming to EN 61131-2	Operating	**°F (°C)**	+32… + 140 (0…+ 60)
	Storage	**°F (°C)**	-40… + 185 (- 40…+ 85)
Resolution	Effective		7-bit
	Maximum		12-bit
Symmetrical tolerance			± 1% max.
Safety accuracy			± 1% max.
Processing time			Approximately 45 µs
Connections			See page 2/43

References

Description	Number of channels	Configuration		Reference	Weight oz (kg)
		Current	Voltage		
Analog output card	8	0...20 mA	- 10…+ 10 V	**XPSMFAO801**	9.877 (0.280)

XPSMFAO801

Connections

Item	Connection	Screw N°	Screw	Function
A	**Analog outputs**	01	O1+	Analog output 1
		02	O1-	Output 1 (reference pole)
		03	O2+	Analog output 2
		04	O2-	Output 2 (reference pole)
		05	O3+	Analog output 3
		06	O3-	Output 3 (reference pole)
		07	O4+	Analog output 4
		08	O4-	Output 4 (reference pole)
		09	⏚	Ground/Shielding
B	**Analog outputs**	10	O5+	Analog output 5
		11	O5-	Output 5 (reference pole)
		12	O6+	Analog output 6
		13	O6-	Output 6 (reference pole)
		14	O7+	Analog output 7
		15	O7-	Output 7 (reference pole)
		16	O8+	Analog output 8
		17	O8-	Output 8 (reference pole)
		18	⏚	Ground/Shielding

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
“In rack” mixed card: counting inputs/digital outputs

Introduction

The mixed counting input and digital output card **XPSMFCIO2401** is designed to manage up to:

- category 4 conforming to EN 954-1,
- performance level “e” conforming to EN/ISO 13849-1,
- SIL 3 (safety integrity level) conforming to EN/IEC 61508.

■ It incorporates:
□ 2 24-bit independent and configurable counting channels (one channel for counting and one channel for increasing or decreasing counting direction). They are configured using software **XPSMFWIN**.
□ 4 digital outputs.

■ The card can be installed in rack **XPSMFGEH01** as many times as required in the six slots available.

Functional diagram





Description

On the front cover of the card:

1 Two process status LEDs (RUN, ERR).
2 Two removable screw terminal blocks (9 terminals per block) for connection of inputs *(1)*.
3 One removable screw terminal block (9 terminals) for connection of outputs *(1)* with four output status LEDs.
4 Grip to assist installation/removal.
5 On the rear: terminals for automatic electrical connection to the back plane bus of rack **XPSMFGEH01**.

LED details

LED	Color	Status	Meaning
RUN	Green	On	Voltage present.
		Off	No voltage.
ERR	Red	On	Card defect or external error, diagnostics response.
		Off	No error regarding the card or on the channels.

*(1) Removable screw terminals are provided with the “in rack” card **XPSMFCIO2401**.*

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
"In rack" mixed card: counting inputs/digital outputs

Specifications

Mixed card type			XPSMFCIO2401
Supply	Voltage	**V**	⎓ 24 (supplied by rack XPSMFGEH01 incorporating power supply module XPSMFPS01)
	Voltage limits		- 15…+ 20%
Ambient air temperature conforming to EN 61131-2	Operating	**°F (°C)**	+32… + 140 (0…+ 60)
	Storage	**°F (°C)**	- 40… + 185 (- 40…+ 85)
Counting inputs			
Number	Counter		2
	Inputs		4 on each pole (A, B, Z, C)
Input voltage		**V**	⎓ 5 or 24
Input current		**mA**	≤ 3
Input resistance		**kΩ**	3.7
Counting frequency		**MHz**	0…1
Resolution			24-bit
Time base accuracy			0.2%
Operational data			⎓ 3.3 V/0.8 A ⎓ 5 V/0.1 A ⎓ 24 V / 0.1 A + output current
Maximum distance of equipment			1640 ft (500 m), with shielded dual twisted pair cable
Input connections			See page 2/43
Digital outputs			
Number			4
Output voltage		**V**	⎓ 18.4…26.8
Output current		**A**	0.5 per channel, 2 max. per card. Continuous short-circuit proof
Internal volt drop		**V**	3 max. at 0.5 A
Minimum current		**mA**	2 per channel
Permissible current	At state 0	**mA**	1 mA max. at 2 V
Current power consumption		**V**	⎓ 24 / 0.1 A + output current
Output connections			See page 2/43

References

Description	Specifications	Reference	Weight oz (kg)
Mixed I/O card	■ 2 x 24-bit counting inputs, configurable: 5 V…24 V ■ 4 digital outputs	**XPSMFCIO2401**	9.171 (0.260)



XPSMFCIO2401

Connections

Item	Connection	Screw N°	Screw	Function
1	**Counting input**	01	C-	Common reference pole
		02	A1	Input A1 or bit 1
		03	B1	Input B1 or bit 2
		04	Z1	Input Z1 or bit 3
		05	C1	Input C1 or bit 4
		06	C-	Common reference pole
		07	C-	Common reference pole
		08	C-	Common reference pole
		09	C-	Common reference pole
2	**Counting input**	10	C-	Common reference pole
		11	A2	Input A2 or bit 1
		12	B2	Input B2 or bit 2
		13	Z2	Input Z2 or bit 3
		14	C2	Input C2 or bit 4
		15	C-	Common reference pole
		16	C-	Common reference pole
		17	C-	Common reference pole
		18	C-	Common reference pole
3	**Digital outputs**	19	L-	Common reference pole
		20	1	Digital output 1
		21	2	Digital output 2
		22	3	Digital output 3
		23	4	Digital output 4
		24	L-	Common reference pole
		25	L-	Common reference pole
		26	L-	Common reference pole
		27	L-	Common reference pole

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
“In rack” digital input card

Introduction

The digital input card **XPSMFDI2401** is designed to manage up to:

■ It incorporates 24 ⎓ 110 / ∿ 127 V digital inputs that are configurable using software **XPSMFWIN**.
■ The card can be installed in rack **XPSMFGEH01** as many times as required in the six slots available.

Functional diagram



Description



On the front cover of the card:
1 Two process status LEDs (RUN, ERR).
2 Three removable terminal blocks (9 terminals per block) for connection of inputs *(1)*, each with eight input status LEDs.
3 Grip to assist installation/removal.
4 On the rear: terminals for automatic electrical connection to the back plane bus of rack **XPSMFGEH01**.

LED details

LED	Color	Status	Meaning
RUN	Green	On	Voltage present.
		Off	No voltage.
ERR	Red	On	Card defect or external error, diagnostics response.
		Off	No error regarding the card or on the channels.

*(1) Removable screw terminals are provided with the “in rack” card **XPSMFDI2401**.*

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
"In rack" digital input card

Specifications

Input card type			XPSMFDI2401
Supply	Voltage	**V**	⎓ 24 (supplied by rack XPSMFGEH01 incorporating power supply module XPSMFPS01)
	Voltage limits		- 15…+ 20%
Ambient air temperature conforming to EN 61131-2	Operating	**°F (°C)**	+32… + 140 (0…+ 60)
	Storage	**°F (°C)**	-40… + 185 (- 40…+ 85)
Number of inputs			24, electrically isolated
Nominal voltage		**V**	⎓ 110/∿ 127 (single-phase)
Input voltage	At state 0	**V**	⩽ 20
	At state 1	**V**	⩾ 79
Input current	At state 1	**mA**	⩾ 2.2 at 79 V
Operational data			⎓ 3.3 V/0.05 A ⎓ 24 V / 0.1 A (79 V at state 1)
LED display			Yes
Connections			Shielded dual twisted pair cable recommended to provide protection against electromagnetic interference, or Ø 0.47 in (12 mm) max. cable with connection to ground of rack XPSMFGEH01

References

Description	Specifications	Reference	Weight oz (kg)
Input card	24 digital inputs ⎓ 110 V / ∿ 127 V	**XPSMFDI2401**	9.171 (0.260)



XPS MFDI2401

Connections

Item	Connection	Screw N°	Screw	Function
A	**Digital inputs**	01	I1	Input 1
		02	I2	Input 2
		03	I3	Input 3
		04	I4	Input 4
		05	I5	Input 5
		06	I6	Input 6
		07	I7	Input 7
		08	I8	Input 8
		09	N/-	Common reference pole
B	**Digital inputs**	10	I9	Input 9
		11	I10	Input 10
		12	I11	Input 11
		13	I12	Input 12
		14	I13	Input 13
		15	I14	Input 14
		16	I15	Input 15
		17	I16	Input 16
		18	N/-	Common reference pole
C	**Digital inputs**	19	I17	Input 17
		20	I18	Input 18
		21	I19	Input 19
		22	I20	Input 20
		23	I21	Input 21
		24	I22	Input 22
		25	I23	Input 23
		26	I24	Input 24
		27	N/-	Common reference pole

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
“In rack” digital input card



Introduction

The digital input card **XPSMFDI3201** is designed to manage up to:
- category 4 conforming to EN 954-1,
- performance level “e” conforming to EN/ISO 13849-1,
- SIL 3 (safety integrity level) conforming to EN/IEC 61508.

■ It incorporates 32 digital inputs that are configurable using programming software **XPSMFWIN**.

b The card can be installed in rack **XPSMFGEH01** as many times as required in the six slots available.

Functional diagram



Line control for card XPSMFDI3201

Line control is a means of short-circuit and line break monitoring.
Using line control outputs enables SIL 3 (EN/IEC 61508) and category 4 (EN 954-1) safety to be achieved. The line control outputs send a high signal with a very short low signal, thus enabling a wiring anomaly (short-circuit, line break) to be seen at the inputs of the safety PLCs.

Description

On the front cover of the card:

1 Two process status LEDs (RUN, ERR).
2 Five removable terminal blocks (9 terminals per block) for connection of inputs *(1)*, with a status LED for each input terminal.
3 Grip to assist installation/removal.
4 On the rear: terminals for automatic electrical connection to the back plane bus of rack **XPSMFGEH01**.

LED details

LED	Color	Status	Meaning
RUN	Green	On	Voltage present.
		Off	No voltage.
ERR	Red	On	Card defect or external error, diagnostics response.
		Off	No error regarding the card or on the channels.

*(1) Removable screw terminals are provided with the “in rack” card **XPSMFDI3201**.*

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
“In rack” digital input card

Specifications

Input card type			XPSMFDI3201
Supply	Voltage	**V**	⎓ 24, supplied by rack XPSMFGEH01 incorporating power supply module XPSMFPS01
	Voltage limits		- 15…+ 20%
Ambient air temperature conforming to EN 61131-2	Operating	**°F (°C)**	+32… + 140 (0…+ 60)
	Storage	**°F (°C)**	-40… + 185 (- 40…+ 85)
Number of digital inputs			32, electrically isolated
Nominal voltage		**V**	⎓ 24
Input voltage	At state 0	**V**	5 max.
	At state 1	**V**	10…30
Input current	At state 0	**mA**	1.0 at 5 V
	At state 1	**mA**	2 at 10 V, 5 at 24 V
Operational data			⎓ 3.3 V / 0.05 A, ⎓ 24 V / 0.2 A
LED display			Yes
Connections			Shielded dual twisted pair cable recommended to provide protection against electromagnetic interference, or Ø 0.47 in (12mm) max. cable with connection to ground of rack XPSMFGEH01



References

Description	Specifications	Reference	Weight oz (kg)
Input card	32 digital inputs	**XPSMFDI3201**	9.171 (0.260)

Connections

Item	Connection	Screw N°	Screw	Function
A	**Digital inputs**	01	LS+	Supply for inputs 1 to 7
		02	I1	Input 1
		03	I2	Input 2
		04	I3	Input 3
		05	I4	Input 4
		06	I5	Input 5
		07	I6	Input 6
		08	I7	Input 7
		09	EGND	Reference pole
B	**Digital inputs**	10	LS+	Supply for inputs 8 to 14
		11	I8	Input 8
		12	I9	Input 9
		13	I10	Input 10
		14	I11	Input 11
		15	I12	Input 12
		16	I13	Input 13
		17	I14	Input 14
		18	EGND	Reference pole
C	**Digital inputs**	19	LS+	Supply for inputs 15 to 21
		20	I15	Input 15
		21	I16	Input 16
		22	I17	Input 17
		23	I18	Input 18
		24	I19	Input 19
		25	I20	Input 20
		26	I21	Input 21
		27	EGND	Reference pole
D	**Digital inputs**	28	LS+	Supply for inputs 22 to 28
		29	I22	Input 22
		30	I23	Input 23
		31	I24	Input 24
		32	I25	Input 25
		33	I26	Input 26
		34	I27	Input 27
		35	I28	Input 28
		36	EGND	Reference pole
E	**Digital inputs**	37	LS+	Supply for inputs 29 to 32
		38	I29	Input 29
		39	I30	Input 30
		40	I31	Input 31
		41	I32	Input 32
		42	EGND	Reference pole
		43	EGND	Reference pole
		44	EGND	Reference pole
		45	EGND	Reference pole

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
"In rack" digital I/O card

Introduction

The digital I/O card **XPSMFDIO241601** is designed to manage up to:
- category 4 conforming to EN 954-1,
- performance level "e" conforming to EN/ISO 13849-1,
- SIL 3 (safety integrity level) conforming to EN/IEC 61508.

■ It incorporates 24 digital inputs and 16 digital outputs.
■ The card can be installed in rack **XPSMFGEH01** as many times as required in the six slots available.

Functional diagrams

■ 24 digital inputs



■ 16 digital outputs



Line control for card XPSMFDIO241601

Line control is a means of short-circuit and line break monitoring.
Using line control outputs enables SIL 3 (EN/IEC 61508) and category 4 (EN 954-1) safety to be achieved. The line control outputs send a high signal with a very short low signal, thus enabling a wiring anomaly (short-circuit, line break) to be seen at the inputs of the safety PLCs.



Description

On the front cover of the card:
1 Two process status LEDs (RUN, ERR).
2 Three removable terminal blocks (9 terminals per block) for connection of inputs *(1)*, each with eight input status LEDs.
3 Two removable screw terminal blocks (9 terminals per block) for connection of outputs *(1)*, each with eight output status LEDs.
4 Grip to assist installation/removal.
5 On the rear: terminals for automatic electrical connection to the back plane bus of rack **XPSMFGEH01**.

LED details

LED	Color	Status	Meaning
RUN	Green	On	Voltage present.
		Off	No voltage.
ERR	Red	On	Card defect or external error, diagnostics response.
		Off	No error regarding the card or on the channels.

*(1) Removable screw terminals are provided with the "in rack" card **XPSMFDIO241601**.*

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
"In rack" digital I/O card

Specifications

I/O card type			XPSMFDIO241601
Supply	Voltage	**V**	⎓ 24, supplied by rack XPSMFGEH01 incorporating power supply module XPSMFPS01
	Voltage limits		- 15…+ 20%
Ambient air temperature conforming to EN 61131-2	Operating	**°F (°C)**	+32… + 140 (0…+ 60)
	Storage	**°F (°C)**	-40… + 185 (- 40…+ 85)
Digital input and output connections			Shielded dual twisted pair cable recommended to provide protection against electromagnetic interference, or Ø 0.47 in (12mm) max. cable with connection to ground of rack XPSMFGEH01
Digital inputs			
Number			24, electrically isolated
Nominal input voltage		**V**	⎓ 24
Input voltage	At state 0	**V**	5 max.
	At state 1	**V**	10…30
Input current	At state 0	**mA**	1.0 at 5 V
	At state 1	**mA**	2 at 10 V, 5 at 24 V
Operational data			⎓ 3.3 V / 0.3 A, ⎓ 24 V / 0.5 A
Digital outputs			
Number			16, electrically isolated
Output voltage		**V**	⎓ 18.4…26.8
Internal volt drop			2 V max. at 2 A
Output current	At 86 °F (30 °C)	**A**	2 per output channel, 8 max. per card. Continuous short-circuit proof
Minimum current		**mA**	2 per channel
Permissible current	At state 0	**mA**	1 max. at 2 V



XPSMFDIO241601

References

Description	Specifications	Reference	Weight oz (kg)
I/O card	■ 24 digital inputs ■ 16 digital outputs, configurable for line control	**XPSMFDIO241601**	9.171 (0.260)

Connections

Digital inputs

Item	Connection	Screw N°	Screw	Function
A	**Digital inputs**	01	LS+	Supply for inputs 1 to 8
		02	I1	Input 1
		03	I2	Input 2
		04	I3	Input 3
		05	I4	Input 4
		06	I5	Input 5
		07	I6	Input 6
		08	I7	Input 7
		09	I8	Input 8
B	**Digital inputs**	10	LS+	Supply for inputs 9 to 16
		11	I9	Input 9
		12	I10	Input 10
		13	I11	Input 11
		14	I12	Input 12
		15	I13	Input 13
		16	I14	Input 14
		17	I15	Input 15
		18	I16	Input 16
C	**Digital inputs**	19	LS+	Supply for inputs 17 to 24
		20	I17	Input 17
		21	I18	Input 18
		22	I19	Input 19
		23	I20	Input 20
		24	I21	Input 21
		25	I22	Input 22
		26	I23	Input 23
		27	I24	Input 24

Digital outputs

Item	Connection	Screw N°	Screw	Function
D	**Digital outputs**	28	L-	Reference pole for outputs 1 to 8
		29	O1	Output 1
		30	O2	Output 2
		31	O3	Output 3
		32	O4	Output 4
		33	O5	Output 5
		34	O6	Output 6
		35	O7	Output 7
		36	O8	Output 8

Item	Connection	Screw N°	Screw	Function
E	**Digital outputs**	37	L-	Reference pole for outputs 9 to 16
		38	O9	Output 9
		39	O10	Output 10
		40	O11	Output 11
		41	O12	Output 12
		42	O13	Output 13
		43	O14	Output 14
		44	O15	Output 15
		45	O16	Output 16

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
“In rack” relay output card



Introduction

The relay output card **XPSMFDO801** is designed to manage up to :
- category 4 conforming to EN 954-1,
- performance level “e” conforming to EN/ISO 13849-1,
- SIL 3 (safety integrity level) conforming to EN/IEC 61508.

■ It incorporates 8 relay safety outputs (3.15 A fuse) that are configurable using software **XPSMFWIN**.
■ The card can be installed in rack **XPSMFGEH01** as many times as required in the six slots available.

Functional diagram



Description

On the front cover of the card:
1 Two process status LEDs (RUN, ERR).
2 Eight output status LEDs.
3 Eight removable screw terminal blocks (2 terminals per block) for connection of outputs *(1)*.
4 Grip to assist installation/removal.
5 On the rear: terminals for automatic electrical connection to the back plane bus of rack **XPSMFGEH0**.

LED details

LED	Color	Status	Meaning
RUN	Green	On	Voltage present.
		Off	No voltage.
ERR	Red	On	Card defect or external error, diagnostics response.
		Off	No error regarding the card or on the channels.

*(1) Removable screw terminals are provided with the “in rack” card **XPSMFDO801**.*

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Modular, XPSMF60
"In rack" relay output card

Specifications

Output card type			XPSMFDO801
Supply	Voltage	**V**	⎓ 24, supplied by rack XPSMFGEH01 incorporating power supply module XPSMFPS01
	Voltage limits		- 15…+ 20%
Ambient air temperature conforming to EN 61131-2	Operating	**°F (°C)**	+ 32… + 122 (0…+ 50) *(1)*
	Storage	**°F (°C)**	- 40… + 185 (- 40…+ 85)
Number and type of outputs			8 relay outputs, relay hard contact, with N.O. contact
Relay	Type		2 safety relays with positively guided contacts
	Degree of protection		IP 40
	Contact material		Silver alloy, gold flashed
	Switching time	**ms**	30 approx.
	Reset time	**ms**	20 approx.
	Bounce time	**ms**	30 approx.
	Mechanical life		≥ 10 million operating cycles
	Electrical life		≥ 250 000 operating cycles on full load (resistive) and ≤ 0.1 operating cycles/s
Switching voltage		**V**	⎓ 6 V…250 V
Switching current		**A**	3.15 A with internal fuse Breaking capacity 100 A
Switching capacity	a.c.	**VA**	700 max., cos ϕ = 1
	d.c. (non inductive)		≤ ⎓ 30 V: 95 W max. (3.15 A) ≤ ⎓ 70 V: 40 W max. (0.5 A) ≤ ⎓ 110 V: 33 W max. (315 A) With suitable external fuse
Operational data			⎓ 3.3 V / 0.2 A, ⎓ 24 V ± 10% *(1)* / 0.7 A
LED display			Yes
Connections			Shielded dual twisted pair cable recommended to provide protection against electromagnetic interference, or Ø 0.47 in (12 mm) max. cable with connection to ground of rack XPSMFGEH01

(1) Limited system data.

References

Description	Specifications	Reference	Weight oz (kg)
Output card	8 relay outputs ⎓ 6 V…250 V	**XPSMFDO801**	21.164 (0.600)



XPSMFDO801

Connections

Item	Connection	Screw N°	Screw	Function
A	**Relay output**	01	1	Contact 1, terminal A
		02		Contact 1, terminal B
B	**Relay output**	03	2	Contact 2, terminal A
		04		Contact 2, terminal B
C	**Relay output**	05	3	Contact 3, terminal A
		06		Contact 3, terminal B
D	**Relay output**	07	4	Contact 4, terminal A
		08		Contact 4, terminal B
E	**Relay output**	09	5	Contact 5, terminal A
		10		Contact 5, terminal B
F	**Relay output**	11	6	Contact 6, terminal A
		12		Contact 6, terminal B
G	**Relay output**	13	7	Contact 7, terminal A
		14		Contact 7, terminal B
H	**Relay output**	15	8	Contact 8, terminal A
		16		Contact 8, terminal B

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular, XPSMF
Communication on network and bus

Introduction

To communicate, Preventa™ compact and modular safety PLCs **XPSMF** are fitted with:
- Integrated 2 or 4 RJ45 Ethernet switched ports for transfer Safety and Non-safety related data (Safety Related using SafeEthernet protocol, Non-Safety Related using Modbus™ TCP/IP protocol),
- and/or serial communication ports for transferring non safety related data.

Safety communication on a single network
The Ethernet network supports the SafeEthernet protocol: physically, a single network is possible for communication between:
- safety products (SafeEthernet protocol),
- non safety related products (Modbus TCP/IP and other protocols),
- safety related and non safety related products (Modbus TCP/IP protocol).

Communication on more than one network: a minimum of two separate cabling systems are established.
- An Ethernet network with Modbus TCP/IP protocol is used for communication between non safety related products and the safety PLCs.
- An Ethernet network with SafeEthernet protocol is used for communication between the safety PLCs **XPSMF** and safety remote I/O modules **XPSMF1/2/3**.
- A Modbus serial network with Modbus serial (RTU) protocol is used for communication between the safety PLCs **XPSMF** and non safety related products.
- A PROFIBUS DP network with PROFIBUS protocol is used for communication between the safety PLCs **XPSMF** and non safety related products.

Safety PLCs	Communication on Ethernet network			Communication on fieldbus	
Compact	**Port** (number x type)	**SafeEthernet protocol: safe communication**	**Modbus TCP/IP protocol: non safe communication**	**Modbus serial (RTU) protocol**	**PROFIBUS DP protocol**
XPSMF31222	4 x RJ45	yes	yes	no	no
XPSMF3022	4 x RJ45	yes	yes	yes (slave) / 1 x SUB-D (9-pin)	no
XPSMF3502	4 x RJ45	yes	yes	no	no
XPSMF3522	4 x RJ45	yes	yes	yes (slave) / 1 x SUB-D (9-pin)	no
XPSMF3542	4 x RJ45	yes	yes	no	yes (slave) / 1 x SUB-D (9-pin)
XPSMF4000	2 x RJ45	yes	no	no	no
XPSMF4002	2 x RJ45	yes	yes	no	no
XPSMF4020	2 x RJ45	yes	no	yes (slave) / 1 x RJ45	no
XPSMF4022	2 x RJ45	yes	yes	yes (slave) / 1 x RJ45	no
XPSMF4040	2 x RJ45	yes	no	no	yes (slave) / 1 x SUB-D (9-pin)
XPSMF4042	2 x RJ45	yes	yes	no	yes (slave) / 1 x SUB-D (9-pin)
Modular					
XPSMFCPU22 (central processing unit)	4 x RJ45	yes	yes	yes (slave) / 1 x SUB-D (9-pin)	no

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs

Compact and modular, XPSMF

Communication on network and bus

Connection on Ethernet network



1 Premium™ processor **TSX P57 ●634M/●623M** or module **TSX ETY 4103** on Premium™ automation platform: Modbus™ TCP/IP client (master).
2 Graphic supervision terminal **XBTGT5230**: Modbus TCP/IP client (master).
3 Modular safety PLC **XPSMF60**: Modbus TCP/IP server (slave).
4 Safety remote I/O modules **XPSMF1/2/3**.
5 Graphic supervision terminal **XBTGT2130**: Modbus TCP/IP client (master).
6 Compact safety PLCs **XPSMF31/30/35**: Modbus TCP/IP server (slave).
7 Shielded twisted pair cables **490 NTW 000 ●●**, lengths 6.6 to 262 ft (2 to 80 m).
8 Compact safety PLCs **XPSMF40**: Modbus TCP/IP server (slave).
9 Programming PC.
10 Ethernet connector.

Specifications

Protocol		**SafeEthernet**	
Compatibility with compact and modular safety PLCs		**XPSMF4000, XPSMF4002, XPSMF4020, XPSMF4022, XPSMF4040, XPSMF4042**	**XPSMF31222, XPSMF3022, XPSMF3502, XPSMF3522, XPSMF3542, XPSMFCPU22 (central processing unit of modular PLC XPSMF60)**
Transmission	Speed (Baud rate)	100 Mbps Half duplex, 10 Mbps Full duplex, Autonegotiation	
	Communication ports	Integrated 2 RJ45 switched Ethernet communications ports	Integrated 4 RJ45 switched Ethernet communications ports
	Medium	Dual twisted pair cable, category 5D or better	
Structure		10BASE-T/100BASE-TX	
Transparent Ready™ service	Class	A10	
	Standard Ethernet TCP/IP communication services (supported by compact and modular safety PLCs)	Modbus™ TCP/IP	
		Modbus TCP/IP messaging (reading/writing of data words) Modbus identification requests	
	TCP port	Standard 502	
	Max. number of TCP/IP connections	1 to 20	

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety PLCs
Compact and modular, XPSMF
Communication on network and bus

Connection on Modbus™ serial (RTU)



1 Premium™ module **TSXSCY21601**: access to Modbus serial, on a Premium™ automation platform: Modbus serial (RTU) master.
2 Cable **TSXSCYCM6030**.
3 Graphic supervision terminal **XBTGT5230**: Modbus serial (RTU) master.
4 Cable **XBTZ938** + adaptor **XBTZG909**.
5 Cables **VW3A83●6R●●** for Modbus serial, lengths 1.0 to 9.8 ft (0.3 to 3 m).
6 Modbus serial splitter box **LU9 GC3** for equipment connection.
7 Cables **TSXCSA ●00** for Modbus serial, lengths 328 to 1640 ft (100 to 500 m).
8 Compact safety PLCs **XPSMF4020/MF4022**: Modbus serial (RTU) slaves, Modbus TCP/IP server.
9 Programming PC.
10 Graphic supervision terminal **XBTGT2130**: Modbus serial (RTU) client.
11 Safety remote I/O modules **XPSMF1/2/3**.
12 Compact safety PLCs **XPSMF3022/3522:** Modbus serial (RTU) slaves, Modbus TCP/IP server.
13 Modular safety PLC **XPSMF60**, Modbus serial (RTU) slaves, Modbus TCP/IP server.
14 Direct connection cables **XPSMCSCY** for safety PLCs to Premium™ module **TSXSCY21601**, length 1 ft (0.3 m).
15 Connector **XPSMFADAPT** (RJ45/SUB-D 9-pin male) for connector FB2 or FB3, depending on PLC.

Specifications

Bus type			**Modbus serial (RTU)**		
Compatibility with compact and modular safety PLCs			**XPSMF3022, XPSMF3522**	**XPSMF4020, XPSMF4022**	**XPSMFCPU22 (CPU of modular PLC XPSMF60)**
Serial link port		Number and type	1 x SUB-D 9-pin female (FB3)	1 x RJ45 (Modbus)	1 x SUB-D 9-pin female (FB2)
		Master/Slave	Slave		
Addressing			122 slave addresses. Addressing range: 1…247		
Medium			Shielded twisted pair cable		
Physical layer			RS 485		
Services			13 Modbus functions (reading/writing of bits and words, event counters, connection events, diagnostics, identification)		
	Functions	**Code**	Modbus slave		
		01	Reading n bits of output		
		02	Reading n bits of inputs		
		03	Reading n words of output		
		04	Reading n words of inputs		
		23	Reading/writing variables		
		15	Writing bit variables		
		16	Writing word variables		
		05	Writing 1 bit of output		
		06	Writing 1 word of output		
		08	Diagnostics		
		43	Reading equipment identification		
Transmission	**Binary transfer rate (bps)**		115 200, 76 800, 62 500, 57 600, 38 400, 19 200, 9600, 4800, 2400, 1200, 600, 300. Default value: 57 600		
Elements	**Parity**		None. Odd. Even. Default value: even		
	Stop bit		Standard. 1 stop bit. 2 stop bits. Default value: standard		

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Connection on PROFIBUS DP



1 Graphic terminal connected to TER/AUX port of Premium automation platform: PROFIBUS DP master.
2 Connecting cable (RS 485) + adaptor .
3 PROFIBUS module on Premium™ processor: PROFIBUS DP master.
4 Connecting cable ●, lengths 328 and 1312 ft (100 and 400 m).
5 Connector (SUB-D 9-pin male) on the FB3 connector of safety PLC or on the “PROFIBUS” connector of safety PLC .
6 Compact safety PLC : PROFIBUS DP slaves, Modbus™ TCP/IP server.
7 Compact safety PLCs : PROFIBUS DP slaves, Modbus TCP/IP server.
8 Graphic supervision terminal : Modbus TCP/IP client.
9 Safety remote I/O modules .

Specifications

Bus type		**PROFIBUS DP**	
Compatibility with compact safety PLCs		**XPSMF3542**	**XPSMF4040, XPSMF4042**
Serial port	Number and type	1 x SUB-D 9-pin female (FB3)	1 x SUB-D 9-pin female (PROFIBUS)
	Master/Slave	Slave, V0	
Physical layer		RS 485	
Topology		Linear, with line terminators at each end	
Medium		Shielded twisted pair cable	
Number of slaves		32 slaves on each segment, 126 slaves maximum with repeaters	
Data exchange speed		9.6 kbps…12 Mbps, depending on the length of the segment (3937...328 ft / 1200...100 m)	

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Programming software XPSMFWIN for Preventa™ compact and modular safety PLCs XPSMF

Introduction

Conforming to standard IEC 61131-3, programming software **XPSMFWIN** is designed for programming all safety PLCs **XPSMF** and safety remote I/O modules. This safety software is part of the Safety Suite V2 software pack.

To create a program the user can use predefined function blocks, such as the elementary logic functions and certified function blocks, by dragging the blocks into the software programming area.
The “drag and drop” operation of the Windows® programming environment enables quick and simple creation of configurations.

Using the **XPSMFWIN** software, it is possible to program complete systems consisting of several safety PLCs and safety remote I/O modules.
The conditions detailed in the software manual must be adhered to and a complete report accompanying the certificate should be established.

Reference

■ Reference **SSV1XPSMFWIN** contains the full version of the programming software XPSMFWIN software for the XPSMF Safety PLCs. The XPSMFWIN is part of our Safety Suite and is not available separately.

Description	Operating system	Composition	Language	Reference	Weight oz (kg)
Configuration software XPSMFWIN for programming compact XPSMF40●●, XPSMF3● and modular XPSMF60 safety PLCs	Windows® 2000, Windows® XP	CD-ROM + user manual	English, German, French	**SSV1XPSMFWIN** *Available with Safety Suite V2 software pack for safety systems*	18.342 (0.520)

Installation



Software XPSMFWIN: project management

Software **XPSMFWIN** uses an electronic key (dongle) for protection against unauthorized use.

A USB dongle is available. It must be connected to the PC before the software is installed.
Drivers must also be installed on the computer to recognise the dongle. These drivers are included with software **XPSMFWIN** and are automatically installed during installation.
To install software **XPSMFWIN**:
□ Connect the dongle.
□ Insert the **SSV1XPSMFWIN** software CD-ROM into the computer.
□ Launch installation.
□ Select the preferred language from the configuration menu.
□ Follow the guided installation procedure for the software.
□ Restart the computer.
□ Launch the software by clicking on the Safety Suite icon on the desktop.

The computer hardware requirements are as follows:
■ Processor (Intel® Pentium II 400 MHz minimum, Intel® Pentium III 800 MHz recommended).
■ RAM (128 Mb minimum, 256 Mb recommended).
■ Graphics card (2 Mb XGA, 1024 x 768, 256 colors minimum, 8 Mb XGA, 1280 x 1024 True color recommended).
■ Hard disk (1 Gigabyte minimum).
■ Operating system:
□ Windows® 2000 Professional with Service Pack 1 or higher.
□ Windows® XP with Service pack 1.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Programming software XPSMFWIN for Preventa™ compact and modular safety PLCs XPSMF

Safety related communication

Safety related communication for the safety systems is performed using SafeEthernet protocol.
SafeEthernet is a TCP/IP based protocol that uses highly intelligent switches to provide extremely reliable deterministic communication.
Connection is made automatically between the master and slaves when assigning the slaves to the corresponding masters. Transmission speeds of up to 100 Mbps in Half duplex mode and 10 Mbps in Full duplex mode can be achieved and using Autonegotiation ensures the correct baud rates for the connection.
Each safety PLC can manage up to 64 safety connections. These 64 connections can consist of safety remote I/Os and other safety PLCs.
Communication between two safety PLCs is established via a Peer-Peer link. This Peer-Peer communication enables data between two or more safety PLCs to be communicated safely.
The connectivity of all the equipment enables centralised or decentralised networks to be established. It also enables safety PLCs and safety remote I/O modules to be connected anywhere on the network with only the assigning of an IP address, to each module, in the software.

Interface

XPSMFWIN features two distinct windows, one for internal configuration and one for hardware management.

- Project management

This window enables creation, archiving and recalling of all the user programs. It contains all the logic functions and predefined certified function blocks.

- Hardware management

This window enables all hardware specific data, inputs and outputs and signal transfer between safety controllers to be defined, as well as the various safety PLCs being used or safety remote I/O modules.

Items included in the XPSMFWIN interface

- Menu and title bar
- Toolbar and status bar
- Windows® layout, structure window and work space
- Error display window

XPSMFWIN is a program offering numerous functions and features intuitive, Windows® style, operation, making it a very user-friendly programming environment.

Project Management window layout

On launching software **XPSMFWIN**, the standard screen shown below opens.
This screen generally includes the following items:



1. Title bar.
2. Structure window.
3. Menu bar.
4. Project management toolbar.
5. Work space.
6. FBD (Function Block Diagram) editor toolbar.
7. Error display window.
8. Status bar with coordinate information of the function plan editor.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Programming software XPSMFWIN for Preventa™ compact and modular safety PLCs XPSMF



Structure window

1 Configuration.
2 Resource folder.
3 Communication protocols.
4 Remote I/O folder.
5 Remote I/O type.
6 Components and modules.
7 Resource type.

The structure window displays the hierarchical structure of the project. Selecting one of three views provides the user with different levels of detail.



Complete project



All POUs (Program Organisation Units)



All data types

FBD (Function Block Diagram) editor

Using this editor, the user can create function blocks in FBD (Function Block Diagram) language or SFC (Sequential Function Chart) language.
The FBD editor consists of the following panes:



1 Drawing field.
2 Variable declaration editor.
3 Overview window.
4 Interface declaration editor.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Programming software XPSMFWIN for Preventa™ compact and modular safety PLCs XPSMF

Programming

Software **XPSMFWIN** enables programming of the entire range of Preventa™ safety PLCs **XPSMF**.
The powerful and easy to use methodology of this software enables users to quickly and simply familiarize themselves with the product. The Windows® based look and user-friendliness provides users with trouble free operation of the software.

On launching the software, the program's start-up assistant opens simultaneously. This assistant enables the user to easily open a new or existing file, delete a file or archive a file. Once a new or existing file is opened, the user quickly accesses the working environment.

Configuration

The user can begin creating a configuration as soon as a personal library is set-up, that will contain the user configuration(s).
Once the personal library is opened, the user can use the standard library function blocks (And, Or, Not, and Flip-Flop) to create exactly what is required.

The user drags the function blocks into the configuration environment and places them where required. Once the function blocks are placed, the user can define specific signals or variables for the inputs and outputs.

The Hardware menu enables assigning of all the signals to the relevant inputs and outputs.

From within the Hardware menu the relevant safety PLCs are selected using the pull-down menu of each resource.
To add additional safety PLCs a new resource is easily created and assigned with the type of safety PLC.

Up to 64 remote inputs/outputs can be assigned to each safety PLC.
Once all the safety PLCs and remote I/Os have been selected, the signals can be simply connected to the relevant safety modules.
The "drag and drop" function enables defining of the inputs and outputs.

Therefore, configuration is very quick and simple.
Once all the inputs and outputs have been defined the user can compile the entire program, which is performed in the configuration menu.
Compilation must be performed twice and the results of both compilations printed and compared. If both results match, the program can be downloaded via the Ethernet RJ45 communication port on any of the safety PLCs.

Program execution

The program will automatically be stored in all the safety PLCs.
The safety PLCs can then execute the configuration and full diagnostics can be viewed on screen.
The software incorporates various diagnostic options that can be used to quickly identify the presence of errors. Some of these diagnostic options are "On-line test": which displays the logic condition of all the I/Os. Others allow the user to view the status of the transmission line, the cycle time and errors that have occurred on the communication line.

The programming tool enables the user to create and design to suit their needs. Other certified function blocks are available, which enable the overall configuration time to be further reduced. Included in these additional blocks are "Muting" and "Emergency stop" functions, together with 12 other certified functions.

Modbus™ TCP/IP, Modbus serial (RTU) and PROFIBUS DP protocols are included in software **XPSMFWIN**. They can be used for non safety related data transfer.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Non safety related communication protocols

Modbus™ TCP/IP server (slave)

The **XPSMF** range of safety PLCs (**XPSMFCPU22**, **XPSMF40●2**, **XPSMF35●2**, **XPSMF3022** and **XPSMF31222**) allow the communication of non safety related data on an Ethernet network via a Modbus TCP/IP link.



On the Ethernet network, several masters (clients) can read data provided by several slaves (servers).

Creation of Modbus TCP/IP servers is quick and simple: Select Protocols / New / Modbus Slave.

Modbus serial (RTU)

The **XPSMF** range of safety PLCs (**XPSMFCPU22**, **XPSMF402●**, **XPSMF352●** and **XPSMF3022**) allow the communication of non safety related data on a Modbus serial (RTU) link.
On the Modbus serial network, a master can read the data provided by several slaves on a network segment.



Creation of Modbus (RTU) servers is quick and simple: Select Protocols / New / Modbus Slave.
Select the serial option in the properties window to activate, then select the signals to send and receive from your standard automation system equipment.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Non safety related communication protocols

PROFIBUS DP

To create a PROFIBUS DP slave on a resource (PLC), a project must be created.
Safety PLCs **XPSMF404●** and **XPSMF3542** are PROFIBUS DP V0 slaves.
Within hardware management, assignment of PROFIBUS DP slaves is simple:
Select Protocols / New / PROFIBUS DP slave from the protocol tag of a resource.





The PROFIBUS DP Slave menu contains the following fields:
□ Connect signals tab: for connecting the inputs and outputs to and from the safety PLC, and predefined signals for diagnostics.
□ Import and Export tool: used for importing and exporting the signal list to/from a .CSV format file (format that can be imported into a standard automation PLC).
□ Properties tab: enabling setting of the station address, interface, baud rate and data refresh rate.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular, XPSMF
Safety remote input, output and input/output modules
XPSMF1/2/3

2

Introduction

Remote input, output and input/output modules:
- Location: within the vicinity of machines to be monitored.
- Extension of the I/O capacity of compact and modular safety PLCs.
- Designed for use in safety related parts of control systems up to category 4 conforming to EN 954-1, up to performance level “e” conforming to EN/ISO 13849-1, and up to SIL 3 conforming to EN/IEC 61508.

*Products referenced **XPSMF1DI1601** and **XPSMF2●●●●●●** are marked **HIMatrix® F1DI** and **HIMatrix® F2DI** (manufactured by Hima, sold by Schneider Electric).*

User memory		Application	–		
		Data	–		
Response time			Depending on size of application		
Maximum power consumption			0.8 A	0.5 A	9 A
Supply			External ⎓ 24 V supply (with separate protection conforming to EN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)		
Inputs	**Digital**	Number of channels	16, not electrically isolated	–	–
		Current at state 0	1.5 mA max., 1 mA at 5 V	–	–
		Current at state 1	≥ 2 mA at ⎓ 15 V	–	–
	Analog	Number of channels	–	–	–
		Range: voltage/current	–	–	–
	Counting	Number of channels	–	–	–
		Current	–	–	–
Outputs	**Digital**	Number of channels	–	4, not electrically isolated	16, not electrically isolated
		Output current	–	5 A max.	1 A max. at 140 °F (60 °C), 2 A max. at 104 °F (40 °C)
	Analog	Number of channels	–	–	–
		Range: voltage/current	–	–	–
	Relay	Number	–	–	–
		Switching voltage	–	–	–
	Line control	Number	4, not electrically isolated	–	–
		Current/Voltage	60 mA/20 V	–	–
Input/output connections			Removable screw terminal blocks *(1)*		
Safety communication on Ethernet network using SafeEthernet protocol			Yes, access to network via integrated 2 RJ45 switched Ethernet communications ports		
Safety remote I/O module type			**XPSMF1DI1601**	**XPSMF2DO401**	**XPSMF2DO1601**
See page			2/78	2/85	

*(1) Removable screw terminal blocks are provided with safety remote I/O modules **XPSMF1/2/3**.*

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular, XPSMF
Safety remote input, output and input/output modules XPSMF1/2/3

*Products referenced **XPSMF2●●●●●●●** and **XPSMF3●●●●●●●** are marked **HIMatrix® F2DO** and **HIMatrix® F3...** (manufactured by Hima, sold by Schneider Electric).*

–					
–					
Depending on size of application					
0.6 A	0.6 A	8 A	14 A	8 A	0.8 A
External ⎓ 24 V supply (with separate protection conforming to EN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)					
–	–	8, not electrically isolated	16, not electrically isolated	20, not electrically isolated	–
–	–	1.5 mA max. 1.25 mA at ⎓ 5 V	1.5 mA max. 1 mA at ⎓ 5 V	1.5 mA max. 1.25 mA at ⎓ 5 V	–
–	–	> 2 mA at ⎓ 15 V	> 2 mA at ⎓ 15 V	⩾ 2 mA at ⎓ 15 V	–
–	–	–	–	–	8 single-pole
–	–	–	–	–	⎓ 0…10 V/0…20 mA *(1)*
–	–	–	–	–	–
–	–	–	–	–	–
–	–	8 DO+ (reference pole L-) 2 DO- (reference pole S+)	8 2-pole or 16 single-pole, not electrically isolated	8, not electrically isolated *(2)*	–
–	–	DO+: channels 1 to 3 and 5 to 7: 0.5 A at 140 °F (60 °C) channels 4 and 8: 1 A at 140 °F (60 °C), 2 A at 104 °F (40 °C) DO-: channels 1 and 2: 1 A at 140 °F (60 °C)	2 A max. at 104 °F (40 °C), 1 A max. at 140 °F (60 °C), 10 mA min.	Channels 1 to 3 and 5 to 7: 0.5 A at 140 °F (60 °C) Channels 4 and 8: 1 A at 140 °F (60 °C), 2 A at 122 °F (50 °C)	–
–	–	–	–	–	4 non safety related outputs
–	–	–	–	–	Usable range: 0…20 mA Nominal range: 4…20 mA
8	16	–	–	–	–
⩾ 5 V, ⩽ ⎓ 250 V/ ∼ 250 V	⩾ 5 V, ⩽ ⎓ 30 V/ ∼ 60 V	–	–	–	–
–	–	2, not electrically isolated		–	–
–	–	60 mA/20 V	60 mA/20 V	–	–
Removable screw terminal blocks *(3)*					
Yes, access to network via integrated 2 RJ45 switched Ethernet communications ports					
XPSMF2DO801	**XPSMF2DO1602**	**XPSMF3DIO8801**	**XPSMF3DIO16801**	**XPSMF3DIO20802**	**XPSMF3AIO8401**
2/85		2/97			

*(1) With 500 Ω jumper (2) Configurable for Line control. (3) Removable screw terminal blocks are provided with safety remote I/O modules **XPSMF1/2/3**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote input modules XPSMF1

XPSMF1DI1601

*This product, referenced **XPSMF1DI1601**, is marked **HIMatrix® F1DI** (manufactured by Hima, sold by Schneider Electric).*

Introduction

XPSMF1DI1601 is a compact safety remote input module which is designed to extend the input capacity of safety PLCs **XPSMF**, either compact or modular, to which it is associated.
The communication with either the compact or modular safety PLCs is managed via one of its' integrated 2 RJ45 switched Ethernet communications ports.
The safety remote input module **XPSMF1DI1601** does not have a user program: it receives its instructions from its parent safety PLC.

Safety remote input module XPSMF1DI1601

Remote digital inputs		
N°	**Safety detection**	**Safety dialog**
16	Limit switches, Guard switches, with reset and with actuator, Light curtains type 2 and type 4, Safety mats and sensing edges	Mushroom head Emergency stops, Enclosures for control and signalling units, Two-hand control stations

Remote line control outputs	
N°	
4	Short-circuit and line break monitoring

Line control

Line control is a means of short-circuit and line break monitoring.
Using line control outputs enables SIL 3 (EN/IEC 61508) and category 4 (EN 954-1) safety to be achieved. The line control outputs send a high signal with a very short low signal, thus enabling a wiring anomaly (short-circuit, line break) to be seen at the inputs of the safety modules.
Example: The line control outputs 1 to 4 are connected to the digital inputs 1 to 16.

Safety PLCs

In order to meet safety requirements, the safety remote input module **XPSMF1DI1601** incorporates two essential functions (**Redundancy** and **Self-monitoring)** complying to category 4 conforming to EN 954-1 and performance level "e" conforming to EN/ISO 13849-1 in addition to the SafeEthernet safety communication protocol between this safety remote input module and the safety PLCs (**Special Switch**).
■ **Redundancy**: the dual processor integrated in the safety remote input module **XPSMF1DI1601** analyzes and compares the data received from the safety inputs and outputs. The incoming and outgoing data (programmed values and received values) are received in parallel by the two processors and compared in real-time.
■ **Self-monitoring ("Watchdog")**: the safety remote input module **XPSMF1DI1601** continuously monitors the data processing cycle and the execution of tasks, and intervenes if the cycle time does not conform to the predefined value.
■ **The integrated switch (Special Switch)** stores for a very short time and sends at very high speed the data provided by the inputs of the safety module on the Ethernet network, while avoiding signal collisions and excessive amounts of data on the network.

Functional diagram



Safety communication on Ethernet network

The safety input module **XPSMF1DI1601** incorporates two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, that enable communication on the Ethernet network using SafeEthernet communication protocol and therefore, data exchange with compact or modular safety PLCs **XPSMF**.

Introduction: page 2/76 | Specifications: page 2/78 | References: page 2/78 | Dimensions, mounting: page 2/79 | Connections: page 2/79

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs

Compact and modular

Safety remote input modules XPSMF1



Description

Safety remote input module XPSMF1DI1601

On the front cover of the metal enclosure:

1 One terminal block *(1)* for c 24 V supply.
2 Four terminal blocks *(1)* for connection of digital inputs, with input status LED (four LEDs per terminal block).
3 One terminal block *(1)* for connection of digital line control outputs, with four digital output status LEDs.
4 Two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, for connection on Ethernet network and for configuring IP address.
5 Eight process status LEDs.
6 One ground connection screw.
7 On the top: one “Reset” button.
8 On the rear face: one spring operated mounting device for mounting on 35 mm DIN rail.

Status LED details

Safety remote input module XPSMF1DI1601

LED	Color	Status	Meaning
Inputs 1…16	Orange	On	Inputs active.
Outputs 1…4	Orange	On	Outputs active.
24 VDC	Green	On	⎓ 24 V voltage present.
		Off	No voltage.
RUN	Green	On	Normal service mode, loaded program running, the PLC receives I/O messages, communication and hardware/ software tests carried out.
		Flashing	The CPU is in STOP and is not executing any user application. All the outputs are reset to a safe, de-energized state.
		Off	The CPU is in “ERROR” state (see ERROR).
ERROR	Red	On	Software error or hardware anomaly detected by the CPU.
			The monitoring program (Watchdog) has triggered the STOP state of the process because the programmed cycle time has been exceeded.
			The CPU has stopped the execution of the user application, ended all hardware and software tests and all outputs have been reset.
			The process can only be started again from the PC.
		Off	No errors detected.
PROG	Orange	On	The CPU is being loaded with a new configuration.
		Flashing	The FLASH ROM is being loaded with a new operating system.
		Off	No loading of configuration or operating system.
FORCE	Orange	On	The CPU is in RUN mode and force is active.
		Flashing	The system is not processing (STOP), but force is prepared and is activated if the dual processor is started.
		Off	Force mode not activated.
FAULT	Orange	On	Error display for line control.
			The user application has caused an error.
			The system configuration is defective.
			The loading of a new operating system was defective and the operating system is corrupt.
		Flashing	An error has occurred while writing to FLASH ROM memory (during updating of the operating system).
			One or more I/O errors have occurred.
		Off	None of the above errors have occurred.
OSL	Orange	Flashing	Emergency loading of the operating system is active.
BL	Orange	Flashing	COM in INIT_Fail state.
RJ45	Green	On	Full duplex mode operation.
		Flashing	Signal collision.
		Off	Half duplex mode operation, no collision.
	Yellow	On	Connection established.
		Flashing	Interface active.

*(1) Removable screw terminals are provided with safety input module **XPSMF1DI1601**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote input modules XPSMF1

Specifications

Safety remote input module type			XPSMF1DI1601
Supply voltage		**V**	⎓ 24 (external supply with separate protection conforming to EN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)
Voltage limits		**V**	- 15…+ 20%
Ambient air temperature	For operation	**°F (°C)**	+ 32… + 140 (0…+ 60)
	For storage	**°F (°C)**	- 40…+ 185 (- 40…+ 85)
Degree of protection			IP 20
Response time		**ms**	Depending on size of application
Current power consumption		**A**	0.8 max.
Backup battery			None
Digital inputs			
Number			16, not electrically isolated
Permissible current	At state 1	**mA**	≥ 2 at ⎓ 15 V
	At state 0	**mA**	1.5 max., 1 mA at 5 V
Switching point		**V**	Typically 7.5
Switching time		**µs**	250
Input supply			4 x 19.2 V/40 mA (on 24 V), protected against short-circuits
Line control outputs			
Number			4, not electrically isolated
Output voltage		**V**	20 (approximately, depending on the supply voltage)
Output current		**mA**	60
Minimum load			None
Response to overload			4 x ≥ 19.2 V, short-circuit current 60 mA at 24 V
Connections			See page 2/26 for wire sizes of the various connector types.

Communication

Ethernet network: safety communication using SafeEthernet protocol			
Transmission	Communication ports		Integrated 2 RJ45 switched Ethernet communications ports
	Baud rate	Mbps	100 Half duplex, 10 Full duplex, Autonegotiation
Structure			10BASE-T/100BASE-TX
Medium			Dual twisted pair cable, category 5D or better (Ethernet)

References

XPSMF1DI1601

*This product, referenced **XPSMF1DI1601**, is marked **HIMatrix® F1DI** (manufactured by Hima, sold by Schneider Electric).*

Safety remote input module (⎓ 24 V supply)

For use with	Digital inputs	Line control outputs	Ports	Reference	Weight oz (kg)
Safety PLCs, modular XPSMF60 or compact XPSMF40 and XPSMF31/30/35	16	4	Integrated 2 RJ45 switched Ethernet communications ports	**XPSMF1DI1601**	24.692 (0.700)

Connecting cables

Description	For	Reference	Weight oz (kg)
Ethernet network connecting cables	Connection between safety remote input modules and modular or compact safety PLCs XPSMF RJ45 connector fitted at each end	See 2/29	–

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs

Compact and modular

Safety remote input modules XPSMF1

Dimensions

XPSMF1DI1601



RJ45 connector for access to Ethernet network (SafeEthernet protocol)



Dual Dimensions: INCHES Millimeters

*(1) Removable screw terminals are provided with safety input module **XPSMF1DI1601**.*

Connections

XPSMF1DI1601



Item	Connection	Screw N°	Screw	Function
A1	**Supply**	–	L+	⎓ 24 V
			L+	⎓ 24 V
			L-	⎓ 24 V (reference pole)
			L-	⎓ 24 V (reference pole)
A2	**Ground**	–	⏚	Ground
B	**Digital inputs**	1	LS+	Sensor supply for inputs 1 to 4
		2	1	Digital input 1
		3	2	Digital input 2
		4	3	Digital input 3
		5	4	Digital input 4
		6	L-	Reference pole
C	**Digital inputs**	7	LS+	Sensor supply for inputs 5 to 8
		8	5	Digital input 5
		9	6	Digital input 6
		10	7	Digital input 7
		11	8	Digital input 8
		12	L-	Reference pole
D	**Digital inputs**	13	LS+	Sensor supply for inputs 9 to 12
		14	9	Digital input 9
		15	10	Digital input 10
		16	11	Digital input 11
		17	12	Digital input 12
		18	L-	Reference pole
E	**Digital inputs**	19	LS+	Sensor supply for inputs 13 to 16
		20	13	Digital input 13
		21	14	Digital input 14
		22	15	Digital input 15
		23	16	Digital input 16
		24	L-	Reference pole
F	**Line control outputs**	25	L+	Outputs common
		26	1	Output 1
		27	2	Output 2
		28	3	Output 3
		29	4	Output 4
		30	L-	Outputs common

Item	Connection	Type	Function
G	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety remote I/O and the programming terminal in a point to point or via an Ethernet network for setting the IP address
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote output modules XPSMF2

XPSMF2DO401

XPSMF2DO1601

XPSMF2DO801

XPSMF2DO801

*Products referenced **XPSMF2●●●●●●** are marked **HIMatrix® F2 DO...** (manufactured by Hima, sold by Schneider Electric).*

Introduction

XPSMF2DO●●●● are compact safety remote output modules which are designed to extend the output capacity of safety PLCs **XPSMF**, either compact or modular, to which they are associated.
The communication with either the compact or modular safety PLCs is managed via one of its' integrated 2 RJ45 switched Ethernet communications ports.
Safety modules **XPSMF2DO●●●●** do not have a user program: they receive their instructions from its parent safety PLC.

Safety remote output modules XPSMF2DO●●●●

Safety output modules	Remote outputs		
	N°	Type	
XPSMF2DO401	**4**	Digital power outputs	**Safety actuators:** Contactors-motors, Control relays, Variable speed drives **Safety dialog:** Beacons and indicator banks, rotating mirror beacons, sirens
XPSMF2DO1601	**16**	Digital outputs	
XPSMF2DO801	**8**	Relay outputs	
XPSMF2DO1602	**16**	Relay outputs	

Safety PLCs

In order to meet safety requirements, the safety remote output modules **XPSMF2DO●●●●** incorporate two essential functions (**Redundancy** and **Self-monitoring)** complying to category 4 conforming to EN 954-1 and performance level "e" conforming to EN/ISO 13849-1 in addition to the SafeEthernet safety communication protocol between these safety remote output modules and the safety PLCs (**Special Switch**).

■ **Redundancy**: the dual processor integrated in the safety remote output modules **XPSMF2** analyzes and compares the data received from the safety inputs and outputs. The incoming and outgoing data (programmed values and received values) are received in parallel by the two processors and compared in real-time.
■ **Self-monitoring ("Watchdog")**: the safety remote output modules **XPSMF2** continuously monitor the data processing cycle and the execution of tasks, and intervenes if the cycle time does not conform to the predefined value.
■ **The integrated switch (Special Switch)** stores for a very short time and sends at very high speed the data provided by the outputs of the safety modules on the Ethernet network, while avoiding signal collisions and excessive amounts of data on the network.

Functional diagrams

Remote output module XPSMF2DO401



Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote output modules XPSMF2

Functional diagrams (continued)

Remote output module XPSMF2DO801



Remote output module XPSMF2DO801



Remote output module XPSMF2DO1602



Safety communication on Ethernet network

The safety remote output modules **XPSMF2DO●●●●** incorporate two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, that enable communication on the Ethernet network using SafeEthernet communication protocol and therefore, data exchange with compact or modular safety PLCs **XPSMF**.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote output modules XPSMF2



Description

Remote output module XPSMF2DO401

On the front cover of the metal enclosure:

1 Two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, for connection on Ethernet network and for configuring IP address.
2 Eight process status LEDs.
3 One ground connection screw.
4 Four terminal blocks *(1)* for connection of digital outputs, with output status LED (one LED per terminal block).
5 On the top: one “Reset” button.
6 On the rear face: one spring operated mounting device for mounting on 35 mm DIN rail.



Remote output module XPSMF2DO1601

On the front cover of the metal enclosure:

1 Two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, for connection on Ethernet network and for configuring IP address.
2 Eight process status LEDs.
3 One ground connection screw.
4 One terminal block *(1)* for ⎓ 24 V supply.
5 Four terminal blocks *(1)* for connection of digital outputs, with output status LED (four LEDs per terminal block).
6 One terminal block for connection of output channels.
7 On the top: one “Reset” button.
8 On the rear face: one spring operated mounting device for mounting on 35 mm DIN rail.



Remote output module XPSMF2DO801

On the front cover of the metal enclosure:

1 Two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, for connection on Ethernet network and for configuring IP address.
2 Eight process status LEDs.
3 One ground connection screw.
4 One terminal block *(1)* for ⎓ 24 V supply.
5 Eight terminal blocks *(1)* for connection of relay outputs, with output status LED (one LED per terminal block).
6 On the top: one “Reset” button.
7 On the rear face: one spring operated mounting device for mounting on 35 mm DIN rail.



Remote output module XPSMF2DO1602

On the front cover of the metal enclosure:

1 Two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, for connection on Ethernet network and for configuring IP address.
2 One terminal block *(1)* for ⎓ 24 V supply.
3 One ground connection screw.
4 Eight process status LEDs.
5 Four terminal blocks *(1)* for connection of relay outputs, with relay output status LEDs.
6 On the top: one “Reset” button.
7 On the rear face: one spring operated mounting device for mounting on 35 mm DIN rail.

*(1) Removable screw terminals are provided with the safety output modules **XPSMF2**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Status LED details

Safety remote output modules XPSMF2DO●●●●

LED	Color	Status	Meaning
Outputs 1…16	Orange	On	Outputs active.
24 VDC	Green	On	⎓ 24 V voltage present.
		Off	No voltage.
RUN	Green	On	Normal service mode, loaded program running, the PLC receives I/O messages, communication and hardware/ software tests carried out.
		Flashing	The CPU is in STOP and is not executing any user application. All the outputs are reset to a safe, de-energized state.
		Off	The CPU is in "ERROR" state (see ERROR).
ERROR	Red	On	Software error or hardware anomaly detected by the CPU.
			The monitoring program (Watchdog) has triggered the STOP state of the process because the programmed cycle time has been exceeded.
			The CPU has stopped the execution of the user application, ended all hardware and software tests and all outputs have been reset.
			The process can only be started again from the PC.
		Off	No errors detected.
PROG	Orange	On	The CPU is being loaded with a new configuration.
		Flashing	The FLASH ROM is being loaded with a new operating system.
		Off	No loading of configuration or operating system.
FORCE	Orange	On	The CPU is in RUN mode and force is active.
		Flashing	The system is not processing (STOP), but force is prepared and is activated if the dual processor is started.
		Off	Force mode not activated.
FAULT	Orange	On	Error display for line control.
			The user application has caused an error.
			The system configuration is defective.
			The loading of a new operating system was defective and the operating system is corrupt.
		Flashing	An error has occurred while writing to FLASH ROM memory (during updating of the operating system).
			One or more I/O errors have occurred.
		Off	None of the above errors have occurred.
OSL	Orange	Flashing	Emergency loading of the operating system is active.
BL	Orange	Flashing	COM in INIT_Fail state.
RJ45	Green	On	Full duplex mode operation.
		Flashing	Signal collision.
		Off	Half duplex mode operation, no collision.
	Yellow	On	Connection established.
		Flashing	Interface active.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote output modules XPSMF2

Specifications

Safety remote output module type			XPSMF2DO401	XPSMF2DO1601	XPSMF2DO801	XPSMF2DO1602
Supply voltage		**V**	⎓ 24 (external supply with separate protection conforming to EN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)			
Voltage limits		**V**	- 15…+ 20%			
Ambient air temperature	For operation	**°F (°C)**	+32… + 140 (0…+ 60)			
	For storage	**°F (°C)**	- 40…+ 185 (- 40…+ 85)			
Degree of protection			IP 20			
Response time		**ms**	Depending on size of application			
Maximum current power consumption		**A**	0.5	9 per group Residual: 0.2 per group	0.6	
External fuse			10 A, slow blow			
Backup battery			None			
Connections			See page 2/26 for wire sizes of the various connector types.			
Digital outputs						
Number of outputs			4, not electrically isolated	16, not electrically isolated	–	
Permissible output channel current		**A**	20 max.	16 max.	–	
Output current		**A**	5 max.	1 max. at 140 °F (60 °C) 2 max. at 104 °F (40 °C)	–	
Maximum lamp load		**W**	60	10 for 1 A outputs 25 for 2 A outputs	–	
Maximum inductive load		**mH**	500	500	–	
Maximum leakage current	At state 0	**mA**	1 at 1 V	1 at 2 V	–	
Response to overload			Shutdown of outputs concerned with cyclic reconnection		–	
Relay outputs						
Relay type per channel			–	–	2, with positively guided contacts 1 magnetic, high resolution	
Outputs	Number		–	–	8	16
	Type				N.O.	
Switching voltage		**V**	–	–	⩾ 5, ⩽ ⎓ 250 V/ ∼ 250 V	⩾ 5, ⩽ ⎓ 30 V/ ∼ 60 V
Switching current		**mA**			3 A, with internal fuse Breaking capacity 100 A	3.15 A, with internal fuse Breaking capacity 100 A
Switching capacity (non inductive)	∼	**VA**	–	–	240 max., cos φ > 0.5	48 max., cos φ > 0.5
	Up to ⎓ 30 V	**W**			90 max. (3.15 A internal fuse)	
	Up to ⎓ 70 V	**W**			35 max. (0.5 A internal fuse)	–
	Up to ⎓ 127 V	**W**			30 max. (315 A internal fuse)	–
Contact material			–	–	Silver alloy	
Mechanical life			–	–	⩾ 1 million operating cycles	
Electrical life			–	–	⩾ 250 000 operating cycles on full load (resistive) and ⩽ 0.1 operating cycles/s	

Communication

Ethernet network: safety communication using SafeEthernet protocol

Transmission	Communication ports		Integrated 2 RJ45 switched Ethernet communications ports
	Baud rate	**Mbps**	100 Half duplex, 10 Full duplex, Autonegotiation
Structure			10BASE-T/100BASE-TX
Medium			Dual twisted pair cable, category 5D or better (Ethernet)

Introduction: page 2/80 | Specifications: page 2/84 | References: page 2/85 | Dimensions, mounting: page 2/86 | Connections: page 2/88

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs

Compact and modular

Safety remote output modules XPSMF2

References

XPSMF2DO401

XPSMF2DO1601

XPSMF2DO801

XPSMF2DO1602

*Products referenced **XPSMF2●●●●●●** are marked **HIMatrix® F2 DO...** (manufactured by Hima, sold by Schneider Electric).*

Safety remote output modules (⎓ 24 V supply)

For use with	Outputs		Ports	Reference	Weight oz (kg)
	Digital	Relay			
Safety PLCs, modular XPSMF60 or compact XPSMF40 and XPSMF31/30/35	4	–	Integrated 2 RJ45 switched Ethernet communications ports	**XPSMF2DO401**	28.219 (0.800)
	16	–	Integrated 2 RJ45 switched Ethernet communications ports	**XPSMF2DO1601**	29.983 (0.850)
	–	8	Integrated 2 RJ45 switched Ethernet communications ports	**XPSMF2DO801**	45.856 (1.300)
	–	16	Integrated 2 RJ45 switched Ethernet communications ports	**XPSMF2DO1602**	70.548 (2.000)

Connecting cables

Description	For	Reference	Weight oz (kg)
Ethernet network connecting cables	Connection between safety remote output modules and modular or compact safety PLCs XPSMF RJ45 connector fitted at each end	See page 2/29	–

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Dimensions

XPSMF2DO401



*(1) Removable screw terminals are provided with the safety output modules **XPSMF2DO401**.*

XPSMF2DO1601



*(1) Removable screw terminals are provided with the safety output modules **XPSMF2DO1601**.*

Dual Dimensions: INCHES Millimieters

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Dimensions

XPSMF2DO801





*(1) Removable screw terminals are provided with the safety output modules **XPSMF2DO801**.*

XPSMF2DO1602





*(1) Removable screw terminals are provided with the safety output modules **XPSMF2DO1602**.*

RJ45 connector for access to Ethernet network (SafeEthernet protocol)



Dual Dimensions: INCHES / Millimieters

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote output modules XPSMF2

Connections

XPSMF2DO401



Item	Connection	Screw N°	Screw	Function
A	**Ground**	–	⏚	Ground
B	**Digital output 1**	1	L+	Supply for output 1
		2	L+	Supply for output 1
		3	L-	Reference pole
		4	L-	Reference pole
		5	O	Digital output 1
		6	L-	Reference pole
C	**Digital output 2**	7	L+	Supply for output 2
		8	L+	Supply for output 2
		9	L-	Reference pole
		10	L-	Reference pole
		11	O	Digital output 2
		12	L-	Reference pole
D	**Digital output 3**	13	L+	Supply for output 3
		14	L+	Supply for output 3
		15	L-	Reference pole
		16	L-	Reference pole
		17	O	Digital output 3
		18	L-	Reference pole
E	**Digital output 4**	19	L+	Supply for output 4
		20	L+	Supply for output 4
		21	L-	Reference pole
		22	L-	Reference pole
		23	O	Digital output 4
		24	L-	Reference pole

Item	Connection	Type	Function
F	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety remote I/O and the programming terminal in a point to point or via an Ethernet network for setting the IP address
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.

XPSMF2DO1601



Item	Connection	Screw N°	Screw	Function
A	**Ground**	–	⏚	Ground
B	**Supply**	–	L-	Reference pole
		–	L-	Reference pole
		–	L+	Supply for outputs 1, 2, 3, 4, 9, 10, 11, 12
		–	L+	Supply for outputs 1, 2, 3, 4, 9, 10, 11, 12
B1	**Digital outputs**	1	L-	Reference pole
		2	1	Digital output 1
		3	2	Digital output 2
		4	3	Digital output 3
		5	4	Digital output 4
		6	L-	Reference pole
B2	**Digital outputs**	13	L-	Reference pole
		14	9	Digital output 9
		15	10	Digital output 10
		16	11	Digital output 11
		17	12	Digital output 12
		18	L-	Reference pole
C	**Supply**	–	L-	Reference pole
		–	L-	Reference pole
		–	L+	Supply for outputs 5, 6, 7, 8, 13, 14, 15, 16
		–	L+	Supply for outputs 5, 6, 7, 8, 13, 14, 15, 16
C1	**Digital outputs**	7	L-	Reference pole
		8	5	Digital output 5
		9	6	Digital output 6
		10	7	Digital output 7
		11	8	Digital output 8
		12	L-	Reference pole
C2	**Digital outputs**	19	L-	Reference pole
		20	13	Digital output 13
		21	14	Digital output 14
		22	15	Digital output 15
		23	16	Digital output 16
		24	L-	Reference pole

Item	Connection	Type	Function
D	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety remote I/O and the programming terminal in a point to point or via an Ethernet network for setting the IP address
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Connections

XPSMF2DO801



Item	Connection	Screw N°	Screw	Function
A1	**Supply**	–	L+	Supply for relay outputs
		–	L+	Supply for relay outputs
		–	L-	Reference pole
		–	L-	Reference pole
A2	**Ground**	–	⏚	Ground
B	**Relay output 1**	1	–	Contact 1, terminal A
		2	–	Contact 1, terminal B
C	**Relay output 2**	3	–	Contact 2, terminal A
		4	–	Contact 2, terminal B
D	**Relay output 3**	5	–	Contact 3, terminal A
		6	–	Contact 3, terminal B
E	**Relay output 4**	7	–	Contact 4, terminal A
		8	–	Contact 4, terminal B
F	**Relay output 5**	9	–	Contact 5, terminal A
		10	–	Contact 5, terminal B
G	**Relay output 6**	11	–	Contact 6, terminal A
		12	–	Contact 6, terminal B
H	**Relay output 7**	13	–	Contact 7, terminal A
		14	–	Contact 7, terminal B
J	**Relay output 8**	15	–	Contact 8, terminal A
		16	–	Contact 8, terminal B

Item	Connection	Type	Function
K	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety remote I/O and the programming terminal in a point to point or via an Ethernet network for setting the IP address
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.

XPSMF2DO1602



Item	Connection	Screw N°	Screw	Function
A1	**Supply**	–	L+	Supply for relay outputs
		–	L+	Supply for relay outputs
		–	L-	Reference pole
		–	L-	Reference pole
A2	**Ground**	–	⏚	Ground
B	**Relay outputs 1 to 4**	1	–	Contact 1, terminal A
		2	–	Contact 1, terminal B
		3	–	Contact 2, terminal A
		4	–	Contact 2, terminal B
		5	–	Contact 3, terminal A
		6	–	Contact 3, terminal B
		7	–	Contact 4, terminal A
		8	–	Contact 4, terminal B
C	**Relay outputs 5 to 8**	9	–	Contact 5, terminal A
		10	–	Contact 5, terminal B
		11	–	Contact 6, terminal A
		12	–	Contact 6, terminal B
		13	–	Contact 7, terminal A
		14	–	Contact 7, terminal B
		15	–	Contact 8, terminal A
		16	–	Contact 8, terminal B
D	**Relay outputs 9 to 12**	17	–	Contact 9, terminal A
		18	–	Contact 9, terminal B
		19	–	Contact 10, terminal A
		20	–	Contact 10, terminal B
		21	–	Contact 11, terminal A
		22	–	Contact 11, terminal B
		23	–	Contact 12, terminal A
		24	–	Contact 12, terminal B
E	**Relay outputs 13 to 16**	25	–	Contact 13, terminal A
		26	–	Contact 13, terminal B
		27	–	Contact 14, terminal A
		28	–	Contact 14, terminal B
		29	–	Contact 15, terminal A
		30	–	Contact 15, terminal B
		31	–	Contact 16, terminal A
		32	–	Contact 16, terminal B

Item	Connection	Type	Function
F	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety remote I/O and the programming terminal in a point to point or via an Ethernet network for setting the IP address
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote mixed I/O modules XPSMF3

XPSMF3DIO8801

XPSMF3DIO16801

XPSMF3DIO20802

XPSMF3AIO8401

*Products referenced **XPSMF3●●●●●●** are marked **HIMatrix® F3...** (manufactured by Hima, sold by Schneider Electric).*

Introduction

XPSMF3DIO/AIO are compact safety remote input/output modules which are designed to extend the I/O capacity of safety PLCs **XPSMF**, either compact or modular, to which they are associated.
The communication with either the compact or modular safety PLCs is managed via one of its' integrated 2 RJ45 switched Ethernet communications ports.
Safety modules **XPSMF3DIO/AIO** do not have a user program: they receive their instructions from its' parent safety PLC.

Safety remote mixed I/O modules XPSMF3DIO/AIO

Mixed I/O safety modules	Remote inputs		Remote outputs	
	N°	Type	N°	Type
XPSMF3DIO8801	**8**	Digital	**8 DO+ / 2 DO-**	Digital
			2	Line control
XPSMF3DIO16801	**16**	Digital	**8 2-pole or 16 single-pole**	Digital
			2	Line control
XPSMF3DIO20802	**20**	Digital	**8**	Digital
XPSMF3AIO8401	**8**	Analog	**4**	Analog (non safety outputs)

Examples of remote inputs of safety modules XPSMF3●IO●●●●●

■ **Digital inputs**

Safety actuators	Safety detection	Safety dialog
Contactors-motors, Control relays, Variable speed drives	Limit switches, Guard switches, with reset and with actuator, Light curtains type 2 and type 4, Safety mats and sensing edges	Mushroom head Emergency stops, Enclosures for control and signalling units, Two-hand control stations

■ **Analog inputs**

Closed circuit scanning of input channels,
Single-pole measuring of 0 to 10 V voltages,
Measuring, using jumper, 0/4 to 20 mA currents (with 500 Ω external resistor).

Examples of remote outputs of safety modules XPSMF3●IO●●●●●

■ **Digital outputs**

Safety actuators	Safety dialog
Contactors-motors, Control relays, Variable speed drives	Beacons and indicator banks, Rotating mirror beacons, Sirens

■ **Line control outputs**

Short-circuit and line break monitoring

■ **Analog outputs**

Closed circuit scanning of output channels,
Single-pole measuring of 0 to 10 V voltages,
Measuring, using jumper, 0/4 to 20 mA currents (with 500 Ω external resistor).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs

Compact and modular

Safety remote mixed I/O modules XPSMF3

Safety PLCs

In order to meet safety requirements, the safety remote mixed I/O modules **XPSMF3●IO●●●●●** incorporate two essential functions (**Redundancy** and **Self-monitoring)** complying to category 4 conforming to EN 954-1 and performance level “e” conforming to EN/ISO 13849-1 in addition to the SafeEthernet safety communication protocol between these safety remote mixed I/O modules and the safety PLCs (**Special Switch**).

■ **Redundancy**: the dual processor integrated in safety modules **XPSMF3●IO●●●●●** analyzes and compares the data received from the safety inputs and outputs. The incoming and outgoing data (programmed values and received values) are received in parallel by the two processors and compared in real-time.
■ **Self-monitoring (“Watchdog”)**: the safety remote mixed I/O modules **XPSMF3●IO●●●●●** continuously monitor the data processing cycle and the execution of tasks, and intervenes if the cycle time does not conform to the predefined value.
■ **The integrated switch (Special Switch)** stores for a very short time and sends at very high speed the data provided by the inputs and outputs of the safety modules on the Ethernet network, while avoiding signal collisions and excessive amounts of data on the network.

Functional diagrams

Remote mixed I/O module XPSMF3DIO8801



Remote mixed I/O module XPSMF3DIO16801



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote mixed I/O modules XPSMF3

Functional diagrams *(continued)*

Remote mixed I/O module XPSMF3DIO20802



Remote mixed I/O module XPSMF3AIO8401



Line control

Line control is a means of short-circuit and line break monitoring.
Using line control outputs enables SIL 3 (EN/IEC 61508) and category 4 (EN 954-1) safety to be achieved. The line control outputs send a high signal with a very short low signal, thus enabling a wiring anomaly (short-circuit, line break) to be seen at the inputs of the safety modules.

Examples

- For **XPSMF3DIO8801** and **XPSMF3DIO16801**, the line control outputs 1 and 2 are connected to the digital inputs of the same circuit.
- For **XPSMF3DIO20802**, the digital outputs 1 to 8 are connected to the digital inputs of the same circuit.

Safety communication on Ethernet network

The safety remote mixed I/O modules **XPSMF3●IO●●●●** incorporate two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, that enable communication on the Ethernet network using SafeEthernet communication protocol and therefore, data exchange with compact or modular safety PLCs **XPSMF**.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs

Compact and modular

Safety remote mixed I/O modules XPSMF3



Description

Remote mixed I/O module XPSMF3DIO8801

On the front cover of the metal enclosure:

1 One terminal block *(1)* for ⎓ 24 V supply.
2 One terminal block *(1)* for connection of line control outputs, with four line control output status LEDs.
3 Two terminal blocks *(1)* for connection of digital outputs, with output status LED (four LEDs per terminal block).
4 Two terminal blocks *(1)* for connection of digital inputs, with input status LED (four LEDs per terminal block).
5 Eight process status LEDs.
6 Two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, for connection on Ethernet network and for configuring IP address.
7 One ground connection screw.
8 One “Reset” button (on the top).
9 On the rear face: One spring operated mounting device for mounting on 35 mm DIN rail.



Remote mixed I/O module XPSMF3DIO16801

On the front cover of the metal enclosure:

1 One terminal block *(1)* for ⎓ 24 V supply.
2 Three terminal blocks for connection of digital output channels.
3 One terminal block *(1)* for connection of line control outputs.
4 Four terminal blocks *(1)* for connection of digital inputs, with input status LED (four LEDs per terminal block).
5 Sixteen digital output status LEDs.
6 Eight process status LEDs.
7 Two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, for connection on Ethernet network and for configuring IP address.
8 One ground connection screw.
9 One “Reset” button (on the top).
10 On the rear face: One spring operated mounting device for mounting on 35 mm DIN rail.



Remote mixed I/O module XPSMF3DIO20802

On the front cover of the metal enclosure:

1 One terminal block *(1)* for ⎓ 24 V supply.
2 Two terminal blocks *(1)* for connection of digital outputs, with output status LED (four LEDs per terminal block)
3 Five terminal blocks *(1)* for connection of digital inputs, with input status LED (four LEDs per terminal block).
4 Eight process status LEDs.
5 Two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, for connection on Ethernet network and for configuring IP address.
6 One ground connection screw.
7 One “Reset” button (on the top).
8 On the rear face: One spring operated mounting device for mounting on 35 mm DIN rail.



Remote mixed I/O module XPSMF3AIO8401

On the front cover of the metal enclosure:

1 One terminal block *(1)* for ⎓ 24 V supply.
2 Four terminal blocks *(1)* for connection of analog inputs.
3 One terminal block *(1)* for connection of analog outputs.
4 One metal plate for securing shielded analog input/output connection cables (EMC).
5 Eight process status LEDs.
6 Two RJ45 (type 10BASE-T/100BASE-TX) integrated switched ports, for connection on Ethernet network and for configuring IP address.
7 One ground connection screw.
8 One “Reset” button (on the top).
9 On the rear face: one spring operated mounting device for mounting on 35 mm DIN rail.

*(1) Removable screw terminals are provided with the safety remote mixed I/O modules **XPSMF3DIO/AIO**.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Status LED details

Safety remote mixed I/O modules XPSMF3●IO●●●●●

LED	Color	Status	Meaning
24 VDC	Green	On	⎓ 24 V voltage present.
		Off	No voltage.
RUN	Green	On	Normal service mode, loaded program running, the PLC receives I/O messages, communication and hardware/ software tests carried out.
		Flashing	The CPU is in STOP and is not executing any user application. All the outputs are reset to a safe, de-energized state.
		Off	The CPU is in “ERROR” state (see ERROR).
ERROR	Red	On	Software error or hardware anomaly detected by the CPU.
			The monitoring program (Watchdog) has triggered the STOP state of the process because the programmed cycle time has been exceeded.
			The CPU has stopped the execution of the user application, ended all hardware and software tests and all outputs have been reset.
			The process can only be started again from the PC.
		Off	No errors detected.
PROG	Orange	On	The CPU is being loaded with a new configuration.
		Flashing	The FLASH ROM is being loaded with a new operating system.
		Off	No loading of configuration or operating system.
FORCE	Orange	On	The CPU is in RUN mode and force is active.
		Flashing	The system is not processing (STOP), but force is prepared and is activated if the dual processor is started.
		Off	Force mode not activated.
FAULT	Orange	On	Error display for line control.
			The user application has caused an error.
			The system configuration is defective.
			The loading of a new operating system was defective and the operating system is corrupt.
		Flashing	An error has occurred while writing to FLASH ROM memory (during updating of the operating system).
			One or more I/O errors have occurred.
		Off	None of the above errors have occurred.
OSL	Orange	Flashing	Emergency loading of the operating system is active.
BL	Orange	Flashing	COM in INIT_Fail state.
RJ45	Green	On	Full duplex mode operation.
		Flashing	Signal collision.
		Off	Half duplex mode operation, no collision.
	Yellow	On	Connection established.
		Flashing	Interface active.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote mixed I/O modules XPSMF3

Specifications

Safety remote mixed I/O module type			XPSMF3DIO8801	XPSMF3DIO16801	XPSMF3DIO20802	XPSMF3AIO8401
Supply voltage		**V**	⎓ 24 (external supply with separate protection conforming toEN/IEC 60950, SELV (Safety Extra Low Voltage) or PELV (Protection Extra Low Voltage) rated)			
Voltage limits		**V**	- 15…+ 20%			
Ambient air temperature	For operation	**°F (°C)**	+ 32… + 140 (0…+ 60)			
	For storage	**°F (°C)**	- 40…+ 185 (- 40…+ 85)	- 40…+ 185 (- 40… + 85) without battery	- 40…+ 185 (- 40…+ 85)	
Degree of protection			IP 20			
Response time		**ms**	Depending on size of application			
Maximum current power consumption		**A**	8	14 (max. load) Residual: 0.6	8 (max. load) Residual: 0.4	0.8
External fuse			10 A, slow blow	16 A, slow blow	–	–
Backup battery			None	–	None	None
Connections			See page 2/26 for wire sizes of the various connector types.			

Digital inputs

Safety remote mixed I/O module type			XPSMF3DIO8801	XPSMF3DIO16801	XPSMF3DIO20802
Number	Inputs not electrically isolated		8	16	20
Voltage	At state 1	**V**	⎓ 15…30		
		mA	> 2 at ⎓ 15 V		⩾ 2 at ⎓ 15 V
	At state 0	**V**	⎓ 5 max.		
		mA	1.5 max. 1.25 at ⎓ 5 V	1.5 max. 1 at ⎓ 5 V	1.5 max. 1.25 at ⎓ 5 V
Switching voltage		**V**	7.5	7.5	7.5
Switching time		**µs**	–	250	–
Supply		**V**	2 x 20 V/100 mA at 24 V, protected against short-circuits	4 x 20 V/40 mA at 24 V, protected against short-circuits, buffered for 20 ms. 20 V/2 A total at 22 V, protected against short-circuits, not buffered Max. current 2 A at 140 °F (60 °C)	5 x 20 V/100 mA at 24 V, protected against short-circuits
LED display			Yes		

Digital outputs

Safety remote mixed I/O module type			XPSMF3DIO8801	XPSMF3DIO16801	XPSMF3DIO20802
Number	Outputs not electrically isolated		8 DO+ (reference pole L-)	8 x 2-pole or 16 x single-pole	8
			2 DO- (reference pole S+)		
Output voltage		**V**	⎓ 24 ± 2	⎓ 24 ± 3	⎓ 24 ± 2
Output current	Channels 1 to 3 and 5 to 7	**A**	DO+: 0.5 at 140 °F (60 °C)	2 max. at 104 °F (40 °C) 1 max. at 140 °F (60 °C) 10 mA min.	0.5 at 140 °F (60 °C)
	Channels 4 and 8	**A**	DO+: 1 at 140 °F (60 °C), 2 at 104 °F (40 °C)		1 at 140 °F (60 °C), 2 at 50 °C
	Channels 1 and 2	**A**	DO-: 1 at 140 °F (60 °C)	–	–
Lamp load	Channels 1 to 3 and 5 to 7	**W**	DO+: 10	25 max.	–
	Channels 4 and 8		DO+: 25		
	Channels 1 and 2		DO-: 25		
Inductive load	Channels 1 to 3 and 5 to 7		DO+: 500	500 mH max.	–
	Channels 4 and 8		DO+: 500		
	Channels 1 and 2		DO-: 500		
Line break		**kΩ**	–	> 5	–
Short-circuit threshold		Ω	–	< 10	–
Minimum load		**mA**	2 per channel		
Leakage current at state 0		**mA**	1 max. at 2 V		
Response to overload			Shutdown of outputs concerned with cyclic reconnection		
Total output current		**A**	7 max.	9 max. (14 A for 2 ms)	7 max.
			Shutdown of all outputs if exceeded with cyclic reconnection		
LED display			Yes		

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Specifications *(continued)*

Line control outputs

Module type			XPSMF3DIO8801	XPSMF3DIO16801
Number	Outputs not electrically isolated		2	2
Output voltage		**V**	20, depending on the supply voltage	
Output current		**mA**	60	
Minimum load			None	
Response to overload			4 x ≥ 19.2 V/60 mA (on 24 V), short-circuit current	
LED display			Yes	

Analog inputs

Safety remote mixed I/O module type			XPSMF3AIO8401
Number	Inputs not electrically isolated		8, single-pole
External jumper		Ω	250 or 500 depending on application
Input values	Nominal value	**V**	⎓ 0…10
		mA	0…20, with 500 Ω jumper
	Service value	**V**	⎓ 0.1…11.5
		mA	0/4…23, with 500 Ω jumper
Input impedance		**MΩ**	2
Maximum distance of equipment			984 ft (300 m)
Internal resistance of signal source		Ω	≤ 500
Overvoltage protection		**V**	+ 15, - 4
Resolution			12-bit
Safety accuracy			± 2%
LED display			No

Analog outputs

Safety remote mixed I/O module type			XPSMF3AIO8401
Number	Outputs not electrically isolated		4 non safety outputs with breaking of safety common
Signal	Nominal range	**mA**	4…20
	Usable range	**mA**	0…20
Load impedance		Ω	600 max.
Maximum distance of equipment			984 ft (300 m)
Resolution			12-bit
Relative error			± 1%
LED display			No

Communication

Ethernet network: safety communication using SafeEthernet protocol

Safety remote mixed I/O module type			XPSMF3DIO8801	XPSMF3DIO16801	XPSMF3DIO20802	XPSMF3AIO8401
Transmission	Communication ports		Integrated 2 RJ45 switched Ethernet communications ports			
	Baud rate	**Mbps**	100 Half duplex, 10 Full duplex, Autonegotiation			
Structure			10BASE-T/100BASE-TX			
Medium			Dual twisted pair cable, category 5D or better (Ethernet)			

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs

Compact and modular

Safety remote mixed I/O modules XPSMF3

XPSMF3DIO8801

XPSMF3DIO16801

XPSMF3DIO20802

XPSMF3AIO8401

Products referenced ***XPSMF3●●●●●●*** *are marked* ***HIMatrix® F3...*** *(manufactured by Hima, sold by Schneider Electric).*

References

Safety remote mixed I/O modules (⎓ 24 V supply)

For use with	Inputs		Outputs			Ports	Reference	Weight oz (kg)
	Digital	Analog	Digital	Line control	Analog			
Safety PLCs, modular XPSMF60 or compact XPSMF40 and XPSMF31/30/35	8	–	8 DO+ 2 DO-	2	–	Integrated 2 RJ45 switched Ethernet communications ports	**XPSMF3DIO8801**	35.274 (1.000)
	16	–	8 x 2 or 16 x 1	2	–	Integrated 2 RJ45 switched Ethernet communications ports	**XPSMF3DIO16801**	45.856 (1.300)
	20	–	8 *(1)*	–	–	Integrated 2 RJ45 switched Ethernet communications ports	**XPSMF3DIO20802**	35.273 (1.000)
	–	8	–	–	4	Integrated 2 RJ45 switched Ethernet communications ports	**XPSMF3AIO8401**	33.510 (0.950)

Connecting cables

Description	For	Reference	Weight oz (kg)
Ethernet network connecting cables	Connection between safety remote mixed I/O modules and modular or compact safety PLCs XPSMF. RJ45 connector fitted at each end	See page 2/29	–

(1) Configurable for line control.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

XPSMF3DIO8801



*(1) Removable screw terminals are provided with the safety remote mixed I/O modules **XPSMF3DIO8801**.*

XPSMF3DIO16801



*(1) Removable screw terminals are provided with the safety remote mixed I/O modules **XPSMF3DIO16801**.*

Dual Dimensions: INCHES Millimieters

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSMF3DIO20802



*(1) Removable screw terminals are provided with the safety remote mixed I/O modules **XPSMF3DIO20802**.*

XPSMF3AIO8401



*(1) Removable screw terminals are provided with the safety remote mixed I/O modules **XPSMF3AIO8401**.*

RJ45 connector for access to Ethernet network (SafeEthernet protocol)



Dual Dimensions: INCHES / Millimieters

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote mixed I/O modules XPSMF3

XPSMF3DIO8801



Item	Connection	Screw N°	Screw	Function
A1	**Supply**	–	L-	⎓ 24 V (reference pole)
		–	L-	⎓ 24 V (reference pole)
		–	L+	⎓ 24 V
		–	L+	⎓ 24 V
A2	**Ground**	–	⏚	Ground
B	**Outputs - Line control/ Digital**	1	L-	Reference pole
		2	1	Line control output 1
		3	2	Line control output 2
		4	4-	Digital output 4- (for increased load)
		5	8-	Digital output 8- (for increased load)
		6	S+	Reference pole
C	**Outputs - Digital**	7	L-	Reference pole
		8	1	Digital output 1
		9	2	Digital output 2
		10	3	Digital output 3
		11	4+	Digital output 4+ (for increased load)
		12	L-	Reference pole
D	**Outputs - Digital**	13	L-	Reference pole
		14	5	Digital output 5
		15	6	Digital output 6
		16	7	Digital output 7
		17	8+	Digital output 8+ (for increased load)
		18	L-	Reference pole
E	**Inputs - Digital**	19	LS+	Sensor supply for inputs 1 to 4
		20	1	Digital input 1
		21	2	Digital input 2
		22	3	Digital input 3
		23	4	Digital input 4
		24	L-	Reference pole
F	**Inputs - Digital**	25	LS+	Sensor supply for inputs 5 to 8
		26	5	Digital input 5
		27	6	Digital input 6
		28	7	Digital input 7
		29	8	Digital input 8
		30	L-	Reference pole

Item	Connection		Function
G	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety remote I/O and the programming terminal in a point to point or via an Ethernet network for setting the IP address
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs

Compact and modular

Safety remote mixed I/O modules XPSMF3

Connections

XPSMF3DIO16801



Item	Connection	Screw N°	Screw	Function
A1	**Supply**	–	L+	⎓ 24 V
			L+	⎓ 24 V
			L-	⎓ 24 V (reference pole)
			L-	⎓ 24 V (reference pole)
A2	**Ground**	–	⏚	Ground
B	**Supply of single-pole digital outputs**	1	S+	–
		2	S+	–
		3	S+	–
		4	S+	–
		5	S-	–
		6	S-	–
		7	S-	–
		8	S-	–
C	**Outputs - Digital**	9	1-	Output 1
		10	1+	Output 1
		11	2-	Output 2
		12	2+	Output 2
		13	3-	Output 3
		14	3+	Output 3
		15	4-	Output 4
		16	4+	Output 4
D	**Outputs - Digital**	17	5-	Output 5
		18	5+	Output 5
		19	6-	Output 6
		20	6+	Output 6
		21	7-	Output 7
		22	7+	Output 7
		23	8-	Output 8
		24	8-	Output 8
E	**Outputs - Line control**	25	1	Output 1
		26	1	Output 1
		27	1	Output 1
		28	1	Output 1
		29	2	Output 2
		30	2	Output 2
		31	2	Output 2
		32	2	Output 2

Item (cont.)	Connection	Screw N°	Screw	Function
F	**Inputs - Digital**	33	LS+	Sensor supply for inputs 1 to 4 (not protected)
		34	LS+	Sensor supply for inputs 1 to 4 (protected)
		35	1	Input 1
		36	2	Input 2
		37	3	Input 3
		38	4	Input 4
		39	L-	⎓ 24 V (reference pole)
		40	L-	⎓ 24 V (reference pole)
		41	PA	Electrically clean ground
		42	PA	Electrically clean ground
G	**Inputs - Digital**	43	LS+	Sensor supply for inputs 5 to 8 (not protected)
		44	LS+	Sensor supply for inputs 5 to 8 (protected)
		45	5	Input 5
		46	6	Input 6
		47	7	Input 7
		48	8	Input 8
		49	L-	⎓ 24 V (reference pole)
		50	L-	⎓ 24 V (reference pole)
		51	PA	Electrically clean ground
		52	PA	Electrically clean ground
H	**Inputs - Digital**	53	LS+	Sensor supply for inputs 9 to 12 (not protected)
		54	LS+	Sensor supply for inputs 9 to 12 (protected)
		55	9	Input 9
		56	10	Input 10
		57	11	Input 11
		58	12	Input 12
		59	L-	⎓ 24 V (reference pole)
		60	L-	⎓ 24 V (reference pole)
		61	PA	Electrically clean ground
		62	PA	Electrically clean ground
J	**Inputs - Digital**	63	LS+	Sensor supply for inputs 13 to 16 (not protected)
		64	LS+	Sensor supply for inputs 13 to 16 (protected)
		65	5	Input 13
		66	6	Input 14
		67	7	Input 15
		68	8	Input 16
		69	L-	⎓ 24 V (reference pole)
		70	L-	⎓ 24 V (reference pole)
		71	PA	Electrically clean ground
		72	PA	Electrically clean ground

Item	Connection		Function
K	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety remote I/O and the programming terminal in a point to point or via an Ethernet network for setting the IP address
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety PLCs
Compact and modular
Safety remote mixed I/O modules XPSMF3

Connections

XPSMFDIO20802



Item	Connection	Screw N°	Screw	Function
A1	**Supply**	–	L+	⎓ 24 V
			L+	⎓ 24 V
			L-	⎓ 24 V (reference pole)
			L-	⎓ 24 V (reference pole)
A2	**Ground**		⏚	Ground
B	**Outputs - Digital**	1	L-	Outputs common
		2	1	Output 1
		3	2	Output 2
		4	3	Output 3
		5	4	Output 4 (for increased load)
		6	L-	Outputs common
C	**Outputs - Digital**	7	L-	Outputs common
		8	5	Output 5
		9	6	Output 6
		10	7	Output 7
		11	8	Output 8 (for increased load)
		12	L-	Outputs common
D	**Inputs - Digital**	13	LS+	Sensor supply for inputs 1 to 4
		14	1	Digital input 1
		15	2	Digital input 2
		16	3	Digital input 3
		17	4	Digital input 4
		18	L-	Inputs common
E	**Inputs - Digital**	19	LS+	Sensor supply for inputs 5 to 8
		20	5	Digital input 5
		21	6	Digital input 6
		22	7	Digital input 7
		23	8	Digital input 8
		24	L-	Inputs common
F	**Inputs - Digital**	25	LS+	Sensor supply for inputs 9 to 12
		26	9	Digital input 9
		27	10	Digital input 10
		28	11	Digital input 11
		29	12	Digital input 12
		30	L-	Inputs common
G	**Inputs - Digital**	31	LS+	Sensor supply for inputs 13 to 16
		32	13	Digital input 13
		33	14	Digital input 14
		34	15	Digital input 15
		35	16	Digital input 16
		36	L-	Inputs common
H	**Inputs - Digital**	37	LS+	Sensor supply for inputs 17 to 20
		38	17	Digital input 17
		39	18	Digital input 18
		40	19	Digital input 19
		41	20	Digital input 20
		42	L-	Inputs common

Item	Connection		Function
J	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety remote I/O and the programming terminal in a point to point or via an Ethernet network for setting the IP address
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Connections

XPSMF3AIO8401



Item	Connection	Screw N°	Screw	Function
A1	**Supply**	–	L+	⎓ 24 V
			L+	⎓ 24 V
			L-	⎓ 24 V (reference pole)
			L-	⎓ 24 V (reference pole)
A2	**Ground**		⏚	Ground
B	**Inputs - Analog**	1	S1	Transmitter supply 1
		2	I1+	Input 1
		3	I1-	Reference pole
		4	S2	Transmitter supply 2
		5	I2+	Input 2
		6	I2-	Reference pole
C	**Inputs - Analog**	7	S3	Transmitter supply 3
		8	I3+	Input 3
		9	I3-	Reference pole
		10	S4	Transmitter supply 4
		11	I4+	Input 4
		12	I4-	Reference pole
D	**Inputs - Analog**	13	S5	Transmitter supply 5
		14	I5+	Input 5
		15	I5-	Reference pole
		16	S6	Transmitter supply 6
		17	I6+	Input 4
		18	I6-	Reference pole
E	**Inputs - Analog**	19	S7	Transmitter supply 7
		20	I7+	Input 7
		21	I7-	Reference pole
		22	S8	Transmitter supply 8
		23	I8+	Input 8
		24	I8-	Reference pole
F	**Outputs - Analog**	25	O1+	Output 1
		26	O1-	Output 1 reference pole
		27	O2+	Output 2
		28	O2-	Output 2 reference pole
		29	O3+	Output 3
		30	O3-	Output 3 reference pole
		31	O4+	Output 4
		32	O4-	Output 4 reference pole

Item	Connection		Function
G	**Programming**	Integrated 2 RJ45 switched Ethernet Communication ports	Either of the two switched Ethernet ports can be used to create a connection between the safety remote I/O and the programming terminal in a point to point or via an Ethernet network for setting the IP address
	Safe Communication (all XPSMF Safety PLCs and Remote I/Os)		Either of the two switched Ethernet ports can be used to create a connection between the safety PLC and other safety related components (e.g other XPSMF safety PLCs or Safety Remote I/O modules) this can be established in a point to point way or via an Ethernet network.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions
Preventa™ safety controllers

Applications



Modules	**Controllers for monitoring 2 independent safety functions simultaneously. User selection of 2 functions from a choice of 15. Programmable from front cover of controller.**

Functions		☐ Emergency stop monitoring ☐ Switch monitoring ☐ Enabling switch monitoring ☐ Sensing mat or edges monitoring ☐ Light curtain monitoring, relay output type
Conformity to standards		EN 954-1 - category 4/ISO 13849-1, EN/IEC 60204-1, DIN V VDE 801 + A1, EN/IEC 60947-1 + A11, EN/IEC 60947-5-1
Product certifications		UL, CSA, BIA
Number of circuits		
	Safety	6 N.O. (3 N.O. per function)
	Additional	3 solid-state outputs for signalling to PLC
Display		12 LEDs
Supply voltage		⎓ 24 V
Communication	CANopen bus	–
	Profibus bus	–
	Modbus™ network	–
Module type		**XPSMP**
Page		2/108

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com







Configurable controllers using software, for several independent safety functions: selection of safety functions using configuration software running on Windows® (16 or 32 inputs and 8 independent safety outputs)

- Emergency stop monitoring
- Limit switch monitoring
- Two-hand control monitoring
- Light curtain monitoring, with or without “muting” function
- Enabling switch monitoring, coded magnetic switch monitoring
- Safety mat monitoring
- Hydraulic press solenoid valve monitoring
- Eccentric press safety stop at top dead center monitoring. Zero speed detection
- Hydraulic press monitoring
- Eccentric press monitoring
- Foot switch monitoring
- Chain shaft breakage monitoring
- Position selector

EN 954-1 - category 4/ISO 13849-1,
IEC 61508 - SIL 3,
EN/IEC 60204-1,
EN 1760-1/ISO 13856-1,
EN/IEC 60947-5-1,
EN/IEC 61496-1,
EN 574/ISO 13851,
EN 954-1/ISO 13849-1

UL, CSA, TÜV

4 N.O. (2 N.O. per function) + 6 solid-state

1 “muting” signalling output

LED display on front cover

⎓ 24 V

Via SUB-D 9-pin male connector, only on XPSMC16ZC and XPSMC32ZC

Via SUB-D 9-pin female connector, only on XPSMC16ZP and XPSMC32ZP

Via RJ45 connector, on all controllers XPSMC●●Z●

XPSMC

2/124

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety controllers type XPSMP

With pre-defined functions

Introduction

Operating principle

Preventa™ safety controller modules XPSMP are designed to conform with category 4 of the standard EN 954-1/ISO 13849-1.
They enable two independent safety functions (selected from a choice of 15 pre-defined configurations) to be performed using the same product. Configuration selection is easily made using 3 buttons on the front cover of the module.

These 15 pre-programmed safety functions provide a solution for the majority of safety applications up to level 4 conforming to the standard EN 954-1/ISO 13849-1, for example: monitoring Emergency stops, limit switches, safety mats and sensing edges, enabling switches, coded magnetic switches, type 4 relay output light curtains conforming to EN/IEC 61496-1 (for example, light curtains type XUS L. Safety controllers XPSMP incorporate 6 safety outputs (3 per function) and 3 solid-state signalling outputs for signalling to the process PLC.

To aid diagnostics, the modules have LEDs on the front cover which provide information on the monitoring circuit status. They also indicate and assist selection of the 2 required configurations.

	Configuration	Synchronization time	Type of start *(1)*		Start test	Notes
			Automatic or unmonitored	Monitored		
Functions disabled	**0**	–	–	–	–	Factory setting
Emergency stop monitoring, 1-channel wiring (category 2)	**1**	–	X	–	–	–
	2	–	–	X	–	–
Emergency stop monitoring, 2-channel wiring, or guard monitoring (category 4)	**3**	Unlimited	X	–	X	–
	4	Unlimited	–	X	X	–
	5	1.5 s	X	–	X	–
	6	1.5 s	–	X	X	–
	7	Unlimited	X	–	–	–
	8	Unlimited	–	X	–	–
Guard monitoring for injection press or blowing machine (category 4)	**9**	1.5 s	–	X	X	Uses both safety outputs *(2)*
Enabling grip switch monitoring (3 position switch) (category 4)	**10**	–	X	–	X	The start button acts as start-up preparation
Sensing mat and edges monitoring (category 3)	**11**	–	X	–	–	Mats with circuit making contacts
	12	–	–	X	–	
Relay output light curtain monitoring (category 4)	**13**	0.5 s	–	X	X	–
Non-contact safety interlock switch monitoring (category 4)	**14**	1.5 s	X	–	–	Magnetic switches with 2 contacts, 1 N.O. and 1 N.C.
	15	1.5 s	–	X	–	

(1) Automatic start: there is no start contact or it is jumpered.
Unmonitored start: the output is activated on closing of the start contact.
Monitored start: the start input is monitored so that there is no start-up in the event of the start contact being jumpered or the start circuit being closed for more than 10 seconds.
Start-up is triggered following activation of the start button (push-release function) on opening of the contact.
(2) Tool zone guard with 3rd switch.
Additional rear guard (optional) with automatic start. The opening of the guard cuts all outputs.

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety controllers type XPSMP

With pre-defined functions

Specifications

Module type			XPSMP11123	XPSMP11123P
Conformity to standards			EN/IEC 60204-1, DIN V VDE 801 + A1, EN/IEC 60947-1 + A11, EN/IEC 60947-5-1	
Product certifications			UL, CSA, BIA	
Product designed for max. use in safety related parts of control systems (conforming to EN 954-1/ISO 13849-1)			Category 4 max.	
Supply		**V**	⎓ 24	
Voltage limits			- 20…+ 20%	
Power consumption		**W**	⩽ 5	
Module inputs fuse protection			Internal, electronic	
Start button monitoring			Yes/No (depending on configuration selected)	
Control unit voltage Between input terminals C1-I1, C2-I2, C3-I3, C4-I4, C5-I5 or C6-I6		**V**	24 (at nominal supply voltage)	
Calculation of wiring resistance RL between input terminals		Ω	100 max. Maximum cable length: 6561 ft (2000 m)	
Synchronization time between inputs		**s**	0.5, 1.5 or unlimited, depending on configuration selected	
Outputs	Voltage reference		Relay hard contacts	
	Number and type of safety circuits		3 N.O. per function (6 N.O. total) (13-14, 23-24, 33-34, 43-44, 53-54, 63-64)	
	Number and type of additional circuits		3 solid-state	
	Breaking capacity in AC-15	**VA**	C300: inrush 1800, maintained 180	
	Breaking capacity in DC-13		24 V/1.5 A L/R = 50 ms	
	Breaking capacity of solid-state outputs		24 V/20 mA	
	Max. thermal current (Ithe) for each group of 3 outputs		3.3 A for all 3 outputs, or 6 A for 1 output and 2 A for the other 2 outputs, or 2 A for 1 output and 4 A for the other 2 outputs	
	Max. total thermal current	**A**	20	
	Output fuse protection		4 gG or 6 fast acting, conforming to EN/IEC 60947-5-1, DIN VDE 0660 part 200	
	Minimum current	**mA**	10	
	Minimum voltage	**V**	17	
Electrical life			See page 3/12	
Response time on input opening		**ms**	< 30	
Rated insulation voltage (Ui)		**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
Rated impulse withstand voltage (Uimp.)		**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
LED display			12	
Operating temperature		**°F (°C)**	+ 14…+ 131 (- 10…+ 55)	
Storage temperature		**°F (°C)**	- 13…+ 267.8 (- 25…+ 85)	
Degree of protection conforming to IEC 60529	Terminals		IP 20	
	Enclosure		IP 40	
Connections	Type		Captive screw clamp terminals	Captive screw clamp terminals, removable terminal block
	1-wire connection, without cable end		Solid or flexible cable: 26-14 AWG (0.14… 2.5 mm²)	Solid or flexible cable: 24-14 AWG (0.2… 2.5 mm²)
	1-wire connection, with cable end		Without bezel, flexible cable: 24-14 AWG (0.25…2.5 mm²)	
			With bezel, flexible cable: 24-16 AWG (0.25…1.5 mm²)	With bezel, flexible cable: 24-14 AWG (0.25…2.5 mm²)
	2-wire connection, without cable end		Solid or flexible cable: 26-20 AWG (0.14…0.75 mm²)	Solid cable: 24-18 AWG (0.2…1 mm²) Flexible cable: 24-18 AWG (0.2…1.5 mm²)
	2-wire connection, with cable end		Without bezel, flexible cable: 24-18 AWG (0.25…1 mm²)	
			Double, with bezel, flexible cable: 22-14 AWG (0.5…1.5 mm²)	

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety controllers type XPSMP

With pre-defined functions

XPSMP11123

XPSMP11123P

References

Description	Type of terminal block connection	Number of safety circuits	Additional outputs	Supply	Reference	Weight oz (kg)
Modules for 2 independent safety functions	Integrated in module	3 N.O. per function (6 N.O. total)	3 solid-state	⎓ 24 V	**XPSMP11123**	11.287 (0.320)
	Removable from module	3 N.O. per function (6 N.O. total)	3 solid-state	⎓ 24 V	**XPSMP11123P**	11.287 (0.320)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety controllers type XPSMP

AM1 DP200 rail mounting

Dimensions

XPSMP●●●●





XPSMP●●●●P





Dual Dimensions: INCHES
Millimieters

LED details



1-2-3	Function 1 configuration code.
4	K1/K2 status (function 1, N.O. safety outputs closed).
5-6-7	Function 2 configuration code.
8	K3/K4 status (function 2, N.O. safety outputs closed).
9	Supply voltage A1-A2.
10	Fault.
11	Function 1 configuration.
12	Function 2 configuration.
F1, F2, OK:	Configuration buttons.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety controllers type XPSMP

With pre-defined functions

2

XPSMP

Emergency stop monitoring, 1-channel wiring

Configuration 1 (1-channel Emergency stop, automatic or unmonitored start) = function 1.
Configuration 2 (1-channel Emergency stop, monitored start) = function 2.



(1) Automatic start.
(2) Function 1 safety outputs.
(3) Function 2 safety outputs.
ESC = External start conditions.

Functional diagrams

Configuration 1

Automatic start



Configuration 1

Unmonitored start



Configuration 2

Monitored start



Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSMP

Guard monitoring with start test

Configuration 3 (locking of guard with start test, automatic or unmonitored start) = function 1.
Configuration 4 (locking of guard with start test, monitored start) = function 2.



(1) Automatic start.
(2) Function 1 safety outputs.
(3) Function 2 safety outputs.
ESC = External start conditions.

Functional diagrams

Configuration 3
Automatic start



Configuration 3
Unmonitored start



Configuration 4
Monitored start



(1) Prevention of start-up necessary: to check the sensors connected, open and reclose the guard.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

XPSMP

Guard monitoring with start test and synchronization time = 1.5 ms

Configuration 5 (locking of guard with start test, automatic or unmonitored start) = function 1.
Configuration 6 (locking of guard with start test, monitored start) = function 2.



(1) Automatic start.
(2) Function 1 safety outputs.
(3) Function 2 safety outputs.
ESC = External start conditions.

Functional diagrams

Configuration 5

Automatic start



Configuration 5

Unmonitored start



Configuration 6

Monitored start



(1) Prevention of start-up necessary: to check the sensors connected, open and reclose the guard.

Introduction: page 2/106 | Specifications: page 2/107 | References: page 2/108 | Dimensions: page 2/109 | Wiring diagrams page 2/110

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSMP

Emergency stop monitoring, 2-channel wiring

Configuration 7 (2-channel Emergency stop, automatic or unmonitored start) = function 1.
Configuration 8 (2-channel Emergency stop, monitored start) = function 2.



(1) Automatic start.
(2) Function 1 safety outputs.
(3) Function 2 safety outputs.
ESC = External start conditions.

Functional diagrams

Configuration 7
Automatic start



Configuration 7
Unmonitored start



Configuration 8
Monitored start



(1) Start button control: the start button must not be activated on power-up.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

XPSMP

Guard monitoring for injection press or blowing machine

Configuration 9 (this configuration uses both functions of the controller. Only function 1 is configured).



(1) If sensors S4 and S5 are not used, terminals C4-I4 and C5-I5 must be linked.

(2) Safety outputs for tool zone.

(3) Safety outputs for rear access safety doors.

In configuration mode 9, the N.C. contacts of the relays or contactors controlled via outputs 43-44, 53-54, 63-64 cannot be monitored by the feedback loop (ESC).

ESC = External start conditions.

Functional diagram

Configuration 9



(1) Prevention of start-up necessary: to check the sensors connected, open and reclose the guard.

Introduction: page 2/106 | Specifications: page 2/107 | References: page 2/108 | Dimensions: page 2/109 | Wiring diagrams page 2/110

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSMP

Enabling switch monitoring, safety mat monitoring

Configuration 10 (enabling switch monitoring, with or without start-up preparation) = function 1.
Configuration 11 (safety mat monitoring, automatic or unmonitored start) = function 2.



(1) Automatic start.
(2) Function 1 safety outputs.
(3) Function 2 safety outputs.
ESC = External start conditions.

Functional diagrams

Configuration 10

Enabling switch



1 With start-up preparation.
2 Without start-up preparation.

Configuration 11

Safety mat with automatic start



Safety mat with unmonitored start



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

XPSMP

Safety mat monitoring, light curtain monitoring

Configuration 12 (sensing mat monitoring, monitored start) = function 1.
Configuration 13 (light curtain monitoring, monitored start; synchronization time = 0.5 s) = function 2.



(1) Function 1 safety outputs.
(2) Function 2 safety outputs.
ESC = External start conditions.

Functional diagrams

Configuration 12

Sensing mat with monitored start



Configuration 13

Light curtain with monitored start



(1) Start button control: the start button must not be activated on power-up.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSMP

Non-contact safety interlock switch monitoring

Configuration 14 (automatic or unmonitored start, synchronization time = 1.5 s) = function 1.
Configuration 15 (monitored start, synchronization time = 1.5 s) = function 2.



(1) Automatic start.
(2) Function 1 safety outputs.
(3) Function 2 safety outputs.
ESC = External start conditions.

Functional diagrams

Configuration 14
Automatic start



Configuration 14
Unmonitored start



Configuration 15
Monitored start



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ configurable safety controllers type XPSMC

XPSMC16ZC

XPSMC32ZC

Introduction

Configurable safety controllers XPSMC●●Z● are designed to provide a solution for safety applications requiring conformity to category 4 of standard EN 954-1/EN/ ISO 13849-1 and SIL 3 requirements of standard IEC 61508.
The range of configurable safety controllers consists of 6 products, each with different technical specifications.

Configurable controllers	Safety inputs	Safety outputs *(1)*	Communication via		
			CANopen bus	Profibus bus	Modbus™ serial link
XPSMC16Z	16	6 + 2 x 2	–	–	Yes, slave
XPSMC16ZC	16	6 + 2 x 2	Yes, slave	–	Yes, slave
XPSMC16ZP	16	6 + 2 x 2	–	Yes, slave	Yes, slave
XPSMC32Z	32	6 + 2 x 2	–	–	Yes, slave
XPSMC32ZC	32	6 + 2 x 2	Yes, slave	–	Yes, slave
XPSMC32ZP	32	6 + 2 x 2	–	Yes, slave	Yes, slave

Line control

The safety inputs are supplied by the various control outputs *(2)*, in such a manner so as to monitor for short-circuits between the inputs, short-circuits between each input and ground or the presence of residual voltages.
The controller, assisted by the control outputs, continuously tests all the connected inputs. As soon as an error is detected on an input, all the outputs associated with this input are disconnected. Safety outputs associated with other inputs remain active.

Configuration

Safety controllers XPSMC●●Z● are configurable and addressable using software XPSMCWIN running on a PC. Connection accessories required: see page 2/125.

Connections

For connection of safety inputs and outputs, safety controllers XPSMC●●Z● can be fitted with a choice of:
- screw connectors type XPSMCTS●●, or
- spring clip connectors type XPSMCTC●●.

These connectors are to be ordered separately, see page 2/124.

(1) 8 independent safety outputs = 6 solid-state safety outputs + 2 x 2 relay outputs (4 relay outputs with guided contacts).
(2) 8 control outputs are available but they are not safety outputs.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety functions

Configuration of the safety functions is carried out using XPSMCWIN software.

30 certified safety functions are available with this software and they are easily assignable to the safety outputs. The safety functions have multiple combination possibilities and various starting conditions.

The safety functions are:
- certified in accordance with EN 954-1/EN/ISO 13849-1 and IEC 61508,
- configurable in controller XPSMC using XPSMCWIN software.

All 8 safety outputs are suitable for use in safety related parts of control systems conforming to category 4 of EN 954-1/EN/ISO 13849-1 and each output can disconnect one of its safety circuits.

Main safety functions

- Emergency stop monitoring, with or without time delay, 1 or 2-channel wiring
- Two-hand control (type III-C conforming to EN 574/ISO 13851)
- Guard monitoring with 1 or 2 limit switches
- Guard monitoring for injection presses and blowing machines
- Magnetic switch monitoring
- Sensing mat monitoring
- Light curtain (type 4 conforming to EN/IEC 61496, relay or solid-state output) monitoring
- Zero speed detection
- Dynamic monitoring of hydraulic valves on linear presses
- Monitoring safety stop at top dead center on eccentric press
- Safety time delays
- “Muting” function of light curtains
- Enabling switch monitoring, 2 or 3 contact
- Hydraulic press
- Eccentric press
- Foot switch monitoring
- Chain shaft breakage monitoring
- Position selector

Wiring diagrams and functional diagrams

See from page 2/126

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ configurable safety controllers type XPSMC



Communication

CANopen fieldbus

Configurable safety controllers XPSMC●●ZC incorporate a SUB-D 9-pin male connector for direct connection on CANopen bus.

CANopen bus is an open bus that ensures deterministic and reliable access to the real-time data of automation equipment. The bus uses a shielded dual twisted pair on which a maximum of 127 devices can be connected by chaining. The data rate varies between 10 Kbps and 1Mbps depending on the length of the bus (16,404 to 66 ft / 5,000 to 20 m).



Profibus bus

Configurable safety controllers XPSMC●●ZP incorporate a SUB-D 9-pin female connector for connection on Profibus bus.
Configurable safety controllers XPSMC●●ZP are slaves on the Profibus bus.

Profibus bus is a fieldbus that meets industrial communication requirements. The topology of the Profibus bus is of the linear type with a centralized master/slave type access procedure. The physical link is a single shielded twisted pair.



Modbus™ serial link

Configurable safety controllers XPSMC●●Z● MC incorporate a Modbus communication interface (RJ45 connector) for configuration and diagnostics.
This interface enables connection of the controllers to:
- a PC (configuration),
- a PLC (diagnostics), or
- an operator dialog terminal (diagnostics).

The Modbus serial link consists of a master station (Premium™ automation platform) and slave stations (configurable controllers XPSMC16/32Z●).
Two exchange mechanisms are possible:
■ **Question/response:** the questions from the master are addressed to a given slave. The response is expected by return from the interrogated slave.
■ **Distribution:** the master distributes a message to all the stations of the Modbus serial link. The latter execute the order without transmitting a reply.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ configurable safety controllers type XPSMC



Configurable safety controller XPSMC●●Z●, with screw connectors

Description

Configurable safety controllers XPSMC●●Z●

Front cover of controllers:

1 LED display and system diagnostics.
2 Two LEDs for CANopen or Profibus (1) connection status.
3 SUB-D 9-pin male connector for connection on CANopen bus (**XPSMC16ZC/MC32ZC**) or SUB-D 9-pin female connector for connection on Profibus bus (**XPSMC16ZP/MC32ZP**).
4 Solid-state safety output and "muting" indicator light terminals.
5 Power supply (⎓ 24 V) and relay safety output terminals.
6 Control output terminals for power supply to safety inputs and safety input terminals.
7 RJ45 connector for connection on Modbus™ serial link.
8 RESET button (resetting of controller).

Rear face of controllers:

9 Mounting plate for mounting on rail.

(1) Depending on controller model.



Illuminated display

LED details

LED	Color	Status	Meaning
1 PWR	Green	On	Supply voltage present.
2 CNF	Yellow	On	In configuration mode.
		Flashing	Not configured, initial power-up.
3 E In	Red	On	Internal error: all safety outputs deactivated.
4 E Ex	Red	On	External error: all safety outputs associated with the defective circuit are deactivated.
5 COM	Green	On	Controller communicating via the TER (RJ45) connection.
6 R1, R2	Green	On	Relay outputs 13/14, 23/24, 33/34 and 43/44 activated.
		Flashing	Fault on these outputs.
7 RUN	Green	Off	Hardware OK for the Profibus bus or the CANopen bus.
		On	Communicating on Profibus bus or on CANopen bus. Normal status.
8 ERR	Red	On	Communication impossible, configuration error, damaged cabling or absence. Bus deactivated
		Off	Communicating on CANopen or Profibus bus. Normal status.
		Flashing (x 1)	Warning limit reach.
		Flashing (x 2)	Control event error on CANopen bus.
		Flashing (x 3)	Synchronization error on CANopen bus.
9 1…16 1…32	Green	On	Input circuit closed.
		Flashing	Error detected on input relating to LED.
10 o1…o6	Green	On	Solid-state output activated.
		Flashing	Short-circuit, anomaly on output.
11 RUN	Green	On	Run mode.
		Flashing	Changing from run mode to stop mode.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ configurable safety controllers type XPSMC

Specifications

Configurable safety controller type				XPSMC16Z and MC32Z, XPSMC16ZC and MC32ZC, XPSMC16ZP and MC32ZP
Conformity to standards				EN/IEC 60204-1, EN 1760-1/ISO 13856-1, EN/IEC 60947-5-1, EN/IEC 61496-1, EN 574/ISO 13851, EN 954-1/EN/ISO 13849-1, IEC 61508
Product certifications				UL, CSA, TÜV
Products designed for max. use in safety related parts of control systems (conforming to EN 954-1/EN/ISO 13849-1 and IEC 61508)				Category 4 max. (EN 954-1/EN/ISO 13849-1), SIL 3 max. (IEC 61508)
Supply voltage			**V**	⎓ 24 ± 20%
Maximum power consumption			**W**	12
Fuse protection			**A**	16 gL max.
Start button monitoring				Configurable
Control circuit voltage				28.8 V/13 mA (between input terminals C1-I1 to C8-I16, resp. I32)
Calculation of wiring resistance RL			Ω	100 max, maximum cable length: 2000 m (Between input terminals)
Synchronization time between inputs			**s**	Depending on configuration selected
Outputs	**Relay**	Voltage reference		Relay hard contacts
		Safety circuit		2 N.O. per function (4 N.O. total) (13-14, 23-24, 33-34, 43-44)
		Breaking capacity in AC-15	**VA**	C300: inrush 1800, maintained 180
		Breaking capacity in DC-13		24 V/1.5 A L/R = 50 ms
		Thermal current (Ithe) for each group of 2 outputs	**A**	6 for 1 output and 2 for the other, **or** 4 for both outputs.
		Current limit	**A**	Ith ⩽ 16 (with several relay output circuits simultaneously loaded)
		Output fuse protection	**A**	4 gL or 6 quick blow
		Minimum current	**mA**	10 *(1)*
		Minimum voltage	**V**	17 *(1)*
	Solid-state	Breaking capacity		24 V/2 A
		Safety circuit		6 solid-state (O1, O2, O3, O4, O5, O6)
		Current limit	**A**	Ith ⩽ 6.5 (with several solid-state output circuits simultaneously loaded)
Electrical life				See page 3/12
Response time on input opening			**ms**	Response time = 20 or 30, configurable using software XPSMCWIN □ if 20 for controllers XPSMC●●Z●: 30 for a safety mat □ if 30 for controllers XPSMC●●Z●: 45 for a safety mat
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to IEC 60647-5-1, DIN VDE 0110 part 1)
Rated impulse withstand voltage (Uimp.)			**kV**	4 (overvoltage category III, conforming to IEC 60647-5-1, DIN VDE 0110 part 1)
LED display				30 (XPSMC16Z), 46 (XPSMC32Z) 32 (XPSMC16ZC/MC16ZP, 48 (XPSMC32ZC/MC32ZP)
Temperature	Operating		**°F (°C)**	+ 14…+ 131 (- 10…+ 55)
	Storage		**°F (°C)**	- 13…+ 267.8 (- 25…+ 85)
Degree of protection				IP 20 conforming to EN/IEC 60529 (connector and enclosure)

(1) The controller is also capable of switching low power loads (17 V/10 mA minimum) provided that the contact has not been used for switching high power loads (possible contamination or wear of the gold layer on the contact tips).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Communication

Modbus™ serial link

Compatibility			**XPSMC16Z, XPSMC32Z, XPSMC16ZC, XPSMC32ZC, XPSMC16ZP, XPSMC32ZP**
Serial link ports	Number and type		1 x RJ45
	Status		Slave
Data exchange			14 words
Addressing			1 …247
Baud rate		**bps**	1200, 2400, 4800, 9600 or 19200
Parity			Even, odd, none
Fixed parameters			RTU (Remote Terminal Unit) mode 1 start bit / 8 data bits 1 stop bit stop with “even” or “odd” parity 2 stop bits without parity
Functions supported			01: 8-bit output data / 32-bit input data (0 = OFF, 1 = ON) 02: 32-bit input data / 8-bit output data (0 = OFF, 1 = ON) 03: information and errors

CANopen bus

Compatibility			**XPSMC16ZC, XPSMC32ZC**
Serial link ports	Number and type		1 x SUB-D 9-pin male
	Status		Slave
Data exchange			14 words By included dual port memory: only data addresses, diagnostics, but no baud rates
Parameters (adjustable using software XPSMCWIN)	Baud rate	**Kbps**	20, 50, 125, 250, 500, 800
		Mbps	1
	Address		1…127

Profibus bus

Compatibility			**XPSMC16ZP, XPSMC32ZP**
Serial link ports	Number and type		1 x SUB-D 9-pin female
	Status		Slave
Data exchange			14 words By included dual port memory: only data addresses
Parameters	Baud rate	**Mbps**	12
	Address		1…125

Connections

Type			**Separate plug-in screw connector XPSMCTS●● *(1)***	**Separate plug-in spring clip connector XPSMCTS●● *(1)***
Power supply and relay output terminals				
1 conductor	Without cable end		Solid or flexible cable: 24-12 AWG (0.2…2.5 mm²)	
	With cable end		Without bezel, flexible cable: 22-12 AWG (0.25…2.5 mm²)	
			With bezel, flexible cable: 22-12 AWG (0.25…2.5 mm²)	
2 conductors	Without cable end		Solid or flexible cable: 24-16 AWG (0.2…1.5 mm²)	–
	With cable end		Without bezel, flexible cable: 22-16 AWG (0.25…1.5 mm²)	–
			Double, with bezel, flexible cable: 20-16 AWG (0.5…1.5 mm²)	Double, with bezel, flexible cable: 20-18 AWG (0.5…1.0 mm²)
Tightening torque of screw terminals			4.2...5.3 lb-in (0.5...0.6 Nm)	–
Wire stripping length			0.39 in (10 mm)	
Other terminals				
1 conductor	Without cable end		Solid or flexible cable: 28-16 AWG (0.14…1.5 mm²)	
	With cable end		Without bezel, flexible cable: 23-16 AWG (0.25…1.5 mm²)	
			With bezel, flexible cable: 23-20 AWG (0.25…0.5 mm²)	
2 conductors	Without cable end		Solid cable: 28-20 AWG (0.14…0.5 mm²) Flexible cable: 28-19 AWG (0.14…0.75 mm²)	–
	With cable end		Without bezel, flexible cable: 23-22 AWG (0.25…0.34 mm²)	–
			Double, with bezel, flexible cable: 20 AWG (0.5 mm²)	–
Enclosure mounting (conforming to DIN EN 50022)			Metal adaptor for mounting on DIN 35 mm metal rail	

(1) To be ordered separately.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ configurable safety controllers type XPSMC

XPSMC16Z

XPSMC32Z

XPSMC16ZC

XPSMC32ZC

XPSMC16ZP

XPSMC32ZP

References

Configurable safety controllers (connector not included)

Number of inputs	Number of outputs		Communication (Link and bus)	Reference	Weight oz (kg)
	Relay	Solid-state			
16	**4 (2 x 2)**	**6**	Modbus™	**XPSMC16Z**	28.925 (0.820)
			Modbus, CANopen	**XPSMC16ZC**	28.925 (0.820)
			Modbus, Profibus	**XPSMC16ZP**	28.925 (0.820)
32	**4 (2 x 2)**	**6**	Modbus	**XPSMC32Z**	29.630 (0.840)
			Modbus, CANopen	**XPSMC32ZC**	29.630 (0.840)
			Modbus, Profibus	**XPSMC32ZP**	29.630 (0.840)

Plug-in connectors for configurable safety controllers *(1)*

Description	For use with	Reference	Weight oz (kg)
Screw connectors	XPSMC16Z, MC16ZC, MC16ZP	**XPSMCTS16**	2.822 (0.080)
	XPSMC32Z, MC32ZC, MC32ZP	**XPSMCTS32**	3.880 (0.110)
Spring clip connectors	XPSMC16Z, MC16ZC, MC16ZP	**XPSMCTC16**	2.822 (0.080)
	XPSMC32Z, MC32ZC, MC32ZP	**XPSMCTC32**	3.880 (0.110)

Configuration software

Description	Operating system	Details *(2)*	Languages	Reference	Weight oz (kg)
Configuration software for controllers XPSMC●●Z● CD-ROM + user manual	Windows® 2000, Windows® XP, Windows® Vista, Windows® 7	Software available on Safety Suite V2 software pack	EN, FR, DE, IT, ES, PT	**XPSMCWIN**	18.342 (0.520)

(1) To be ordered separately to the controllers.
(2) EDS and GSD files are available on the XPSMCWIN configuration software CD-ROM.

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSMCCPC

TSX PCX 1031

490 NT● 000 ●●

TSX CUSB485

TSX CAN TDM4

ABL8RPS24100

References

Connecting cables *(1)*

Function			Length ft (m)	Reference	Weight oz (kg)
Diagnostics using Magelis™ operator dialog terminal type XBT GT			9.8 (3)	**VW3A8306R30**	39.860 (1.130)
Configuration software	1	Adaptor: RJ45 socket/PC connection cables	–	**XPSMCCPC**	0.388 (0.011)
	2	Cable to PC serial port (type SUB-D9)	8.2 (2.5)	**TSXPCX1031**	5.997 (0.170)
	3	Straight shielded twisted pair cables, EIA/TIA 568 standard (RJ45 connector at each end)	6.6 (2)	**490NTW00002**	–
			16.4 (5)	**490NTW00005**	–
			39.4 (12)	**490NTW00012**	–
		Straight shielded twisted pair cables, UL and CSA 22.1 approved (RJ45 connector at each end)	6.6 (2)	**490NTW00002U**	–
			16.4 (5)	**490NTW00005U**	–
			39.4 (12)	**490NTW00012U**	–
	with	RJ45/PC USB port converter *(2)*	1.3 (0.4)	**TSXCUSB485**	–



Function	Medium		Length ft (m)	Reference	Weight oz (kg)
Modbus serial link access	Premium™ automation platform TSXSCY21601		–	**XPSMCSCY**	–
CANopen bus access	1	CANopen connection cables (fitted with: 1 SUB-D 9-pin female connector at each end)	1 (0.3)	**TSXCANCADD03**	–
			3.3 (1)	**TSXCANCADD1**	–
			9.8 (3)	**TSXCANCADD3**	–
			16.4 (5)	**TSXCANCADD5**	–
	2	CANopen tap-off box	–	**TSCCANTDM4**	–
	3	Standard CANopen cables	164 (50)	**TSXCANCA50**	–
			328 (100)	**TSXCANCA100**	–
			984 (300)	**TSXCANCA300**	–
Profibus bus access			328 (100)	**TSXPBSCA100**	–
			1312 (400)	**TSXPBSCA400**	–



Accessories *(1)*

Regulated switch mode power supply, single-phase	Output voltage: ⎓ 24…28.8 V Nominal current: 10 A Nominal power: 240 W	**ABL8RPS24100**	35.274 (1.000)

(1) To be ordered separately.
*(2) The converter **TSX CUSB485** is installed using **Driver Pack V2.3**. This "driver" is available on the Safety Suite V2 software pack or downloadable from our site: www.schneider-electric.com*

Dimensions, mounting

XPSMC●●Z●



(1) 6.02 in (153 mm) with screw connector XPSMCTS●●. 5.96 in (151.4 mm) with spring clip connector XPSMCTC●●.
(2) Metal adaptor for mounting on metal DIN 35 mm rail.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Emergency stop monitoring, with or without time delay, 1-channel wiring, with automatic start

Category 4 achieved with necessary precautions taken to eliminate input circuit anomalies.

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagram



Key 0 1

tv = delay time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Emergency stop monitoring, with or without time delay, 2-channel wiring, with start button

Category 4 conforming to standard EN 954-1.

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagram



tv = delay time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Two-hand control (type III-C conforming to EN 574-1)

Category 4 conforming to standard EN 954-1.

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagram



tv = delay time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Guard monitoring with 1 safety limit switch

Category 1 conforming to standard EN 954-1.

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagrams

Start test = NO

Automatic start



Rising edge monitored start



Falling edge monitored start



Start test = YES

Automatic start



Rising edge monitored start



Falling edge monitored start



Key 0 1

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Guard monitoring with 2 safety limit switches

Category 4 conforming to standard EN 954-1.

Wiring diagram



ESC = external start conditions
EDM = external devices monitoring

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Guard monitoring with 2 safety limit switches (continued)

Functional diagrams

Start test = NO

Automatic start



Rising edge monitored start



Falling edge monitored start



Start test = YES

Automatic start



Rising edge monitored start



Falling edge monitored start



Key 0 — 1

EDM = external devices monitoring
t EDM = maximum monitoring time of external devices
t sync. = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Guard monitoring with 2 safety limit switches, with guard locking

Category 4 conforming to standard EN 954-1.

Wiring diagram



ESC = external start conditions
EDM = external devices monitoring

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Guard monitoring with 2 safety limit switches, with guard locking (continued)

Functional diagrams

Start test = NO

Automatic start



Rising edge monitored start



Falling edge monitored start



Start test = YES

Automatic start



Rising edge monitored start



Falling edge monitored start



Key 0 — 1

t sync. = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Guard monitoring for injection presses and blowing machines

Category 4 conforming to standard EN 954-1.

Wiring diagram



ESC = external start conditions
EDM = external devices monitoring

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Guard monitoring for injection presses and blowing machines (continued)

Functional diagrams

Start test = NO

Automatic start



Start test = YES

Automatic start



Rising edge monitored start



Rising edge monitored start



Falling edge monitored start



Falling edge monitored start



Key 0 ⌐ 1

t sync. = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Non-contact safety interlock (magnetic switch) monitoring

Wiring diagram



ESC = external start conditions
EDM = external devices monitoring

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Non-contact safety interlock (magnetic switch) monitoring (continued)

Functional diagrams

Start test = NO

Automatic start



Rising edge monitored start



Falling edge monitored start



Start test = YES

Automatic start



Rising edge monitored start



Falling edge monitored start



Key 0 — 1

EDM = external devices monitoring
t EDM = maximum monitoring time of external devices
t sync. = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Sensing mat monitoring

- Category 3 conforming to standard EN 954-1.
- Control outputs connected to a sensing mat cannot be used for other items.

Wiring diagram



ESC = external start conditions
EDM = external devices monitoring

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Sensing mat monitoring (continued)

Functional diagrams

Start-up test

Automatic start



Rising edge monitored start



Falling edge monitored start



Key 0 1

EDM = external devices monitoring
t EDM = maximum monitoring time of external devices

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Light curtain monitoring, relay output type

Category 4 conforming to standard EN 954-1.

Wiring diagram



ESC = external start conditions
ESPE = electro-sensitive protection equipment
OSSD1/OSSD2 = output signal switching device

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain monitoring, relay output type (continued)

Functional diagrams

Start test = NO

Automatic start



Rising edge monitored start



Falling edge monitored start



Start test = YES

Automatic start



Rising edge monitored start



Falling edge monitored start



Key 0 ⌐ 1

EDM = external devices monitoring
t EDM = maximum monitoring time of external devices
t sync. = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Light curtain monitoring, solid-state output type

Category 4 conforming to standard EN 954-1.

Wiring diagram



ESC = external start conditions
ESPE = electro-sensitive protection equipment
OSSD1/OSSD2 = output signal switching device

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain monitoring, solid-state output type (continued)

Functional diagrams

Start test = NO

Automatic start



Rising edge monitored start



Falling edge monitored start



Start test = YES

Automatic start



Rising edge monitored start



Falling edge monitored start



Key 0 — 1

EDM = external devices monitoring
t EDM = maximum monitoring time of external devices
t sync. = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Zero speed detection

Category 4 conforming to standard EN 954-1.

Wiring diagram



The zero speed signal (validation of the output) will be activated only if:
1: one input is in a high state,
2: the other input is in a low state,
3: the frequency of the two inputs is less than the stated value.

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.
(3) Only one "Zero speed detection" function can be connected to an XPSMC controller, and only to the inputs i1 and i2.

Functional diagram

Sensor control





Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Dynamic monitoring of hydraulic valves on linear presses

Category 4 conforming to standard EN 954-1.

Wiring diagram



ESC = external start conditions

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagrams

Valve control



BDC = Bottom Dead Center
TDC = Top Dead Center
t sync. = synchronization time

Valve sensor signals



***Note:** The valve sensor signals must function as described above.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Monitoring safety stop at top dead center on eccentric press

- Category 4 conforming to standard EN 954-1.
- This function consists of several monitoring modes including:
  - safety stop at top dead center *(1)*,
  - monitoring braking travel,
  - as an option, dynamic monitoring of doubled-bodied solenoid valves *(2)*.

Wiring diagram



S8: Operating modes:
0 - stop,
1 - adjust,
2 - jog,
3 - automatic continuous run.
OTS = Limit switch associated with top dead center (TDC)
UN = Limit switch associated with bottom dead center (BDC)
PSV = safety valve

(3) Technical specifications for maximum rating of fuses, see page 2/122.
(4) Only applicable to XPSMC32Z●.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Monitoring safety stop at top dead center on eccentric press (continued)

Functional diagram in adjust mode



Key 0 — 1

OTS = Limit switch associated with top dead center (TDC)
UN = Limit switch associated with bottom dead center (BDC)
PSV = safety valve
t sync = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Monitoring safety stop at top dead center on eccentric press (continued)

Functional diagram in jog mode



Key 0 1

BDC = Bottom Dead Center
TDC = Top Dead Center
OTS = Limit switch associated with top dead center (TDC)
UN = Limit switch associated with bottom dead center (BDC)
PSV = safety valve
t sync = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Monitoring safety stop at top dead center on eccentric press (continued)

Functional diagram in automatic continuous run mode



Key 0 1

BDC = Bottom Dead Center
TDC = Top Dead Center
OTS = Limit switch associated with top dead center (TDC)
UN = Limit switch associated with bottom dead center (BDC)
PSV = safety valve
t sync = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Safety time delays

Category 4 conforming to standard EN 954-1.

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagrams



Functions:
EV = On-delay
AV = Off-delay
EW = Pulse on energization
AW = Pulse on de-energization

On-delay



Pulse on energization



Off-delay



Pulse on de-energization



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

"Muting" function for light curtains

Category 4 conforming to standard EN 954-1.

Wiring diagram



ESC = external start conditions
EDM = external devices monitoring
ESPE = electro-sensitive protection equipment
OSSD1/OSSD2 = output signal switching device

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.
(3) A light curtain with relay outputs can also be used with the "Muting" function.
(4) Only one "Muting" function can be connected to an XPSMC controller.
(5) Example using 2 safety outputs to control 2 contactors linked to one safety function.

Functional diagram



tM = "Muting" time
tF = free passage activation time
t sync. = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Enabling switch monitoring, 2 contact type

Category 1 conforming to standard EN 954-1.

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagram



t Z = enabling time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Enabling switch monitoring, 3 contact type

Category 4 conforming to standard EN 954-1.

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagram



t Z = enabling time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Hydraulic press

Category 4 conforming to standard EN 954-1.

Wiring diagram



S8: Operating modes:
0 - stop,
1 - adjust,
2 - jog.

AUF = open, to be used in inching.
OT = Limit switch associated with top dead center (TDC).
UT = Limit switch associated with bottom dead center (BDC).
NWK = overtravel monitoring.

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z● (I17…I32).

Functional diagram

Hydraulic press, adjust mode



(1) Not used.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Hydraulic press

Functional diagrams *(continued)*

Hydraulic press, mode = jog, with overtravel monitoring and opening and closing control coming from the automation platform



Hydraulic press, mode = jog



Hydraulic press, mode = automatic, with overtravel monitoring and opening and closing control coming from the automation platform



Hydraulic press, mode = automatic



Key 0 — 1

(1) Not used.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Eccentric press

Category 4 conforming to standard EN 954-1.

Wiring diagram



S8: Operating modes:
0 - stop,
1 - adjust,
2 - jog,
3 - automatic continuous run.
OTS = Limit switch associated with top dead center (TDC)
UN = Limit switch associated with bottom dead center (BDC)
PSV = safety valve
B1 = sensor at tooth wheel in cam switch mechanism.

(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z● (I17…I32).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Eccentric press (continued)

Functional diagrams

Eccentric press: Jog



Eccentric press: Continuous



Eccentric press: automatic continuous



Key 0 — 1

t sync. = synchronization time
t tot. = dead time

(1) Not used.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Foot switch monitoring

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagrams

Without start interlock



With start interlock



Key 0 1

t sync. = synchronization time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Chain shaft breakage monitoring

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Functional diagrams



Key 0 1

tp = pulse time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

2

Position selector

Wiring diagram



(1) Technical specifications for maximum rating of fuses, see page 2/122.
(2) Only applicable to XPSMC32Z●.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Position selector (continued)

Functional diagrams





Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety relay modules

Selection guide: Preventa™ safety relay modules *3/2*

Electrical ratings *3/12*

For Emergency stop and switch monitoring
- Types XPSAC, XPSAXE *3/14*
- Types XPSAV, XPSABV, XPSATE *3/18*
- Type XPSATR *3/28*
- Type XPSAF *3/32*
- Type XPSAFL *3/36*

For Emergency stop, switch or light curtain monitoring
- Type XPSAR *3/40*

For Emergency stop, switch, sensing mat/edges or light curtain monitoring
- Type XPSAK *3/46*

For electrical monitoring of two-hand control stations
- Types XPSBAE, XPSBCE, XPSBF *3/52*

For forming a type 2 light curtain
- Types XPSCM, XU2S (single-beam photoelectric sensor) *3/60*

For monitoring 2 to 4 light curtains type 2 and type 4
- Type XPSLCD *3/68*

For "muting" function of type 2 and type 4 light curtains
- Type XPSLCM *3/72*

For increasing the number of safety contacts
- Types XPSECME, XPSECPE *3/80*

For safety time delays
- Types XPSTSA, XPSTSW *3/84*

For non-contact safety interlock (coded magnetic) switch monitoring
- Types XPSDMB, XPSDME *3/88*

For zero speed detection
- Type XPSVNE *3/94*

For dynamic monitoring of hydraulic valves on linear presses
- Type XPSPVT *3/100*

For dynamic monitoring of double-bodied solenoid valves
- Type XPSPVK *3/104*

For safety stop with automatic overtravel monitoring and control
- Type XPSOT *3/108*

Dimensions *3/112*

Safety solutions on AS-Interface™ cabling system

Selection guide: Safety monitors and interfaces *3/114*

AS-Interface "Safety at work" monitors *3/116*

Safety interfaces *3/120*

Safety reliability values

Safety reliability values according to standard EN/ISO 13849-1 and EN/IEC 62061 . . . . . *3/124*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays
Preventa™ safety relay modules

Applications			
Modules		**For Emergency stop and switch monitoring**	
Maximum achievable safety level		PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061	PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061
Conformity to standards		EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1	EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1
Product certifications		UL, CSA, TÜV	UL, CSA, BG
Number of circuits			
	Safety	3 N.O.	3 N.O.
	Additional	1 solid-state output for signalling to PLC	1 relay output for signalling to PLC
Display		2 LEDs	2 LEDs
Supply voltage		∼ and 24 V ⎓ 48 V ∼ 115 V ∼ 230 V ∼	∼ and 24 V ⎓
Synchronization time between inputs		Unlimited	Unlimited
Input channel voltage			
	24 V/48 V version	∼ and 24 V ⎓/48 V ∼	24 V ⎓
	24 V/48 V or 110 V/120 V/230 V version	115 V ∼/230 V –	–
Module type		**XPSAC**	**XPSAXE**
Pages		3/15	3/15

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com







For Emergency stop and switch monitoring	For Emergency stop and protective guard applications	For Emergency stop and switch monitoring	
PLe/Category 4 (instantaneous safety outputs) and PLd/Category 3 (time delay safety outputs) conforming to EN/ISO 13849-1, SILCL3 (instantaneous safety outputs) and SILCL2 (time delay safety outputs) conforming to EN/IEC 61508 and EN/IEC 62061	PLe/Category 4 conforming to EN ISO 13849-1, SILCL3 conforming to EN/IEC 62061	PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061	PLe/Category 4 (instantaneous safety outputs) and PLd/Category 3 (time delay safety outputs) conforming to EN/ISO 13849-1, SILCL3 (instantaneous safety outputs) and SILCL2 (time delay safety outputs) conforming to EN/IEC 61508 and EN/IEC 62061
EN/IEC 60204-1, EN/ISO 13850, EN 1088/ISO 14119, EN/IEC 60947-1, EN/IEC 60947-5-1	EN 62061 EN ISO 13849-1 EN 50156-1 EN 60204-1 EN/IEC 61496-1 IN/IEC 60947-5-1	EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1, EN/ISO 13850, EN 1088/ISO 14119
UL, CSA, TÜV	UL, CSA, TÜV	UL, CSA, TÜV	UL, CSA, BG
2 N.O. instantaneous + 3 N.O. time delay	3 N.O. instantaneous + 3 N.O. time delay	3 N.O. instantaneous + 3 N.O. time delay	2 N.O. instantaneous + 1 N.O. time delay
4 solid-state outputs for signalling to PLC	1 N.C.	3 solid-state outputs for signalling to PLC	–
4 LEDs	5 LEDs	11 LEDs	3 LEDs
∼ and 24 V ⎓ 115 V ∼ 230 V ∼	⎓ 24 V ∼ 115…230 V	24 V ⎓	24 V ⎓
75 ms (automatic start)	1	Unlimited or 1.5 s (depending on wiring)	Unlimited
24 V ⎓/–	24 V ⎓/–	24 V ⎓/–	24 V ⎓/–
48 V ∼/48 V –	24 V ⎓/–	– –	– –
XPSATE	**XPSATR**	**XPSAV**	**XPSABV**
3/20	3/29	3/20	3/20

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays
Preventa™ safety relay modules

Applications





Modules	**For Emergency stop and switch monitoring**	**For Emergency stop, switch or solid-state output safety light curtain monitoring**	
Maximum achievable safety level	PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061	PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061	PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061
Conformity to standards	EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1	EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1, EN/IEC 61496-1 (type 4)	EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1
Product certifications	UL, CSA, TÜV	UL, CSA, TÜV	UL, CSA, TÜV
Number of circuits			
Safety	3 N.O.		7 N.O.
Additional	–		2 N.C. + 4 solid-state outputs for signalling to PLC
Display	3 LEDs		4 LEDs
Supply voltage	∿ and 24 V ⎓		∿ and 24 V ⎓ 115 V ∿ and 24 V ⎓ 230 V ∿ and 24 V ⎓
Synchronization time between inputs	Unlimited		
Input channel voltage			
24 V/48 V version	⎓ 24 V/–		24 V ⎓/–
24 V/48 V or 110 V/120 V/230 V version	– –		24 V ∿/24 V –
Module type	**XPSAF**	**XPSAFL**	**XPSAR**
Pages	3/33	3/37	3/41

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com





For Emergency stop, switch, sensing mat/edges or solid-state output safety light curtain monitoring	For electrical monitoring of two-hand control stations		
PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061	PLc/Category 1 conforming to EN/ISO 13849-1 SILCL1 conforming to EN/IEC 62061	PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061	PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061
EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1	EN 574 type III A, EN/IEC 60204-1, EN/IEC 60947-5-1, EN 62061	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1, EN 574 type III C/ISO 13851	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1, EN 574 type III C/ISO 13851
UL, CSA, TÜV	UL, CSA, TÜV	UL, CSA, BG	UL, CSA, TÜV
3 N.O. instantaneous	1 N.O.	2 N.O.	2 N.O.
1 N.C. + 4 solid-state outputs for signalling to PLC	1 N.C.	1 N.C.	2 solid-state outputs for signalling to PLC
4 LEDs	2 LEDs	3 LEDs	3 LEDs
∼ and 24 V ⎓ 48 V ∼ 110 V ∼ and 24 V ⎓ 120 V ∼ and 24 V ⎓ 230 V ∼ and 24 V ⎓	∼ and 24 V ⎓ 115/230 V ∼	∼ and 24 V ⎓ 115/120 V ∼ 230 V ∼	24 V ⎓
Unlimited or 2 s, 4 s (depending on wiring)	500 ms	500 ms	500 ms
24 V ⎓/–	24 V ⎓/–	24 V ⎓	24 V ⎓/–
– 24 V ⎓/24 V/24 V	– 24 V ∼/24 V	– –	– –
XPSAK	**XPSBAE**	**XPSBCE**	**XPSBF**
3/47	3/55	3/55	3/55

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays
Preventa™ safety relay modules

Applications			
Modules		**For control of 1 to 4 single-beam photo-electric sensors XU2 S (transmitter-receiver pair)**	**For monitoring 2 to 4 type 2 and type 4 light curtains (transmitter-receiver pair)**
Maximum achievable safety level		PLc/Category 2 conforming to EN/ISO 13849-1, SILCL1 conforming to EN/IEC 61508 and EN/IEC 62061	PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Conformity to standards		EN/IEC 61496-1, EN/IEC 61496-2, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1	EN 954-1 - category 4/EN/ISO 13849-1, EN/IEC 61496-1, EN/IEC 61496-2
Product certifications		UL, CSA, IFA	UL, CSA, TÜV
Number of circuits			
	Safety	2 N.O.	2 solid-state PNP (N.O.)
	Additional	4 solid-state PNP N.O. outputs for signalling to PLC	1 PNP N.O. + 1 NPN N.O. output for signalling to PLC
Display		4 LEDs	9 LEDs + 2-digit display
Supply voltage		24 V ⎓	⎓ 24 V
Synchronization time between inputs		–	–
Input channel voltage			
	24 V/48 V version	–	24 V/–
	115 V/230 V version	–	–
Module type		**XPSCM**	**XPSLCD**
Pages		3/62	3/69

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com







For monitoring type 2 and type 4 light curtains Compact and slim ranges	For extending the number of safety contacts	
PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061	PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061 (when connected to the appropriate module)	PLe/Category 4 conforming to EN/ISO 13849-1, SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061 (when connected to the appropriate module)
EN/IEC 61496-1, EN/IEC 61496-2, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1
UL, CSA, TÜV	UL, CSA, BG	UL, CSA, TÜV
2 solid-state	4 N.O.	8 N.O.
1 PNP + 1 NPN output for signalling to PLC	2 N.C.	1 N.C.
14 LEDs + 2-digit display	2 LEDs	3 LEDs
24 V ⎓	∿ and 24 V ⎓	∿ and 24 V ⎓ 115 V ∿ 230 V ∿
3 s or infinite	–	–
–	–	–
–	–	–
XPSLCM	**XPSECME**	**XPSECPE**
3/74	3/81	3/81

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays
Preventa™ safety relay modules

Applications



Modules	**For the monitoring of applications requiring safety time delays**	
Maximum achievable safety level	PLd/Category 3 conforming to EN/ISO 13849-1, SILCL2 conforming to EN/IEC 61508 and EN/IEC 62061	PLd/Category 3 conforming to EN/ISO 13849-1, SILCL2 conforming to EN/IEC 61508 and EN/IEC 62061
Conformity to standards	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1
Product certifications	UL, CSA, TÜV	UL, CSA, TÜV
Number of circuits		
Safety	1 N.O. time delayed	1 N.O. pulse type
Additional	2 N.C. + 2 solid-state outputs for signalling to PLC	
Display	4 LEDs	
Supply voltage	∿ and 24 V ⎓ 115 V ∿ 230 V ∿	
Synchronization time between inputs	–	–
Module type	**XPSTSA**	**XPSTSW**
Pages	3/85	3/85

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com





For coded magnetic switch monitoring		For zero speed detection of AC or DC motors which produce a remanent voltage in their windings due to residual magnetism
For 2 max.	For 6 max.	
PLe/Category 4 conforming to EN/ISO 13849-1 SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061	PLe/Category 4 conforming to EN/ISO 13849-1 SILCL3 conforming to EN/IEC 61508 and EN/IEC 62061	PLd/Category 3 conforming to EN/ISO 13849-1, SILCL2 conforming to EN/IEC 61508 and EN/IEC 62061
EN/IEC 60204-1, EN 1088/ISO 14119, EN/IEC 60947-1, EN/IEC 60947-5-1, EN/IEC 60947-5-3	EN/IEC 60204-1, EN 1088/ISO 14119, EN/IEC 60947-1, EN/IEC 60947-5-1, EN/IEC 60947-5-3	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1
UL, CSA, TÜV	UL, CSA, TÜV	UL, CSA, TÜV
2 N.O.		1 N.O. + 1 N.C.
2 solid-state outputs for signalling to PLC		2 solid-state outputs for signalling to PLC
3 LEDs	15 LEDs	4 LEDs
⎓ 24 V		24 V ⎓ 115 V ∿ 230 V ∿
500 ms		–

XPSDMB	XPSDME	XPSVNE
3/89	3/89	3/95

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays
Preventa™ safety relay modules

Applications



Modules	**For dynamic monitoring of hydraulic valves on linear presses**

Functions	PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Conformity to standards	EN 954-1 - category 4/EN/ISO 13849-1, EN/IEC 60204-1, EN/IEC 60947-5-1, EN 693, EN 50082-2
Product certifications	UL, CSA
Number of circuits	
Safety	2 N.O. + 1 N.C.
Additional	–
Display	8 LEDs
Supply voltage	⎓ 24 V
Synchronization time between inputs	–
Module type	**XPSPVT**
Pages	3/101

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com





For dynamic monitoring of double-bodied solenoid valves	For safety stop at top dead center with automatic overtravel monitoring and control
PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061	PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
EN 954-1 - category 4/EN/ISO 13849-1, EN/IEC 60204-1, EN/IEC 60947-5-1, EN 692, EN 50082-2	EN 954-1 - category 4/EN/ISO 13849-1, EN/IEC 60204-1, EN/IEC 60947-5-1, EN 692, EN 50082-2
UL, CSA	UL, CSA
1 N.O. + 1 N.C.	3 N.O.
4 solid-state outputs for signalling to PLC	4 solid-state outputs for signalling to PLC
8 LEDs	8 LEDs
⎓ 24 V ∿ 115 V ∿ 230 V	– ∿ 115 V ∿ 230 V
–	–
XPSPVK	**XPSOT**
3/105	3/110

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

Electrical life

Electrical life curves of safety contacts conforming to EN 60947-5-1, table C2

XPSAC, XPSTSA, XPSTSW, XPSBAE, XPSCM, XPSOT, XPSPVK, XPSPVT, XPSVNE



XPSAXE, XPSECME



XPSATR



XPSECPE



XPSATE

24 V ⎓ version



115 V ∼ + 230 V ∼ version



XPSAF, XPSAK, XPSAFL



XPSAV, XPSMP, XPSVC, XPSBF, XPSMC



XPSABV

Contacts 13-14, 23-24



Contacts 37-38



Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Electrical life (continued)

Electrical life curves of safety contacts conforming to EN 60947-5-1, table C2

XPSBCE



XPSAR



XPSDMB, XPSDME



Electrical life

The product life expressed is based on average usage and normal operating conditions. The above statements are not intended to nor shall they create any express or implied warranties as to product operation or life. For information on the limited warranty offered on this product please refer to the Square D terms and conditions of sale found in the "Square D by Schneider Electric" *Digest.*

Definition of tests

Determination of electrical life conforming to EN 60947-5-1 (table C2)

Type of current	Utilization category	Start-up			Breaking		
		Current	Voltage	Cos φ	Current	Voltage	Cos φ
a.c. supply	AC-15	10 x Ie	Ue	0.7	Ie	Ue	0.4
Type of current	**Utilization category**	**Start-up**			**Breaking**		
		Current	**Voltage**	**T0.95**	**Current**	**Voltage**	**T0.95**
d.c. supply	DC-13	Ie	Ue	50 ms	Ie	Ue	50 ms

Ie: operational current measured. Ue: operational voltage measured. Cos φ: power factor. T0.95: time taken to reach 95% of nominal current.

Notes

The tests are carried out with a frequency of 6 switching operations per minute and with no additional protection of the components connected to the safety outputs.
The use of additional protection for the components connected to the safety outputs significantly increases the durability of the safety outputs.

Determination of the breaking capacity conforming to EN 60947-5-1 (table 4)

Utilization category	Start-up			Breaking			Total number of switching operations	Switching operations per minute for 1 to 1000 switching operations	Switching operations per minute for 1001 to 6050 switching operations	Minimum duration of switching operation
	Current	Voltage	Cos φ	Current	Voltage	Cos φ				
AC-15	10 x Ie	Ue	0.3	Ie	Ue	0.3	6050	60	6	50 ms
Utilization category	**Start-up**			**Breaking**			**Total number of switching operations**	**Switching operations per minute for 1 to 1000 switching operations**	**Switching operations per minute for 1001 to 6050 switching operations**	**Minimum duration of switching operation**
	Current	**Voltage**	**T0.95**	**Current**	**Voltage**	**T0.95**				
DC-13	Ie	Ue	50 ms	Ie	Ue	50 ms	6050	60	6	50 ms

Ie: operational current measured. Ue: operational voltage measured. Cos φ: power factor. T0.95: time taken to reach 95% of nominal current.

Notes

The maximum values for the breaking capacity of the safety outputs in the various utilization categories are not fixed and depend on the power factor and on the switching frequency. The test definition for the "breaking capacity" and "durability" tables in the European standard EN 60947-5-1 uses different values for the power factor and the switching frequency.
The power factor (cos φ) in the "breaking capacity" table (0.3) is greater than that in the "durability" table (0.7).
In the "breaking capacity" table, the switching frequency of the safety outputs is higher for the first 1000 switching operations (60 per minute) than that for 1001 to 6050 switching operations (6 per minute).
Consequently, the maximum breaking capacity values determined using the "breaking capacity" table are lower than those in the "durability" table.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSAC, XPSAXE

For Emergency stop and switch monitoring

Operating principle

Safety relay modules XPSAC and XPSAXE are used for monitoring Emergency stop circuits conforming to standards EN/ISO 13850 and EN/IEC 60204-1 and also meet the requirements for the electrical monitoring of switches in protection devices conforming to standard EN 1088/ISO 14119. They provide protection for both the machine operator and the machine by immediately stopping the dangerous movement on receipt of a stop instruction from the operator, or on detection of an anomaly in the safety circuit itself.
To aid diagnostics, the modules have LEDs which provide information on the monitoring circuit status.

The XPSAC module has 3 safety outputs and a solid-state output for signaling to the PLC.
The XPSAXE module has 3 safety outputs and a relay output for signaling to the PLC.

Specifications

Module type			XPSAC, XPSAC●●●●P	XPSAXE●●●●P, XPSAXE●●●●C
Maximum achievable safety level			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061	PL e/Category 4 conforming to EN/ISO 13849-1 SILCL 3 conforming to EN/IEC 62061
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)	**Years**	210.4	457
	Diagnostic Coverage (DC)	**%**	> 99	> 99
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	3.56×10^{-9}	3×10^{-8}
Conformity to standards			EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1	EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1
Product certifications			UL, CSA, TÜV	UL, CSA, BG
Supply	Voltage	**V**	∿ and 24 ⎓, 48 ∿, 115 ∿, 230 ∿	∿ and 24 ⎓
	Voltage limits		- 20 to + 10% (24 V ∿) - 20 to + 20% (24 V ⎓) - 15 to + 10% (48 V ∿) - 15 to + 15 % (115 V) - 15 to + 10% (230 V)	- 15 to + 10%
	Frequency	**Hz**	50/60	50/60
Power consumption		**W**	< 1.2 (24 V ⎓)	–
		VA	< 2.5 (24 V ∿) < 6 (48 V ∿) < 7 (115 V ∿) < 6 (230 V ∿)	< 1.6 (for 24VDC) / < 2.2 (for 24VAC)
Start button monitoring			No	No
Control unit voltage (at nominal supply voltage)			Identical to supply voltage	
	24 V version	**V**	24 ∿ (approx. 90 mA), 24 ⎓ (approx. 40 mA)	24 ⎓
	48 V version	**V**	48 ∿ (approx. 100 mA)	–
	115 V version	**V**	115 ∿ (approx. 60 mA)	–
	230 V version	**V**	230 ∿ (approx. 25 mA)	–
Outputs	Voltage reference		Relay hard contacts	Relay hard contacts
	Number and type of safety circuits		3 N.O. (13-14, 23-24, 33-34)	3 N.O. (13-14, 23-24, 33-34)
	Number and type of additional circuits		1 solid-state	1 N.C. relay (41-42)
	Breaking capacity in AC-15	**VA**	C300: inrush 1800, maintained 180	B300
	Breaking capacity in DC-13		24 V/2 A L/R = 50 ms	24 V/1.5 A L/R = 50 ms
	Max. thermal current (Ithe)	**A**	6	8/5 (N.O. / N.C.)
	Max. total thermal current	**A**	10.5	12
	Output fuse protection, using fuses conforming to IEC/EN 947-5-1, DIN VDE 0660 part 200	**A**	4 gG (gI) or 6 fast acting	6gG
	Minimum current	**mA**	10	10
	Minimum voltage	**V**	17	17
Electrical life			See page 3/12	
Response time on input opening		**ms**	< 100	< 80
Rated insulation voltage (Ui)		**V**	300 (degree of pollution 2 conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)	
Rated impulse withstand voltage (Uimp)		**kV**	3 (overvoltage category III, conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)	4 (overvoltage category III, conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)
LED display			2	2
Operating temperature		**°F (°C)**	+ 14 to + 131 (- 10 to + 55)	- 13 to +131 (- 25 to + 55)
Storage temperature		**°F (°C)**	- 13 to +185 (- 25 to + 85)	- 13 to +167 (- 25 to + 75)
Degree of protection conforming to IEC/EN 60529	Terminals		IP 20	IP 20
	Enclosure		IP 40	IP 40

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Principle: page 3/14 | Specifications: page 3/14 | References: page 3/15 | Wiring diagrams: page 3/16 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSAC, XPSAXE

For Emergency stop and switch monitoring

Specifications (continued)

Module type				XPSAC	XPSAC●●●●P	XPSAXE●●●●P	XPSAXE●●●●C
Connection	Type	Terminals		Captive screw clamp terminals	Captive screw clamp terminals	Captive screw clamp terminals	Spring terminals
		Terminal block		Integrated in module	Removable from module	Removable from module	Removable from module
	1-wire connection	Without cable end		Solid or flexible cable: 26-14 AWG (0.14 to 2.5 mm²)	Solid or flexible cable: 24-14 AWG (0.2 to 2.5 mm²)		
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm²)			
				With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm²)	With bezel, flexible cable: 0.25 to 2.5 mm²	With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm²)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm²)
	2-wire connection	Without cable end		Solid or flexible cable: 26-20 AWG (0.14 to 0.75 mm²)	Solid cable: 24-18 AWG (0.2 to 1 mm²), flexible cable: 24-16 AWG (0.2 to 1.5 mm²)	Solid or flexible cable: 24-18 AWG (0.2 to 1 mm²)	–
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25 – 1.0 mm²)			–
				Double, with bezel, flexible cable: 20-16 AWG (0.5 to 1.5 mm²)			Double, with bezel, flexible cable: 0-18 AWG (0.5 to 1 mm²)

References

XPSAC●●●●

XPSAC●●●●P

XPSAXE5120P

XPSAXE5120C

Description	Connection	Number of instantaneous opening safety circuits	Additional outputs	Supply	Reference	Weight oz (kg)
Safety modules for Emergency stop and switch monitoring	Captive screw clamp terminals Terminal block integrated in module	3	1 solid-state	∼ and ⎓, 24 V	**XPSAC5121**	5.643 (0.160)
				48 V ∼	**XPSAC1321**	7.408 (0.210)
				115 V ∼	**XPSAC3421**	7.408 (0.210)
				230 V ∼	**XPSAC3721**	7.408 (0.210)
	Captive screw clamp terminals Terminal block removable from module	3	1 solid-state	∼ and ⎓, 24 V	**XPSAC5121P**	5.643 (0.160)
				48 V ∼	**XPSAC1321P**	7.408 (0.210)
				115 V ∼	**XPSAC3421P**	7.408 (0.210)
				230 V ∼	**XPSAC3721P**	7.408 (0.210)
			1 relay	∼ and ⎓, 24 V	**XPSAXE5120P**	8.078 (0.229)
	Spring terminals Terminal block removable from module	3	1 relay	∼ and ⎓, 24 V	**XPSAXE5120C**	8.078 (0.229)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAC

For Emergency stop and switch monitoring

XPSAC

Module XPSAC associated with an Emergency stop button with 1 N.C. contact



S1: Emergency stop
S2: Start button
Y1-Y2: Feedback loop.
ESC: External start conditions.

Module XPSAC associated with an Emergency stop button with 2 N.C. contacts (recommended application)



S1: Emergency stop
S2: Start button
Y1-Y2: Feedback loop.
ESC: External start conditions.

Functional diagram of module XPSAC



LED details



1 Supply voltage A1-A2.
2 K1-K2 status (N.O. safety outputs closed).

Principle: page 3/14 | Specifications: page 3/14 | References: page 3/15 | Wiring diagrams: page 3/16 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSAXE

Module XPSAXE associated with an Emergency stop button with 1 N.C. contact



S1: Emergency stop
S2: Start
Y1-Y2: Feedback loop
ESC: External start conditions
(1) Automatic reset
(2) Maximum fuse rating: see page 3/14.

Module XPSAXE associated with an Emergency stop button with 2 N.C. contacts (recommended application)



S1: Emergency stop
S2: Start
Y1-Y2: Feedback loop
ESC: External start conditions
(1) Automatic reset
(2) Maximum fuse rating: see page 3/14.

Functional diagram of module XPSAXE



(1) Only for Emergency stop button with 2 N.C. contacts.

LED details



1 Supply voltage A1-A2.
2 K1-K2 status (N.O. safety outputs closed).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSAV, XPSABV, XPSATE

For Emergency stop and switch monitoring

Operating principle

Safety relay modules XPSAV, XPSABV and XPSATE are used for monitoring Emergency stop circuits conforming to standards EN/ISO 13850 and EN/IEC 60204-1 and also meet the requirements for the electrical monitoring of switches in protection devices conforming to standard EN 1088 / ISO 14119.
They provide protection for both the machine operator and the machine by immediately stopping the dangerous movement on receipt of a stop instruction from the operator, or on detection of an anomaly in the safety circuit itself.

In addition to the stop category 0 instantaneous opening safety outputs (3 for XPSAV, 2 for XPSABV and 2 for XPSATE), the modules incorporate stop category 1 time delay outputs (3 for XPSAV, 1 for XPSABV and 3 for XPSATE) which allow for controlled deceleration of the motor components until a complete stop is achieved (for example, motor braking by variable speed drive).

At the end of the preset delay, the supply is disconnected by opening the time delay output circuits.
For module XPSAV, the time delay of the 3 output circuits is adjustable, in 15 preset values, between 0 and 300 seconds using selector buttons.
For module XPSABV, the time delay of the output circuit is adjustable between 0.15 and 3 seconds or 1.5 and 30 seconds, depending on the model, using a selector switch.
For module XPSATE, the time delay of the 3 output circuits is adjustable between 0 and 30 seconds using a 12-position selector switch.
Module XPSAV also incorporates 3 solid-state signaling outputs for signaling to the process PLC.
Module XPSATE incorporates 4 solid-state signaling outputs for signaling to the process PLC.
To aid diagnostics, the modules have LEDs which provide information on the monitoring circuit status.

The Start button monitoring function is configurable depending on the wiring.

Specifications

Module type			**XPSAV11113, XPSAV11113P**	**XPSABV●●●●C, XPSABV●●●●P**	**XPSATE●●●●, XPSATE●●●●P**
Maximum achievable safety level			PL e/Category 4 conforming to EN/ISO 13849-1 SILCL 3 (instantaneous safety outputs and time delay safety outputs) conforming to EN/IEC 62061	PL e/Category 4 (instantaneous safety outputs) and PL d/Category 3 (time delay safety outputs) conforming to EN/ISO 13849-1, SILCL 3 (instantaneous safety outputs) and SILCL 2 (time delay safety outputs) conforming to EN/IEC 62061	PL e/Category 4 (instantaneous safety outputs) and PL d/Category 3 (time delay safety outputs) conforming to EN/ISO 13849-1, SILCL 3 (instantaneous safety outputs) and SILCL 2 (time delay safety outputs) conforming to EN/IEC 62061
Reliability data (1) (instantaneous safety outputs)	Mean Time To dangerous Failure ($MTTF_d$)	**Years**	75.8	53	134.8
	Diagnostic coverage (DC)	**%**	> 99	> 99	> 99
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	7.95×10^{-9}	3×10^{-8}	6.81×10^{-9}
Reliability data (1) (time delay safety outputs)	Mean Time To dangerous Failure ($MTTF_d$)	**Years**	75.8	53	54.5
	Diagnostic coverage (DC)	**%**	> 99	> 60 and < 90	98.4
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	7.95×10^{-9}	2×10^{-7}	1.96×10^{-8}
Conformity to standards			EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1, EN/ISO 13850, EN 1088/ISO 14119,	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1, EN/ISO 13850, EN 1088/ISO 14119	EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1, EN/ISO 13850, EN 1088/ISO 14119
Product certifications			UL, CSA, TÜV	UL, CSA, BG	UL, CSA, TÜV
Supply	Voltage	**V**	24 ⎓	24 ⎓	∿ and 24 ⎓, 115 ∿, 230 ∿
	Voltage limits		- 20 to + 20%	- 15 to + 10%	- 20 to + 10% (24 V) - 15 to + 15% (115 V) - 15 to + 10% (230 V)
	Frequency	**Hz**	–	–	50/60
Power consumption		**W**	< 5	< 3	< 8
Module inputs fuse protection			Internal, electronic		
Adjustable time delay		**s**	0 to 300	0.15 to 3 or 1.5 to 30	0 to 30
Start button monitoring			Yes/No (configurable by terminal wiring diagrams)		
Control unit voltage (at nominal supply voltage)			Between input terminals S21-S22, S31-S32 or S11-S12	Between input terminals S11-S12, S21-S22 or S11-S31	Between input terminals S11-S12, S21-S22 or S11-B1
	24 V version	**V**	24	24	24
	115 V, 230 V version	**V**	–		48

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Principle: page 3/18 | Specifications: page 3/18 | References: page 3/20 | Wiring diagrams: page 3/21 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSAV, XPSABV, XPSATE

For Emergency stop and switch monitoring

Specifications (continued)

Module type			XPS...	AV11113	AV11113P	ABV●●●●P	ABV●●●●C	ATE●●●●	ATE●●●●P
Calculation of wiring resistance RL between input terminals			Ω	100 max. Maximum cable length: 2000 m		RL = $\frac{Ue}{Un}$ x 160-127 Ue = true voltage applied to terminals A1-A2 Un = nominal supply voltage		RL max. = $\frac{U\ int - U\ min.}{I\ min.}$ Ue = true voltage applied to terminals A1-A2 U int (terminals S11-S21) = supply voltage Ue - 3 V (24 V version) U int between 42 V and 45 V, with typical value = 45 V (115 V, 230 V version) Calculated max. RL must be equal to or greater than the true value	
Synchronization time between inputs			**s**	For guard: 1.5 For Emergency stop: unlimited		< 0.5		Approx. 0.075 For automatic start, terminals S33-Y2 and Y3-Y4 linked	
Outputs	Voltage reference			Relay hard contacts					
	No. and type of instantaneous opening safety circuits			3 N.O. (03-04, 13-14, 23-24)		2 N.O. (13-14, 23-24)		2 N.O. (13-14, 23-24, 33-34)	
	No. and type of time delay opening safety circuits			3 N.O. (37-38, 47-48, 57-58)		1 N.O. (37-38)		3 N.O. (57-58, 67-68, 77-78)	
	Number and type of additional circuits			3 solid-state		–		4 solid-state	
	Breaking capacity in AC-15	Instantaneous outputs	**VA**	C300: inrush 1800, maintained 180		B300: inrush 3600, maintained 360		C300: inrush 1800, maintained 180	
		Time delay outputs	**VA**	C300: inrush 1800, maintained 180		B300: inrush 3600, maintained 360		C300: inrush 1800, maintained 180	
	Breaking capacity in DC-13	Instantaneous outputs		24 V/1.25 A L/R = 50 ms		24 V/1.5 A L/R = 50 ms		24 V/1.0 A L/R = 50 ms	
		Time delay outputs		24 V/1.25 A L/R = 50 ms		24 V/1.5 A L/R = 50 ms		24 V/1.0 A L/R = 50 ms	
	Breaking capacity of solid-state outputs			24 V/20 mA		–		–	
	Max. thermal current (Ithe)	Instantaneous outputs	**A**	3.3 for all 3, or 6 for 1 and 2 for 2, or 4 for 2 and 2 for 1		6		5	
		Time delay outputs	**A**	3.3 for all 3, or 6 for 1 and 2 for 2, or 4 for 2 and 2 for 1		6		2.5	
	Max. total thermal current		**A**	20		12		8	
	Output fuse protection, using fuses conforming to IEC/EN 60947-5-1, DIN VDE 0660 part 200	Instantaneous outputs	**A**	4 gG or 6 fast acting		6 gG		6 gG	
		Time delay outputs	**A**	4 gG or 6 fast acting		6 gG		4 gG	
	Minimum current		**mA**	10 *(1)*		10		10 *(1)*	
	Minimum voltage		**V**	17 *(1)*		17		17 *(1)*	
Electrical life				See page 3/12					
Response time on instantaneous opening inputs			**ms**	< 30		< 200		< 20	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)					
Rated impulse withstand voltage (Uimp)			**kV**	4 (overvoltage category III, conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)					
LED display				11		3		4	
Operating temperature			**°F (°C)**	+ 14 to + 131 (- 10 to + 55)		- 13 to +131 (- 25 to + 55)		+ 14 to + 131 (- 10 to + 55)	
Storage temperature			**°F (°C)**	- 13 to +185 (- 25 to + 85)		- 13 to +167 (- 25 to + 75)		- 13 to +185 (- 25 to + 85)	
Degree of protection conforming to IEC/EN 60529		Terminals		IP 20					
		Enclosure		IP 40					
Wiring diagrams		Type of terminals		Captive screw clamp terminals			Spring terminals	Captive screw clamp terminals	
		Type of terminal block		Integrated in module	Removable from module				
	1-wire connection	Without cable end		Solid or flexible cable: 26-14 AWG (0.14 to 2.5 mm²)	Solid or flexible cable: 24-14 AWG (0.2 to 2.5 mm²)			Solid or flexible cable: 26-14 AWG (0.14 to 2.5 mm²)	Solid or flexible cable: 24-14 AWG (0.25 to 2.5 mm²)
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm²)					
				With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm²)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm²)	With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm²)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm²)	With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm²)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm²)
	2-wire connection	Without cable end		Solid or flexible cable: 26-20 AWG (0.14 to 0.75 mm²)	Solid cable: 24-18 AWG (0.2 to 1 mm²) Flexible cable: 24-16 AWG (0.2 to 1.5 mm²)	Solid or flexible cable: 24-18 AWG (0.2 to 1 mm²)	–	Solid or flexible cable: 26-20 AWG (0.14 to 0.75 mm²)	Solid cable: 24-18 AWG (0.2 to 1 mm²) Flexible cable: 24-16 AWG (0.2 to 1.5 mm²)
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25 to 1 mm²)			–	Without bezel, flexible cable: 24-18 AWG (0.25 to 1 mm²)	
				Double, with bezel, flexible cable: 20-16 AWG (0.5 to 1.5 mm²)		Double, with bezel, flexible cable: 20-18 AWG (0.5 to 1 mm²)		Double, with bezel, flexible cable: 20-16 AWG (0.5 to 1.5 mm²)	

(1) The module is also capable of switching low power loads (17 V/10 mA) provided that the contact has not been used for switching high power loads (possible contamination or wear of the gold layer on the contact tips).

Principle: page 3/18 | Specifications: page 3/18 | References: page 3/20 | Wiring diagrams: page 3/21 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSAV, XPSABV, XPSATE

For Emergency stop and switch monitoring

XPSAV11113

XPSAV11113P

XPSABV●●●●P

XPSABV●●●●C

XPSATE5110

References

Description	Number of safety circuits	Additional outputs	Setting range of time delay	Supply	Connection	Reference	Weight oz (kg)
Safety modules for Emergency stop and switch monitoring	6 N.O. (3 N.O. time delay)	3 solid-state	0 to 300 s	24 V ⎓	Captive screw clamp terminals Terminal block integrated in module	**XPSAV11113**	11.288 (0.320)
	6 N.O. (3 N.O. time delay)	3 solid-state	0 to 300 s	24 V ⎓	Captive screw clamp terminals Terminal block removable from module	**XPSAV11113P**	11.288 (0.320)
	3 N.O. (1 N.O. time delay)	–	0.15 to 3 s	24 V ⎓	Captive screw clamp terminals Terminal block removable from module	**XPSABV1133P**	9.877 (0.280)
				24 V ⎓	Spring terminals Terminal block removable from module	**XPSABV1133C**	9.700 (0.275)
			1.5 to 30 s	24 V ⎓	Captive screw clamp terminals Terminal block removable from module	**XPSABV11330P**	9.877 (0.280)
				24 V ⎓	Spring terminals Terminal block removable from module	**XPSABV11330C**	9.700 (0.275)
	5 N.O. (3 N.O. time delay)	4 solid-state	0 to 30 s	∿/24 V ⎓	Captive screw clamp terminals Terminal block integrated in module	**XPSATE5110**	9.877 (0.280)
					Captive screw clamp terminals Terminal block removable from module	**XPSATE5110P**	9.877 (0.280)
				115 V ∿	Captive screw clamp terminals Terminal block integrated in module	**XPSATE3410**	13.404 (0.380)
					Captive screw clamp terminals Terminal block removable from module	**XPSATE3410P**	13.404 (0.380)
				230 V ∿	Captive screw clamp terminals Terminal block integrated in module	**XPSATE3710**	13.404 (0.380)
					Captive screw clamp terminals Terminal block removable from module	**XPSATE3710P**	13.404 (0.380)

Principle: page 3/18 | Specifications: page 3/18 | References: page 3/20 | Wiring diagrams: page 3/21 | Dimensions: page 3/112

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays
Preventa™ safety relay modules type XPSAV
For Emergency stop and switch monitoring

XPSAV

Module XPSAV associated with an Emergency stop button with 1 N.C. contact, automatic start or unmonitored start



(1) Link for automatic start.
(2) Instantaneous opening safety outputs (stop category 0).
(3) Time delay opening safety outputs (stop category 1).
ESC = External start conditions.

Functional diagrams

Automatic start



Unmonitored start



Automatic start
There is no start contact or it is jumpered (wiring between terminals S13 - S14).
Note: Automatic start function is not available on the XPSAV with 2 channel wiring on the inputs. Automatic start function is only available on single channel wiring on the inputs.

Unmonitored start
The output is activated on closing of the start contact.

Monitored start
The start input is monitored so that there is no start-up in the event of the start contact being jumpered or the start circuit being closed for more than 10 seconds. Start-up is triggered following activation of the start button (push-release function) on opening of the contact (wiring between terminals S33-S34).

Principle: page 3/18 | Specifications: page 3/18 | References: page 3/20 | Wiring diagrams: page 3/21 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

XPSAV

Module XPSAV associated with an Emergency stop button with 2 N.C. contacts, monitored start*



(1) Instantaneous opening safety outputs (stop category 0).
(2) Time delay opening safety outputs (stop category 1).
ESC = External start conditions.

**Automatic start function is not available on the XPSAV with 2 channel wiring on the inputs. Automatic start function is only available on single channel wiring on the inputs.*

Functional diagram

Monitored start



Emergency stop monitoring function configuration

1-channel wiring



2-channel wiring, with short-circuit detection



Principle: page 3/18 | Specifications: page 3/18 | References: page 3/20 | Wiring diagrams: page 3/21 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAV

For Emergency stop and switch monitoring

XPSAV

Monitoring of a movable guard associated with 2 switches
Automatic start (diagram shown for guard closed)



(1) Instantaneous opening safety outputs (stop category 0).
(2) Time delay opening safety outputs (stop category 1).
ESC = External start conditions.

Functional diagram



LED details



1 S12 input status.
2 S22 input status.
3 S32 input status.
4 S34 input status.
5 S14 input status.
6 Y40 input status (time delay stop).
7 K1/K2 status (N.O. instantaneous opening safety outputs).
8 K3/K4 status (time delay opening safety outputs).
9 Supply voltage A1-A2.
10 Fault.
11 Configuration mode.

Principle: page 3/18 | Specifications: page 3/18 | References: page 3/20 | Wiring diagrams: page 3/21 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

XPSABV

Module XPSAV associated with an Emergency stop button with 2 N.C. contacts, monitored start



S1: Emergency stop
S2: Start button
ESC = External start conditions.
(1) With start button monitoring.
(2) Without start button monitoring or automatic start.
(3) Maximum fuse rating: see page 3/18.

Emergency stop or switch monitoring function configurations

1



1-channel Emergency stop, manual start	Start with S34 button monitoring	Jumper

2



Short-circuit monitoring 2-channel Emergency stop, manual start	Start with S34 button monitoring	Jumper

3



Short-circuit monitoring 2-channel Emergency stop, manual start	Start with S34 button monitoring	Jumper

4



Machine guard with short-circuit monitoring, automatic start	Jumper or feedback loop for external contactors (automatic start S35)	Jumper

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSABV

Functional diagrams

Emergency stop monitoring: configurations 1, 2 and 3



tW: Recovery time
tE: On-delay
tm: Min. ON time
tA: Response time
tV: Off-delay (adjustable)
tS: Synchronization time

Switch monitoring: configuration 4



tW: Recovery time
tE: On-delay
tm: Min. ON time
tA: Response time
tV: Off-delay (adjustable)
tS: Synchronization time

LED details



1 Supply voltage A1-A2
2 K1/K2 status
3 K3/K4 status

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

XPSATE

Module XPSATE associated with an Emergency stop button*



S1: Emergency stop button with 2 N.C. contacts (recommended application).
S2: Start button.
ESC: External start conditions.
Y1 (S33) - Y2: Feedback loop.
F1: 4 A max.
(1) With start button monitoring.
(2) Without start button monitoring.
(3) The outputs must be fuse protected. Technical specifications for maximum rating of fuses, see page 3/18.
(4) ∼ 115/230 V only.

**For automatic start, jumper S2 (N.O. start button between terminals S33-Y1). This is only feasible when configured without start button monitoring (Y3 and Y4 jumpered). If S2 is jumpered and the module is configured for start button monitoring (Y3 and Y5 jumpered), the N.O. safety contacts will not close.*

Functional diagram of module XPSATE with Emergency stop button monitoring



1 With start button monitoring (Y3-Y5 connection).
2 Without start button monitoring (Y3-Y4 connection).
3 Without start button (connection Y3-Y4 and S33-Y1). Tv: adjustable time.

LED details



1 1Supply voltage A1-A2, internal electronic fuse status.
2 S12 (A) input status.
3 S22 (B) input status.
4 Stop category 1 outputs closed.

Principle: page 3/18 | Specifications: page 3/18 | References: page 3/20 | Wiring diagrams: page 3/21 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSATE

Example of a circuit combining an Emergency stop module with a variable speed drive



S1: Emergency stop button with 2 N.C. contacts (recommended application).
S2: Start button
(1) With start button monitoring.
(2) Technical specifications for establishing maximum rating of fuses, see page 3/18.

Connection with 1 Emergency stop button



Both input channels are supplied at the same potential.
S1: Emergency stop button with 2 N.C. contacts
A short-circuit between the 2 inputs is not detected.

Connection with multiple Emergency stop buttons



The 2 input channels are supplied at different potentials.
A short-circuit between the 2 inputs is detected.

Configuration with start button monitoring
(functional diagram for Start button 1, see page 3/21)



(1) Auxiliary terminal (to be used to separate the feedback loop from the wiring to the start button).

Configuration without start button monitoring
(functional diagram for Start button 2, see page 3/21)



(1) Auxiliary terminal (to be used to separate the feedback loop from the wiring to the start button).

Monitoring an Emergency stop button with 1 N.C. contact



S1: Emergency stop button with 1 N.C. contact.
Not all faults are detected: a short-circuit on the Emergency stop pushbutton is not detected.

Principle: page 3/18 | Specifications: page 3/18 | References: page 3/20 | Wiring diagrams: page 3/21 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSATR

For Emergency stop and switch monitoring

Specifications

Module type				XPSATR●●●●P	XPSATR●●●●C
Maximum achievable safety level				PL e/Category 4 (instantaneous safety outputs and time delay safety outputs) conforming to EN/ISO 13849-1, SILCL 3 (instantaneous safety outputs and time delay safety outputs) conforming to EN/IEC 62061	
Reliability data (1) (instantaneous safety outputs and time delay safety outputs)	Mean Time To dangerous Failure ($MTTF_d$)		**Years**	85	
	Diagnostic coverage (DC)		**%**	> 99	
	Probability of dangerous Failure per Hour (PFH_d)		**1/h**	2×10^{-9}	
Conformity to standards				EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1, EN/ISO 13850, EN 1088/ISO 14119	
Product certifications				UL, CSA, BG	
Supply	Voltage		**V**	24 V ⎓, 115–230 V ∿	
	Voltage limits			- 15 to + 10% (24 V ⎓) - 15 to + 10% (115–230 V ∿)	
	Frequency		**Hz**	50/60	
Power consumption			**W/VA**	24 V ⎓: 2.8 W 115–230 V ∿: 3.2 W/6.3 VA	
Module inputs fuse protection				Internal, electronic	
Adjustable time delay			**s**	0.1 to 3 or 0.1 to 30	
Outputs	Voltage reference			Relay hard contacts	
	No. and type of instantaneous opening safety circuits			3 N.O. (13-14, 23-24, 33-34)	
	No. and type of time delay opening safety circuits			3 N.O. (57-58, 67-68, 77-78)	
	Number and type of additional circuits			1 N.C. (41-42)	
	Breaking capacity in AC-15	Instantaneous outputs	**VA**	C300: inrush 1800, maintained 180	
		Time delay outputs	**VA**	C300: inrush 1800, maintained 180	
	Breaking capacity in DC-13	Instantaneous outputs		24 V/1.5 A L/R = 50 ms	
		Time delay outputs		24 V/1.5 A L/R = 50 ms	
	Max. total thermal current		**A**	8	
	Output fuse protection		**A**	6 gG, conforming to IEC/EN 60947-5-1, DIN VDE 0660 part 200	
	Minimum current		**mA**	5	
	Minimum voltage		**V**	17	
Electrical life				See page 3/12	
Response time on instantaneous opening inputs			**ms**	< 200	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)	
Rated impulse withstand voltage (Uimp)			**kV**	4 (overvoltage category III, conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)	
LED display				5	
Operating temperature			**°F (°C)**	- 13 to +131 (- 25 to + 55)	
Storage temperature			**°F (°C)**	- 13 to +167 (- 25 to + 75)	
Degree of protection conforming to IEC/EN 60529		Terminals		IP20	
		Enclosure		IP40	
Wiring diagrams		Type of terminals		Captive screw clamp terminals	Spring terminals
		Type of terminal block		Removable from module	
	1-wire connection	Without cable end		Solid or flexible cable: 24-12 AWG (0.2 to 2.5 mm^2)	
		With cable end		Solid or flexible cable: 24-12 AWG (0.2 to 2.5 mm^2)	
				With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm^2)
	2-wire connection	Without cable end		Solid cable: 24-18 AWG (0.2 to 1.0 mm^2) Flexible cable: 24-16 AWG (0.2 to 1.5 mm^2)	–
		With cable end		Without bezel, flexible cable: 22-18 AWG (0.25 to 1.0 mm^2)	–
				With bezel, flexible cable: 20-16 AWG (0.5 to 1.5 mm^2)	With bezel, flexible cable: 20-18 AWG (0.5 to 1.0 mm^2)

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSATR

For Emergency stop and switch monitoring

Operating principle

Safety relay modules XPSATR meet the requirements of Performance Level PL e/ Category 4 conforming to standard EN ISO 13849-1.

Safety relay modules XPSATR are electronic, redundant and self-monitoring devices with positively driven relays.

They are used for monitoring Emergency stop circuits (single or two-channel) and protective guarding applications.
The modules conform to standards EN/ISO 13850 and EN 60204-1.

They provide protection for both the machine operator and the machine by immediately stopping the hazardous movement on receipt of a stop instruction from the operator or guarding switches, or on detection of an anomaly in the safety circuit itself. XPSATR incorporates 3 N.O. and 1 N.C. instantaneous contacts and 3 time-delayed N.O. contacts.

To aid diagnostics, the modules have 5 LEDs on the front face which provide information on the monitoring circuit status.

References

XPSATR●●●●P

XPSATR●●●●C

Description	Connection	Number of safety circuits	Additional outputs	Time setting range	Supply	Reference	Weight oz (kg)
Safety relay modules for emergency stop and safety guards monitoring	Captive screw clamp terminals Terminal block removable from module	3 N.O. + 3 N.O. time delay	1 N.C.	0.1…3 s	⎓ 24 V	**XPSATR1153P**	11.640 (0.330)
				0.1…3 s	~ 115…230 V	**XPSATR3953P**	12.346 (0.350)
				0…30 s	⎓ 24 V	**XPSATR11530P**	11.640 (0.330)
				0…30 s	~ 115…230 V	**XPSATR39530P**	12.346 (0.350)
	Cage clamp terminals Terminal block removable from module	3 N.O. + 3 N.O. time delay	1 N.C.	0.1…3 s	⎓ 24 V	**XPSATR1153C**	11.640 (0.330)
				0.1…3 s	~ 115…230 V	**XPSATR3953C**	12.346 (0.350)
				0…30 s	⎓ 24 V	**XPSATR11530C**	11.640 (0.330)
				0…30 s	~ 115…230 V	**XPSATR39530C**	12.346 (0.350)

Principle: page 3/29 | Specifications: page 3/28 | References: page 3/29 | Wiring diagrams: page 3/30 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSATR

For Emergency stop and switch monitoring

XPSATR

Module XPSATR associated with an Emergency stop button with 2 N.C. contacts, monitored start



S1=
EMERGENCY STOP - push button with two NC contacts

S2 =
Reset button

(1) =
Feedback circuit

(2) =
⏚ only on 115-230 V ∼

(3) =
See Technical Data for maximum fuse sizes.

Emergency stop monitoring function configuration

1-channel wiring
Emergency stop button with single N.C. contact



2-channel wiring
Emergency stop button with 2 N.C. contacts, without short circuit protection



2-channel wiring
Emergency stop button with 2 N.C. contacts, with short circuit protection



ESPE (light curtain) without short circuit protection



Time clear, end delay time



Start configurations

Automatic start with feedback loop



With start button monitoring and feedback loop



Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSATR

Functional diagrams

Switch monitoring with automatic start



Switch monitoring with monitored start



Switch monitoring withend time delay function



t_B Ready time
t_A Response time
t_M Minimum actuation time
t_R Release time
t_{RV} Release delay time
t_W Recovery time
t_D Discrepancy time

Legend:
On Off

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAF

For Emergency stop and switch monitoring

Operating principle

Safety relay modules XPSAF are used for:

- Monitoring Emergency stop circuits conforming to standards EN/ISO 13850 and EN/IEC 60204-1.
- Electrical monitoring of switches activated by protection devices conforming to standard EN 1088/ISO 14119.

Housed in a compact enclosure, the modules have 3 safety outputs.
Preventa™ safety relay modules XPSAF●●●●P incorporate removable terminal blocks, thus optimizing machine maintenance.
To aid diagnostics, the modules have 3 LEDs on the front cover which provide information on the monitoring circuit status.
The Start button monitoring function is configurable depending on the wiring.

Specifications

Module type				XPSAF5130	XPSAF5130P
Maximum achievable safety level				PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061	
Reliability data (1)	Mean Time To dangerous Failure (MTTFd)		**Years**	243	
	Diagnostic Coverage (DC)		**%**	> 99	
	Probability of dangerous Failure per Hour (PFHd)		**1/h**	4.62×10^{-9}	
Conformity to standards				EN/IEC 60204-1, EN 1088/ISO 14119, EN/IEC 60947-5-1, EN/ISO 13850, EN 50082-2	
Product certifications				UL, CSA, BG	
Supply	Voltage		**V**	∿ and ⎓ 24	
	Voltage limits			- 15…+ 10%	
	Frequency		**Hz**	50/60	
Power consumption			**VA**	≤ 5	
Module inputs fuse protection				Internal, electronic	
Start button monitoring				Yes/No (configurable by terminal connections)	
Control unit voltage and current				⎓ 24 V/30 mA approx. (at nominal supply voltage)	
Maximum wiring resistance RL			Ω	90	
Synchronization time between inputs A and B				Unlimited	
Outputs	Voltage reference			Relay hard contacts	
	Number and type of safety circuits			3 N.O. (13-14, 23-24, 33-34)	
	Breaking capacity in AC-15		**VA**	C300: inrush 1800, maintained 180	
	Breaking capacity in DC-13			24 V/1.5 A - L/R = 50 ms	
	Max. thermal current (Ithe)		**A**	6	
	Max. total thermal current		**A**	18	
	Output fuse protection		**A**	4 gG or 6 fast acting, conforming to EN/IEC 60947-5-1, DIN VDE 0660 part 200	
	Minimum current		**mA**	10	
	Minimum voltage		**V**	17	
Electrical life				See page 3/12	
Response time on input opening			**ms**	≤ 40	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
Rated impulse withstand voltage (Uimp.)			**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
LED display				3	
Operating temperature			**°F (°C)**	+ 14…+ 131 (- 10…+ 55)	
Storage temperature			**°F (°C)**	- 13…+ 267.8 (- 25…+ 85)	
Degree of protection conforming to IEC/EN 60529		Terminals		IP 20	
		Enclosure		IP 40	
Connections		Type		Captive screw clamp terminals	Captive screw clamp terminals, removable terminal block
	1-wire connection	Without cable end		Solid or flexible cable: 26-14 AWG (0.14…2.5 mm^2)	Solid or flexible cable: 24-14 AWG (0.2…2.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)	
		With cable end		With bezel, flexible cable: 24-16 AWG (0.25…1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)
	2-wire connection	Without cable end		Solid or flexible cable: 26-18 AWG (0.14…0.75 mm^2)	Solid cable: 24-18 AWG (0.2…1 mm^2), flexible cable: 24-16 AWG (0.2…1.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25…1 mm^2)	
		With cable end		Double, with bezel, flexible cable: 20-16 AWG (0.5…1.5 mm^2)	Double, with bezel, flexible cable: 20-16 AWG (0.5…1.5 mm^2)

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Principle: page 3/32 | Specifications: page 3/32 | References: page 3/33 | Wiring diagrams: page 3/33 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAF

For Emergency stop and switch monitoring

References

XPSAF5130

XPSAF5130P

Description	Type of terminal block connection	Number of safety circuits	Supply	Reference	Weight oz (kg)
Safety modules for Emergency stop and limit switch monitoring	Integrated in module	3	∿ and ⎓ 24 V	**XPSAF5130**	8.818 (0.250)
	Removable from module	3	∿ and ⎓ 24 V	**XPSAF5130P**	8.818 (0.250)

Wiring diagrams

XPSAF

Module XPSAF associated with an Emergency stop button with 2 N.C. contacts



(1) With start button monitoring.
(2) Without start button monitoring.
ESC = External start conditions.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

XPSAF

Functional diagrams

Emergency stop function



Guard function with automatic start



(1) With start button monitoring.
(2) Without start button monitoring.

Module XPSAF with connection of multiple Emergency stop buttons, combined with a PLC



(1) Other circuits controlled by the XPSAF module.
ESC = External start conditions.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAF

For Emergency stop and switch monitoring

XPSAF

Emergency stop monitoring function configuration

1-channel wiring



Emergency stop button with a single N.C. contact.
Not all anomalies are detected: a short-circuit on the Emergency stop push button is not detected.

2-channel wiring



Emergency stop button with 2 N.C. contacts (recommended application).
The 2 input channels are supplied at different potentials. A short-circuit between the 2 inputs is detected.



Connection of multiple Emergency stop buttons with 2 N.C. contacts (recommended application).
The 2 input channels are supplied at different potentials. A short-circuit between the 2 inputs is detected.

Monitoring of a movable guard associated with 2 switches with 1 contact each in combined mode (switch 1 with N.O. contact, switch 2 with N.C. contact)



Configuration with automatic or manual start



Automatic start.



Without start button monitoring, manual reset.



Function: push-release.
With start button monitoring, manual reset.

LED details



1 Supply voltage A1-A2 internal electronic, fuse status.
2 Relay K1 energized.
3 Relay K2 energized.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAFL

For Emergency stop, switch and light curtain monitoring

Operating principle

Safety relay modules XPSAFL are used for:

- Monitoring Emergency stop circuits conforming to standards EN/ISO 13850 and EN/IEC 60204-1.
- Electrical monitoring of switches activated by protection devices conforming to standard EN 1088/ISO 14119, devices such as safety interlocks or safety limit switches.

They can also be used for monitoring type 4 light curtains conforming to EN/IEC 61496-1 which have solid-state safety outputs with test function (for example, light curtains type XUSL, see Section 5).

Housed in a compact enclosure, the modules have 3 safety outputs.
Preventa™ safety relay modules XPSAFL●●●●P incorporate removable terminal blocks, thus optimizing machine maintenance.
To aid diagnostics, the modules have 3 LEDs on the front cover which provide information on the monitoring circuit status.
The Start button monitoring function is configurable depending on the wiring.

Specifications

Module type				**XPSAFL5130**	**XPSAFL5130P**
Maximum achievable safety level				PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061	
Reliability data (1)	Mean Time To dangerous Failure (MTTFd)		**Years**	172.1	
	Diagnostic Coverage (DC)		**%**	> 99	
	Probability of dangerous Failure per Hour (PFHd)		**1/h**	5.61 x 10^{-9}	
Conformity to standards				EN/IEC 60204-1, EN 1088/ISO 14119, EN/IEC 60947-5-1, EN/ISO 13850, EN 50082-2, EN/IEC 61496-1 (type 4)	
Product certifications				UL, CSA, BG	
Supply	Voltage		**V**	∿ and ⎓ 24	
	Voltage limits			- 15…+ 10%	
	Frequency		**Hz**	50/60	
Power consumption			**VA**	≤ 5	
Module inputs fuse protection				Internal, electronic	
Start button monitoring				No (configurable by terminal connections)	
Control unit voltage and current				⎓ 24 V/30 mA approx. (at nominal supply voltage)	
Maximum wiring resistance RL			Ω	90	
Synchronization time between inputs A and B				Unlimited	
Outputs	Voltage reference			Relay hard contacts	
	Number and type of safety circuits			3 N.O. (13-14, 23-24, 33-34)	
	Breaking capacity in AC-15		**VA**	C300: inrush 1800, maintained 180	
	Breaking capacity in DC-13			24 V/1.5 A - L/R = 50 ms	
	Max. thermal current (Ithe)		**A**	6	
	Max. total thermal current		**A**	18	
	Output fuse protection		**A**	4 gG or 6 fast acting, conforming to EN/IEC 60947-5-1, DIN VDE 0660 part 200	
	Minimum current		**mA**	10	
	Minimum voltage		**V**	17	
Electrical life				See page 3/12	
Response time on input opening			**ms**	≤ 20	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
Rated impulse withstand voltage (Uimp.)			**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
LED display				3	
Operating temperature			**°F (°C)**	+ 14…+ 131 (- 10…+ 55)	
Storage temperature			**°F (°C)**	- 13…+ 267.8 (- 25…+ 85)	
Degree of protection conforming to IEC/EN 60529		Terminals		IP 20	
		Enclosure		IP 40	
Connection		Type		Captive screw clamp terminals	Captive screw clamp terminals, removable terminal block
	1-wire connection	Without cable end		Solid or flexible cable: 26-14 AWG (0.14…2.5 mm^2)	Solid or flexible cable: 24-14 AWG (0.2…2.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)	
		With cable end		With bezel, flexible cable: 24-16 AWG (0.25…1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)
	2-wire connection	Without cable end		Solid or flexible cable: 26-18 AWG (0.14…0.75 mm^2)	Solid cable: 24-18 AWG (0.2…1 mm^2), flexible cable: 24-16 AWG (0.2…1.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25…1 mm^2)	
		With cable end		Double, with bezel, flexible cable: 20-16 AWG (0.5…1.5 mm^2)	

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Principle: page 3/36 | Specifications: page 3/36 | References: page 3/37 | Wiring diagrams: page 3/38 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAFL

For Emergency stop, switch and light curtain monitoring

References

	Description	Type of terminal block connection	Number of safety circuits	Supply	Reference	Weight oz (kg)
XPSAFL5130	**Safety modules for Emergency stop, switch and light curtain monitoring**	Integrated in module	3	∿ and ⎓ 24 V	**XPSAFL5130**	8.818 (0.250)
XPSAFL5130P		Removable from module	3	∿ and ⎓ 24 V	**XPSAFL5130P**	8.818 (0.250)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAFL

For Emergency stop, switch and light curtain monitoring

XPSAFL

Module XPSAFL associated with an Emergency stop button with 2 N.C. contacts



(1) With start button monitoring.
(2) Without start button monitoring.
ESC: External start conditions.

Functional diagrams

Emergency stop function



(1) With start button monitoring.
(2) Without start button monitoring.

Guard function with automatic start



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSAFL

Emergency stop monitoring function configuration

1-channel wiring
Emergency stop button with a single N.C. contact

A short-circuit on the Emergency stop push button is not detected.

2-channel wiring
Emergency stop button with 2 N.C. contacts



A short-circuit between the 2 inputs is not detected.

2-channel wiring
Connection of multiple Emergency stop buttons



A short-circuit between the 2 inputs is not detected.

Monitoring of a movable guard associated with 2 switches with 1 contact each in combined mode (switch 1 with N.O. contact, switch 2 with N.C. contact)

Without short-circuit detection



Monitoring of electro-sensitive protection equipment (ESPE)



LED details



1 Supply voltage A1-A2, fuse status.
2 Relay K1 energized.
3 Relay K2 energized.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAR

For Emergency stop, switch or light curtain monitoring

Operating principle

Safety relay modules XPSAR are designed for the following safety applications:

- Monitoring Emergency stop circuits conforming to EN/ISO 13850 and EN/IEC 60204-1.
- Electrical monitoring of switches activated by protection devices conforming to standard EN 1088/ISO 14119.
- Monitoring type 4 light curtains conforming to EN/IEC 61496-1 which have solid-state safety outputs with test function, for example, light curtains type XUSL.

In addition to 7 safety outputs, modules XPSAR incorporate 2 relay signalling outputs and 4 solid-state signalling outputs for signalling to the process PLC.

Safety modules XPSAR●●●●●●P incorporate removable terminal blocks, thus optimizing machine maintenance. To aid diagnostics, the modules have 4 LEDs on the front cover which provide information on the monitoring circuit status. The Start button monitoring function is configurable depending on the wiring.

Specifications

Module type				**XPSAR3●1144**	**XPSAR3●1144P**
Maximum achievable safety level				PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061	
Reliability data (1)	Mean Time To dangerous Failure (MTTFd)		**Years**	277.8	
	Diagnostic Coverage (DC)		**%**	> 99	
	Probability of dangerous Failure per Hour (PFHd)		**1/h**	2.22×10^{-9}	
Conformity to standards				EN/IEC 60204-1, EN 1088/ISO 14119, EN/ISO 13850, EN/IEC 60947-1, EN/IEC 60947-5-1	
Product certifications				UL, CSA, BG	
Supply	Voltage		**V**	∿ and ⎓ 24, ∿ 115, ∿ 230	
	Voltage limits	⎓ 24 V	**%**	- 15…+ 10	
		∿ 24 V	**%**	- 15…+ 10	
		∿ 115 V	**%**	- 15…+ 15	
		∿ 230 V	**%**	- 15…+ 10	
	Frequency		**Hz**	50/60	
Power consumption				⎓ 24 V version: < 4 W, ∿24 V version: < 7 VA, 115/230 V version: < 9 VA	
Module inputs fuse protection				Internal, electronic	
Start button monitoring				Yes/No (configurable by terminal connections)	
Control unit voltage and current (between terminals S11-S52 and S21-S22). 24 V, 115 V and 230 V version			**V**	⎓ 24 (20 mA approx.) (at nominal supply voltage)	
Maximum wiring resistance RL (between terminals S11-S52 and S21-S22)			Ω	50	
Synchronization time between inputs A and B Automatic start, terminals S33, S34 linked			**ms**	100	
Safety outputs	Voltage reference			Relay hard contacts	
	Number and type of safety circuits			7 N.O. (13-14/23-24/33-34/43-44/53-54/63-64/73-74)	
	Number and type of additional outputs			4 solid-state (Y31-Y32, Y31-Y64, Y31-Y74, Y31-Y35)	
	Number and type of auxiliary contacts			2 N.C. (81-82/91-92)	
	Breaking capacity in AC-15		**VA**	B300 (inrush: 3600, maintained: 360)	
	Breaking capacity in DC-13			24 V/2 A, L/R = 50 ms	
	Breaking capacity of solid-state outputs			24 V/20mA	
	Max. thermal current (Ithe)		**A**	10	
	Max. total thermal current		**A**	40	
	Output fuse protection		**A**	6 gG or 10 fast acting, conforming to EN/IEC 947-5-1, DIN VDE0660 part 200	
	Minimum current		**mA**	170	
	Minimum voltage		**V**	17	
Electrical life				See page 3/12	
Response time on input opening			**ms**	< 20	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
Rated impulse withstand voltage (Uimp.)			**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
LED display				4	
Operating temperature			**°F (°C)**	+ 14…+ 131 (- 10…+ 55)	
Storage temperature			**°F (°C)**	- 13…+ 267.8 (- 25…+ 85)	
Degree of protection conforming to IEC 529				Terminals: IP 20, enclosure: IP 40	
Connection	Type			Captive screw clamp terminals	Captive screw clamp terminals, removable terminal block
	1-wire connection	Without cable end		Solid or flexible cable: 26-14 AWG (0.14…2.5 mm^2)	Solid or flexible cable: 24-14 AWG (0.2…2.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)	
		With cable end		With bezel, flexible cable: 24-16 AWG (0.25…1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)
	2-wire connection	Without cable end		Solid or flexible cable: 26-18 AWG (0.14…0.75 mm^2)	Solid cable: 24-18 AWG (0.2…1 mm^2), flexible cable: 24-16 AWG (0.2…1.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25…1 mm^2)	
		With cable end		Double, with bezel, flexible cable: 20-16 AWG (0.5…1.5 mm^2)	

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Principle: page 3/40 | Specifications: page 3/40 | References: page 3/41 | Wiring diagrams: page 3/42 | Dimensions: page 3/112

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAR

For Emergency stop, switch or light curtain monitoring

XPSAR3●1144

References

Description	Type of terminal block connection	Number of safety circuits	Additional outputs/ solid-state outputs to PLC	Supply	Reference	Weight
				V		oz (kg)
Safety modules for Emergency stop, switch or light curtain monitoring	Integrated in module	7	2 / 4	∼ 24 ⎓ 24	**XPSAR311144**	10.582 (0.300)
				∼ 115 ⎓ 24	**XPSAR351144**	14.110 (0.400)
				∼ 230 ⎓ 24	**XPSAR371144**	14.110 (0.400)
	Removable from module	7	2 / 4	∼ 24 ⎓ 24	**XPSAR311144P**	10.582 (0.300)
				∼ 115 ⎓ 24	**XPSAR351144P**	14.110 (0.400)
				∼ 230 ⎓ 24	**XPSAR371144P**	14.110 (0.400)

3

Principle: page 3/40 | Specifications: page 3/40 | References: page 3/41 | Wiring diagrams: page 3/42 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAR

For Emergency stop, switch or light curtain monitoring

XPSAR

Emergency stop monitoring function configuration

1-channel wiring
Emergency stop button with a single N.C. contact



Not all faults are detected:
a short-circuit on the Emergency stop push button is not detected

2-channel wiring
Emergency stop button with 2 N.C. contacts, without short-circuit detection



Emergency stop button with 2 N.C. contacts, with short-circuit detection (recommended application)



The 2 input channels are supplied at different potentials.
A short-circuit between the 2 inputs is detected

Connection of multiple Emergency stop buttons with 2 N.C. contacts (recommended application)



Start configurations

Automatic start



With start button monitoring



Without start button monitoring



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSAR

Monitoring of a movable guard associated with 2 switches with 1 contact each in combined mode (switch 1 with N.O. contact, switch 2 with N.C. contact)

Automatic start, without synchronization time monitoring



Manual start by start button



Monitoring of a movable guard associated with 2 switches in combined mode and automatic start
(shown with guard open)



Module XPSAR associated with an Emergency stop button with 2 N.C. contacts



Supply connection according to voltage:
~ across terminals A1/A2, or ⎓ 24 V across terminals B1/B2

ESC: External start conditions
(1) Operating status of internal electronic fuse

Principle: page 3/40 | Specifications: page 3/40 | References: page 3/41 | Wiring diagrams: page 3/42 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

XPSAR

Module XPSAR for monitoring electro-sensitive protection equipment (ESPE)



ESC: External start conditions
(1) Operating status of internal electronic fuse
(2) ESPE indicator light deactivated

Example of safety circuit combining module XPSAR for switch monitoring and a PLC



ESC: External start conditions
(1) Operating status of internal electronic fuse

Principle: page 3/40 | Specifications: page 3/40 | References: page 3/41 | Wiring diagrams: page 3/42 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Functional diagrams of module XPSAR

Limit switch monitoring function with automatic start



Limit switch monitoring function with automatic start and synchronization time monitoring



Emergency stop monitoring or limit switch monitoring function with monitored start



Light curtain monitoring (ESPE) function, curtains with solid-state outputs, and monitored start



LED details



1 Supply voltage A1-A2, internal electronic fuse status
2 Input S22 (A)
3 Input S52 (B)
4 K1/K2 status (N.O. safety outputs closed)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAK

For Emergency stop, switch, sensing mat/edges or light curtain monitoring

Operating principle

Safety relay modules XPSAK are are used for:
- Monitoring Emergency stop circuits conforming to standards EN/ISO 13850 and EN/IEC 60204-1.
- Electrical monitoring of switches activated by protection devices, with optional selection of synchronization time between signals.
- Monitoring 4-wire sensing mats or edges.
- Monitoring type 4 light curtains conforming to EN/IEC 61496-1 which have solid-state safety outputs with test function, for example, light curtains type XUSL.

Housed in a compact enclosure, the modules have 3 safety outputs, a relay signalling output and 4 solid-state signalling outputs for signalling to the process PLC.
Preventa™ safety relay modules XPSAK●●●●P incorporate removable terminal blocks, thus optimizing machine maintenance.
To aid diagnostics, the modules have 4 LEDs on the front cover which provide information on the monitoring circuit status.
The Start button monitoring function is configurable depending on the wiring.

Specifications

Module type				**XPSAK3●1144**	**XPSAK3●1144P**
Maximum achievable safety level				PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061	
Reliability data (1)	Mean Time To dangerous Failure (MTTFd)		**Years**	154.5	
	Diagnostic Coverage (DC)		**%**	> 99	
	Probability of dangerous Failure per Hour (PFHd)		**1/h**	7.39 x 10^{-9}	
Conformity to standards				EN/IEC 60204-1, EN 1088/ISO 14119, EN/IEC 60947-5-1, EN/ISO 13850, EN/IEC 60947-1 + A11	
Product certifications				UL, CSA, BG	
Supply	Voltage		**V**	∿ and ⎓ 24, ∿ 48, ∿ 110 and ⎓ 24, ∿ 120 and ⎓ 24, ∿ 230 and ⎓ 24	
	Voltage limits			- 15…+ 10%	
	Frequency		**Hz**	50/60	
Power consumption	24 V version		**VA**	≤ 5	
	110/120/230 V versions			≤ 6	
Module inputs fuse protection				Internal, electronic	
Start button monitoring				Yes/No (configurable by terminal connections)	
Control unit voltage and current between terminals S21-S22, S31-S32				⎓ 24 V/30 mA approx. (at nominal supply voltage)	
Maximum wiring resistance RL between terminals S21-S22, S31-S32			Ω	28	
Synchronization time between inputs A and B (terminals S21-S22, S31-S32)			**s**	Automatic start: 2 or 4 depending on wiring Manual start (start button between S33 and S34): unlimited	
Outputs	Voltage reference			Relay hard contacts	
	Number and type of safety circuits			3 N.O. (13-14, 23-24, 33-34)	
	Number and type of additional circuits			1 N.C. (41-42) + 4 solid-state	
	Breaking capacity in AC-15		**VA**	C300: inrush 1800, maintained 180	
	Breaking capacity in DC-13			24 V/1.5 A - L/R = 50 ms	
	Breaking capacity of solid-state outputs			24 V/20 mA, 48 V/10 mA	
	Max. thermal current (Ithe)		**A**	6	
	Max. total thermal current		**A**	18	
	Output fuse protection		**A**	4 gG or 6 fast acting, conforming to EN/IEC 60947-5-1, DIN VDE 0660 part 200	
	Minimum current		**mA**	10	
	Minimum voltage		**V**	17	
Electrical life				See page 3/12	
Response time on input opening			**ms**	≤ 40	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
Rated impulse withstand voltage (Uimp)			**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
LED display				4	
Operating temperature			**°F (°C)**	+ 14…+ 131 (- 10…+ 55)	
Storage temperature			**°F (°C)**	- 13…+ 267.8 (- 25…+ 85)	
Degree of protection	Conforming to IEC 60529	Terminals		IP 20	
		Enclosure		IP 40	
Connections		Type		Captive screw clamp terminals	Captive screw clamp terminals, removable terminal block
	1-wire connection	Without cable end		Solid or flexible cable: 26-14 AWG (0.14…2.5 mm^2)	Solid or flexible cable: 24-14 AWG (0.2…2.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)	
		With cable end		With bezel, flexible cable: 24-16 AWG (0.25…1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)
	2-wire connection	Without cable end		Solid or flexible cable: 26-18 AWG (0.14…0.75 mm^2)	Solid cable: 24-18 AWG (0.2…1 mm^2), flexible cable: 24-16 AWG (0.2…1.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25…1 mm^2)	
		With cable end		Double, with bezel, flexible cable: 20-16 AWG (0.5…1.5 mm^2)	

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Principle: page 3/46 | Specifications: page 3/46 | References: page 3/47 | Wiring diagrams: page 3/48 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAK

For Emergency stop, switch, sensing mat/edges or light curtain monitoring

References

XPSAK3●1144

XPSAK3●1144P

Description	Type of terminal block connection	Number of safety circuits	Outputs: Additional / Solid-state for PLC	Supply	Reference	Weight oz (kg)
Safety modules for Emergency stop, switch, sensing mat/edges or light curtain monitoring	Integrated in module	3	1 / 4	∿ 24 V ⎓ 24 V	**XPSAK311144**	10.582 (0.300)
				∿ 120 V ⎓ 24 V	**XPSAK351144**	14.110 (0.400)
				∿ 230 V ⎓ 24 V	**XPSAK371144**	14.110 (0.400)
	Removable from module	3	1 / 4	∿ 24 V ⎓ 24 V	**XPSAK311144P**	10.582 (0.300)
				∿ 120 V ⎓ 24 V	**XPSAK351144P**	14.110 (0.400)
				∿ 230 V ⎓ 24 V	**XPSAK371144P**	14.110 (0.400)

3

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAK

For Emergency stop, switch, sensing mat/edges or light curtain monitoring

XPSAK

Emergency stop monitoring function configuration

1-channel wiring

Emergency stop button with a single N.C. contact



Not all anomalies are detected: a short-circuit on the Emergency stop push button is not detected.

2-channel wiring

Emergency stop button with 2 N.C. contacts, without short-circuit detection



Emergency stop button with 2 N.C. contacts, with short-circuit detection (recommended application)



The 2 input channels are supplied at different potentials. A short-circuit between the 2 inputs is detected.

Connection of multiple Emergency stop buttons with 2 N.C. contacts (recommended application).



The 2 input channels are supplied at different potentials. A short-circuit between the 2 inputs is detected.

Start configurations

Automatic start



With start button monitoring



Proximity sensor monitoring

Proximity sensors with PNP outputs
Without short-circuit detection



Proximity sensors with NPN and PNP outputs
With short-circuit detection



Sensing mat or edges monitoring



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAK

For Emergency stop, switch, sensing mat/edges or light curtain monitoring

XPSAK

Monitoring of a movable guard associated with 2 switches with 1 contact each in combined mode (switch 1 with N.O. contact, switch 2 with N.C. contact)

Automatic start, without synchronization time monitoring



Manual start by Start button



Monitoring of a movable guard associated with 2 switches and automatic start
(shown with guard open)



For synchronization monitoring of the inputs, S13 and S14 must be wired per the diagram to the left (if S13 and S14 are jumpered, the result would be automatic start without synchronization monitoring). The synchronization time is determined by the first limit switch that is activated.
If S1 is actuated before S2, then the synchronization time is two seconds on closing.
If S2 is actuated before S1, then the synchronization time is four seconds on closing.
There is no synchronization on opening the door or guard.

Functional diagram of outputs



Module XPSAK associated with an Emergency stop button with 2 N.C. contacts



Supply connection according to voltage: ∿ across terminals A1/A2, or ⎓ 24 V across terminals B1/B2.

(1) Operating status of internal electronic fuse.
ESC: External start conditions.

Principle: page 3/46 | Specifications: page 3/46 | References: page 3/47 | Wiring diagrams: page 3/48 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

XPSAK

Module XPSAK for monitoring electro-sensitive protection equipment (ESPE)



(1) Operating status of internal electronic fuse.
(2) ESPE indicator light deactivated.
ESC: External start conditions.

Example of safety circuit combining module XPSAK for limit switch monitoring and a PLC



(1) Operating status of internal electronic fuse.
ESC: External start conditions.

Principle: page 3/46 | Specifications: page 3/46 | References: page 3/47 | Wiring diagrams: page 3/48 | Dimensions: page 3/112

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSAK

For Emergency stop, switch, sensing mat/edges or light curtain monitoring

XPSAK

Functional diagrams

Switch monitoring function with automatic start



Switch monitoring function with automatic start and synchronization time monitoring



Emergency stop monitoring or switch monitoring function



Light curtain monitoring (ESPE) function, curtains with solid-state outputs



Sensing mat or edge monitoring function, with monitored start



LED details



1 Supply voltage A1-A2, fuse status.
2 Input S22 (A).
3 Input S32 (B).
4 K1/K2 status (N.O. safety outputs closed).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSBAE, XPSBCE, XPSBF

For electrical monitoring of two-hand control stations

Operating principle

Two-hand control stations are designed to provide protection against hand injury. They require machine operators to keep their hands clear of the hazardous movement zone.

The use of two-hand control is an individual protective measure, which can protect only one operator. Separate two-hand control stations must be provided for each operator in a multiple-worker environment.

Safety relay modules XPSBAE, XPSBCE and XPSBF for two-hand control stations comply with the requirements of European standard EN 574/ISO 13851 for two-hand control systems.

The control stations must be designed and installed such that they cannot be activated involuntarily or easily rendered inoperative. Depending on the application, the requirements of type C standards specific to the machinery involved must be met (additional personal protection methods may have to be considered).

To initiate a hazardous movement, both operators (two-hand control pushbuttons) must be activated within an interval ≤ 0.5 s (synchronous activation). If one of the two pushbuttons is released during a hazardous operation, the control sequence is cancelled. Resumption of the hazardous operation is possible only if both pushbuttons are returned to their initial position and reactivated within the required time interval.

The control sequence does not occur if:

- Both two-hand control push buttons are pressed during a time period greater than 0.5 seconds,
- A short-circuit is present in a push button contact,
- The feedback loop is not closed at start-up.

The safety distance between the control units and the hazardous zone must be sufficient that when only one operator is released, the hazardous zone cannot be reached before the hazardous movement has been completed or stopped.

XPSBAE

This module is designed for use on lighter duty applications where a two-hand control function is desired, but where the Performance Level required (PLr) is PLa, b, or c and the two-hand control requirements meet Type III A (per EN 574/ISO 13851). **This module is not to be used for applications, such as presses, which require a Type III C module or where the application is not PLa, b, or c.** For press applications, for applications in PLd or e, or if application calls for a Type III C module, use XPSBCE or XPSBF module.

XPSBCE and XPSBF

These modules can be used on applications, such as presses, which require a Type III C module. The XPSBCE and XPSBF can be used for a two-hand control application, including presses and similar equipment.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSBAE, XPSBCE

For electrical monitoring of two-hand control stations

Specifications

Module type				XPSBAE●●●●P	XPSBAE●●●●C	XPSBCE●●●●P	XPSBCE●●●●C
Maximum achievable safety level				PL c/Category 1 conforming to EN/ ISO 13849-1, SILCL1 conforming to EN/ IEC 62061		PL e/Category 4 conforming to EN/ ISO 13849-1,SILCL 3 conforming to EN/ IEC 62061	
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)		**Years**	55		37	
	Diagnostic Coverage (DC)		**%**	–		> 99	
	Probability of dangerous Failure per Hour (PFH_d)		**1/h**	2.1×10^{-6}		3×10^{-8}	
Conformity to standards				EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1, EN 574 type III A/ISO 13851		EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1, EN 574 type III C/ISO 13851	
Product certifications				UL, CSA, TÜV		UL, CSA, BG	
Supply	Voltage		**V**	24 ⎓, 115/230 ∿		24 ⎓, 24 ∿, 115 ∿, 230 ∿	
	Voltage limits			- 15 to + 10% (24 V ⎓), - 15 to + 10% (115/230 V ∿)		- 15 to + 10% (24 V ⎓, 24 V ∿), - 15 to + 15% (115 V ∿), - 15 to + 10% (230 V ∿)	
	Frequency		**Hz**	50/60			
Power consumption			**VA**	24 V ⎓ 0.7 W/2 VA 115/230 V ∿ 3 VA		< 4	
Module inputs fuse protection				Internal, electronic			
Inputs				S1: 1 N.C. + N.O., S2: 1 N.C. + N.O.			
Two-hand control type Conforming to EN 574				III A		III C	
Synchronization time			**s**	0.5 maximum			
Control unit voltage	24 V ⎓ version		**V**	24		24	
	24 V ∿, 115 V, 230 V version		**V**	24		24	
Calculation of wiring resistance RL (for XPSBCE only) between terminals S11-S13, S21-S23			Ω	–		⎓ $RL = \frac{Ue}{Un} \times 160-127$ ∿ $RL = \frac{Ue}{Un} \times 160-135$ Ue = true voltage applied to terminals A1-A2 Un = nominal supply voltage	
Outputs	Voltage reference			Relay hard contacts			
	Number and type of safety circuits			1 N.O. (11-14)		2 N.O. (13-14, 23-24)	
	Number and type of additional circuits			1 N.C. (11-12)		1 N.C. (31-32)	
	Breaking capacity in AC-15		**VA**	C300: inrush 1800, maintained 180		B300: inrush 3600, maintained 360	
	Breaking capacity in DC-13			24 V/1.5 A to L/R = 50 ms			
	Max. thermal current (Ithe)		**A**	5		6	
	Output fuse protection, using fuses conforming to IEC/EN 60947-5-1, VDE 0660 part 200		**A**	4 gG		6 gG	
	Minimum current		**mA**	10			
	Minimum voltage		**V**	17			
Electrical life				See page 3/12			
Response time			**ms**	< 20		< 50	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)			
Rated impulse withstand voltage (Uimp)			**kV**	4 (overvoltage category III, conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)			
LED display				2		3	
Operating temperature			**°F (°C)**	- 13 to + 131 (- 25 to + 55)		- 13 to + 131 (- 25 to + 55)	
Storage temperature			**°F (°C)**	- 13 to + 167 (- 25 to + 75)		- 13 to + 167 (- 25 to + 75)	
Degree of protection conforming to IEC/EN 60529		Terminals		IP 20			
		Enclosure		IP 40			
Wiring diagrams	Type	Terminals		Captive screw clamp terminals	Spring terminals	Captive screw clamp terminals	Spring terminals
		Terminal block		Removable from module		Removable from module	
	1-wire connection	Without cable end		Solid or flexible cable: 26-14 AWG (0.2 to 2.5 mm^2)		Solid or flexible cable: 24-14 AWG (0.2 to 2.5 mm^2)	
		With wire end		Without bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm^2)			
		With cable end		With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm^2)	With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm^2)
	2-wire connection	Without cable end		Solid: 26-18 AWG (0.2 to 1.0 mm^2) Stranded: 26-16 AWG (0.2 to 1.5 mm^2)	–	Solid or flexible cable: 24-18 AWG (0.2 to 1.0 mm^2)	–
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25 to 1.0 mm^2)	–	Without bezel, flexible cable: 24-18 AWG (0.25 to 1.0 mm^2)	–
		With cable end		Double, with bezel, flexible cable: 20-16 AWG (0.5 to 1.5 mm^2)	Double, with bezel, flexible cable: 20-18 AWG (0.5 to 1.0 mm^2)	Double, with bezel, flexible cable: 20-16 AWG (0.5 to 1.5 mm^2)	Double, with bezel, flexible cable: 20-18 AWG (0.5 to 1.0 mm^2)

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Principle: page 3/52 | Specifications: page 3/53 | References: page 3/55 | Wiring diagrams: page 3/56 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSBF

For electrical monitoring of two-hand control stations

Specifications

Module type				XPSBF1132	XPSBF1132P
Maximum achievable safety level				PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061	
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)		**Years**	50.1	
	Diagnostic Coverage (DC)		**%**	> 99	
	Probability of dangerous Failure per Hour (PFH_d)		**1/h**	1.3×10^{-8}	
Conformity to standards				EN 60204-1, EN 60947-1, EN 60947-5-1, EN 574 type III C/ISO 13851	
Product certifications				UL, CSA, TÜV	
Supply		Voltage	**V**	24 ⎓	
		Voltage limits		- 20 to + 20%	
Power consumption			**W**	< 2.5	
Module inputs fuse protection				Internal, electronic	
Inputs				S1: 1 N.C. + N.O., S2: 1 N.C. + N.O.	
Two-hand control type				III C conforming to EN 574	
Synchronization time			**s**	0.5 maximum	
Control unit voltage			**V**	24 V/8 mA	
Outputs	Voltage reference			Relay hard contacts	
	Number and type of safety circuits			2 N.O. (13-14, 23-24)	
	Number and type of additional circuits			2 solid-state (type 24 V to 20 mA)	
	Breaking capacity in AC-15		**VA**	C300: inrush 1800, maintained 180	
	Breaking capacity in DC-13			24 V/1.5 A to L/R = 50 ms	
	Max. thermal current (Ithe)		**A**	4.2	
	Max. total thermal current		**A**	8.4	
	Output fuse protection, using fuses conforming to IEC/EN 60947-5-1, VDE 0660 part 200		**A**	4 gG or 6 fast acting	
	Minimum current		**mA**	10	
	Minimum voltage		**V**	17	
Electrical life				See page 3/12	
Response time			**ms**	< 20	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)	
Rated impulse withstand voltage (Uimp)			**kV**	4 (overvoltage category III, conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)	
LED display				3	
Operating temperature			**°F (°C)**	+ 14 to + 131 (- 10 to + 55)	
Storage temperature			**°F (°C)**	-13 to +185 (- 25 to + 85)	
Degree of protection conforming to IEC/EN 60529		Terminals		IP 20	
		Enclosure		IP 40	
Connection	Type	Terminals		Captive screw clamp terminals	Captive screw clamp terminals
		Terminal block		Integrated in module	Removable from module
	1-wire connection	Without cable end		Solid or flexible cable: 26-14 AWG (0.14 to 2.5 mm^2)	Solid or flexible cable: 24-14 AWG (0.2 to 2.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm^2)	
		With cable end		With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm^2)
	2-wire connection	Without cable end		Solid or flexible cable: 26-20 AWG (0.14 to 0.75 mm^2)	Solid cable: 24-18 AWG (0.2 to 1 mm^2), flexible cable: 24-16 AWG (0.2 to 1.5 mm^2)
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25 to 1 mm^2)	
		With cable end		Double, with bezel, flexible cable: 20-16 AWG (0.5 to 1.5 mm^2)	

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSBAE, XPSBCE, XPSBF

For electrical monitoring of two-hand control stations

XPSBAE●●●●P

XPSBAE●●●●C

XPSBCE●●●●P

XPSBCE●●●●C

XPSBF1132

Selection

Standard EN 574/ ISO 13851 defines the selection of two-hand controls according to the control system category. The following table details the 3 types of two-hand control conforming to EN 574/ISO 13851. For each type, it lists the operating characteristics and minimum requirements.

Requirements of standard EN 574/ISO 13851	Type I	Type II	Type III		
			A	B	C
Use of both hands (simultaneous action)					
Link between input and output signals					
Output signal inhibited					
Prevention of accidental operation					
Tamper-proof					
Output signal reinitialized					
Synchronous action (specified time limit)					
Use of proven components (Category 1 conforming to EN/ISO 13849-1)			XPSBAE		
Redundancy with partial error detection (Category 3 conforming to EN/ISO 13849-1)				XPSBCE XPSBF	
Redundancy + Self-monitoring (Category 4 conforming to EN/ISO 13849-1)					XPSBCE XPSBF
Two-hand control station	XY2SB●●				

Conforming to standard EN/ISO 13849-1

Meets the requirements of standard EN 574/ISO 13851

References

Description	Type conforming to standard EN 574	Connection	Number of safety circuits	Additional outputs	Supply	Reference	Weight oz (kg)
Safety relay modules for electrical monitoring of two-hand control stations	III A	Captive screw clamp terminals Terminal block removable from module	1 N.O.	1 N.C.	∿ and 24 V ⎓	**XPSBAE5120P**	3.527 (0.100)
					∿ 115/230V	**XPSBAE3920P**	3.527 (0.100)
		Spring terminals Terminal block removable from module	1 N.O.	1 N.C.	∿ and 24 V ⎓	**XPSBAE5120C**	3.527 (0.100)
					∿ 115/230V	**XPSBAE3920C**	3.527 (0.100)
	III C	Captive screw clamp terminals Terminal block removable from module	2 N.O.	1 N.C. relay	∿ and 24 V ⎓	**XPSBCE3110P**	9.594 (0.272)
					∿ 115/120 V	**XPSBCE3410P**	11.358 (0.322)
					∿ 230 V	**XPSBCE3710P**	11.358 (0.322)
		Spring terminals Terminal block removable from module	2 N.O.	1 N.C. relay	∿ and 24 V ⎓	**XPSBCE3110C**	9.594 (0.272)
					∿ 115 /120 V	**XPSBCE3410C**	11.358 (0.322)
					∿ 230 V	**XPSBCE3710C**	11.358 (0.322)
		Captive screw clamp terminals Terminal block removable from module	2 N.O.	2 solid-state	⎓ 24 V	**XPSBF1132**	5.291 (0.150)
			2 N.O.	2 solid-state	⎓ 24 V	**XPSBF1132P**	5.291 (0.150)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSBAE

For electrical monitoring of two-hand control stations

XPSBAE

Module XPSBAE associated with a two-hand control station

Type III A conforming to EN 574/ISO 13851



1 See technical data for fuse sizes
2 Signaling output 11-12
3 Safety output 11-14

S1 and S2: pushbuttons. Must not be used for applications (presses) which require a type III C module (XPSBCE or XPSBF).

Functional diagram of module XPSBAE



1 Enable for synchronous operation
2 No re-enable if operation is interrupted
3 No enable as recovery time t_W is too short
4 No enable as synchronous monitoring time t_S is too long

t_R Response time
t_E ON delay
t_W Recovery time
t_S Synchronous monitoring time

LED details (XPSBAE)



1 Supply voltage A1-A2.
2 K1 status (N.O. safety output 11-14 closed).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSBCE

Module XPSBCE associated with a two-hand control station

Type III C conforming to EN 574/ISO 13851

~ and 24 V ⎓



S1, S2: Two-hand control station pushbuttons
ESC: External start conditions
(1) Maximum fuse rating: see page 3/53.

115 ~ and 230 V



S1, S2: Two-hand control station pushbuttons
ESC: External start conditions
(1) Maximum fuse rating: see page 3/53.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

XPSBCE (continued)

Functional diagram of module XPSBCE



ts, Synchronization time: 500 ms max.
tr, Response time: 50 ms.

LED details (XPSBCE)



1 Supply voltage A1-A2.
2 K1 status (N.O. safety outputs closed).
3 K2 status (N.O. safety outputs closed).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSBF

Module XPSBF associated with a two-hand control station



ESC: External start conditions.
Y1-Y2: feedback loop

Functional diagram of module XPSBF



LED details (XPSBF)



1 Supply voltage A1-A2 (fuse status).
2 Fault signalling.
3 K1-K2 status (N.O. safety outputs closed).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSCM and single-beam photoelectric sensors type XU2S

With a test input associated with a built-in “muting” function

Operating principle

XPSCM safety relay modules, when combined with XU2S single-beam photoelectric sensors (periodically tested), form a category 2 light curtain conforming to standards IEC/EN 61496 parts 1 and 2 and EN 60825-1.
The connection of 1–4 pairs of XU2S photoelectric sensors makes it possible to create a protected space up to 47.2 in. (1200 mm) high, conforming to EN 999/ ISO 13855, and 26.2 ft (8 m) long.

The built-in “muting” function allows the automatic passage of parts for machining or loaded pallets, without interrupting the transportation movement within the zone protected by the electro-sensitive protection equipment (ESPE).
When the system is switched on by the start command, and the light protection is not interrupted, the main circuit is closed by the two safety relays of the XPSCM module.

An interruption of the protection field causes the safety outputs to open instantaneously, and the process PLC receives a stop command. The LED on the XPSCM front panel changes from green to red. The Open state is maintained until the module is restarted using the start button.

The “muting” function allows the light protection to be inhibited (muted). This function allows a trolley transporting materials to pass through without triggering the main circuit. The Muting function cannot be activated by energizing the inhibition devices unless the safety outputs have been switched on beforehand.

To trigger the “muting” function, the inhibition devices (muting sensors) must be activated within the 3-second interval. This synchronization time for the two inhibition inputs can be deactivated by connecting two configuration terminals. The muting cycle has a maximum duration of 60 seconds. During this period, materials can be transported through the protection field without deactivating the safety outputs. The 60 second limit value of the muting cycle may be made infinite by connecting two configuration terminals.

During the muting operation process, a light indicating the muting state is controlled by the XPSCM module. The indicator light comes on when a muting signal is generated, and indicates the inhibition of the protection function. An indicator light error (short-circuit, open-circuit) will be recognized, and will deactivate the Muting function.



D1, D2, D3, D4: monitoring photoelectric sensors
MA1, MB1, MA2, MB2: muting photoelectric sensors
m = trolley length
dM = distance between MA1/MB1 and MA2/MB2

Conditions to be observed for the “muting” function

- “Muting” sensors must be of the XU2 M18PP340 thru-beam or XU9 M18PP340 polarized reflex type, or mechanical limit switches with contacts.
- *dM* ≤ *m* to obtain continuous validation of the “muting” function.
- Avoid the intrusion of persons during the muting phase. This phase is indicated by an indicator light connected to the muting indicator output of the XPSCM module.
- A materials transportation trolley (i.e.: AGV) must generate the muting signal before it enters the protection field, and discontinue the muting signal on exiting once it has cleared all the sensors of the protection field.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSCM and single-beam photoelectric sensors type XU2S

With a test input associated with a built-in “muting” function

Specifications of safety modules

Module type			XPSCM1144	XPSCM1144P
Maximum achievable safety level *(1)*			PL c/Category 2 conforming to EN/ISO 13849-1, SILCL 1 conforming to EN/IEC 62061	
Reliability data	Mean Time To dangerous failure ($MTTF_d$)	**Years**	16.6	
	Diagnostic Coverage (DC)	**%**	95.5	
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	3.12×10^{-7}	
Conformity to standards			EN/IEC 61496-1, EN/IEC 61496-2, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1,	
Product certifications			UL, CSA, IFA	
Ambient air temperature		**°F (°C)**	Operation: +14 to +131 (-10 to +55). Storage: –13 to +185 (–25 to +85)	
Degree of protection conforming to IEC 529			Terminals: IP 20, enclosure: IP 40	
Supply voltage		**V**	⎓ 24, voltage limits: ±20%	
Maximum power consumption		**W**	< 15, with thru-beam photoelectric sensors and muting signaling	
Module fuse protection			Internal, electronic	
Rated insulation voltage (Ui)		**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 and 2)	
Rated impulse withstand voltage (Uimp)		**kV**	4 (overvoltage category 3, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 and 2)	
Inputs for sensors	Number of inputs to be monitored		4 (terminals Z1, Z2, Z3, Z4)	
	Input voltage	**V**	⎓ 24	
	Supply voltage of sensors	**V**	⎓ 24 (terminal U+/U-)	
	Supply current of sensors	**mA**	< 200	
Inputs for the Muting function	Number of muting inputs		2 (terminals MA, MB)	
	Input voltage	**V**	⎓ 24 (terminal U+/U-)	
	Maximum current	**mA**	< 200	
	Synchronization time for the activation of the MA/MB muting signal	**s**	3 (±20%) for activation of the MA/MB “muting” signal	
	Muting maximum duration	**s**	60 (–10 to +30%)	
Single-beam thru-beam photoelectric sensors for input monitoring Z1-Z2-Z3-Z4 -sensors authorized for the protection field (max. 4)			XU2S18PP340●●● (infrared)	
-muting sensors			XU2 M18PP340●●● or XU9 M18PP340●●● photoelectric sensors or XC limit switches	
-sensor supply resistivity		Ω	10 max.	
Safety outputs -number and type			2 N.O. (terminals 13-14, 23-24), hard contacts	
-solid-state output breaking capacity			4 N.O. 24 V/20 mA, (Y33-Y34, Y33-Y44, Y33-Y54, Y33-Y64)	
-breaking capacity in AC-15		**VA**	C300: inrush 1800, maintained 180	
-breaking capacity in DC-13			24 V/1.5 A, L/R = 50 ms	
-maximum thermal current (Ithe)		**A**	5.6	
-sum of maximum thermal current		**A**	11	
-minimum current (volt-free contact)		**mA**	10	
-minimum voltage (volt-free contact)		**V**	17	
-short-circuit protection		**A**	4 gG or 6 fast-acting fuse cartridge, conforming to EN/IEC 60947-5-1 and DIN VDE 0660 part 200	
Muting signaling sensors for incandescent lamp			Number 1 (terminal H1), maximum power: 6.5 W/⎓ 24 V, minimum power: 4 W/⎓ 24 V	
Response time on input change of state		**ms**	< 25	
Electrical life			See page 3/12.	
Display			4 LEDs	
Connection	Type		Captive screw clamp terminals	Captive screw clamp terminals, separate, removable terminal block
1-wire connection	Without cable ends		Solid or flexible cable: 26-14 AWG ($0.14 – 2.5\ mm^2$)	Solid or flexible cable: 24-14 AWG ($0.2 – 2.5\ mm^2$)
	With cable ends, without bezel		Flexible cable: 24-14 AWG ($0.25 – 2.5\ mm^2$)	Flexible cable: 24-14 AWG ($0.25 – 2.5\ mm^2$)
	With cable ends, with bezel		Flexible cable: 24-16 AWG ($0.25 – 1.5\ mm^2$)	Flexible cable: 24-14 AWG ($0.25 – 2.5\ mm^2$)
2-wire connection	Without cable ends		Solid or flexible cable: 26-18 AWG ($0.14 – 0.75\ mm^2$)	Solid cable: 24-18 AWG ($0.2 – 1.0\ mm^2$), Flexible cable: 24-16 AWG ($0.2 – 1.5\ mm^2$)
	With cable ends, without bezel		Flexible cable: 24-18 AWG ($0.25 – 1.0\ mm^2$)	Flexible cable: 24-18 AWG ($0.25 – 1.0\ mm^2$)
	With cable ends, double with bezel		Flexible cable: 22-14 AWG ($0.5 – 1.5\ mm^2$)	Flexible cable: 22-14 AWG ($0.5 – 1.5\ mm^2$)

(1) Using an appropriate and correctly connected control system.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSCM and single-beam photoelectric sensors type XU2S

With a test input associated with a built-in “muting” function

Specifications of photoelectric sensors

Conformity to standards			IEC 61496-1 and IEC 61496-2 (Type 2 ESPE)
Maximum safety level *(1)*			PL=c/category 2 conforming to EN/ISO 13849-1
Reliability data	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	PFH_d=4.6E^{-7} conforming to EN/IEC 61508 PFH_d=5.5E^{-7} conforming to EN/IEC 61508, with “muting” function
Ambient air temperature		**°F (°C)**	Operation: –13 to +131 (–25 to +55) (infrared transmission sensors), Storage: –40 to +158 (–40 to +70)
Vibration resistance			7 gn (10–55 Hz), conforming to EN/IEC 60068-2-6
Shock resistance			30 gn, 3 axes: 3 times, conforming to EN/IEC 60068-2-27
Degree of protection			IP 67 conforming to EN/IEC 60529
Connection	Pre-cabled		PVC cable, diameter 0.20 in. (5 mm), 16.4 ft (5 m) long wire: 4 x 22 AWG (0.34 mm²) for thru-beam transmitter
	Connector		M12 male connector, 4-pin (suitable jumper cables and female connectors M12, 4-contact. See the "Machine Cabling" section.)
Materials			Case: nickel-plated brass (infrared transmission sensors). Lenses: PMMA
Nominal sensing distance		**ft (m)**	26.2 (8) (infrared transmission sensors)
Rated supply voltage		**V**	⎓ 12–24 (with protection against reverse polarity)
Voltage limits		**V**	⎓ 10–30 V (including ripple)
Switching capacity (sealed)		**mA**	≤ 100 mA (with overload and short-circuit protection)
Voltage drop, closed state		**V**	≤ 1.5
Current power consumption, no-load		**mA**	≤ 35
Maximum switching frequency		**Hz**	500
Delays		**ms**	Response: ≤ 1; recovery: ≤ 1

(1) Using an appropriate and correctly connected control system.

***XPS**CM1144●*

Safety modules

Description	Type of terminal block connection	Number of safety circuits	Additional outputs	Supply	References	Weight oz (kg)
Safety modules for monitoring single-beam photoelectric sensors, with a test input associated with a built-in “muting” function	Integrated in module	2	4	⎓ 24 V	**XPSCM1144**	12.35 (0.350)
	Separate, can be removed from module	2	4	⎓ 24 V	**XPSCM1144P**	12.35 (0.350)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSCM and single-beam photoelectric sensors type XU2S

With a test input associated with a built-in “muting” function

XU2S18●P340L5

XU2S18●P340WL5

XU2S18KP340L5T

XU2S18KP340WL5T

XU2S18PP340DR

XU2S18PP340WL5R

Single-beam photoelectric sensors with a test input

Description	Transmission type	Line of sight	Connection	References	Weight oz (kg)
PNP thru-beam pair (transmitter + receiver) Light or dark programmable switching	Infrared Sensing distance: 26.2 ft (8 m)	Along case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18PP340L5**	17.11 (0.485)
			M12 connector	**XU2S18PP340D**	5.47 (0.155)
		90° to case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18PP340WL5**	17.11 (0.485)
			M12 connector	**XU2S18PP340WD**	5.47 (0.155)
Thru-beam transmitter alone (for XPSCM1144●)	Infrared	Along case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18KP340L5T**	8.29 (0.235)
			M12 connector	**XU2S18KP340DT**	2.65 (0.075)
		90° to case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18KP340WL5T**	8.29 (0.235)
			M12 connector	**XU2S18KP340WDT**	5.47 (0.155)
PNP thru-beam receiver alone (for XPSCM1144●)	Infrared	Along case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18PP340L5R**	8.82 (0.250)
			M12 connector	**XU2S18PP340DR**	2.82 (0.080)
		90° to case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18PP340WL5R**	8.82 (0.250)
			M12 connector	**XU2S18PP340WDR**	2.82 (0.080)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSCM and single-beam photoelectric sensors type XU2S

With a test input associated with a built-in “muting” function

Functional diagram of XPSCM module



Functional diagram of the XPSCM module with “muting” function



Key to LEDs



1 A1-A2 supply voltage, electronic internal fuse status (Green)
2 Signaling for restarting (Yellow)
3 Safety output closed (Green)
4 Safety output open (Red)

Principle: page 3/60 | Specifications: page 3/61 | References: page 3/62 | Dimensions: page 3/65, 3/112 | Wiring diagrams: page 3/65

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSCM and single-beam photoelectric sensors type XU2S

With a test input associated with a built-in “muting” function

Operation

	Light switching		Dark switching	
	No object in beam	Object in beam	No object in beam	Object in beam
Output state (PNP) indicator, yellow LED (illuminated when sensor output is on)				

Curves

Infrared detection curve



Functional check



Dimensions

XU2S18PP340L5, XU2S18PP340L5L



(1) LED

(2) Potentiometer

XU2S18PP340D



Mounting nut tightening torque: 17.7 lb-ft (24 N•m)

Connector tightening torque: 1.5 lb-ft (2 N•m)

XU2S18PP340WL5



(1) LED

(2) Potentiometer

XU2S18PP340WD



Dual Dimensions: Inches / Millimeters

Mounting nut tightening torque: 17.7 lb-ft (24 N•m)

Connector tightening torque: 1.5 lb-ft (2 N•m)

Wiring diagrams (3-wire ⎓)

Cable connection

Transmitter



Receiver

Light switching (no object present). PNP output



Receiver

Dark switching (no object present). PNP output



Plug-in connector

Transmitter



Receiver

Light switching (no object present). PNP output



Receiver

Dark switching (no object present). PNP output



Cable connections

(–)	BU	(Blue)
(+)	BN	(Brown)
(OUT)	BK	(Black) (receiver)
(Prog.)	OG	(Orange) (receiver)
(Test)	VI	(Violet) (transmitter)

Connector diagrams

Sensor connector pin view

Transmitter Receiver



Beam break test (for transmitter only)

Beam made Beam broken



Principle: page 3/60 | Specifications: page 3/61 | References: page 3/62 | Dimensions: page 3/65, 3/112 | Wiring diagrams: page 3/65

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSCM and single-beam photoelectric sensors type XU2S

With a test input associated with a built-in “muting” function

Wiring diagrams (continued)

Connection of XPSCM module with 4 pairs of XU2S single-beam sensors

(Connection of 1 to 4 pairs of XU2 S single-beam sensors to XPS CM, see page 3/67)



XU2S sensors can be programmed for light switching or dark switching (dark switching with sensors 1 and 3 and light switching with sensors 2 and 4, for example).
ESC: external start conditions
Y1-Y2: feedback loop.
STM: for stopping time measurement.

(1) Protection field sensors

(2) Muting sensors

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Wiring diagrams (continued)

Connection of XPSCM module with 1 pair of XU2S sensors

(dark switching)



Connection of XPSCM module with 2 pairs of XU2S sensors

(dark switching)



Connection of XPSCM module with 3 pairs of XU2S sensors

(2 for dark switching, 1 for light switching)



Connection of XPSCM module with 4 pairs of XU2S sensors

(2 for dark switching, 2 for light switching)



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSLCD

For monitoring 2 to 4 light curtains type 2 and type 4

Operating principle

The safety monitoring module XPSLCD1141 enables independent monitoring of 2 to 4 light curtains type 2 and type 4.
Each output of the light curtain is separately connected to the inputs of the safety monitoring module, which either authorises or prevents activation of its two safety outputs.
The module manages starting and EMD/MPCE functions and therefore, the light curtains connected to it must be configured for automatic start and the EDM/MPCE function deactivated. The safety monitoring module XPSLCD1141 provides the supply and also manages, in addition to its own auxiliary outputs (1 PNP and 1 NPN), the auxiliary outputs of the light curtains.
At the slightest intrusion through one or more light beams of any of the light curtains, the outputs of the safety monitoring module open. This also applies in the event of any internal fault or output relay(s) fault (subject to the EDM/MPCE configuration on the module).
The light curtain system conforms to the standard EN/IEC 61496-1 (type 4).
The Preventa™ safety monitoring module XPSLCD1141 incorporates removable terminal blocks, thus optimizing machine maintenance.
To aid diagnostics, the safety monitoring module has 9 LEDs and a 2-digit display on the front cover which provide information on the monitoring circuit status.

Environmental specifications

Safety monitoring module type			**XPSLCD1141**
Maximum achievable safety level (1)			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Conformity to standards			EN/IEC 61496-1, EN/IEC 61496-2, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1
Certifications			CE, TÜV, CSA, UL
Ambient air temperature		**°F (°C)**	Operation: 0…+ 55; storage: - 25…+ 75
Relative humidity			95% maximum, without condensation
Degree of protection			IP 20
Shock and vibration resistance	Conforming to EN/IEC 61496-1		Shock resistance: 10 gn, impulse 16 ms. Vibration resistance: 5…55 Hz max. on all 3 axes
Materials			ABS thermoplastic enclosure
Mounting			35 mm rail

Electrical specifications

Power supply		**V**	⎓ 24 ± 10%
Current		**A**	10 max.
Response time		**ms**	< 1
Safety outputs			2 solid-state PNP outputs (N.O.), 625 mA on ⎓ 24 V
Alarm or auxiliary output			1 solid-state PNP (N.O.), 500 mA on ⎓ 24 V, and 1 solid-state NPN (N.O.),100 mA on ⎓ 24 V, output
Monitoring activation of output switching devices (EDM/MPCE)		**mA**	50 ± 20% on ⎓ 24 V
Signalling			9 LEDs plus 2-digit display
Functions			-Auto/Manual, manual 1st cycle, -Monitoring of external switching devices (EDM: External Devices Monitoring), -Restart request indicator light, -Display of operating modes and alarm by 9 LEDs and 2-digit display. Selection of Auto/Manual, blanking relay monitoring, floating/blanking and blanking + floating/ blanking relay monitoring using configuration switches behind front cover of module. -Independent monitoring of 2 to 4 light curtains.
Monitoring of external switching devices (EDM = External Devices Monitoring)			Monitoring of the function (open or closed) as well as the response time of the power components. Selectable by using configuration switches.
Start input		**mA**	50 at 24 V
Connection	Type		Captive screw clamp terminals, removable terminal block
1-wire connection	Without cable end		Solid cable: 14 AWG (1.63 mm²)
	Without cable end		Flexible cable: 26-16 AWG (0.14...1.5 mm²)
	With cable end		Without bezel, flexible cable: 26-16 AWG (0.14…1.5 mm²)
2-wire connection	Without cable end		Solid cable: 26-16 AWG (0.14...1.5 mm²)
	Without cable end		Flexible cable: 26-16 AWG (0.14...1.5 mm²)

(1) Using an appropriate and correctly connected control system.

Principle: page 3/68 | Specifications: page 3/68 | References: page 3/69 | Wiring diagrams: page 3/70 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSLCD

For monitoring 2 to 4 light curtains type 2 and type 4

Reference

XPSLCD1141

Description	Type of terminal block connection	Number of safety circuits	Additional outputs	Supply	Reference	Weight
				V		oz (kg)
Safety module for monitoring 2 to 4 light curtains type 2 and type 4	Removable from module	2 PNP	5 (4 PNP + 1 PNP or NPN)	⎓ 24 V	**XPSLCD1141**	26.455 (0.750)

Dimensions

Safety monitoring module

XPSLCD1141

Mounting on 35 mm rail



(1) 2 elongated holes Ø 4 x 5.7.

Dual Dimensions: INCHES Millimeters

LED details

The safety monitoring module XPSLCD has 9 LEDs and a 2-digit display on the front cover.



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSLCD

For monitoring 2 to 4 light curtains type 2 and type 4

Connection via the safety monitoring module XPSLCD1141

Example: configuration with light curtains XUSLT, XUSLP and XUSLN



(1) Arc suppressor.
(2) Restart request indicator light.
(3) When module XPSLCD1141 is used with a type 2 light curtain (example: XUSLN), the entire protection system is downgraded to category 2.

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSLCD

For monitoring 2 to 4 light curtains type 2 and type 4

Functional diagram of module XPSLCD1141

Automatic start and restart mode



Manual start and restart mode



(1) Start button.

Principle: page 3/68 | Specifications: page 3/68 | References: page 3/69 | Wiring diagrams: page 3/70 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays
Preventa™ safety monitoring module XPSLCM
For “muting” function of type 2 and type 4 light curtains

Operating principle

Safety monitoring modules XPSLCM are used with type 4 light curtains conforming to EN/IEC 61496-1 to provide a system inhibiting the light curtain protection, i.e. “muting”. This function enables the automatic passage of parts for machining or loaded pallets, without interrupting the transportation movement within the zone protected by the electro-sensitive protection equipment (ESPE) system. In addition to the electro-sensitive protection and safety relay modules XPSLCM, the system consists of 4 to 8 inhibition sensors, 2 indicator lights and a key switch to reset the system to the initial state in the event of a sequence error.

When the system is switched on by the start command and the light curtain protection not interrupted, the main circuit is closed by the safety outputs of the XPSLCM modules (solid-state safety outputs). In addition to safety outputs, the modules incorporate signalling outputs for sending system status information to the PLC. Either 5 or 14 LEDs and a 2-digit display, mounted on the front cover of the module, provide information on the safety circuit status.

An interruption of the protection field monitored by the electro-sensitive protection equipment causes instantaneous opening of the safety outputs; the process PLC receives a stop command and the LED display mounted on the front cover indicates the change of state of the safety circuits. The “open” state is maintained until the module is restarted using the Start button.

The “muting” function cannot be activated by supplying the inhibition sensors unless the safety outputs have been switched on beforehand. To trigger the “muting” function, the inhibition devices must be activated within the 3 second time interval. During the activated “muting” phase, materials can be transported through the protection field without deactivating the safety outputs. In the event of intrusion into the hazardous zone, a person cannot activate the inhibition sensors in the same way and the system stops.

During the muting operation process, a light indicating the muting state is controlled by the XPSLCM module. The indicator light comes on when a muting signal is generated, and indicates the inhibition of the protection function. An indicator light error (short-circuit, open-circuit) will be recognized, and will deactivate the Muting function.



ESPE: electro-sensitive protection equipment (light curtain).
A, B, D, C: “muting” sensors.
m: trolley length and dM = distance between A, B and D, C.

Conditions to be observed for the “muting” function

- The “muting” sensors must either be thru-beam type XUB 0BPSNL2 + XUB 0BKSNL2T, polarized reflex type XUB 0BPSNL2 + XUC Z50 or mechanical limit switches with contacts.
- dM ≤ m to obtain continuous validation of the “muting” function.
- Avoid the intrusion of persons during the “muting” phase. This phase is indicated by the indicator light connected to the “muting” indicator output of the XPSLCM module.
- A materials trolley must provide the “muting” signal before entering the protection field and cease it once it has cleared all the sensors of the protection field on exiting.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety monitoring module XPSLCM

For “muting” function of type 2 and type 4 light curtains

Specifications

Module type			XPSLCM1150
Maximum achievable safety level *(1)*			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Conformity to standards			EN/IEC 61496-1, EN/IEC 61496-2, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1
Certifications			CE, TÜV, CSA, UL
Ambient air temperature	For operation	**°F (°C)**	0…+ 55
	For storage	**°F (°C)**	- 25…+ 75
Degree of protection conforming to IEC 529	Terminals		IP 20
	Enclosure		IP 20
Power supply	Voltage	**V**	⎓ 24
	Voltage limits		- 10…+ 10%
Maximum power consumption		**W**	< 150
Rated insulation voltage (Ui)		**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 and 2)
Rated impulse withstand voltage (Uimp)		**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 and 2)
Number of light curtains monitored			1 or 2 transmitter-receiver pairs
Inputs for “muting” sensors	Number of inputs to be monitored		2 to 4 per “muting” function
	Supply voltage of sensors	**V**	24
	Output current of each sensor	**mA**	< 20
Type of “muting” sensors			Thru-beam, polarised reflex or sensors with relay hard contacts
Synchronization time of “muting” sensors		**s**	3 or unlimited
Maximum “muting” time		**min**	2 or unlimited
Safety outputs			
- number and type			2 PNP (terminals 1 and 2), 0.625 A at 24 V
- max. thermal current (Ithe)	1 output	**A**	–
	2 outputs	**A**	2 x 0.108
	3 outputs	**A**	–
	3 contacts	**A**	–
Auxiliary outputs 1 PNP (terminal 5) + 1 NPN (terminal 6)	Breaking capacity of solid-state PNP outputs	**mA**	24 V/500
	Breaking capacity of solid-state NPN outputs	**mA**	24 V/100
“Muting” indicator light power		**W**	1 to 7 max.
Response time on input change of state		**ms**	1
Signalling			14 LEDs plus 2-digit display
Connection	Type		Captive screw clamp terminals, removable terminal block
1-wire connection	Without cable end		Solid cable: 14 AWG (1.63 mm²)
	Without cable end		Flexible cable: 26-16 AWG (0.14...1.5 mm²)
	With cable end		Without bezel, flexible cable: 26-16 AWG (0.14…1.5 mm²)
2-wire connection	Without cable end		Solid cable: 26-16 AWG (0.14...1.5 mm²)
	Without cable end		Flexible cable: 26-16 AWG (0.14...1.5 mm²)

(1) Using an appropriate and correctly connected control system.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety monitoring module XPSLCM

For “muting” function of type 2 and type 4 light curtains

XPSLCM1150

References

Safety module

Description	Type of terminal block connection	Number of safety circuits	Auxiliary outputs	Supply	Reference	Weight
						oz (kg)
Safety module for “muting” function	Removable from module	2 PNP	1 PNP + 1 NPN	⎓ 24 V	**XPSLCM1150**	23.281 (0.660)

Spare parts

Description	Power	Reference	Weight
	W		oz (kg)
“Muting” indicator light kit	5	**XSZCM01**	0.423 (0.012)
Replacement bulbs for “muting” indicator light kit consisting of one lot of 10 replacement bulbs and 1 removal/insertion tool XBF-X13	1 to 7	**XSZCM02**	0.564 (0.016)



LED details

XPSLCM1150

To aid diagnostics, the safety monitoring module has 14 LEDs and a 2-digit display on the front cover which provide information on the monitoring circuit status.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety monitoring module XPSLCM

For “muting” function of type 2 and type 4 light curtains

Dimensions

XPSLCM1150

Mounting on 35 mm rail





Rear view



(1) 2 elongated holes Ø 4 x 5.7

“Muting” indicator light kit XSZ CM01



Dual Dimensions: INCHES / Millimeters

(1) Faston connector 4.7.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety monitoring module XPSLCM

For “muting” function of type 2 and type 4 light curtains

Connection via the safety monitoring module XPSLCM1150

Example: configuration with light curtains XUSL



(1) Arc suppressor.
(2) Inhibition activation/deactivation key switch.

Principle: page 3/72 | Specifications: page 3/73 | References: page 3/74 | Dimensions: page 3/75 | Wiring diagrams: page 3/76

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety monitoring module XPSLCM

For “muting” function of type 2 and type 4 light curtains

Connection via the safety monitoring module XPSLCM1150

Example: configuration with 2 light curtains XUSLP and XUSLN



(1) Arc suppressor.
(2) Inhibition activation/deactivation key switch.
(3) When module XPSLCM1150 is used with a type 2 light curtain (example: XUSLN), the entire protection system is downgraded to category 2.

Principle: page 3/72 | Specifications: page 3/73 | References: page 3/74 | Dimensions: page 3/75 | Wiring diagrams: page 3/76

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

Functional diagram of safety monitoring module XPSLCM1150

“Start/restart interlock” mode with 2 sensors



(1) Press Start button.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Functional diagram of safety monitoring module XPSLCM1150

“Start/restart interlock” mode with 4 sensors



(1) Press Start button.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSECME, XPSECPE

For increasing the number of safety contacts

Operating principle

Safety relay modules XPSECME and XPSECPE, for increasing the number of safety contacts, are available as additions to Preventa XPS base modules (Emergency stop, limit switch, two-hand control, etc.). They are used to increase the number of safety output contacts of the base modules.

Specifications

Module type				XPSECME●●●●P	XPSECME●●●●C	XPSECPE●●●●P	XPSECPE●●●●C
Maximum achievable safety level				PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061 (when connected to the appropriate module)			
Reliability data *(1)*	Mean Time To dangerous Failure ($MTTF_d$)		**Years**	45		30	
	Diagnostic Coverage (DC)		**%**	60 to 90		99	
	Probability of dangerous Failure per Hour (PFH_d)		**1/h**	2.00×10^{-7}		3.00×10^{-9}	
Conformity to standards				EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1			
Product certifications				UL, CSA, BG		UL, CSA, TÜV	
Supply	Voltage		**V**	∿ and 24 ⎓		∿ and 24 ⎓, 115 to 230 ∿	
	Voltage limits			- 15 to + 10%		-15 to +10%	
	Frequency		**Hz**	50/60			
Power consumption	24 V		**VA**	< 5		4	
	115 V/230 V		**VA**	–		6	
Module inputs fuse protection				Internal, electronic		Internal PTC	
Outputs	Voltage reference			Relay hard contacts			
	Number and type of safety circuits			4 N.O.		8 N.O.	
	Number and type of additional circuits			2 N.C.		1 N.C.	
	Breaking capacity in AC-15		**VA**	B300: inrush 3600, maintained 360			
	Breaking capacity in DC-13			24 V/1.5 A - L/R = 50 ms		24 V/3 A - L/R = 50 ms	
	Max. thermal current (Ithe)		**A**	6			
	Max. total thermal current		**A**	12		24	
	Output fuse protection		**A**	6 gG			
	Minimum current (relay contact)		**mA**	10 (conforming to EN/IEC 60947-5-1, VDE 0660 part 200)			
	Minimum voltage (relay contact)		**V**	17		5	
Electrical life				See page 3/12			
Response time on input opening			**ms**	< 20		10	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to IEC/EN 60947-5-1, DIN VDE 0110 parts 1 & 2)			
Rated impulse withstand voltage (Uimp)			**kV**	4 (overvoltage category III, conforming to IEC/EN 60947-1, DIN VDE 0110 parts 1 & 2)			
LED display				2		3	
Operating temperature			**°F (°C)**	- 13 to + 131 (- 25 to + 55)		- 13 to + 131 (- 25 to + 55)	
Storage temperature			**°F (°C)**	- 13 to + 167 (- 25 to + 75)		- 13 to + 158 (- 25 to + 70)	
Degree of protection conforming to IEC 60529	Terminals			IP 20			
	Enclosure			IP 40			
Connection	Type	Terminals		Captive screw clamp terminals	Spring terminals	Captive screw clamp terminals	Spring terminals
		Terminal block		Removable from module			
	1-wire connection	Without cable end		Solid or flexible cable: 24-14 AWG (0.2 to 2.5 mm^2)			
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm^2)			
				With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm^2)	With bezel, flexible cable: 24-16 AWG (0.25 to 1.5 mm^2)	With bezel, flexible cable: 24-14 AWG (0.25 to 2.5 mm^2)
	2-wire connection	Without cable end		Solid or flexible cable: 24-18 AWG (0.2 to 1 mm^2)	–	Solid or flexible cable: 24-18 AWG (0.2 to 1 mm^2)	–
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25 to 1 mm^2)	–	Without bezel, flexible cable: 24-18 AWG (0.25 to 1 mm^2)	–
				Double, with bezel, flexible cable: 20-16 AWG (0.5 to 1.5 mm^2)	Double, with bezel, flexible cable: 20-18 AWG (0.5 to 1 mm^2)	Double, with bezel, flexible cable: 20-16 AWG (0.5 to 1.5 mm^2)	Double, with bezel, flexible cable: 20-18 AWG (0.5 to 1 mm^2)

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSECME, XPSECPE

For increasing the number of safety contacts

XPSECME5131P

XPSECME5131C

XPSECPE5131P

XPSECPE5131C

References

Description	Number of safety circuits	Additional outputs	Supply	Connection	Reference	Weight oz (kg)
Safety modules for increasing the number of safety contacts, for use with XPS base modules	4	2	∼ and 24 V ⎓	Captive screw clamp terminals Terminal block removable from module	**XPSECME5131P**	9.524 (0.270)
				Spring terminals Terminal block removable from module	**XPSECME5131C**	9.524 (0.270)
	8	1	∼ and 24 V ⎓	Captive screw clamp terminals Terminal block removable from module	**XPSECPE5131P**	19.401 (0.550)
				Spring terminals Terminal block removable from module	**XPSECPE5131C**	22.928 (0.650)
			115 to 230 V ∼	Captive screw clamp terminals Terminal block removable from module	**XPSECPE3910P**	22.928 (0.650)
				Spring terminals Terminal block removable from module	**XPSECPE3910C**	22.928 (0.650)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSECME

For increasing the number of safety contacts

XPSECME

Wiring diagram



Functional diagram



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSECPE

For increasing the number of safety contacts

XPSECPE

Wiring diagram



S1: Start Button.
(1) Feedback loop.

Functional diagram



tA : response time (K1 and K2)
tR : release time

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSTSA, XPSTSW

For safety time delays

Operating principle

Safety relay modules XPSTSA and XPSTSW are used in applications requiring safety time delays:

- modules XPSTSA in applications with interlocking on high inertia machines with long rundown time (guards unlocked after safety time delay has elapsed),
- modules XPSTSW in applications with a safety switchover contact (jumpering contact in association with XPSVN modules for zero speed detection, solenoid valve monitoring, etc.).

The time delay of safety circuits can be set to 16 preset values, using 2 selectors located on the front cover of the modules.

To aid diagnostics, the modules have LEDs which provide information on the monitoring circuit status and 2 solid-state outputs for signalling to the process PLC.

In addition, their removable terminal blocks optimize machine maintenance.

Specifications

Module type				XPSTSA	XPSTSW
Maximum achievable safety level				PL d/Category 3 conforming to EN/ISO 13849-1, SILCL 2 conforming to EN/IEC 62061	
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)		**Years**	126	
	Diagnostic Coverage (DC)		**%**	60 to 90	
	Probability of dangerous Failure per Hour (PFH_d)		**1/h**	1.3 x 10^{-7}	
Conformity to standards				EN/IEC 60204-1, EN/IEC 60947-5-1	
Product certifications				UL, CSA, BG	
Supply	Voltage		**V**	⎓ and ⎓ 24, ∿ 115, ∿ 230	
	Voltage limits			- 15…+ 15% (⎓ 24 V) - 20…+ 10% (∿ 24 V) - 15…+ 15% (115 V) - 15…+ 10% (230 V)	
	Frequency		**Hz**	50/60	
Power consumption	⎓ 24		**VA**	< 2.3	
	∿ 24 V			< 4.3	
	∿ 115			< 6.5	
	∿ 230 V			< 5.5	
Module inputs fuse protection				Internal, electronic	
Time delay			**s**	1…31 (16 positions)	–
Pulse time			**s**	–	0.1…3.1 (16 positions)
Outputs	Voltage reference			Relay hard contacts	
	Number and type of safety circuits			1 N.O. (17-18) + 2 N.C. (25-26, 35-36)	
	Number and type of additional circuits			2 solid-state (Y53-Y54, Y63-Y64)	
	Breaking capacity in AC-15		**VA**	C300: inrush 1800, maintained 180	
	Breaking capacity in DC-13			24 V/1.5 A - L/R = 50 ms	
	Breaking capacity of solid-state outputs			24 V/20 mA, 48 V/10 mA	
	Max. thermal current (Ithe)		**A**	6	
	Output fuse protection		**A**	4 gG (gl) or 6 fast acting, conforming to EN/IEC 60947-5-1, DIN VDE 0660 part 200	
	Minimum current		**mA**	10	
	Minimum voltage		**V**	17	
Electrical life				See page 3/12	
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
Rated impulse withstand voltage (Uimp.)			**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)	
LED display				4	
Operating temperature			**°F (°C)**	+ 14…+ 131 (- 10…+ 55)	
Storage temperature			**°F (°C)**	- 13…+ 185 (- 25…+ 85)	
Degree of protection conforming to IEC 60529		Terminals		IP 20	
		Enclosure		IP 40	
Connection		Type		Captive screw clamp terminals, removable terminal block	
	1-wire connection	Without cable end		Solid or flexible cable: 24-14 AWG (0.2…2.5 mm^2)	
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)	
		With cable end		With bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)	
	2-wire connection	Without cable end		Solid cable: 24-18 AWG (0.2…1 mm^2), flexible cable: 24-16 AWG (0.2…1.5 mm^2)	
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25…1 mm^2)	
		With cable end		Double, with bezel, flexible cable: 20-16 AWG (0.5…1.5 mm^2)	

(1) Using an appropriate and correctly connected control system.

Principle: page 3/84 | Specifications: page 3/84 | References: page 3/85 | Wiring diagrams: page 3/85 | Dimensions: page 3/112

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSTSA, XPSTSW

For safety time delays

References

XPSTSA●●●●P

XPSTSW●●●●P

Description	Number of safety circuits	Number of additional outputs	Supply	Reference	Weight oz (kg)
Safety modules for applications with interlocking on high inertia machines	1 delayed	2 N.C. + 2 solid-state to PLC	∼ and ⎓ 24 V	**XPSTSA5142P**	8.818 (0.250)
			∼ 115 V	**XPSTSA3442P**	12.699 (0.360)
			∼ 230 V	**XPSTSA3742P**	12.699 (0.360)
Safety modules for applications with safety switchover contact	1 pulse type	2 N.C. + 2 solid-state to PLC	∼ and ⎓ 24 V	**XPSTSW5142P**	8.818 (0.250)
			∼ 115 V	**XPSTSW3442P**	12.699 (0.360)
			∼ 230 V	**XPSTSW3742P**	12.699 (0.360)

Wiring diagrams

XPSTSA

Delayed unlocking of a guard application



Contacts 95/96 and 97/98 are trip contacts for an overload relay.
S1 is one of the N.C. safety contacts in an XCSE switch
Y1 is the N.C. solenoid contact in the XCSE switch (wired in series with the S1)
S2 is the motor stop push button
S3 is the motor start push button, in parallel of KM1 contact
S4 is the push button to energize the XCSE solenoid to unlock the guard

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

XPSTSA

Wiring diagram



(1) Signal to be delayed.
(2) Relay hard contact outputs with on-delay.
ESC: External start conditions.

Functional diagram of module XPSTSA



LED details (XPSTSA, XPA TSW)



1 Supply voltage A1-A2 (fuse status).
2 Safety output closed.
3 Feedback loop Y1-Y2 status.
4 Time function active.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XPSTSW

Guard unlocking application using zero speed detection



Wiring diagram



Functional diagram of module XPSTSW



(1) Control signal.
(2) Relay hard contact outputs with pulse time delay.
ESC: External start conditions.
LED details: see page 3/86.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSDMB, XPSDME

For non-contact safety interlock (coded magnetic) switch monitoring

Operating principle

Safety relay modules XPSDMB and XPSDME are specifically designed for monitoring coded magnetic safety switches. They incorporate two safety outputs and two solid-state outputs for signalling to the process PLC.
XPSDMB safety relay modules can monitor two independent sensors and modules XPSDME can monitor up to six independent sensors.
To monitor a higher number of magnetic switches using these safety modules, the magnetic switches can be connected in series, while meeting the requirements of category 3 of EN/ISO 13849-1.

Safety modules XPSDM●●●●●P incorporate removable terminal blocks, thus optimizing machine maintenance.

To aid diagnostics, the modules have LEDs on the front cover which provide information on the monitoring circuit status.

Specifications

Module type				**XPSDMB1132**	**XPSDME1132**	**XPSDMB1132P**	**XPSDME1132P**
Maximum achievable safety level				PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061			
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)		**Years**	83.1	82.4	83.1	82.4
	Diagnostic Coverage (DC)		**%**	> 99			
	Probability of dangerous Failure per Hour (PFH_d)		**1/h**	3.92×10^{-9}	3.97×10^{-9}	3.92×10^{-9}	3.97×10^{-9}
Conformity to standards				EN/IEC 60204-1, EN 1088/ISO 14119, EN/IEC 60947-5-1, EN/IEC 60947-5-3, DIN V VDE 0801 (1990), DIN V VDE 0801 A1 (1994)			
Product certifications				UL, CSA, BIA			
Supply (Ue) conforming to IEC 38	Voltage		**V**	⎓ 24			
	Voltage limits	⎓ 24 V		- 20…+ 20%			
Power consumption			**W**	< 2.5	< 3.5	< 2.5	< 3.5
Module inputs fuse protection				Internal, electronic			
Maximum wiring resistance RL between the module and the coded magnetic switches			Ω	100			
Control unit voltage and current				28 V/8 mA			
Synchronization time between magnetic switch inputs			**s**	< 0.5			
Safety outputs	Voltage reference			Relay hard contacts			
	Number and type of safety circuits			2 N.O.			
	Number and type of solid-state outputs			2			
	Breaking capacity in AC-15		**VA**	C300: inrush 1800, sealed: 180			
	Breaking capacity in DC-13			24 V/1.5 A, L/R = 50 ms			
	Max. thermal current (Ithe)		**A**	6			
	Max. total thermal current		**A**	12			
	Output fuse protection		**A**	4 gG or 6 fast acting			
	Minimum current		**mA**	10			
	Minimum voltage		**V**	17			
Electrical life				See page 3/12			
Response time on input opening			**ms**	< 20			
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)			
Rated impulse withstand voltage (Uimp.)			**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)			
LED display				3	15	3	15
Ambient air temperature			**°F (°C)**	For operation: + 14…+ 131 (- 10…+ 55), for storage: - 13…+ 185 (- 25…+ 85)			
Degree of protection conforming to IEC 60529				Terminals: IP 20, enclosure: IP 40			
Connection	Type			Captive screw clamp terminals		Captive screw clamp terminals, removable terminal block	
	1-wire connection	Without cable end		Solid or flexible cable: 26-14 AWG (0.14… 2.5 mm^2)		Solid or flexible cable: 24-14 AWG (0.2…2.5 mm^2)	
		With cable end		Without bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)			
		With cable end		With bezel, flexible cable: 24-16 AWG (0.25…1.5 mm^2)		With bezel, flexible cable: 24-14 AWG (0.25…2.5 mm^2)	
	2-wire connection	Without cable end		Solid or flexible cable: 26-18 AWG (0.14…0.75 mm^2)		Solid cable: 24-18 AWG (0.2…1 mm^2), flexible cable: 24-16 AWG (0.2…1.5 mm^2)	
		With cable end		Without bezel, flexible cable: 24-18 AWG (0.25…1 mm^2)			
		With cable end		With bezel, flexible cable: 20-16 AWG (0.5… 1.5 mm^2)			

(1) Per EN/ISO 13849-1 and EN/IEC 62061

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSDMB, XPSDME

For non-contact safety interlock (coded magnetic) switch monitoring

XPSDMB1132●

XPSDME1132

References

Description	Type of terminal block connection	Number of safety circuits	Solid-state outputs for PLC	Supply V	Reference	Weight oz (kg)
Safety module for monitoring 2 coded magnetic switches	Integrated in module	2 N.O.	2	⎓ 24	**XPSDMB1132**	8.818 (0.250)
Safety module for monitoring 6 coded magnetic switches	Integrated in module	2 N.O.	2	⎓ 24	**XPSDME1132**	10.582 (0.300)
Safety module for monitoring 2 coded magnetic switches	Removable from module	2 N.O.	2	⎓ 24	**XPSDMB1132P**	8.818 (0.250)
Safety module for monitoring 6 coded magnetic switches	Removable from module	2 N.O.	2	⎓ 24	**XPSDME1132P**	10.582 (0.300)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSDMB, XPSDME

For non-contact safety interlock (coded magnetic) switch monitoring

XPSDMB

Wiring to category 4 conforming to EN/ISO 13849-1. Example with 2-pole N.C. + N.O. (N.C. staggered) contact.



ESC: External start conditions.

Wiring to category 3 conforming to EN/ISO 13849-1. Example with 3 switches with 2-pole N.C. + N.O. (N.C. staggered) contacts.



Input: S11, S12, S13 or S21, S22, S23.
Unused inputs must be jumpered: i.e.: if only input S11, S12, S13 is used, then terminals S21 and S23 must be jumpered.
The order in which the inputs are wired or jumpered will not affect operation.

Principle: page 3/88 | Specifications: page 3/88 | References: page 3/89 | Wiring diagrams: page 3/90 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSDMB, XPSDME

For non-contact safety interlock (coded magnetic) switch monitoring

XPSDME

Wiring to category 4 conforming to EN/ISO 13849-1. Example with 2-pole N.C. + N.O. (N.C. staggered) contact



ESC: External start conditions.

Wiring to category 3 conforming to EN/ISO 13849-1. Example with 3 switches with 2-pole N.C. + N.O. (N.C. staggered) contacts.



Input: S11, S12, S13 or S21, S22, S23 or S31, S32, S33 or S41, S42, S43 or S51, S52, S53 or S61, S62, S63.
Unused inputs must be jumpered i.e.: if input S61, S62, S63 is not used, then terminals S61 and S63 must be jumpered.
Terminals to be jumpered if the input is not used are: S11 and S13, S21 and S23, S31 and S33, S41 and S43, S51 and S53, S61 and S63.

The order in which the inputs are wired will not affect device operation.

Principle:	Specifications:	References:	Wiring diagrams:	Dimensions:
page 3/88	page 3/88	page 3/89	page 3/90	page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSDMB, XPSDME

For non-contact safety interlock (coded magnetic) switch monitoring

XPSDMB

Functional diagram



LED details



1 Supply voltage A1-A2, internal electronic fuse status.
2 Fault signalling.
3 Safety outputs closed.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules types XPSDMB, XPSDME

For non-contact safety interlock (coded magnetic) switch monitoring

XPSDME

Functional diagram



LED details



1 Supply voltage A1-A2, internal electronic fuse status.
2 Fault signalling.
3 Safety outputs closed.
4 Magnetic switch 1 activated.
5 Magnetic switch 1 deactivated.
6 Magnetic switch 2 activated.
7 Magnetic switch 2 deactivated.
8 Magnetic switch 3 activated.
9 Magnetic switch 3 deactivated.
10 Magnetic switch 4 activated.
11 Magnetic switch 4 deactivated.
12 Magnetic switch 5 activated.
13 Magnetic switch 5 deactivated.
14 Magnetic switch 6 activated.
15 Magnetic switch 6 deactivated.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSVNE

For zero speed detection

Operating principle

Preventa™ safety relay modules type XPSVNE for zero speed detection are used to detect the stop condition of electric motors. Their most common applications include: providing the unlock signal for electrically interlocked sliding or removable machine guards, controlling rotation direction signals for reversing motors and engaging locking brakes after a motor has come to a standstill.

As electric motors run down, a remanent voltage is produced in the windings of the motor due to residual magnetism. This voltage is proportional to the speed of the motor and, therefore, decreases as the motor comes to a standstill.
This remanent voltage is measured in a redundant manner so as to detect the stop condition of the motor. The cabling between the motor windings and the inputs of the XPSVNE module is also monitored to prevent a cabling breakage or anomaly being seen as a stopped motor.
A transformer should not be used to connect the motor to terminals Z1, Z2 and Z3 since there is no monitoring of the connection with the motor winding via the resistance monitoring.

Modules XPSVNE are suitable for detecting the stop condition of all types of a.c. or d.c. motor driven machines which, when the motor runs down, produce a remanent voltage in the windings due to residual magnetism. These machines can be controlled by electronic devices, such as variable speed drives or d.c. injection brakes.
The input filters for standard XPSVNE modules are designed for a frequency of up to 60 Hz.
For motors operating at a frequency higher than 60 Hz, which therefore produce a high frequency remanent voltage, special modules XPSVNE●●●●HS should be used.

The XPSVNE is not compatible with Wound Rotor Motors. These motors are typically used in high HP (1000+) low speed applications, where the additional windings (required for these types of motors) pay for themselves. If power is removed from stator, but rotor is left energized, then transformer coupling between the two could create a small voltage across the stator. This could make the XPSVNE think the motor is still turning, which means the safety outputs would never energize or change state. These motors do not have residual magnetism in the rotor that can act as a source of flux for generator effect, in which case the XPSVNE may think the motor is at zero speed, and could energize the safety outputs while the motor is still running. Wound Rotor motors are not in common use today, and very rare.

The XPSVNE is not designed for use with single phase motors.

The XPSVNE is not designed to detect locked rotor conditions. Here the motor still has voltage applied to it, but in essence has zero speed. Generally, a locked rotor condition is not a safe state for machinery nor the operators. The XPSVN will sense voltage applied to the windings, and will not indicate the motor's "apparent" zero speed. The outputs of the XPSVN will not change state, the gates or guards will not be unlocked, and operators will not be allowed access to the unsafe area.

Modules XPSVNE have 2 potentiometers mounted on the front cover of the module which allow independent adjustment of the switching threshold for each input circuit. This allows adjustment for different types of motors and application requirements.

To aid diagnostics, modules XPSVNE have 4 LEDs and 2 solid-state outputs to provide information on the status of the zero speed detection circuit.

Principle: page 3/94 | Specifications: page 3/95 | References: page 3/95 | Wiring diagrams: page 3/96 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSVNE

For zero speed detection

Specifications

Module type			XPSVNE
Maximum achievable safety level			PL d/Category 3 conforming to EN/ISO 13849-1, SILCL 2 conforming to EN/IEC 62061
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)	**Years**	124.1
	Diagnostic Coverage (DC)	**%**	> 99
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	9.26×10^{-9}
Conformity to standards			EN 60204-1, EN/IEC 60947-5-1, EN 50082-2
Product certifications			UL, CSA, BG
Supply	Voltage	**V**	⎓ 24 ∿ 115 ∿ 230
	Voltage limits		- 15…+ 10% (⎓ 24 V) - 15…+ 15% (∿ 115 V) - 15…+ 10% (∿ 230 V)
	Frequency	**Hz**	50/60 (115 V, 230 V)
Power consumption		**W**	≤ 3.5 (⎓ 24 V)
		VA	≤ 7.5 (∿115 V), ≤ 7 (∿ 230 V)
Frequency of motor power supply		**Hz**	≤ 60 Hz (XPSVN●●42), > 60 Hz (XPSVN●●42HS)
Inputs	Maximum voltage between terminals Z1 - Z2 - Z3	**V**	500 rms
	Detection threshold	**V**	0.01 - 0.1 (adjustable)
Outputs	Voltage reference		Hard contacts
	Number and type of safety circuits		1 N.O. (13-14), 1 N.C. (21-22)
	Number and type of additional circuits		2 solid-state
	Breaking capacity in AC-15		C300 (inrush: 1800 VA/maintained: 180 VA)
	Breaking capacity in DC-13		24 V/1.5 A - L/R = 50 ms (contact 13-14) 24 V/1.2 A - L/R = 50 ms (contact 21-22)
	Breaking capacity of solid-state outputs		24 V/20 mA, 48 V/10 mA
	Max. thermal current (Ithe)	**A**	2.5
	Output fuse protection	**A**	4 gG, conforming to EN/IEC 60947-5-1, DIN VDE 0660 part 200
	Minimum current (volt-free contact)	**mA**	10
	Minimum voltage (volt-free contact)	**V**	17
Electrical life			See page 3/12
Rated insulation voltage (Ui)		**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)
Rated impulse withstand voltage (Uimp)		**kV**	4 (overvoltage category III, conforming to EN//IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)
LED display			4
Operating temperature		**°F (°C)**	+ 14…+ 131 (- 10…+ 55)
Storage temperature		**°F (°C)**	- 13…+ 185 (- 25…+ 85)
Degree of protection Conforming to IEC 60529	Terminals		IP 20
	Enclosure		IP 40
Connection	Type		Captive screw clamp terminals, removable terminal block
1-wire connection	Without cable end		Solid or flexible cable: 24-14 AWG (0.2…2.5 mm^2)
	With cable end		Without bezel, solid or flexible cable: 24-14 AWG (0.25…2.5 mm^2)
			With bezel, solid or flexible cable: 24-14 AWG (0.25…2.5 mm^2)
2-wire connection	Without cable end		Solid cable: 24-18 AWG (0.2…1 mm^2), flexible cable: 24-16 AWG (0.2…1.5 mm^2)
	With cable end		Without bezel, flexible cable: 24-18 AWG (0.25…1 mm^2)
			With bezel, flexible cable: 22-14 AWG (0.5…1.5 mm^2)

(1) Per EN/ISO 13849-1 and EN/IEC 62061

References

XPSVNE

Description	Number of safety circuits	Solid-state outputs for PLC	Supply	Frequency of motor power supply	Reference	Weight oz (kg)
Safety modules for zero speed detection	2	2	⎓ 24 V	≤ 60 Hz	**XPSVNE1142P**	17.637 (0.500)
				> 60 Hz	**XPSVNE1142HSP**	17.637 (0.500)
			∿ 115 V	≤ 60 Hz	**XPSVNE3442P**	21.164 (0.600)
				> 60 Hz	**XPSVNE3442HSP**	21.164 (0.600)
			∿ 230 V	≤ 60 Hz	**XPSVNE3742P**	21.164 (0.600)
				> 60 Hz	**XPSVNE3742HSP**	21.164 (0.600)

Principle: page 3/94 | Specifications: page 3/95 | References: page 3/95 | Wiring diagrams: page 3/96 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSVNE

For zero speed detection

XPSVNE

Wiring diagram



(1) Technical specifications for establishing maximum rating of fuses, see page 3/95.
(2) Contacts are open when motor is running, closed when motor is stopped.
(3) Contacts are closed when motor is running, open when motor is stopped.
F1 = 2 A

Functional diagram of module XPSVNE



Key 0 1

The voltages at terminals Z1, Z2 and Z3 are indicated solely for the purposes of schematic diagram reintroduction.

LED details



1 Supply voltage A1-A2.
2 Stop detected by channel 1.
3 Stop detected by channel 2.
4 Motor stop condition detected by both channels within time window.

Principle: page 3/94 | Specifications: page 3/95 | References: page 3/95 | Wiring diagrams: page 3/96 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Module XPSVNE associated with a d.c. motor



F1 = 2 A

Module XPSVNE associated with a 3-phase motor



F1 = 2 A

Module XPSVNE associated with a 3-phase motor + variable speed drive



F1 = 2 A

Module XPSVNE associated with a 3-phase motor with start-delta starting



F1 = 2 A
KM1: Fast rotation speed
KM2: Slow rotation speed
KM3: Star
The “Star” contactor (KM3) must be closed after the motor is de-energized, in order to allow detection of zero speed.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

Module XPSVNE associated with a 3-phase motor with variable number of poles and star-delta starting



F1 = 2 A
KM1: Fast rotation speed
KM2: Slow rotation speed
KM3: Star
KM4: Delta

Module XPSVNE associated with a star-delta motor starter and guard switch type XCS E



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSVNE

For zero speed detection

Association of safety modules XPSVNE and XPSAK



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSPVT

For dynamic monitoring of hydraulic valves on linear presses

Operating principle

Safety relay module XPSPVT is specifically designed for monitoring hydraulic safety system valves which control the movements of potentially hazardous machines.
The operating principle of this module is explained in the circuit diagram of a hydraulic safety system for linear presses (see below).

This hydraulic safety system features a 3 position piston which controls the up and down stroke of the operating cylinder. The circuit is equipped with a safety valve, to complete the redundant system. This circuit must be activated to enable the up and down stroke of the cylinder.
If either of the 2 pistons becomes defective (for example, due to a broken spring or to oil contamination), and the valve piston shifts from its normal position towards the open position, the XPSPVT module will detect it and prevent resumption of the piston stroke.
Proximity sensors integrated in the valve to detect the piston positions and connected to the XPSPVT module must be damped when the valve coils are in the de-energized state (zero position).
The sensor circuits of the XPSPVT module are designed to allow connection of NPN and PNP proximity sensors or sensing components. Either 2-wire or 3-wire types can be used.
The wiring diagram on page 3/102 shows how to connect proximity sensors.

Hydraulic safety system circuit operating on a linear press.
Monitoring of valves in position 0.



(1) 3 position hydraulic valve.
(2) 2 position hydraulic valve.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSPVT

For dynamic monitoring of hydraulic valves on linear presses

Specifications

Module type				XPSPVT
Maximum achievable safety level (2)				PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)		**Years**	50.9
	Diagnostic Coverage (DC)		**%**	0 to 99
	Probability of dangerous Failure per Hour (PFH_d)		**1/h**	2.24×10^{-8}
Conformity to standards				EN 60204-1, EN/IEC 60947-5-1, EN 693, EN 50082-2
Product certifications				UL, CSA
Supply	Voltage		**V**	⎓ 24
	Voltage limits			- 10…+ 10%
Power consumption			**W**	< 6
Outputs	Voltage reference			Relay hard contacts
	Number and type of safety circuits			2 N.O. (13-14, 33-34) + 1 N.C. (21-22)
	Number and type of additional circuits			–
	Wiping time		**ms**	100 (minimum value)
	Breaking capacity	AC-15	**VA**	C300: inrush 1800, maintained 180
		DC-13	**VA**	24 V/1.5 A - L/R = 50 ms
	Max. thermal current (Ithe)		**A**	2.5
	Output fuse protection, using fuses conforming to EN/IEC 60947-5-1, VDE 0660 part 200		**A**	4 gG
	Minimum current		**mA**	10
	Minimum voltage		**V**	17
Electrical life				See page 3/12
Response time			**ms**	< 15
Rated insulation voltage (Ui)			**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)
Rated impulse withstand voltage (Uimp.)			**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-1, DIN VDE 0110 parts 1 & 2)
LED display				8
Operating temperature			**°F (°C)**	+ 14…+ 131 (- 10…+ 55)
Storage temperature			**°F (°C)**	- 13…+ 185 (- 25…+ 85)
Degree of protection conforming to IEC 60529		Terminals		IP 20
		Enclosure		IP 40
Polycarbonate enclosure		Type		Removable
		Number of terminals		20
Connection		Type		Captive screw clamp terminals: without cable end 2 x 14 AWG (2 x 2.5 mm²), with cable end 2 x 16 AWG (2 x 1.5 mm²), min. Ø 0.5 mm

Reference

XPSPVT

Description	Display	Supply	Reference	Weight oz (kg)
Safety module for dynamic monitoring of hydraulic valves on linear presses	8 LEDs	⎓ 24 V	**XPSPVT1180**	19.048 (0.540)

(1) Using an appropriate and correctly connected control system.
(2) The Category, the Performance Level (PL) or the Safety Integrity Level Claim Level (SILCL) are only achieved with the full connection to the base unit or start unit.

Principle: page 3/100 | Specifications: page 3/101 | References: page 3/101 | Wiring diagrams: page 3/102 | Dimensions: page 3/112

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSPVT

For dynamic monitoring of hydraulic valves on linear presses

XPSPVT

Wiring diagram for module XPSPVT



(1) Two-hand control or presence sensor outputs.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSPVT

For dynamic monitoring of hydraulic valves on linear presses

XPSPVT

Functional diagram of module XPSPVT



Sensor Status During Press Cycle

Description	Valve Y1 Sensor S1 (N.O.)	Valve Y2 Sensor S2 (N.O.)	Valve Y3 Sensor S3 (N.C.)
Press Ram Stopped	**Contact closed**	**Contact closed**	**Contact open**
Press Ram Moving	**Contact open**	**Contact closed**	**Contact closed**
Press Ram Closing	**Contact closed**	**Contact open**	**Contact closed**

LED details



1 Closing command.
2 Closing test.
3 Opening command.
4 Opening test.
5 Opening valve (Y2) in position 0.
6 Closing enabled.
7 Safety valve (Y3) activated.
8 Closing valve (Y2) in position 0.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSPVK

For dynamic monitoring of double-bodied solenoid valves

Operating principle

Safety relay module XPSPVK is specially designed for dynamic monitoring of the safety valves in eccentric presses, conforming to European standard EN 692.
This standard establishes the specifications related to safety control systems for presses equipped with friction clutches.
To meet the requirements of this standard, the clutch/brake control must be monitored dynamically.
This function is provided by a double-bodied solenoid valve (safety valve for presses) which performs the functions of two valves mounted in one body.

The position of the two valve pistons can be monitored by proximity sensors, mechanical limit switches or pressure switches.
Module XPSPVK checks for the correct operation of the double-bodied safety valves at 3 points in the cycle.

- Start at top dead center: checks the rest position of the two valves.
- Take-on point (transfer function): checks that the two valves are in the “activated” (energized) position.
- Press stop trigger point: checks that the two valves return to the rest position. Return must be simultaneous for both valves within a defined time period.

To set up an automatic disconnect of the XPSPVK module at the first machine stroke, a N.C. auxiliary contact mounted on the main control contactor or on another contactor/relay, activated at the same time, can be wired to terminals 7 and 8 in parallel with the RESET button.
If an anomaly is detected during the cycle, the XPSPVK module will stop the slide stroke and will also inhibit the start of another cycle.

Specifications

Module type			**XPSPVK**
Maximum achievable safety level (2)			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)	**Years**	90.2
	Diagnostic Coverage (DC)	**%**	0 to 99
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	1.25×10^{-8}
Conformity to standards			EN 60204-1, EN/IEC 60947-5-1, EN 692, EN 50082-2
Product certifications			UL, CSA
Supply	Voltage	**V**	⎓ 24, ∿115, ∿ 230
	Voltage limits		- 10…+ 10% (⎓ 24 V) - 15…+ 15% (∿ 115 V) - 15…+ 10% (∿ 230 V)
	Frequency	**Hz**	50/60
Power consumption	⎓ 24 V	**W**	< 9
	∿ 115 V/230 V	**VA**	< 16
Outputs	Voltage reference		Relay hard contacts
	Number and type of safety circuits		1 N.O. (13-14) transfer function + 1 N.C. (21-22) feedback loop
	Number and type of additional circuits		4 solid-state outputs
	Breaking capacity in AC-15	**VA**	C300: inrush 1800, maintained 180
	Breaking capacity in DC-13		24 V/1.5 A - L/R = 50 ms
	Max. thermal current (Ithe)	**A**	2.5
	Breaking capacity of solid-state outputs		24 V/20 mA, 48 V/10 mA
	Output fuse protection	**A**	4 gG, conforming to EN/IEC 60947-5-1, VDE 0660 part 200
	Minimum current (relay hard contacts)	**mA**	10
	Minimum voltage (relay hard contacts)	**V**	17
Response time		**ms**	< 40
Electrical life			See page 3/12
Rated insulation voltage (Ui)		**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)
Rated impulse withstand voltage (Uimp.)		**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-1, DIN VDE 0110 parts 1 & 2)
LED display			8
Operating temperature		**°F (°C)**	+ 14…+ 131 (- 10…+ 55)
Storage temperature		**°F (°C)**	- 13…+ 185 (- 25…+ 85)
Degree of protection Conforming to IEC 60529	Terminals		IP 20
	Enclosure		IP 40
Polycarbonate enclosure	Type		Removable
	Number of terminals		32
Connection	Type		Captive screw clamp terminals: without cable end 2 x14 AWG (2 x 2.5 mm^2), with cable end 2 x16 AWG (2 x 1.5 mm^2), min. Ø 0.5 mm

(1) Using an appropriate and correctly connected control system.
(2) The Category, the Performance Level (PL) or the Safety Integrity Level Claim Level (SILCL) are only achieved with the full connection to the base unit or start unit.

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSPVK

For dynamic monitoring of double-bodied solenoid valves

References



XPSPVK

Description	Display	Supply	Reference	Weight oz (kg)
Safety modules for dynamic monitoring of double-bodied solenoid valves	8 LEDs	⎓ 24 V	**XPSPVK1184**	24.692 (0.700)
		~ 115 V	**XPSPVK3484**	31.747 (0.900)
		~ 230 V	**XPSPVK3784**	31.747 (0.900)

Wiring diagrams

XPSPVK

Monitoring of a press safety valve by an XPSPVK module



LED details



1 DC internal supply n° 1.
2 DC internal supply n° 2.
3 Valve n° 1 blocked.
4 Valve n° 2 blocked.
5 Ready for monitoring
6 Disconnect synchronized.
7 Reset.
8 Valves 1 and 2 energized.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

3

XPSPVK

Functional diagram of module XPSPVK



Connection of module XPSPVK with 3-wire (or 2-wire) proximity sensors

3-wire sensors



2-wire sensors



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSPVK

For dynamic monitoring of double-bodied solenoid valves

XPSPVK

Connection of module XPSPVK with an eccentric press safety valve



(1) Internal supply n° 1.
(2) Internal supply n° 2.
(3) For a ⎓ 24 V version: integrated ⎓/⎓ adaptor.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSOT

For safety stop with automatic overtravel monitoring and control

Operating principle

Safety relay module XPSOT is used on eccentric presses to monitor overtravel and ensure that the press slide stops in a non-hazardous position, that is, top dead center (TDC) during normal (non-emergency) operation. Use of this module, designed in accordance with standard EN 692 relating to mechanical press safety, makes it possible to create a redundant, self-monitoring control system.

The two essential functions of this safety module are to:

■ **Trigger the end of cycle stop sequences slightly before top dead center (at point A) so as to come to complete stop at TDC.**

After TDC, the permissible overtravel is approximately 10°. The safety module immediately detects any overtravel. Overtravel is indicative of braking device deterioration and, in this case, jog mode must be used to move the slide back to TDC. The next cycle will be inhibited to allow maintenance to be performed on the braking device (cam 1).

■ Take over control monitoring during the dangerous part of the cycle (slide downstroke). Any stop instruction issued between TDC (0°) and point C (approximately 150° after TDC) causes an immediate stop of the press. **This approximate value of 150° corresponds to the 0.315" (8mm) tool closure dimension (safety point).**

When a stop instruction is issued after this safety point, the press completes the cycle and comes to a complete stop at TDC (cam 2).

Control of the hazardous part of the cycle (generally the slide downstroke) is usually activated from a two-hand control station associated with a safety module (type XPSBC) monitoring this station to qualify as a category 4 control system according to standard EN 954-1/ISO 13849-1.

Overtravel monitoring is performed **on each cycle** by safety module XPSOT.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays
Preventa™ safety relay modules type XPSOT
For safety stop with automatic overtravel monitoring and control

Operating principle (continued)

Press diagram



Control cams diagram





1 Permissible overtravel zone.
2 Dangerous zone (usually slide downstroke).
3 Non-dangerous zone (usually slide upstroke).

S Permissible overtravel.
A Stop instruction trip point.
B Point at which permissible overtravel is exceeded (a stop instruction issued after point **B** will lock up the press).
C Takeover point, beyond which the press will complete its cycle up to **TDC**.
TDC Top dead center, actual stopping zone of the press.
BDC Bottom dead center.

Cam operation
Cam 1 is associated with the **OTS** limit switch (LS), cam 2 with the **UN** limit switch (the limit switches must be located on different cams for safety reasons).
The **OTS** limit switch is deactivated at TDC, at which point the **UN** limit switch is activated.
Point A1 of **cam 1** is located approximately 300° after TDC and, when reached, the press stops and comes to a standstill: **A1 is the press stop trigger point.**
Point B1, located approximately 10° after TDC, constitutes the end of cam 1: **If B1 is exceeded during stopping**, the overtravel is abnormally long, **the press locks up** and the next cycle is inhibited.
Point A2 of cam 2 functions like point A1 on cam 1 (contact state of the **UN** limit switch reversed in relation to the state of the **OTS** limit switch).
Point C2, located approximately 150° after TDC, corresponds to the 8 mm tool closing dimension. Stop instructions issued after C2 is reached are not executed until point A2 is reached.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSOT

For safety stop with automatic overtravel monitoring and control

Specifications

Module type			XPSOT
Maximum achievable safety level (2)			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)	**Years**	60.9
	Diagnostic Coverage (DC)	**%**	0 to 99
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	1.33×10^{-8}
Conformity to standards			EN 60204-1, EN/IEC 60947-5-1, EN 692, EN 50082-2
Product certifications			UL, CSA
Supply	Voltage	**V**	∼ 115, ∼ 230
	Voltage limits		- 15…+ 15% (115 V) - 15…+ 10% (230 V)
	Frequency	**Hz**	50/60
Power consumption		**VA**	< 12
Module inputs fuse protection			Internal, electronic
Outputs	Voltage reference		Relay hard contacts
	Number and type of safety circuits		3 N.O. (11-12, 11-13, 11-14)
	Number and type of additional circuits		4 solid-state outputs
	Breaking capacity in AC-15	**VA**	C300: inrush 1800, maintained 180
	Breaking capacity in DC-13		24 V/1.5 A - L/R = 50 ms
	Breaking capacity of solid-state outputs		24 V/20 mA, 48 V/10 mA
	Max. thermal current (Ithe)	**A**	2.5
	Output fuse protection	**A**	4 gG, conforming to EN/IEC 60947-5-1, VDE 0660 part 200
	Minimum current (relay hard contacts)	**mA**	10
	Minimum voltage (relay hard contacts)	**V**	17
Electrical life			See page 3/12
Response time		**ms**	< 20
Rated insulation voltage (Ui)		**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 & 2)
Rated impulse withstand voltage (Uimp.)		**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-1, DIN VDE 0110 parts 1 & 2)
LED display			4
Operating temperature		**°F (°C)**	+ 14…+ 131 (- 10…+ 55)
Storage temperature		**°F (°C)**	- 13…+ 185 (- 25…+ 85)
Degree of protection conforming to IEC 60529	Terminals		IP 20
	Enclosure		IP 40
Polycarbonate enclosure	Type		Removable
	Number of terminals		42
Connection	Type		Captive screw clamp terminals: - - without cable end 2 x 14 AWG (2 x 2.5 mm^2), - - with cable end 2 x 16 AWG (2 x 1.5 mm^2), - - min. Ø 0.5 mm

References



XPSOT

Description	Display	Supply	Reference	Weight oz (kg)
Safety modules for safety stop with automatic overtravel monitoring and control	4 LEDs	∼ 115 V	**XPSOT3444**	38.801 (1.100)
		∼ 230 V	**XPSOT3744**	38.801 (1.100)

(1) Using an appropriate and correctly connected control system.
(2) The Category, the Performance Level (PL) or the Safety Integrity Level Claim Level (SILCL) are only achieved with the full connection to the base unit or start unit.

Principle: page 3/108 | Specifications: page 3/110 | References: page 3/110 | Wiring diagrams: page 3/111 | Dimensions: page 3/112

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules type XPSOT

For safety stop with automatic overtravel monitoring and control

XPSOT

Wiring diagram



(1) The 2 coils of the safety valve must be wired separately.

Functional diagram



LED details



1 Voltage present on terminals A1/A2.
2 Close instruction.
3 OTS limit switch activated.
4 UN limit switch activated.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Preventa™ safety relay modules

AM1 DP200 rail mounting

Dimensions

XPSAC●●●●, XPSAF●●●●, XPSAFL●●●●, XPSDMB●●●●, XPSVC●●●●, XPSEDA



XPSAC●●●●P, XPSABV●●●●P, XPSAXE●●●●P, XPSAF●●●P, XPSAFL●●●●P, XPSBCE●●●●P, XPSBF●●●●P, XPSECME●●●●P, XPSDMB●●●●P, XPSVC●●●●P



XPSABV●●●●C, XPSAXE●●●●C, XPSBCE●●●●C, XPSECME●●●●C



XPSAK●●●●, XPSAV●●●●, XPSCM●●●●, XPSDME●●●●, XPSATE●●●●, XPSECPE●●●●P



XPSAK●●●●P, XPSAV●●●●P, XPSCM●●●●P, XPSTSA●●●●P, XPSTSW●●●●P, XPSDME●●●●P, XPSATE●●●●P, XPSVNE●●●●P



XPSAK●●●●C, XPSAV●●●●C, XPSCM●●●●C, XPSTSA●●●●C, XPSTSW●●●●C, XPSDME●●●●C, XPSATE●●●●C, XPSVNE●●●●C



Dual Dimensions: INCHES
Millimieters

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Dimensions

XPSAR●●●●●●



XPSAR●●●●●●P



XPSPVT, XPSPVK

Common side view



XPSPVT



XPSPVK



XPSOT



Dual Dimensions: INCHES / Millimieters

Mounting

All safety modules: 1.38 in (35 mm) DIN rail mounting.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety solutions on AS-Interface™ cabling system

Safety monitors and interfaces

Applications	Safety monitors on AS-Interface cabling system		Safety interfaces on AS-Interface cabling system	
				
AS-Interface "Safety at work"	Safety is incorporated into the AS-Interface cabling system by adding a monitor and a safety interface connected together with other standard AS-Interface components on the AS-Interface line			
Functions	Safety applications integrated on the AS-Interface line Emergency stop, safety switches and light curtain monitoring		Emergency stop interfaces	
			Metal	Plastic
AS-Interface profile	7.F		0.B.F.F	0.B.F.F
Addressing	Using configuration software ASISWIN2		Using adjustment terminal ASI TERV2 and adaptor ASI SAD1	
Maximum achievable safety level	PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 61508		PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061	
Conformity to standards	EN 50295, EN/IEC 60204-1, EN/IEC 61496-1, EN 574/ISO 13851, EN/IEC 60947-1, EN/IEC 60947-5-1		EN 50295, EN/ISO 13850, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1	
Product certifications	UL, CSA, TÜV		UL, CSA, TÜV	
Number of safety circuits	2 N.O.	2 x 2 N.O.	–	
Number of additional circuits	1 solid-state output for signalling to PLC	2 solid-state outputs	–	
Display	5 LEDs	8 LEDs	2 LEDs	
Supply voltage	24 V ⎓		By AS-Interface line	
Type	**ASISAFEMON1●**	**ASISAFEMON2●**	**ASISSLB●**	
Pages	3/118		3/122	

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com







Interfaces for safety products			Interfaces premounted in Emergency stop mushroom head pushbutton stations XAL K	Interfaces for mounting in enclosure for Harmony® Ø 22 mm Emergency stop mushroom head pushbuttons
1 x M12 entry	2 x M12 entries	1 x ISO M16 entry	1 x M12 entry	Connector
0.B.F.F	0.B.F.F	0.B.F.F	0.B.F.F	
Using adjustment terminal ASI TERV2 and adaptor ASI SAD1			Using adjustment terminal ASI TERV2	
PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061	
EN 50295, EN/IEC 60204-1, EN 1088/ISO 14119, EN 574/ISO 13851, EN/IEC 61496-1, EN/IEC 60947-5-3, EN/IEC 60947-1, EN/IEC 60947-5-1			EN 50295, EN/ISO 13850, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1	
UL, CSA, TÜV			UL, CSA, TÜV	
–			–	
–			–	
2 LEDs			–	
By AS-Interface line			By AS-Interface line	
ASISSLC●		**ASISSLLS**	**ASISE●1C**	**ASISSLE●**
3/122			3/122	

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety solutions on AS-Interface™ cabling system

AS-Interface “Safety at work” monitors

Operating principle



AS-Interface, the recognized cabling system for sensors and actuators, has evolved. Standard process information and information relating to safety can now be transmitted over the same cable. Capable of managing safety functions up to Performance Level PL e/Category 4 conforming to standard EN/ISO 13849-1 and SILCL 3 conforming to standard EN/IEC 61508, the AS-Interface “Safety at work” system meets the needs of the most common safety applications, such as:

- monitoring of Emergency stops with instantaneous break contacts (stop category 0),
- monitoring of Emergency stops with delayed break contacts (stop category 1),
- monitoring of switches with and without interlocking,
- monitoring of light curtains, etc.

Parameters for options relative to the selected safety function (for example, start button monitoring) may be set for all pre-defined, certified functions.
Safety is incorporated into the AS-Interface cabling system by adding a safety monitor and safety interfaces connected together with other standard AS-Interface components on the yellow cable.
Safety information is exchanged only between the safety monitor, the AS-Interface line master and the safety interfaces. This is transparent for the other standard AS-Interface components.
Based on this principle, AS-Interface cabling systems that are already installed can be updated with safety functions without having to replace the existing components (masters, I/O interfaces, power supplies, etc.). Safety circuits are diagnosed readily, and with no additional wiring, by the standard AS-Interface cabling system master communicating with the safety monitor(s) via the yellow cable.

The AS-Interface “Safety at work” system is configured using software ASISWIN2 running on Windows®. A library of pre-defined and certified safety functions is made available by the software and the user can graphically select the desired safety functions, even at the last minute, by using the “Drag and drop” method in the configuration software. Knowledge of a programming language or specific tools is not necessary to parameter the system. The configuration is loaded into the safety monitor(s) by means of a PC by carrying out a secure serial transmission and using the parameter setting connector on the front cover of the monitor.

The AS-Interface “Safety and work” enhanced monitor is available with:

- 1 safety output with 2 contacts, or
- 2 independent safety outputs with 2 x 2 contacts.

In addition to safety outputs with relay hard contacts, AS-Interface “Safety at work” safety monitors are equipped, depending on the model, with one or two solid-state signalling outputs and LEDs on the front cover to indicate the status of the system and of the monitoring circuits. To monitor more safety functions simultaneously or to stop several safety circuits at different locations, an increased number of safety monitors can be used in an AS-Interface cabling system.
The safety interfaces are connected directly on the yellow cable via an insulation displacement connector (IDC). Their addressing is carried out using self-addressing via the AS-Interface cabling system master or manually, using addressing terminal ASISTERV2.
The compactness of the safety interfaces enables their direct attachment to control devices such as Emergency stop buttons or switches. In addition to interfaces that can be attached to products, versions with 1 or 2 M12 connectors are also available.

Principle: page 3/116 | Specifications: page 3/117 | References : page 3/118 | Dimensions: page 3/119

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety solutions on AS-Interface™ cabling system

AS-Interface “Safety at work” monitors

Monitoring functions

	AS-Interface “Safety at work” monitors For enhanced monitoring of safety devices ASISAFEMON1B, ASISAFEMON2B
Monitoring of safety devices	■ Emergency stops ■ Safety switches ■ Light curtains ■ Button for validation of linked devices ■ Conditionally dependent devices ■ Devices with bouncing contacts
Logic functions	■ “OR” (up to 6 devices) ■ “AND” ■ “FLIP FLOP” ■ On-delay ■ Off-delay ■ “PULSE” on positive edge
External devices monitoring (EDM)	■ Feedback loop ■ Feedback loop monitoring over the AS-Interface cabling system
Start devices	■ Automatic start ■ Start monitored by the AS-Interface cabling system slave ■ Start monitored by connection to monitor ■ Start monitored by the safety interface
Output devices	■ Stop category 1 ■ Stop category 0

Specifications

AS-Interface “Safety at work” monitor type			**ASISAFEMON1B** **ASISAFEMON2B**
Maximum achievable safety level			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)	**Years**	451
	Diagnostic Coverage (DC)	**%**	> 99
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	9×10^{-9}
Conformity to standards			EN 50295, EN/IEC 60204-1, EN/IEC 61496-1, EN 574/ISO 13851, EN/IEC 60947-1, EN/IEC 60947-5-1
Product certifications			UL, CSA, TÜV
AS-Interface profile			7.F
Power consumption on AS-Interface line		**mA**	44
Type of protection (suitable only for use in electronic rooms/ electrical enclosures with a minimum IP 54 degree of protection)			IP 20
Operating voltage Ub		**V**	⎓ 24 ± 15%
Rated operating current		**mA**	150: **ASISAFEMON1B** 200: **ASISAFEMON2B**
Response duration		**ms**	< 40
Pick-up delay		**s**	< 10
Inputs	“Start”		Opto-electronic coupler input (active when High), input current approximately 10 mA at ⎓ 24 V
	“Protection control (EDM)”		Opto-electronic coupler input (active when High), input current approximately 10 mA at ⎓ 24 V
Outputs	“Safety on” indication		PNP transistor output, 200 mA
	Safety		Relay hard contacts N.O. contacts, max. contact load
Fuse protection			External, with max. of 4 A MT
Operating temperature		**°F (°C)**	- 4…+ 140 (- 20…+ 60)
Storage temperature		**°F (°C)**	- 22…+ 158 (- 30…+ 70)
Enclosure	Material		Polyamide PA66
	Mounting		Clip-on mounting on DIN rail conforming to EN 50022

(1) Using an appropriate and correctly connected control system.

Note: The impedance of a safety monitor must be taken into account when selecting the number of interfaces on the AS-Interface cabling system, even if it is used in “watchdog” mode.

Principle: page 3/116 | Specifications: page 3/117 | References : page 3/118 | Dimensions: page 3/119

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety solutions on AS-Interface™ cabling system

AS-Interface “Safety at work” monitors

References

AS-Interface “Safety at work” monitors

Type	Number of safety circuits	Solid-state outputs for PLC	Supply	Reference	Weight oz (kg)
For enhanced monitoring of safety devices	2 N.O.	1	⎓ 24 V	**ASISAFEMON1B**	12.346 (0.350)
	2 x 2 N.O.	2	⎓ 24 V	**ASISAFEMON2B**	15.874 (0.450)

Configuration software

Description	For use with	Operating system	Languages	Reference	Weight oz (kg)
AS-Interface “Safety at work” configuration software CD-ROM + user manual	Safety monitors ASISAFEMON●B for enhanced monitoring of safety devices	Windows® 95, Windows® 98, Windows® ME, Windows® NT, Windows® 2000, Windows® XP	EN, FR, DE, IT, ES, PT	**ASISWIN2**	18.342 (0.520)

ASITERV2

Setting-up and diagnostic tools

Description	Application	Reference	
Adjustment terminal	Addressing and diagnostics of AS-Interface V2.1 interfaces AS-Interface I/O test while powered-up AS-Interface interface diagnostics	**ASITERV2**	17.637 (0.500)
AS-Interface line analyzer	Identification of transmission errors on the AS-Interface line	**ASISA01**	5.644 (0.160)

ASISA01

Accessories

Description	Function	Reference	Weight oz (kg)
Cables	For configuring AS-Interface “Safety at work” monitors, RS 232	**ASISCPC**	3.527 (0.100)
	Transfer between 2 monitors	**ASISCM**	17.637 (0.500)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Dimensions

ASISAFEMON●, ASISAFEMON●B



Dual Dimensions: INCHES / Millimieters

LED details



ASISAFEMON1B

1 AS-Interface line supply (green)
2 AS-Interface line fault (red)
3 Restart signal (yellow)
4 Safety outputs closed (green)
5 Safety outputs open (red) or output error (flashing red)

ASISAFEMON2B

Output 1

1 AS-Interface line supply (green)
2 AS-Interface line fault (red)
3 Restart signal (yellow)
4 Safety outputs closed (green)
5 Safety outputs open (red) or output error (flashing red)

Output 2

6 AS-Interface line supply (green)
7 AS-Interface line fault (red)
8 Restart signal (yellow)
9 Safety outputs closed (green)
10 Safety outputs open (red) or output error (flashing red)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety solutions on AS-Interface™ cabling system

Safety interfaces

Operating principle

Safety is incorporated into the AS-Interface cabling system by adding a safety monitor and safety interfaces connected together with other standard AS-Interface components on the yellow cable.

Safety information is exchanged only between the safety monitor, the AS-Interface line master and the safety interfaces. This is transparent for the other standard AS-Interface components. Based on this principle, AS-Interface cabling systems that are already installed can be updated with safety functions without having to replace the existing components (master, I/O interfaces, power supplies, etc.).

Safety circuits are diagnosed readily, and with no additional wiring, by the standard AS-Interface cabling system master communicating with the safety monitor via the yellow cable.

Introduction

Interfaces for Harmony™ Ø 22 mm Emergency stop



Metal



Plastic

Interfaces for products with M12 connector



1 x M12 entry



2 x M12 entries

Interfaces for products with ISO entry



ISO M16 or M20 entry

Interfaces pre-mounted in Emergency stop mushroom head push button stations XAL K, with M12 entry



“Turn to release”



Key release (n° 455)

Interfaces for mounting in enclosure for Harmony™ Ø 22 mm Emergency stop mushroom head push buttons



Metal



Plastic

Principle: page 3/120 | Specifications: page 3/121 | References : page 3/122 | Dimensions: page 3/123 | Wiring diagrams: page 3/123

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety solutions on AS-Interface™ cabling system

Safety interfaces

Safety interface type			ASI SSLB4	ASI SSLB5	ASI SSLC1	ASI SSLC2	ASI SSLLS	ASI SEA1C	ASI SEK1C	ASI SSLE4	ASI SSLE5
Environment											
Maximum achievable safety level			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061								
Reliability data (1)	Mean Time To dangerous Failure ($MTTF_d$)	**Years**	103								
	Diagnostic Coverage (DC)	**%**	> 99								
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	1.82×10^{-8}								
Conformity to standards			EN 50295, EN/ISO 13850, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1		EN 50295, EN/IEC 60204-1, EN 1088/ISO 14119, EN 574/ISO 13851, EN/IEC 61496-1, EN/IEC 60947-5-3, EN/IEC 60947-1, EN/IEC 60947-5-1			EN 50295, EN/ISO 13850, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1			
Product certifications			UL, CSA, TÜV					UL, CSA , TÜV			
Degree of protection	Conforming to IEC 529		IP 20		IP 67			IP 65		IP 00	
AS-Interface profile			0.B.F.F								
Addressing			Using adjustment terminal ASITERV2								
Ambient air temperature	For operation	**°F (°C)**	+ 14…+ 131 (- 10…+ 55)								
	For storage	**°F (°C)**	- 13…+ 185 (- 25…+ 85)								
Mechanical specifications											
Mechanical life*	In thousands of operating cycles		0.3		–		–	0.3		–	
Shock resistance			10 gn								
Vibration resistance			5 gn								
Electrical specifications											
Supply by AS-Interface line	Voltage	**V**	Via AS-Interface, ⎓ 24								
	Voltage limits		- 15…+ 15%								
Power consumption		**W**	1.2								
Power consumption on AS-Interface line		**mA**	45								
Connection on AS-Interface line	IDC (Insulation Displacement Connector)		■		–		■	–		–	
	Connector (type)		–		■ (M12)		–	■ (M12)		■	

(1) Using an appropriate and correctly connected control system.

***Mechanical Life**

The product life expressed is based on average usage and normal operating conditions. The above statements are not intended to nor shall they create any express or implied warranties as to product operation or life. For information on the limited warranty offered on this product please refer to the Square D terms and conditions of sale found in the "Square D by Schneider Electric" *Digest*.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety solutions on AS-Interface™ cabling system

Safety interfaces

ASISSLB4 + ZB4BS844

ASISSLB5 + ZB5AS844

ASISSLC1

ASISSLC2

ASISSLLS

ASISEA1C

ASISSLE4

ASISSLE5

ASISAD1

References

Interfaces for Ø 22 Emergency stop

Type	Type of contact	Connection on AS-Interface line	Reference	Weight oz (kg)
Metal	N.C. + N.C.	IDC	**ASISSLB4**	2.822 (0.080)
Plastic	N.C. + N.C.	IDC	**ASISSLB5**	1.411 (0.040)

Interfaces for products with connector

Type	Number of contacts	Connection on AS-Interface line	Reference	Weight oz (kg)
1 x M12 entry *(1)*	2	Connector	**ASISSLC1**	1.411 (0.040)
2 x M12 entries *(1) (2)*	2	Connector	**ASISSLC2**	1.764 (0.050)

Interfaces for products with ISO entry

Type	Number of contacts	Connection on AS-Interface line	Reference	Weight oz (kg)
1 x ISO M16 entry *(1) (3)*	2	IDC	**ASISSLLS**	1.411 (0.040)

Interfaces pre-mounted in Emergency stop mushroom head push button stations XAL K

Type	Number of contacts	Connection on AS-Interface line	Reference	Weight oz (kg)
"Turn to release"	2	Connector	**ASISEA1C**	5.997 (0.170)
Key release (n° 455)	2	Connector	**ASISEK1C**	6.702 (0.190)

Interfaces for mounting in enclosure for Harmony™ Ø 22 mm Emergency stop mushroom head push buttons

Type	Number of contacts	Connection on AS-Interface line	Reference	Weight oz (kg)
Metal	2	Connector	**ASISSLE4**	2.116 (0.060)
Plastic	2	Connector	**ASISSLE5**	0.882 (0.025)

Addressing accessories

Description	Application	Reference	
Adaptor specifically for safety interfaces type ASISSLB●, ASISSLC●, ASISSLLS	Connection to adjustment terminal ASITERV2	**ASISAD1**	2.116 (0.060)

Setting-up and diagnostic tools

Description	Application	Reference	
Adjustment terminal	Addressing and diagnostics of AS-Interface V2.1 interfaces AS-Interface I/O test while powered-up AS-Interface interface diagnostics	**ASITERV2**	17.637 (0.500)
AS-Interface line analyzer	Identification of transmission errors on the AS-Interface line	**ASISA01**	5.644 (0.160)

Accessories

Type	Material	Unit reference	Weight oz (kg)
Adaptor for ISO M20 (sold in lots of 5)	Metal	**DE9RI2016**	1.411 (0.040)
Ø 40 red mushroom head Emergency stop buttons, turn to release *(4)*	Metal	**ZB4BS844**	2.116 (0.060)
	Plastic	**ZB5AS844**	1.764 (0.050)
Ø 40 red mushroom head Emergency stop buttons, key release (n° 455) *(4)*	Metal	**ZB4BS944**	3.457 (0.098)
	Plastic	**ZB5AS944**	2.504 (0.071)

*(1) To be used with yellow AS-Interface "standard" version cable **XZCB●●●●●**.*
*The yellow AS-Interface "TPE" version cable **XZCB●●●●●H** cannot be used with the safety interfaces **ASISSLC●** and **ASISSLLS**.*

*(2) Only use pre-wired connectors **XZCP1541L●**, refer to our Sensors catalog 9007CT1007R06/12.*

(3) For ISO M20 product, see adaptor DE9R12016.

Principle: page 3/120 | Specifications: page 3/121 | References : page 3/122 | Dimensions: page 3/123 | Wiring diagrams: page 3/123

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Dimensions

ASISSLB4



ASISSLB5



ASISSLC1



ASISSLC2



ASISSLLS





ASISAD1





ASISE•1C







Dual Dimensions: INCHES / Millimeters

ASISSLE4





ASISSLE5





Connections

ASISSLC1



ASISSLC2



ASISSLLS



ASISE•1C



ASISSLE•



Principle: page 3/120
Specifications: page 3/121
References : page 3/122
Dimensions: page 3/123
Wiring diagrams: page 3/123

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety reliability values

according to standard EN/ISO 13849-1
and EN/IEC 62061

	EN/ISO 13849-1					
	Category for the device internal		**$MTTF_d$ (mean time to dangerous failure.** *in years*)		**PL (Performance Level): up to...**	
	Device + outputs in Stop category 0	Device + outputs in Stop category 1	Single channel with output in Stop category 0	Single channel with output in Stop category 1	Device + outputs in Stop category 0	Device + outputs in Stop category 1
Preventa safety Modules						
XPSABV1133P	4	3	53	53	e	d
XPSABV11330P	4	3	53	53	e	d
XPSABV1133C	4	3	53	53	e	d
XPSABV11330C	4	3	53	53	e	d
XPSAC3421P	4	–	210.4	–	e	–
XPSAC3721P	4	–	210.4	–	e	–
XPSAC5121P	4	–	210.4	–	e	–
XPSAC3721	4	–	210.4	–	e	–
XPSAC1321	4	–	210.4	–	e	–
XPSAC5121	4	–	210.4	–	e	–
XPSAC3421	4	–	210.4	–	e	–
XPSAC1321P	4	–	210.4	–	e	–
XPSAF5130	4	–	243.0	–	e	–
XPSAF5130P	4	–	243.0	–	e	–
XPSAFL5130P	4	–	172.1	–	e	–
XPSAFL5130	4	–	172.1	–	e	–
XPSAK371144P	4	–	154.5	–	e	–
XPSAK351144P	4	–	154.5	–	e	–
XPSAK371144	4	–	154.5	–	e	–
XPSAK351144	4	–	154.5	–	e	–
XPSAK361144	4	–	154.5	–	e	–
XPSAK311144	4	–	154.5	–	e	–
XPSAK311144P	4	–	154.5	–	e	–
XPSAK361144P	4	–	154.5	–	e	–
XPSAR351144	4	–	277.8	–	e	–
XPSAR371144	4	–	277.8	–	e	–
XPSAR311144	4	–	277.8	–	e	–
XPSAR351144P	4	–	277.8	–	e	–
XPSAR371144P	4	–	277.8	–	e	–
XPSAR311144P	4	–	277.8	–	e	–
XPSAT5110	4	3	139.7	54.0	e	d
XPSAT3410	4	3	139.7	54.0	e	d
XPSAT3710	4	3	139.7	54.0	e	d
XPSAT5110T100	4	3	139.7	54.0	e	d
XPSATE5110	4	3	134.8	54.5	e	d
XPSATE5110P	4	3	134.8	54.5	e	d
XPSATE3410	4	3	134.8	54.5	e	d
XPSATE3410P	4	3	134.8	54.5	e	d
XPSATE3710	4	3	134.8	54.5	e	d
XPSATE3710P	4	3	134.8	54.5	e	d
XPSAV11113P	4	4	75.8	75.8	e	e
XPSAV11113T050	4	4	75.8	75.8	e	e
XPSAV11113	4	4	75.8	75.8	e	e
XPSAX5120	4	–	222.2	–	e	–
XPSAXE5120P	4	–	457.0	–	e	–
XPSAXE5120C	4	–	457.0	–	e	–
XPSBAE5120P	1	–	55	–	c	–
XPSBAE3920P	1	–	55	–	c	–
XPSBAE5120C	1	–	55	–	c	–
XPSBAE3920C	1	–	55	–	c	–
XPSBC1110	4	–	63.9	–	e	–
XPSBC3110	4	–	63.9	–	e	–
XPSBC3410	4	–	63.9	–	e	–
XPSBC3710	4	–	63.9	–	e	–
XPSBCE3110P	4	–	37.0	–	e	–
XPSBCE3110C	4	–	37.0	–	e	–
XPSBCE3410P	4	–	37.0	–	e	–
XPSBCE3410C	4	–	37.0	–	e	–
XPSBCE3710P	4	–	37.0	–	e	–
XPSBCE3710C	4	–	37.0	–	e	–
XPSBF1132	4	–	50.1	–	e	–
XPSBF1132P	4	–	50.1	–	e	–

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

EN/IEC 62061 (EN/IEC 61508)						
DC (diagnostic capability) for the device internal		**PFH_d (Dangerous Failure per Hour)**		**SILCL (Safety Integrity Level Claim Level)**		**HFT (Hardware Fault Tolerance)**
Device + outputs in Stop category 0	Device + outputs in Stop category 1	Device + outputs in Stop category 0	Device + outputs in Stop category 1	Device + outputs in Stop category 0	Device + outputs in Stop category 1	
> 99 %	60…90 %	3.00×10^{-8}	2.00×10^{-7}	3	2	1
> 99 %	60…90 %	3.00×10^{-8}	2.00×10^{-7}	3	2	1
> 99 %	60…90 %	3.00×10^{-8}	2.00×10^{-7}	3	2	1
> 99 %	60…90 %	3.00×10^{-8}	2.00×10^{-7}	3	2	1
> 99 %	–	3.56×10^{-9}	–	3	–	1
> 99 %	–	3.56×10^{-9}	–	3	–	1
> 99 %	–	3.56×10^{-9}	–	3	–	1
> 99 %	–	3.56×10^{-9}	–	3	–	1
> 99 %	–	3.56×10^{-9}	–	3	–	1
> 99 %	–	3.56×10^{-9}	–	3	–	1
> 99 %	–	3.56×10^{-9}	–	3	–	1
> 99 %	–	3.56×10^{-9}	–	3	–	1
> 99 %	–	4.62×10^{-9}	–	3	–	1
> 99 %	–	4.62×10^{-9}	–	3	–	1
> 99 %	–	5.61×10^{-9}	–	3	–	1
> 99 %	–	5.61×10^{-9}	–	3	–	1
> 99 %	–	7.39×10^{-9}	–	3	–	1
> 99 %	–	7.39×10^{-9}	–	3	–	1
> 99 %	–	7.39×10^{-9}	–	3	–	1
> 99 %	–	7.39×10^{-9}	–	3	–	1
> 99 %	–	7.39×10^{-9}	–	3	–	1
> 99 %	–	7.39×10^{-9}	–	3	–	1
> 99 %	–	7.39×10^{-9}	–	3	–	1
> 99 %	–	7.39×10^{-9}	–	3	–	1
> 99 %	–	2.22×10^{-9}	–	3	–	1
> 99 %	–	2.22×10^{-9}	–	3	–	1
> 99 %	–	2.22×10^{-9}	–	3	–	1
> 99 %	–	2.22×10^{-9}	–	3	–	1
> 99 %	–	2.22×10^{-9}	–	3	–	1
> 99 %	–	2.22×10^{-9}	–	3	–	1
> 99 %	96.9 %	6.84×10^{-9}	2.05×10^{-8}	3	2	1
> 99 %	96.9 %	6.84×10^{-9}	2.05×10^{-8}	3	2	1
> 99 %	96.9 %	6.84×10^{-9}	2.05×10^{-8}	3	2	1
> 99 %	96.9 %	6.84×10^{-9}	2.05×10^{-8}	3	2	1
> 99 %	98.4 %	6.81×10^{-9}	1.96×10^{-8}	3	2	1
> 99 %	98.4 %	6.81×10^{-9}	1.96×10^{-8}	3	2	1
> 99 %	98.4 %	6.81×10^{-9}	1.96×10^{-8}	3	2	1
> 99 %	98.4 %	6.81×10^{-9}	1.96×10^{-8}	3	2	1
> 99 %	98.4 %	6.81×10^{-9}	1.96×10^{-8}	3	2	1
> 99 %	98.4 %	6.81×10^{-9}	1.96×10^{-8}	3	2	1
> 99 %	> 99 %	7.95×10^{-9}	7.95×10^{-9}	3	3	1
> 99 %	> 99 %	7.95×10^{-9}	7.95×10^{-9}	3	3	1
> 99 %	> 99 %	7.95×10^{-9}	7.95×10^{-9}	3	3	1
> 99 %	–	1.90×10^{-9}	–	3	–	1
> 99 %	–	3.00×10^{-8}	–	3	–	1
> 99 %	–	3.00×10^{-8}	–	3	–	1
–	–	2.1×10^{-6}	–	1	–	0
–	–	2.1×10^{-6}	–	1	–	0
–	–	2.1×10^{-6}	–	1	–	0
–	–	2.1×10^{-6}	–	1	–	0
> 99 %	–	1.75×10^{-8}	–	3	–	1
> 99 %	–	1.75×10^{-8}	–	3	–	1
> 99 %	–	1.75×10^{-8}	–	3	–	1
> 99 %	–	1.75×10^{-8}	–	3	–	1
> 99 %	–	3.00×10^{-8}	–	3	–	1
> 99 %	–	3.00×10^{-8}	–	3	–	1
> 99 %	–	3.00×10^{-8}	–	3	–	1
> 99 %	–	3.00×10^{-8}	–	3	–	1
> 99 %	–	3.00×10^{-8}	–	3	–	1
> 99 %	–	3.00×10^{-8}	–	3	–	1
> 99 %	–	1.30×10^{-8}	–	3	–	1
> 99 %	–	1.30×10^{-8}	–	3	–	1

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety relays

Safety reliability values

according to standard EN/ISO 13849-1
and EN/IEC 62061

	EN/ISO 13849-1					
	Category for the device internal		**$MTTF_d$ (mean time to dangerous failure** *in years*)		**PL (Performance Level): up to...**	
	Device + outputs in Stop category 0	Device + outputs in Stop category 1	Single channel with output in Stop category 0	Single channel with output in Stop category 1	Device + outputs in Stop category 0	Device + outputs in Stop category 1
Preventa safety Modules (continued)						
XPSCM1144P	2	–	16.6	–	c	–
XPSCM1144	2	–	16.6	–	c	–
XPSDMB1132P	4	–	83.1	–	e	–
XPSDMB1132	4	–	83.1	–	e	–
XPSDME1132TS220	4	–	82.4	–	e	–
XPSDME1132	4	–	82.4	–	e	–
XPSDME1132P	4	–	82.4	–	e	–
XPSECM3431	4 *(1)*	–	346.2	–	e *(1)*	–
XPSECM5131	4 *(1)*	–	346.2	–	e *(1)*	–
XPSECM3731	4 *(1)*	–	346.2	–	e *(1)*	–
XPSECME5131P	4 *(1)*	–	45	–	e *(1)*	–
XPSECME5131C	4 *(1)*	–	45	–	e *(1)*	–
XPSECP5131	4 *(1)*	–	346.2	–	e *(1)*	–
XPSECP3431	4 *(1)*	–	346.2	–	e *(1)*	–
XPSECP3731	4 *(1)*	–	346.2	–	e *(1)*	–
XPSECPE5131P	4 *(1)*	–	30	–	e *(1)*	–
XPSECPE5131C	4 *(1)*	–	30	–	e *(1)*	–
XPSECPE3910P	4 *(1)*	–	30	–	e *(1)*	–
XPSECPE3910C	4 *(1)*	–	30	–	e *(1)*	–
XPSFB3411	4	–	55.8	–	e	–
XPSFB3711	4	–	55.8	–	e	–
XPSFB5111	4	–	55.8	–	e	–
XPSFB5311	4	–	55.8	–	e	–
XPSTSA3442P	3	–	126	–	d	–
XPSTSA3742P	3	–	126	–	d	–
XPSTSA5142P	3	–	126	–	d	–
XPSTSW3742P	3	–	126	–	d	–
XPSTSW3442P	3	–	126	–	d	–
XPSTSW5142P	3	–	126	–	d	–
XPSVC1132	4	–	50.0	–	e	–
XPSVC1132P	4	–	50.0	–	e	–
XPSVNE1142P	3	–	124.1	–	d	–
XPSVNE1142HSP	3	–	124.1	–	d	–
XPSVNE1142LFP	3	–	124.1	–	d	–
XPSVNE3442P	3	–	124.1	–	d	–
XPSVNE3442HSP	3	–	124.1	–	d	–
XPSVNE3442LFP	3	–	124.1	–	d	–
XPSVNE3742P	3	–	124.1	–	d	–
XPSVNE3742HSP	3	–	124.1	–	d	–
Preventa safety controllers						
XPSMP11123P	4	–	75.8	–	e	–
XPSMP11123	4	–	75.8	–	e	–
XPSMC••Z• (transistor outputs)	4	4	76.6	76.6	e	e
XPSMC••Z•(Relay outputs)	4	4	71.0	71.0	e	e
Safety monitors and interfaces on AS-Interface cabling system						
ASISAFEMON1	4	4	451	451	e	e
ASISAFEMON1B	4	4	451	451	e	e
ASISAFEMON2	4	4	451	451	e	e
ASISAFEMON2B	4	4	451	451	e	e
ASISSLB5	4	4	103.4	103.4	e	e
ASISSLB4	4	4	103.4	103.4	e	e
ASISSLC1	4	4	103.6	103.6	e	e
ASISSLC2	4	4	103.6	103.6	e	e
ASISSLLS	4	4	103.6	103.6	e	e
ASISEA1C	4	4	103.9	103.9	e	e
ASISEK1C	4	4	103.9	103.9	e	e
ASISSLE4	4	4	103.9	103.9	e	e
ASISSLE5	4	4	103.9	103.9	e	e

(1) The Category, the Performance Level (PL) or the Safety Integrity Level Claim Level (SILCL) are only achieved with the full connection to the base unit or start unit.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

EN/IEC 62061 (EN/IEC 61508)						
DC (diagnostic capability) for the device internal		**PFH_d (Dangerous Failure per Hour)**		**SILCL (Safety Integrity Level Claim Level)**		**HFT (Hardware Fault Tolerance)**
Device + outputs in Stop category 0	Device + outputs in Stop category 1	Device + outputs in Stop category 0	Device + outputs in Stop category 1	Device + outputs in Stop category 0	Device + outputs in Stop category 1	
95.5 %	–	3.12×10^{-7}	–	1	–	1
95.5 %	–	3.12×10^{-7}	–	1	–	1
> 99 %	–	3.92×10^{-9}	–	3	–	1
> 99 %	–	3.92×10^{-9}	–	3	–	1
> 99 %	–	3.97×10^{-9}	–	3	–	1
> 99 %	–	3.97×10^{-9}	–	3	–	1
> 99 %	–	3.97×10^{-9}	–	3	–	1
0…99 % *(1)*	–	7.51×10^{-9}	–	3 *(1)*	–	1
0…99 % *(1)*	–	7.51×10^{-9}	–	3 *(1)*	–	1
0…99 % *(1)*	–	7.51×10^{-9}	–	3 *(1)*	–	1
60…90 %	–	2.00×10^{-7}	–	3 *(1)*	–	1
60…90 %	–	2.00×10^{-7}	–	3 *(1)*	–	1
0…99 % *(1)*	–	7.51×10^{-9}	–	3 *(1)*	–	1
0…99 % *(1)*	–	7.51×10^{-9}	–	3 *(1)*	–	1
0…99 % *(1)*	–	7.51×10^{-9}	–	3 *(1)*	–	1
0…99 % *(1)*	–	3.00×10^{-9}	–	3 *(1)*	–	1
0…99 % *(1)*	–	3.00×10^{-9}	–	3 *(1)*	–	1
0…99 % *(1)*	–	3.00×10^{-9}	–	3 *(1)*	–	1
0…99 % *(1)*	–	3.00×10^{-9}	–	3 *(1)*	–	1
> 99 %	–	1.13×10^{-8}	–	3	–	1
> 99 %	–	1.13×10^{-8}	–	3	–	1
> 99 %	–	1.13×10^{-8}	–	3	–	1
> 99 %	–	1.13×10^{-8}	–	3	–	1
60…90 %	–	1.30×10^{-7}	–	2	–	1
60…90 %	–	1.30×10^{-7}	–	2	–	1
60…90 %	–	1.30×10^{-7}	–	2	–	1
60…90 %	–	1.30×10^{-7}	–	2	–	1
60…90 %	–	1.30×10^{-7}	–	2	–	1
60…90 %	–	1.30×10^{-7}	–	2	–	1
> 99 %	–	1.30×10^{-8}	–	3	–	1
> 99 %	–	1.30×10^{-8}	–	3	–	1
> 99 %	–	9.26×10^{-9}	–	2	–	1
> 99 %	–	9.26×10^{-9}	–	2	–	1
> 99 %	–	9.26×10^{-9}	–	2	–	1
> 99 %	–	9.26×10^{-9}	–	2	–	1
> 99 %	–	9.26×10^{-9}	–	2	–	1
> 99 %	–	9.26×10^{-9}	–	2	–	1
> 99 %	–	9.26×10^{-9}	–	2	–	1
> 99 %	–	7.95×10^{-9}	–	3	–	1
> 99 %	–	7.95×10^{-9}	–	3	–	1
> 99 %	> 99 %	1.29×10^{-8}	1.29×10^{-8}	3	3	1
> 99 %	> 99 %	1.40×10^{-8}	1.40×10^{-8}	3	3	1
> 99 %	> 99 %	9.00×10^{-9}	9.00×10^{-9}	3	3	1
> 99 %	> 99 %	9.00×10^{-9}	9.00×10^{-9}	3	3	1
> 99 %	> 99 %	9.00×10^{-9}	9.00×10^{-9}	3	3	1
> 99 %	> 99 %	9.00×10^{-9}	9.00×10^{-9}	3	3	1
> 99 %	> 99 %	1.82×10^{-8}	1.82×10^{-8}	3	3	1
> 99 %	> 99 %	1.82×10^{-8}	1.82×10^{-8}	3	3	1
> 99 %	> 99 %	1.82×10^{-8}	1.82×10^{-8}	3	3	1
> 99 %	> 99 %	1.82×10^{-8}	1.82×10^{-8}	3	3	1
> 99 %	> 99 %	1.82×10^{-8}	1.82×10^{-8}	3	3	1
> 99 %	> 99 %	1.82×10^{-8}	1.82×10^{-8}	3	3	1
> 99 %	> 99 %	1.82×10^{-8}	1.82×10^{-8}	3	3	1
> 99 %	> 99 %	1.82×10^{-8}	1.82×10^{-8}	3	3	1
> 99 %	> 99 %	1.82×10^{-8}	1.82×10^{-8}	3	3	1

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Selection guide: Preventa™ XCS safety switches 4/2

Overview 4/10

Safety limit switches

Miniature design
- Type XCSM (Metal) 4/26

Compact design
- Type XCSD (Metal) 4/30
- Type XCSP (Plastic) 4/30

Safety interlock switches

With lever or rotary shaft operator, double insulated, turret head
- Types XCSPL, XCSTL, XCSPR, XCSTR (Plastic) 4/36

Actuator operated
- Types XCSMP, XCSPA, XCSTA (Plastic, double insulated, turret head) 4/40
- Types XCSA, XCSB, XCSC (Metal, turret head) 4/40

Actuator operated with solenoid interlocking, turret head
- Type XCSLF (Metal) 4/54
- Type XCSLE (Plastic, double insulated) 4/54

Actuator operated with solenoid interlocking
- Type XCSE (Metal, turret head) 4/66
- Type XCSTE (Plastic, double insulated) 4/66

Coded magnetic switches
- Types XCSDMC, XCSDMP, XCSDMR (Plastic) 4/80

Coded magnetic system
- Types XCSDM3, XCSDM4 . . . . . 4/92

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Preventa™ XCS safety switches

4

Switch type		Preventa XCS safety limit switches		
Applications		**Protection of operators by stopping the machine when the gate is opened All machines with quick rundown time.**		
Design		**Miniature format**	**Compact format**	
		Metal, pre-cabled	**Plastic or metal, with 1 cable entry**	
Enclosure		Metal	Plastic	Metal
Features		Pre-wired with cable	–	
Conformity to standards	Products	EN/IEC 60947-5-1, EN/ISO 13849-1, EN/IEC 62061, UL 508, CSA C22-2 n° 14		
	Machine assemblies	EN/IEC 60204-1, EN/ISO 14119		
Product certifications		UL, CSA		
Dimensions (w x h x d) in. (mm)	Switch	1.18 x 1.97 x0.62 (30 x 50 x 16)	1.22 x 1.34 x 3.5 (31 x 34 x 89)	
	Mounting	Centers: 0.79 (20)	Centers: 0.79/0.87 (20/22)	
Head		Plunger or rotary head Head adjustable in 15° steps throughout 360° Linear (plunger) or rotary (lever) actuation.		
Contact blocks		N.C. contacts with positive opening operation		
		2 N.C. + 1 N.O. break before make, slow break 2 N.C. + 1 N.O. and 2 N.C. + 2 N.O. snap action	2 N.C. + 1 N.O. break before make, slow break or snap action	
Degree of protection		IP 66, IP 67 and IP 68	IP 66 and IP 67	
Ambient air temperature	For operation	-13 … +158° F (-25 … +70° C)		
Connection	Screw terminals (cable entry via cable gland)	–	Tapped entry for Pg 13.5, ISO M20 cable gland or tapped 1/2" NPT	
	Pre-cabled	L = 3.3, 6.6, or 16.4 ft. (1, 2, or 5 m)	–	
Type reference		**XCSM**	**XCSP**	**XCSD**
Pages		4/28	4/34	4/32

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Preventa XCS lever or spindle operated switches

Protection of operators by stopping the machine when the operating lever (attached to hinged machine guard) is displaced by 5°. All light industrial machines fitted with hinged or rotary protective covers with small opening radius.		**Protection of operators by stopping the machine when the guard hinge rotates through 5°. All light industrial machines fitted with hinged access doors.**	
Compact format			
Plastic with 1 or 2 cable entries			
Plastic, double insulated			
2 types of lever: straight or elbowed (flush with rear of switch) 3 lever positions: to left, centerd or to right		2 types of spindle: length 1.18 or 3.15 in. (30 or 80 mm)	
EN/IEC 60947-5-1, EN/ISO 13849-1, EN/IEC 62061, UL 508, CSA C22-2 n°14, JIS C4520			
EN/IEC 60204-1, EN/ISO 14119			
UL, CSA, BG			
1.18 x 3.45 x 1.18 (30 x 87.5 x 30)	2.05 x 4.27 x 1.18 (52 x 108.4 x 30)	1.18 x 3.78 x 1.18 (30 x 96 x 30)	2.05 x 4.61 x 1.18 (52 x 117 x 30)
Centers: 0.79 x 0.87 (20 x 22)	Centers: 0.79 x 0.87 or 1.59 (20 x 22 or 40.3)	Centers: 0.79 x 0.87 (20 x 22)	Centers: 0.79 x 0.87 x 1.59 (20 x 22 or 40.3)
Turret head: 4 positions Rotary actuation (lever)		Turret head: 4 positions Rotary actuation (spindle)	
Slow break safety contacts with positive opening operation N.C. contacts open when lever or spindle displaced by more then 5°			
1 N.C. + 1 N.O. break before make 2 N.C.	1 N.C. + 2 N.O. break before make 2 N.C. + 1 N.O. break before make 3 N.C.	1 N.C. + 1 N.O. break before make 2 N.C.	1 N.C. + 2 N.O. break before make 2 N.C. + 1 N.O. break before make 3 N.C.
IP 67			
-13 … +158° F (-25 … +70° C)			
1 tapped entry for Pg 11, ISO M16 cable gland or tapped 1/2" NPT	2 tapped entries for Pg 11, ISO M16 cable gland or tapped 1/2" NPT	1 tapped entry for Pg 11, ISO M16 cable gland or tapped 1/2" NPT	2 tapped entries for Pg 11, ISO M16 cable gland or tapped 1/2" NPT
–	–	–	–
XCSPL	**XCSTL**	**XCSPR**	**XCSTR**
4/38			

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Preventa™ XCS safety switches

4

Switch type		**Preventa XCS key operated switches**		
Applications		**Protection of operators by stopping the machine when the actuator (attached to machine guard) is withdrawn from the head of the switch. All light industrial machines, with quick rundown time** *(1)*.		
Design		**Miniature format**	**Compact format**	
		Plastic, pre-cabled	**Plastic with 1 or 2 cable entries**	
Enclosure		Plastic		
Features		Without locking of actuator.	Without locking of actuator. Optional accessory: guard retaining device.	
Conformity to standards	Products	EN/IEC 60947-5-1, EN/ISO 13849-1, EN/IEC 62061, UL 508, CSA C22-2 n° 14 and JIS C4520		
	Machine assemblies	EN/IEC 60204-1, EN/ISO 14119		
Product certifications		cULus, BG	UL, CSA	
Dimensions (w x h x d) in. (mm)	Switch	1.18 x 3.4 x 0.6 (30 x 87 x 15)	1.18 x 3.68 x 1.18 (30 x 93.5 x 30)	2.05 x 4.51 x 1.18 (52 x 114.5 x 30)
	Mounting	Centers: 0.79 x 0.87 (20 x 22)	Centers: 0.79 x 0.87 (20 x 22)	Centers: 0.79 x 0.87 or 1.59 (20 x 22 or 40.3)
Head		Fixed head: 2 positions for insertion of actuator.	Turret head: 8 positions for insertion of actuator.	
Contact blocks		Safety contacts actuated by the actuator. Slow break and positive opening operation.		
		1 N.C. + 1 N.O. break before make 2 N.C. 2 N.C. + 1 N.O. break before make 3 N.C.	1 N.C. + 1 N.O. slow break contacts, break before make or make before break, or snap action 2 N.C. slow break or snap action	1 N.C. + 2 N.O. break before make 2 N.C. + 1 N.O. break before make 3 N.C.
Degree of protection		IP 67		
Ambient air temperature	For operation	-13 … +158° F (-25 … +70° C)		
Connection	Screw terminals (cable entry via cable gland)	–	Tapped entry for Pg 11, ISO M16 cable gland or tapped 1/2" NPT	
	Pre-cabled	L = 6.6, 16.4, or 32.8 ft. (2, 5, or 10 m)	–	–
Type reference		**XCSMP**	**XCSPA**	**XCSTA**
Pages		4/42	4/46	

(1) Stopping time of machine less than time taken for operator to access hazardous zone.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Preventa XCS key operated switches	
All heavy industrial machines, with quick rundown time *(1)*	
Industrial format with or without locking	
Metal with 1 cable entry, without locking	**Metal with 1 cable entry, with manual locking/unlocking**
Metal	
Without locking of actuator.	Manual locking and unlocking of actuator by pushbutton or key operated lock (can be mounted on left or right-hand side of switch head).
EN/IEC 60947-5-1, EN/ISO 13849-1, EN/IEC 62061, UL 508, CSA C22-2 n°14 and JIS C4520	
EN/IEC 60204-1, EN/ISO 14119	
UL, CSA	
1.58 x 4.47 x 1.73 (40 x 113.5 x 44)	2.05 x 4.47 x 1.73 (52 x 113.5 x 44)
1.18 x 2.36 (30 x 60)	1.18 x 2.36 (30 x 60)
Turret head: 8 positions for insertion of actuator.	Turret head: 8 positions for insertion of actuator.
Safety contacts actuated by the actuator. Slow break and positive opening operation.	Safety contacts actuated by the actuator. Slow break and positive opening operation.
1 N.C. + 2 N.O. break before make 2 N.C. + 1 N.O. break before make 3 N.C.	1 N.C. + 2 N.O. break before make 2 N.C. + 1 N.O. break before make 3 N.C.
IP 67	
-13 … +158° F (-25 … +70° C)	
Screw clamp terminals. Tapped entry for Pg 13.5, ISO M20 cable gland or tapped 1/2" NPT	Screw clamp terminals. Tapped entry for Pg 13.5 cable gland, ISO M20 or tapped 1/2" NPT.
–	–
XCSA	**XCSB, XCSC**
4/50	

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Preventa™ XCS safety switches

Switch type		Preventa XCS key operated switches, locking and unlocking by solenoid	
Applications		**Protection of operators by stopping the machine when the actuator (attached to machine guard) is withdrawn from the head of the switch. All industrial machines, with slow rundown time** *(1)*	
Design		**Slim format**	
		Plastic with 3 cable entries	**Metal with 3 cable entries**
Enclosure		Plastic	Metal
Features		Locking and unlocking of actuator by solenoid (either on energization or on de-energization). Manual unlocking (using tool) of actuator in abnormal conditions.	Locking and unlocking of actuator by solenoid (either on energization or on de-energization). Manual unlocking (using key lock) of actuator in abnormal conditions. 1 Emergency unlocking mushroom head pushbutton (only for XCSLF●●●●4●● and XCSLF●●●●6●●).
Conformity to standards	Products	EN/IEC 60947-5-1, EN/ISO 13849-1, EN/IEC 62061, UL 508 and CSA C22-2 n° 14	
	Machine assemblies	EN/IEC 60204-1, EN/ISO 12100	
Product certifications		UL, CSA, TÜV	
Dimensions (w x h x d or Ø) in. (mm)	Switch	2.01 x 8.07 x 1.71 (51 x 205 x 43.5)	
	Mounting	Centers: 1.18 x 6.04 (30 x 153.3)	
Head		Turret head: 8 positions for insertion of actuator.	
Contact blocks or outputs		Safety contacts actuated by the actuator. Slow break and positive opening operation.	
		1 N.C. + 1 N.O. break before make 2 N.C. 1 N.C. + 2 N.O. break before make 2 N.C. + 1 N.O. break before make 3 N.C. + auxiliary contacts controlled by the solenoid, 1 N.C. + 1 N.O. break before make 2 N.C. 1 N.C. + 2 N.O. break before make 2 N.C. + 1 N.O. break before make 3 N.C. with positive opening operation.	
Degree of protection		IP 66/IP 67	
Ambient air temperature	For operation	-13 … +140° F (-25 … +60° C)	
Connection	Terminals	Spring terminals, 3 cable entries. Tapped entry for ISO M20 cable gland or tapped 1/2" NPT.	
	Pre-cabled	–	
Type reference		**XCSLE**	**XCSLF**
Pages		4/58	4/56

(1) Stopping time of machine greater than time taken for operator to access hazardous zone.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Preventa XCS key operated switches, locking and unlocking by solenoid

Protection of operators by stopping the machine when the actuator (attached to machine guard) is withdrawn from the head of the switch. All industrial machines, with slow rundown time *(1)*

Rectangular format

Metal with 2 cable entries	**Plastic with 1 cable entry**
Metal	Plastic
Locking and unlocking of actuator by solenoid (either on energization or on de-energzation). Manual unlocking (using tool) of actuator in abnormal conditions.	
EN/IEC 60947-5-1, EN/ISO 13849-1, EN/IEC 62061, UL 508, CSA C22-2 n°14 and JIS C4520	
EN/IEC 60204-1, EN/ISO 12100	
UL, CSA	
3.86 x 5.75 x 1.73 (98 x 146 x 44)	4.33 x 3.68 x 1.30 (110 x 93.5 x 33)
3.47 x 3.74 (88 x 95)	Centers: 0.79 x 0.87 (20 x 22)
Turret head: 8 positions for insertion of actuator.	
Safety contacts actuated by the actuator. Slow break and positive opening operation.	
N.C. + N.O. + N.O. (2 N.O. staggered) N.C. + N.C. + N.O. (N.O. staggered) N.C. + N.C. + N.C. + N.C. + N.O. auxiliary contact with positive opening operation, controlled by solenoid	N.C. + N.O. (N.O. staggered) N.O. + N.C. make before break N.C. + N.C. + N.C. auxiliary contact with positive opening operation, controlled by solenoid
IP 67	
-13 … + 158° F (-25 … + 70° C)	
Screw clamp terminals. Tapped entry for Pg 13.5, ISO M20 cable gland or tapped 1/2" NPT	Screw clamp terminals. Tapped entry for n° 11 cable gland, tapped ISO M16 x 1.5 or tapped 1/2" NPT.
–	–
XCSE	**XCSTE**
4/68	4/74

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Preventa™ XCS safety switches

4

Switch type		**Preventa XCS coded magnetic switches for detection without contact**	
Applications		**Protection of operators by stopping the machine when the gate is opened All light industrial machines fitted with access gates with imprecise guidance and/or subjected to frequent washing**	
Design		**Miniature rectangular format**	**Compact rectangular format**
		Plastic, pre-cabled or M8 connector on 5.9" pigtail	**Plastic, pre-cabled or M12 connector on 5.9" pigtail**
Enclosure		Plastic	
Features		3 approach directions	
Conformity to standards	Products	EN/IEC 60947-5-1, EN/ISO 13849-1, EN/IEC 62061, UL 508 and CSA C22-2 n° 14	
	Machine assemblies	EN/IEC 60204-1, EN/ISO 14119	
Product certifications		UL, CSA BG combined with safety modules XPSAF, XPSDM, XPSMP, XPSMC	
Dimensions (w x h x d or Ø) in. (mm)	Switch	0.63 x 2 x 0.27 (16 x 51 x 7)	0.98 x 3.46 x 0.51 (25 x 88 x 13)
	Mounting	Centers: 0.63 (16)	Centers: 3.07 (78)
Head		–	
Contact blocks or outputs		Independent Reed type contacts operated by coded magnet. Contacts change state from a distance of 8 mm (5 mm for XCSDMC). Must be used with Preventa safety relay modules.	
		1 N.C. + 1 N.O. staggered 2 N.O. staggered	1 N.C. + 1 N.O. staggered 2 N.O. staggered 2 N.C. + 1 N.O. (N.C. staggered) 1 N.C. + 2 N.O. (N.O. staggered)
Degree of protection		IP 66 and IP 67 for pre-cabled version IP 67 for connector on pigtail version	
Ambient air temperature	For operation	-13 … +185° F (-25 … +85° C)	
Connection	Terminals	–	
	Pre-cabled	L = 6.6, 16.4, or 32.8 ft. (2, 5, or 10 m)	
	Connector	M8, on 5.9 in (0.15 m) pigtail	M12, on 5.9 in (0.15 m) pigtail
Type reference		**XCSDMC**	**XCSDMP**
Pages		4/82	

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Preventa XCS coded magnetic switches for detection without contact	
Protection of operators by stopping the machine when the gate is opened All light industrial machines fitted with access gates with imprecise guidance and/or subjected to frequent washing	
Cylindrical format	**Coded magnetic systems with dedicated transmitter**
Plastic, pre-cabled or M12 connector on 5.9" pigtail	**Plastic, pre-cabled or M12 connector**
Plastic	
1 approach direction	9 approach directions
EN/IEC 60947-5-1, EN/ISO 13849-1, EN/IEC 62061, UL 508 and CSA C22-2 n° 14	EN/IEC 61508 (SIL 2 or SIL 3), EN/ISO 13849-1 (PL = d or e, cat 3 or 4), EN/IEC 60947-1, EN/IEC 60947-2, EN/IEC 60947-5-3, EN/ISO 13849-1, EN/IEC 62061
EN/IEC 60204-1, EN/ISO 14119	EN/ISO 14119
UL, CSA BG combined with safety modules XPSAF, XPSDM, XCSMP, XPSMC	UL, CSA, TÜV
Ø 30, L 1.51 (Ø 30, L 38.5)	1.33 x 3.94 x 1.26 (34 x 100 x 32)
–	Centers: 3.23 (82)
–	
Independent Reed type contacts operated by coded magnet. Contacts change state from a distance of 0.31 in. (8 mm) [0.20 in. (5 mm) for XCSDMC]. Must be used with Preventa safety relay modules.	Self-contained system does not require the use of a safety relay module or non-magnetic shim.
1 N.C. + 1 N.O. staggered 2 N.O. staggered	2 PNP solid-state outputs XCS DM4: EDM function + 1 alarm output
IP 66 and IP 67 for pre-cabled version IP 67 for connector on pigtail version	Pre-cabled version: IP 66, IP 67 and IP 69K Connector version: IP 67
-13 … +185° F (-25 … +85° C)	-13 … + 158° F (-25 … + 70° C)
–	
L = 6.6, 16.4, or 32.8 ft. (2, 5, or 10 m)	
M12, on 5.9 in (0.15 m) pigtail	M12 (A coding)
XCSDMR	**XCSDM3, XCSDM4**
4/82	4/94

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Preventa™ safety interlock switches

Refer to standards EN/ISO 12100-2 and EN/ISO 14119

Removable or moveable protective guards for potentially dangerous machine functions must be used in conjunction with locking or interlocking devices.
Application requiring an interlocking device: high inertia (long rundown time) machines.
An interlocking device must be used when the rundown time is greater than the time it takes for a person to reach the danger zone.
This device ensures that the guard remains locked until the potentially dangerous movement has stopped.

Guard switches

The mechanical actuator guard switches (i.e.: safety interlock switches), specifically designed for machine guarding applications, provide an ideal solution for the locking or interlocking of movable guards associated with industrial machinery. They meet the requirements of standards
EN/ISO 12100, EN/ISO 13852, EN/ISO 14119 and EN/IEC 60204-1.
They contribute to the protection of operators working on potentially dangerous machines by breaking the start control circuit of the machine when a protective guard is opened or removed, using **positive opening operation contacts**, thus stopping the dangerous movement of the machine.
The removal/opening of the guard (after the dangerous movement has stopped) can either be:
- at the time the machine is switched-off for low inertia machines (machines where the rundown time is less than the time it takes for the operator to access the hazardous zone), or
- delayed for high inertia machines (machines where the rundown time is greater than the time it takes for the operator to access the hazardous zone).

Control circuit categories

Safety interlock switches used in conjunction with a Preventa™ safety relay module enables designers to achieve PL=e, category 4 control systems with reference to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061. When used on their own or combined with another switch, they can achieve up to category 1, 2 or 3 control circuits.
Safety related parts of control systems should be developed taking into account the results of an appropriate Risk Assessment.

Safety of personnel

The start command for the machine can only be initiated following correct operation of the safety interlock switch.
On its release, the N.C. safety contacts are opened by **positive action** or, for coded magnetic, non-contact safety interlocks, change state **(must be monitored using a Preventa safety relay module)**.

Safety of operation

Safety interlock switches incorporate slow break or snap action contacts with **positive opening operation** (except for non-contact safety interlocks where this is not possible). For mechanical safety interlock switches, on closing of the guard the actuator fitted to it enters the head of the switch, operates the multiple interlock device and closes the N.C. contacts. For coded magnetic, non-contact safety interlocks, the presence of the magnet causes the contacts to change state.

Safety in use

All safety interlock switches are designed to accept a few millimeters of misalignment between the actuator and the switch in order to compensate for mechanical play and vibration.

Design to minimize defeat

Both mechanically and magnetically actuated safety interlock switches are designed to be operated by specific actuators so that they cannot be defeated in a simple manner using common tools, rods, metal plates, and simple magnets. When loosening the mounting screws for re-orientation of the turret head on mechanical actuator guard switches, the head itself remains attached to the switch body and the contact states remain unchanged.
All safety interlock switches and safety limit switches are designed to avoid any head setting adjustments, switch removal, or access to the contacts without using the appropriate tool.
There are various methods for obtaining a higher level of tamper proofing, for example:
- using a cage device to prevent the insertion of a spare actuator or magnet, or any other foreign body,
- mounting the actuator or coded magnet to the guard by means that make it very difficult to remove (riveting or welding).

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Metal safety interlock switches

Without locking of actuator



Metal safety interlock switches for use on machines **with low inertia** and operating in **normal conditions** (no vibration or shock and guard mounted vertically, without risk of rebound on closing), thus eliminating unintentional opening of the guard.

With locking of actuator and manual unlocking



Metal safety interlock switches for use on heavy machines **with low inertia** and operating in **arduous conditions** (shock or vibration exist), whereby the guard could open unintentionally.
A key operated lock or a pushbutton enables the positive locking of the guard and its subsequent unlocking.

With interlocking and locking of actuator by solenoid



Metal safety interlock switches for use on machines **with high inertia** or with a controlled opening of the protective guard.
The locking of the moving guard can either be on de-energization or energization of the solenoid.
A key operated lock enables manual unlocking of the guard in the event of an interlocking circuit malfunction, and also provides extra protection for maintenance personnel likely to be working on the machine.
The switches incorporate 2 LEDs: one indicating guard “open/closed” and the other, guard “locked/unlocked”.

Metal safety interlock switches, mushroom head pushbutton for escape release on XCSLF

With interlocking and locking of actuator by solenoid



Safety interlock switches type XCSLF are available with a mushroom head pushbutton mounted on the rear of the switch for unlocking the machine guard while being held in the locked position by the solenoid.
This manual unlocking using the mushroom head pushbutton for escape release is useful in the following cases:
- while the machine or a group of machines is undergoing maintenance, enabling operation at reduced speed or while stopped with the guard(s) closed.

This allows the maintenance personnel to escape in the event of:
- a power failure,
- an interlocking circuit malfunction,
- personnel finding themselves in a dangerous situation.

Unlocking using the escape release mushroom head pushbutton takes priority over any other action. It therefore enables a person to leave the zone if the need arises.
The re-initialization of this function is performed by turning (with or without key) the escape release mushroom head.

Plastic safety interlock switches with mechanical actuator

Without locking of actuator



Plastic safety interlock switches case for use on light machines **with low inertia**.
For use in arduous conditions (shock or vibration exist, guard not vertical or risk of rebound on closing) where the guard could open unintentionally, a **guard retaining device (XCSPA or XCSTA)** is available as an accessory.

With interlocking and locking of actuator by solenoid



Plastic safety interlock switches case for use on machines **with high inertia** or with a controlled opening of the protective guard.
The locking of the moving guard can either be on de-energization or energization of the solenoid.
A special tool enables manual unlocking of the guard in the event of an interlocking circuit malfunction, and also provides extra protection for maintenance personnel likely to be working on the machine.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Preventa™ safety interlock switches

Rotary lever and rotary shaft operated guard switches for hinged guards

With head for rotary movement (lever or rotary shaft)



Plastic safety interlock switches with straight or elbowed operating lever or rotary shaft operator.
Specifically designed for small industrial machines fitted with small sized **hinged doors, covers or protective guards**.
They protect the operator by stopping the dangerous movement of the machine as soon as the rotary lever or rotary shaft displacement reaches an angle of 5°.

Safety limit switches

With head for linear movement (plunger) or rotary movement (lever)



Metal or plastic limit switches.
For use on machines with low inertia and also on machines with high inertia, when used in conjunction with actuator operated guard switches, for monitoring access doors and/or guards. When used on their own, they are always installed in “positive mode” or combined in pairs, with one switch being in “positive mode” and the other in “negative mode”.

Coded magnetic safety interlocks

With an associated coded magnet



Plastic body guard switches for use on machines with low inertia.
Specifically designed for industrial machines fitted with **doors, covers or guards with imprecise guiding**.
They are ideally suited for machines subjected to frequent washing or liquid spray.
They protect the operator by immediately stopping any dangerous movement, as soon as the distance between the switch and its magnet is greater than 0.31 or 0.20 in (8 or 5 mm), depending on the switch model.

Coded magnetic safety interlock systems

With dedicated transmitter



Plastic body system for use on machines with low inertia.
Specifically designed for industrial machines fitted with **one or more doors, covers or guards with imprecise guiding**.
They are ideally suited for machines subjected to frequent washing or liquid spray and that are not necessarily equipped with an enclosure or control cabinet.
These self-contained SIL 2/category 3, PL=d or SIL 3/category 4, PL=e systems protect the operator by stopping any dangerous movement, as soon as the distance between the transmitter and receiver is greater than 0.39 in. (10 mm).

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Actuating keys

The actuating keys are common to all XCSA, XCSB, XCSC, XCSE, and XCSLF



Their oblong mounting holes enable simple adjustment when mounting on moving guards.
A pivoting actuator (both horizontally and vertically) is available when using guard switches in conjunction with hinged guards or guards with imprecise guiding.
Straight actuators are supplied with an adaptor for simple replacement of an **XCSL5** or **XCSL7** safety interlock switch by an **XCS** switch, without the need to drill additional mounting holes for the switch or actuator.

Turret head

All XCSA, XCSB, XCSC, XCSE, and XCSLF are fitted with a square turret head which can be rotated through 360° in 90° steps



8 directions of actuation are possible for the actuating key:
- 4 in the horizontal plane,
- 4 from above the switch (4 alternative positions of the actuator slot, depending on the orientation of the head).

When loosening the mounting screw for re-orientation of the operating head, the head itself remains attached to the body and the contact states remain unchanged.

Safety contacts

XCSA, XCSB, XCSC, XCSE, and XCSLF incorporate a **3-pole contact block** with positive opening operation, which is actuated by insertion or withdrawal of the actuating key attached to the guard.



The withdrawal of the actuating key opens the N.C. safety contact(s), even in the event of the contact sticking or welding.
The 3-pole contact block enables redundant safety circuits to be established (for example: N.C. + N.C. or N.C. + N.O.) and also, to provide signalling (for example: PLCs and illuminated beacons).

LED indicators

An orange LED (optional for type XCSA, XCSB and XCSC, standard for type XCSE) **indicates the position of the machine guard:**

LED illuminated: actuating key not inserted in head of switch, N.C. contact(s) open, guard open.

LED not illuminated: actuating key inserted in head of switch, N.C. contact(s) closed, guard closed.

A green LED (incorporated on type XCSE, XCSLE and XCSLF) **indicates the locking of the machine guard:**

LED not illuminated: actuating key not inserted in head of switch: the machine cannot be operated,

LED illuminated: actuating key inserted in head of switch **and actuating key locked**. The machine is either ready for starting, running or decelerating to a standstill.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Manual locking/unlocking by pushbutton or key operated lock on XCSB and XCSC

The pushbutton or key operated lock fitted to key operated switches type XCSB and XCSC allows manual locking/unlocking of the machine guard



Their use is not necessary for the normal operation of the guard switch.
For ease of access, the pushbutton or lock may be mounted on the right or the left of the key operated switch head.
For key operated switches type XCSC, when the machine guard is locked (key in position “LOCK”), the resistance to forcible withdrawal of the actuator fitted to the guard is **337 lbs. (1,500 N)**.
The key is removable from the locking device in the “LOCK” position.

Locking/unlocking by solenoid on XCSE and XCSLF

Safety interlock switches type XCSE and XCSLF incorporate a solenoid for locking/unlocking of the machine guard



With the machine guard closed and locked, the resistance to forcible withdrawal of the actuator fitted to the guard is **450 lbf (2000 N)** for the XCSE and **674.4 lbf (3000 N)** for the XCSLF.
In addition to the 3-pole contacts, positively operated by the actuator fitted to the guard, XCSLF safety interlock switches incorporate **N.C. + N.O.** or **2 N.C.** or **1 N.C. + 2 N.O.** or **2 N.C. + 1 N.O.** or **3 N.C. contact blocks mechanically linked to the solenoid**. The XCSE safety interlock switches incorporate **N.C. + N.O. contacts mechanically linked to the solenoid**.
The N.C. contact(s) are for use in the safety circuit of the machine and the N.O. contact for signalling the status of the solenoid.

Key operated lock on XCSE and XCSLF

Safety interlock switches type XCSE and XCSLF are fitted with a key operated lock allowing the unlocking of the machine guard while being held in the lock position by the solenoid (for use by authorized personnel only)



The manual unlocking of the guard using the key operated lock is useful in the following cases:
- while the machine is undergoing maintenance (with the key turned to the “UNLOCK” position and then removed, the level of protection is higher in preventing an accidental machine start. The protection for maintenance personnel is thus improved):
- in the event of a power failure
- in the event of an interlocking circuit malfunction (interlocked condition maintained: positive safety).

The electrical supply providing the unlocking via the solenoid always takes priority over manual unlocking using the key operated lock.
The lock fitted to standard safety interlock switches has key withdrawal from the “LOCK” and “UNLOCK” positions.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ metal safety interlock switches type XCSLF

Example of operation for an XCSLF safety interlock switch: locking without power (locking on de-energization of solenoid)

Machine status	Power off, machine off	Power on, machine off	Machine stopped, ready to start	Machine running	Stopping sequence	Machine stopped, power on
Guard position	Open	Open	Closed	Closed	Closed	Closed
Guard status	Free	Free	Free	Locked	Locked	Free
Solenoid status	"O" (de-energized)	"1" (energized)	"1" (energized)	"O" (de-energized)	"O" (de-energized)	"1" (energized)
2-pole contact state for XCSLF25●●●						
2-pole contact state for XCSLF27●●●						
3-pole contact state for XCSLF35●●●						
3-pole contact state for XCSLF37●●●						
3-pole contact state for XCSLF38●●●						
Functions	Machine in a non-operational state	Machine cannot be operated.	Guard closed, actuator can be locked. It will be locked as soon as the start instruction is given.	Start instruction given, the machine is running.	Stop instruction given, the machine stops gradually (deceleration then complete stop of motor).	Machine has stopped. The guard can be opened.
Solenoid contact states						
2-pole contact state for XCSLF●●25●●●						
2-pole contact state for XCSLF●●27●●●						
3-pole contact state for XCSLF●●35●●●						
3-pole contact state for XCSLF●●37●●●						
3-pole contact state for XCSLF●●38●●●						
Orange LED						
Green LED						
Safety circuit of the machine	Open	Open	Open	Closed	Closed	Open

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Example of operation for an XCSE safety interlock switch: locking without power (locking on de-energization of solenoid)

Actuating key locks into the switch when inserted. This is typically preferred as the door is secured, regardless of electrical power availability or power failure. Applying power to the electromagnet will unlock the actuating key and allow it to be removed from the switch. The N.C. Safety contacts will not open until the actuating key is removed.

Machine status	Power off, machine off	Power on, machine off	Machine stopped, ready to start	Machine running	Stopping sequence	Machine stopped, power on
Guard position	Open	Open	Closed	Closed	Closed	Closed
Guard status	Free	Free	Free	Locked	Locked	Free
Solenoid status	"O" (de-energized)	"1" (energized)	"1" (energized)	"O" (de-energized)	"O" (de-energized)	"1" (energized)
3-pole contact state for XCSE5●●●						
3-pole contact state for XCSE7●●●						
Status	Machine in a non-operational state.	Machine cannot be operated.	Guard closed, actuating key can be locked. It will be locked as soon as the start instruction is given.	Start instruction given, the machine is running.	Stop instruction given, the machine stops gradually (deceleration then complete stop of motor).	Machine has stopped. The guard can be opened.
Contact states (N.C. + N.O.) of solenoid						
Orange LED						
Green LED						
Safety circuit of the machine	Open	Open	Open	Closed	Closed	Open

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Preventa™ plastic safety interlock switches

Key actuators

The actuating keys are common to XCSPA, XCSTA and XCSTE plastic safety interlock switches. XCSLE actuating keys are the same as XCS metal safety interlocks.



Their oblong mounting holes enable simple adjustment when mounting on moving guards.

A pivoting actuator (both horizontally and vertically) is available when using guard switches in conjunction with hinged guards or guards with imprecise guiding.

Straight actuating keys are supplied with an adaptor for simple replacement of an **XCKP** key operated switch by an **XCSPA** switch, or an **XCKT** key operated switch by an **XCSTA** switch, without the need to drill additional mounting holes for the switch or the actuator.

Turret head

All XCSPA, XCSTA, XCSTE, and XCSLE are fitted with a square turret head which can be rotated through 360° in 90° steps. XCSMP safety interlock switches have a fixed head



8 directions of actuation are possible for the actuator:
4 in the horizontal plane (1 for **XCSMP**),
4 from above the switch (1 for **XCSMP**),
(4 alternative positions of the actuator slot, depending on the orientation of the head).

When loosening the 2 or 4 mounting screws (**XCSLE and XCSTE**) for re-orientation of the operating head, the head itself remains attached to the body and the contact states remain unchanged (**XCSPA, XCSTA, XCSTE**).

Safety contacts

The key operated switches incorporate either a 2-pole contact block (XCSMP, XCSPA, XPSTA, XCSTE, and XCSLE) or a 3-pole contact block (XCSMP, XCSTA, XCSTE, and XCSLE), with positive opening operation, which is actuated by insertion or withdrawal of the actuating key attached to the guard

XCSLE



or **XCSPA, XCSTE**



or **XCSTA**



or **XCSMP**



In addition, safety interlock switches type XCSLE incorporate 1 N.C. or 2 N.C. contacts (with positive opening operation) actuated by the solenoid.
The N.C. contact(s) are for use in the safety circuit of the machine. The withdrawal of the actuating key opens the N.C. safety contact(s), even in the event of the contact sticking or welding.
The two-pole **2 N.C.** or three-pole **2 N.C. + 1 N.O.** or **3 N.C.** (XCSMP, XCSPA, XCSTA, XCSTE, XCSLE) contact block enables up to PL = d, category 3 control circuit to be established conforming to EN/ISO 13849-1, by using both N.C. safety contacts in redundancy, or up to PL = b, category 1 control circuit by using one N.C. contact in the safety circuit and the N.O. other contact for signalling (for example: PLCs and illuminated beacons).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Guard retaining device

The guard retaining device XCSZ21 can be used with all plastic safety interlock switches type XCSPA and XCSTA that are used in conjunction with either the wide (XCSZ12) or pivoting (XCSZ13) actuator



It assists in holding the guard closed by providing an extra retaining force of **11.2 lbs (50 N)**.

It is specially suited for use with light machines operating in arduous conditions (vibration, mechanical shock, guard not vertical, risk of guard rebound on closing).

It can be used for horizontal actuator actuation directions as well as those from above.

Locking/unlocking by solenoid on XCSLE

Safety interlock switches type XCSLE incorporate a solenoid for locking/unlocking of the machine guard



With the machine guard closed and locked, the resistance to forcible withdrawal of the actuator fitted to the guard is **314.7 lbf (1400 N)**. In addition to the 2-pole or 3-pole contact block, positively operated by the actuator fitted to the guard, the switches incorporate **1 or 2 N.C. contacts mechanically linked to the solenoid**.
The N.C. contact(s) are for use in the safety circuit of the machine.

Unlocking by special tool for XCSLE

Safety interlock switches type XCSLE are supplied with a special tool 1 that enables unlocking of the machine guard while being held in the locked position by the solenoid (for use by authorized personnel only)



The manual unlocking of the guard using the tool 1 is useful in the following cases:
- while the machine is undergoing maintenance (with the tool turned to the "UNLOCK" position and then removed, the level of protection is higher in preventing an accidental machine start. The protection for maintenance personnel is thus improved),
- in the event of a power failure,
- in the event of an interlocking circuit malfunction (interlocked condition maintained: positive safety). The electrical supply providing the unlocking via the solenoid always takes priority over manual unlocking using the special tool.

Resilience XCSLE / XCSLF

XCSLE against the partition: max = 1.2 J
XCSLE without partition: max = 4.9 J

XCSLF against the partition: max = 9.6 J
XCSLF without partition: max = 6.4 J



Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Locking/unlocking by solenoid on XCSTE

Type XCSTE incorporate a solenoid for locking/unlocking of the machine guard



With the machine guard closed and locked, the resistance to forcible withdrawal of the actuator fitted to the guard is **112 lbs. (500 N)**.
In addition to the 2-pole contact block, positively operated by the actuator mounted to the guard, XCSTE switches incorporate a **N.C. contact block mechanically linked to the solenoid**.
The N.C. contact is for use in the safety circuit of the machine.

Unlocking by special tool for XCSTE

Type XCSTE are supplied with a special tool 1 that enables unlocking of the machine guard while being held in the locked position by the solenoid (for use by authorized personnel only)



The manual unlocking of the guard using the tool 1 is useful in the following cases:
- while the machine is undergoing maintenance (with the tool turned to the "UNLOCK" position and then removed, the level of protection is higher in preventing an accidental machine start. The safety for maintenance personnel is thus improved),
- in the event of a power failure,
- in the event of an interlocking circuit malfunction (interlocked condition maintained: positive safety). The electrical supply providing the unlocking via the solenoid always takes priority over manual unlocking using the special tool.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ plastic safety interlock switches type XCSLE

Example of operation for an XCSLE safety interlock switch: locking without power (locking on de-energization of solenoid)

Machine status	Power off, machine off	Power on, machine off	Machine stopped, ready to start	Running	Stopping sequence	Machine stopped, power on
Guard position	Open	Open	Closed	Closed	Closed	Closed
Guard status	Free	Free	Free	Locked	Locked	Free
Solenoid status	"O" (de-energized)	"1" (energized)	"1" (energized)	"O" (de-energized)	"O" (de-energized)	"1" (energized)
2-pole contact state for XCSLE25●●●						
2-pole contact state for XCSLE27●●●						
3-pole contact state for XCSLE35●●●						
3-pole contact state for XCSLE37●●●						
3-pole contact state for XCSLE38●●●						
Functions	Machine in a non-operational state	Machine cannot be operated.	Guard closed, actuator can be locked. It will be locked as soon as the start instruction is given.	Start instruction given, the machine is running.	Stop instruction given, the machine stops gradually (deceleration then complete stop of motor).	Machine has stopped. The guard can be opened.
Solenoid contact states						
2-pole contact state for XCSLE●●25●●●						
2-pole contact state for XCSLE●●27●●●						
3-pole contact state for XCSLE●●35●●●						
3-pole contact state for XCSLE●●37●●●						
3-pole contact state for XCSLE●●38●●●						
Orange LED						
Green LED						
Safety circuit of the machine	Open	Open	Open	Closed	Closed	Open

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Example of operation for an XCSTE safety interlock switch: locking without power (locking on de-energization of solenoid)

Actuating key locks into switch when inserted. This is typically preferred as the door is secured regardless of electrical power availability or failure. Applying power to the electromagnet will unlock actuating key and allow it to be removed from the switch. The N.C. safety contacts will not open until the actuating key is removed.

Machine status	Power off, machine off	Power on, machine off	Machine stopped, ready to start	Running	Stopping sequence	Machine stopped, power on
Guard position	Open	Open	Closed	Closed	Closed	Closed
Guard status	Free	Free	Free	Locked	Locked	Free
Solenoid status	"O" (de-energized)	"1" (energized)	"1" (energized)	"O" (de-energized)	"O" (de-energized)	"1" (energized)
2-pole contact state for XCSTE5●●●						
2-pole contact state for XCSTE7●●●						
Status	Machine is in non-operational state.	Machine cannot be operated.	Guard closed, actuating key can be locked. It will be locked as soon as the start instruction is given.	Start instruction given, the machine is running.	Stop instruction given, the machine stops gradually (deceleration then complete stop of motor).	Machine has stopped. The guard can be opened.
Contact state of solenoid						
Safety circuit of the machine	Open	Open	Open	Closed	Closed	Open

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ rotary lever and rotary shaft operated safety interlock switches

Introduction

Turret head



Safety interlock switches for hinged covers or guards, featuring a hinged lever or rotary shaft operator, incorporate a turret head that can be rotated through 360° in 90° steps.
Two additional self-locking screws are included with each switch for positive mounting of the head.

2 types of body



XCSPL *XCSTR*

- Plastic body, narrow, with 1 conduit entry for **XCSPL** and **XCSPR**.
- Plastic body, wide, with 2 conduit entries for **XCSTL** and **XCSTR**.

2 types of operating lever, 2 rotary shaft lengths



- Levers

Straight or elbowed (flush with rear of switch), making the lever switches suitable for use with all types of hinged guards, whether:
- flush with the machine framework (use a switch with an elbowed flush lever),
- overhanging in relation to the machine framework (use a switch with a straight lever).

3 alternative operating lever positions allow the switches to be used with guards that open to the left, center or right.

- Rotary shaft operators

2 shaft lengths: 1.18 or 3.15 in. (30 or 80 mm).

Safety contacts



Types **XCSPL** and **XCSPR** incorporate a 2-pole contact block, with positive opening operation. The contact arrangements can be: N.C. + N.O. (N.O. staggered) or N.C. + N.C.
Types **XCSTL** and **XCSTR** incorporate a 3-pole contact, with positive opening operation. The contact arrangements can be:
N.C. + N.O. + N.O. (2 N.O. staggered) or N.C. + N.C. + N.O.) (N.O. staggered).
Opening of the N.C. safety contact(s) occurs when the operating lever or spindle is displaced by an angle equal to or greater than 5°.

Applications

These safety interlock switches provide a solution for monitoring **hinged protective guards** with small opening radius on machines with low inertia (no rundown time).
They are specially suitable for existing machines which need to be brought in-line with the latest standards and directives since they can be used in conjunction with existing covers, including those whose mounting is somewhat imprecise.
Mounting of these switches improve the machine operator's level of safety by limiting the opening of the protective guard and reducing the risk of touching any moving parts before they have come to a stop.



Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Introduction

Coded magnetic safety interlocks



3 body types

- PBT plastic body
- Compact rectangular, **XCSDMC**
- Standard rectangular, **XCSDMP**
- Cylindrical Ø 30, **XCSDMR**
- Pre-cabled, length 6.6, 16.4, or 32.8 ft. (2, 5, or 10 m)
- Connector on pigtail connection:
  - M8: DMC
  - M12: DMP, DMR

Contacts

Coded magnetic safety interlocks are fitted with 2-pole **(XCSDMC/XCSDMR/XCSDMP)** or 3-pole **(XCSDMP)** Reed type contacts and are available with or without a "guard closed" LED indicator.
The N.C. and N.O. contacts change state as soon as the magnet is at a distance from the sensor of approximately 0.31 in. (8 mm) for types **XCSDMP** and **XCSDMR** and approximately 0.20 in. (5mm) for type **XCSDMC**.

Connection

When used in safety circuits, the Reed technology contacts must always be used in conjunction with a Preventa™ safety relay module, safety controller, or safety PLC.

Coded magnetic safety interlock systems with dedicated transmitter



1 body type

- PBT plastic body
- Self-contained range: category 3 and SIL 2 - **XCSDM3** and category 4 and SIL 3 - **XCSDM4** (SIL 2 and SIL 3 per IEC 61508 and EN/IEC 62061)
- Pre-cabled, length 6.6, 16.4, or 32.8 ft. (2, 5, or 10 m)
- Pigtail with M12 connector

Technology

Coded "Hall effect" detection
PNP safety outputs
Integrated self-monitoring using micro-processors.
Detection distance from 0 to 0.39 in. (0 to 10 mm) obtained on approach of dedicated transmitter XCSDMT.

Functions

- Dynamic EDM (External Device Monitoring) only for **XCSDM4**,
- Fault and short-circuit detection,
- Output diagnostics (non safety related) only for **XCSDM4**
- LED indicator
- Series wiring of up to a maximum of 32 systems for **XCSDM3** only.

Applications



These switches provide a solution for monitoring moveable machine guards on machines with quick rundown times.
They are particularly suitable for guards without accurate guidance and for use in difficult environments (dust and liquids).
Installing self-contained systems provides an optimum solution (no control system required).
They enable
- monitoring of one or several guards (opening, closing) on small machines,
- savings in space and the elimination of enclosures and/or control cabinets.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Presentation

Safety limit switches XCSM

With head for linear movement (plunger) or rotary movement (lever)



- Narrow metal body.
- With protective cover, preventing access to the mounting screws or adjustment of the head by non-authorized personnel.
- Torx mounting screws.
- A removable cable entry to facilitate wiring.

Contacts

XCSM3 limit switches are fitted with 3-pole contacts and **XCSM4** switches are fitted with 4-pole contacts.
4 versions of complete switches are available incorporating these contacts:
- metal end plunger,
- roller plunger,
- thermoplastic roller lever,
- 0.75 in. (19 mm) diameter steel roller lever.

Connection

Pre-cabled switches, either 7 x 20 AWG (0.5 mm²) or 9 x 22 AWG (0.34 mm²).

Safety limit switches XCSD and XCSP

With head for linear movement (plunger) or rotary movement (lever)



- Compact metal XCSD and plastic XCSP.
- With protective cover, preventing access to the mounting screws or adjustment of the head by non-authorized personnel.
- Torx mounting screws.
- A removable cable entry to facilitate wiring.

Contacts

XCSP3●●●● and **XCSD3●●●●** limit switches are fitted with 3-pole contacts.
4 versions of complete switches are available incorporating these contacts:
- metal end plunger,
- roller plunger,
- thermoplastic roller lever,
- 0.75 in. (19 mm) diameter steel roller lever.

Applications

These switches provide a solution for monitoring covers, guards or grilles on machines with low inertia (quick rundown time), either in conjunction with safety interlock switches or not.
When used on their own, they are always installed in “positive mode” or combined in pairs, with one switch being in “positive mode” and the other in “negative mode”, and can, when connected to Preventa™ safety relay modules, achieve a PL=e, category 4/SIL 3 system.



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Application information for all guard switches

Application information for all safety interlock and safety limit switches

When designing a door or gate guarding system, these guidelines must be followed:

- The actuating key, coded magnet or lever alone must not be used as the sole means to hold the gate or guard closed. A separate locking or latching mechanism must be used to hold the door closed.
- The safety interlock switch or safety limit switch must not be used as a mechanical stop for the moving guard. A separate mechanical stop must be provided. (EN 1088 - 1995: 5.2.2)
- The actuating key must not be used as a gate guiding device. Install a guide for the guard to ensure proper alignment.
- Actuating keys must be securely attached to gates, guards, and doors only. They should not be attached to cables, cords or chains.
- Actuating keys for safety interlocks should not be inserted further than the maximum depth indicated for that device.
- Levers or plungers on safety limit switches should not be operated in excess of the parameters indicated for maximum travel.
- Consider the width of hinged doors and guards when selecting a mechanical actuating key - narrow doors and guards require the use of pivoting actuating keys for proper insertion of the key upon closing of the door or guard.
- Non-Contact safety interlock switches or actuating keys should not be used as a mechanical stop. Their operation is to be non-contact.

Operation of solenoid locking

Operation of safety interlock switches with solenoid locking

Safety interlocks are available with two types of locking of the actuating key: locking with power and locking without power. The operation of each is described below.

- **Locking Without Power (locking on de-energization of solenoid).** Actuating key locks into switch when inserted. This is typically preferred as the door is secured regardless of electrical power availability or power failure. Applying power to the electromagnet will unlock actuating key and allow it to be removed from the switch. The N.C. safety contacts will not open until the actuating key is removed.
- **Locking With Power (locking on energization of solenoid).** Actuating key locks into switch only when actuating key is inserted and power is applied to the electromagnet. Door or guard is not locked in the event of a power failure or when power is removed from the electro-magnet. Removing power from the electromagnet will unlock actuating key and allow it to be removed from the switch. The N.C. safety contacts will not open until the actuating key is removed.

Note: “Locking with power” devices do not meet European standards regarding the safety of machinery, regarding guard locking. European standards do not allow a “locking with power” function for gate or door guarding/locking. Locking without power devices meets European requirements, and should be used when machinery is to be shipped to Europe or where machinery must meet European standards.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Miniature design, metal, type XCSM

XCSM precabled

With head for linear movement (plunger). Mounting by the body

page 4/28

With head for rotary movement (lever). Mounting by the body



page 4/28

4

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Miniature design, metal, type XCSM

Environment

Conforming to standards	Products	IEC/EN 60947-5-1, UL 508, CSA C22-2 No. 14
	Machine assemblies	IEC/EN 60204-1, EN 1088
Product certifications		UL, CSA
Maximum safety level *(1)*		PL=e, category 4 conforming to EN/ISO 13849-1 and SIL 3 conforming to EN/IEC 61508
Reliability data B_{10d}		50,000,000 (data value for a service life of 10 years can be limited by contact and mechanical wear)
Protective treatment		Standard version: **TC**
Ambient air temperature		Operation: –13 to +158 °F(–25 to +70 °C). Storage: –40 to +158 °F (–40 to +70 °C)
Vibration resistance		XCSM snap action: 5 gn. XCSM slow break: 25 gn (10–500 Hz) conforming to IEC 60068-2-6
Shock resistance		25 gn, (18 ms) conforming to IEC 60068-2-27
Electric shock protection		Class I, conforming to IEC 6140 and NF C 20-030
Degree of protection		**IP66, IP67 and IP68** *(2)* **conforming to IEC 60529; IK06 conforming to EN 50102**
Materials		Body: Zamak. Head: Zamak. Protective cover: steel.
Repeat accuracy		0.002 in. (0.05 mm) on the tripping points with 1 million operating cycles for head with end plunger

Contact block specifications

Rated operational specifications	**~ AC-15; B300 (Ue = 240 V, Ie = 1.5 A)** **⎓ DC-13 ; R300 (Ue = 250 V, Ie = 0.1 A), conforming to IEC 60947-5-1 Appendix A, EN 60947-5-1**
Rated insulation voltage	Ui = 400 V degree of pollution 3 conforming to IEC 60947-5-1 Ui = 300 V conforming to UL 508, CSA C22-2 No. 14
Rated impulse withstand voltage	Uimp = 4 kV conforming to IEC 60947-1, IEC 60664
Positive operation (depending on model)	N.C. contacts with positive opening operation conforming to IEC/EN 60947-5-1 Appendix K
Resistance across terminals	≤ 25 mΩ conforming to IEC 60255-7 category 3
Short-circuit protection	6 A cartridge fuse type gG (gl)
Minimum actuation speed	Snap action contact: 0.01 m/minute Break before make, slow break: 6 m/minute

(1) Using an appropriate and correctly connected control system.

(2) Protection against prolonged immersion: the test conditions are subject to agreement between the manufacturer and the user.

Electrical life

- Conforming to 60947-5-1 Appendix C
- Utilization category AC-15 and DC-13
- Maximum frequency: 3600 operating cycles/hour
- Load factor: 0.5

AC supply
~ 50/60 Hz
⎓ inductive circuit

XCSM snap action (N.C.+ N.C. + N.O., N.C.+ N.C. + N.O. + N.O. contacts)



XCSM slow break (N.C.+ N.C. + N.O. contact)



DC supply ⎓

Power (in W) broken for 5 million operating cycles

Voltage	V	24	48	120
⎓	W	3	2	1

Power (in W) broken for 5 million operating cycles

Voltage	V	24	48	120
⎓	W	4	3	3

The product life expressed is based on average usage and normal operating conditions. Actual operating life will vary with conditions. The above statements are not intended to nor shall they create any express or implied warranties as to product operation or life. For information on the limited warranty offered on this product please refer to the Schneider Electric Conditions of Sale found in the *Digest*.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Miniature design, metal, type XCSM
Precabled

Type of head		Plunger		Rotary	
	Mounting by the body				
Type of operator		Metal end plunger	Roller plunger	Thermoplastic roller lever	Steel roller lever

References with 6.6 ft (2 m) cable *(1)*

	**3-pole N.C.+N.C.+N.O. snap action contact**	**XCSM3910L2** 	**XCSM3902L2** 	**XCSM3915L2** 	**XCSM3916L2** 
	**3-pole N.C.+N.C.+N.O. break before make, slow break contact**	**XCSM3710L2** 	**XCSM3702L2** 	**XCSM3715L2** 	**XCSM3716L2**
	**4-pole N.C.+N.C.+N.O.+N.O. snap action contact**	**XCSM4110L2** 	**XCSM4102L2** 	**XCSM4115L2** 	**XCSM4116L2** 
Weight lb (kg)		0.36 (0.165)	0.37 (0.170)	0.45 (0.205)	0.46 (0.210)
Contact operation		*closed* / *open*		*(A) = cam displacement* *(P) = positive opening point* *⊖ N.C. contact with opening positive operation*	

Additional specifications not shown under General Specifications (page 4/27)

Switch actuation		On end	By 30° cam	
Type of actuation				
Maximum actuation speed		1.64 ft/s (0.5 ms)	1.64 ft/s (0.5 ms)	4.9 ft/s (1.5 ms)
Minimum force or torque	Tripping	1.9 lb-in. (8.5 N•m)	1.6 lb-in. (7 N•m)	0.9 lb-in. (0.1 N•m)
	Positive opening	9.6 lb-in. (42.4 N•m)	7.9 lb-in. (35 N•m)	4.4 lb-in. (0.5 N•m)
Cabling	3-pole contacts	PVR precabled, 7 x 20 AWG (0.5 mm²)		
	4-pole contacts	PVR precabled, 9 x 22 AWG (0.34 mm²),		

(1) Devices shown have a 6.6 ft (2 m) cable, and are available with other lengths of cable:
For a 3.3 ft (1 m) cable, replace L2 with L1.
For a 16.4 ft (5 m) cable, replace L2 with L5.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Miniature design, metal, type XCSM
Precabled

Dimensions *in. (mm)*

XCSM●●10L1



Cover masks the mounting screws

(1) Protective cover mounted with 5-lobe torque safety screws.

XCSM●●02L1



XCSM●●15L1



XCSM●●16L1



Dual Dimensions: INCHES / Millimeters

(1) Protective cover mounted with 5-lobe torque safety screws.

Wiring diagrams

Wiring to PL=b, category 1 conforming to EN/ISO 13849-1

Example with 3-pole N.C.+N.C.+N.O. contact and protective fuse to prevent jumpering of the N.C. contacts, either by cable damage or by tampering.



(1) Signaling contact

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1

Example with 3-pole N.C.+N.C.+N.O. contact with mixed redundancy of the contacts and the associated control relays. Opening and closing of the guard necessary to activate K1.



H1: Guard Closed indicator light

Example of guard monitoring using 2 limit switches and 1 safety relay module (PL=e, category 4 conforming to EN/ISO 13849-1)

Operation in positive and negative (combined) mode



Introduction: page 4/26 | Specifications: page 4/27 | References: page 4/28 | Dimensions: page 4/29 | Wiring diagrams: page 4/29

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Compact design, metal, type XCSD
Compact design, plastic, type XCSP

XCSD, XCSP
with 1 conduit entry
conforming to EN 50047

With head for linear movement (plunger)

XCSD	XCSP
	
Pages 4/32 and 4/33	Pages 4/34 and 4/35

With head for rotary movement (lever)

XCSD	XCSP
	
Pages 4/32 and 4/33	Pages 4/34 and 4/35

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Compact design, metal, type XCSD
Compact design, plastic, type XCSP

Environmental specifications

Conformity to standards	Products	IEC/EN 60947-5-1, UL 508, CSA C22-2 n° 14
	Machine assemblies	IEC/EN 60204-1, EN 1088/ISO 14119
Product certifications		UL, CSA
Maximum safety level *(1)*		PL=e, category 4 conforming to EN/ISO 13849-1 and SIL 3 conforming to EN/IEC 61508
Reliability data B_{10d}		50,000,000 (value given for a service life of 20 years can be limited by contact and mechanical wear)
Protective treatment	Standard version	**TC**
Ambient air temperature	For operation	–13 to +158 °F (–25 to +70 °C)
	For storage	–40 to +158 °F (–40 to +70 °C)
Vibration resistance	Conforming to IEC 60068-2-6	25 gn (10–500 Hz)
Shock resistance	Conforming to IEC 60068-2-27	50 gn (11 ms)
Electric shock protection		Class I conforming to IEC 61140 and NF C 20-030 for **XCSD**
		Class II conforming to IEC 61140 and NF C 20-030 for **XCSP**
Degree of protection	Conforming to IEC 60529	**IP66 and IP67**
	Conforming to EN 50102	**IK06 for XCSD** **IK04 for XCSP**
Repeat accuracy		0.004 in. (0.1 mm) on the tripping points, with 1 million operating cycles for head with end plunger
Cable entry	Depending on model	Tapped entry for 13.5 cable connector, tapped ISO M20 x 1.5 or tapped 1/2"-14 NPT
Materials		**XCSD** Zamak bodies and heads, **XCSP** plastic bodies, Zamak heads Plastic protective cover, secured by 5-lobe socket head safety screw

Contact block specifications

Rated operational specifications	∼ AC-15; B300 (Ue = 240 V, Ie = 1.5 A); Ithe = 6 A ⎓ DC-13; R300 (Ue = 250 V, Ie = 0.1 A), conforming to IEC/EN 60947-5-1 Appendix A
Rated insulation voltage	Ui = 400 V degree of pollution 3 conforming to EN/IEC 60947-1 Ui = 300 V conforming to UL 508, CSA C22-2 n° 14
Rated impulse withstand voltage	Uimp = 4 kV conforming to EN/IEC 60947-1, IEC 60664
Positive operation	N.C. contacts with positive opening operation conforming to IEC/EN 60947-5-1 Appendix K
Resistance across terminals	≤ 25 mΩ conforming to IEC 60255-7 category 3
Short-circuit protection	6 A cartridge fuse type gG (gI)
Connection (screw clamp terminals)	Clamping capacity, min: 1 x 22 AWG (0.34 mm²), max: 1 x 18 AWG (1 mm²) or 2 x 18 AWG (0.75 mm²)
Minimum actuation speed (for head with end plunger) — Snap action	0.39 in/ (0.01 m) per minute
Minimum actuation speed (for head with end plunger) — Slow break	19.7 ft/ (6 m) per minute

(1) Using an appropriate and correctly connected control system.

Electrical life

- Conforming to EN/IEC 60947-5-1 Appendix C
- Utilization categories AC-15 and DC-13
- Maximum operating rate: 3600 operating cycles/hour
- Load factor: 0.5

AC supply
∼ 50/60 Hz
inductive circuit

Snap action contacts



Slow break contacts



DC supply ⎓

Power (in W) broken for 5 million operating cycles.

Voltage	V	24	48	120
	W	3	2	1

Power (in W) broken for 5 million operating cycles.

Voltage	V	24	48	120
	W	4	3	2

The product life expressed is based on average usage and normal operating conditions. Actual operating life will vary with conditions. The above statements are not intended to nor shall they create any express or implied warranties as to product operation or life. For information on the limited warranty offered on this product please refer to the Schneider Electric Conditions of Sale found in the *Digest*.

Introduction: page 4/30 | Specifications: page 4/31 | References: pages 4/32 to 4/35 | Dimensions: pages 4/32 to 4/35

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Compact design, metal, type XCSD

Type of head	Plunger		Rotary	
				
Type of operator	Metal end plunger	Steel roller plunger	Thermoplastic roller lever	Steel roller lever

References of assembled devices with 3-pole N.C. + N.C. + N.O. snap action contact

With 1/2"-14 NPT cable entry				
	XCSD3910N12 ⊖	**XCSD3902N12** ⊖	**XCSD3918N12** ⊖	**XCSD3919N12** ⊖
With ISO M20 x 1.5 cable entry				
	XCSD3910P20 ⊖	**XCSD3902P20** ⊖	**XCSD3918P20** ⊖	**XCSD3919P20** ⊖
With Pg 13.5 cable entry				
	XCSD3910G13 ⊖	**XCSD3902G13** ⊖	**XCSD3918G13** ⊖	**XCSD3919G13** ⊖
Weight lb (kg)	0.47 (0.215)	0.49 (0.220)	0.56 (0.255)	0.56 (0.255)

Contact functional diagrams



3-pole N.C. + N.C. + N.O. snap action contact

				

Contact operation

contact closed *(A) = cam displacement*
contact open *(P) = positive opening point*
⊖ *N.C. contact with positive opening operation*

Additional specifications not shown under General Specifications (page 4/31)

Switch actuation		On end	By 30° cam	
Type of actuation				
Maximum actuation speed		1.64 ft/s (0.5 ms)		4.9 ft/s (1.5 ms)
Minimum force or torque	For tripping	3.72 lb-in. (15 N•m)	2.70 lb-in. (12 N•m)	0.89 lb-in. (0.1 N•m)
	For positive opening	10.12 lb-in. (45 N•m)	8.09 lb-in. (36 N•m)	2.21 lb-in. (0.25 N•m)
Conduit entry		1 entry tapped M20 x 1.5 mm for ISO cable connector, clamping capacity 7 to 13 mm 1 entry tapped Pg 13.5 for cable connector, clamping capacity 9 to 12 mm 1 entry tapped for 1/2"-14 NPT (USAS B2-1) conduit		

Dimensions *in. (mm)*

XCSD3●10●●●



XCSD3●02●●●



(1) Tapped entry for ISO M20 x 1.5 or Pg 13.5 cable connector or 1/2"-14 NPT conduit.
(2) 2 elongated holes Ø0.17 x 0.25 in. (Ø4.3 x 6.3 mm) on 0.87 in. (22 mm) centers or 2 holes Ø0.17 in. (Ø4.3 mm) on 0.79 in. (20 mm) centers.
(3) 0.08 x Ø0.12 in. (2 x Ø3 mm) holes for studs, depth . 16 in. (4 mm).

Dual Dimensions: INCHES Millimeters

Introduction: page 4/30 | Specifications: page 4/31 | References: pages 4/32 to 4/35 | Dimensions: pages 4/32 to 4/35

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Compact design, metal, type XCSD

Type of head	Plunger		Rotary	
				
Type of operator	Metal end plunger	Steel roller plunger	Thermoplastic roller lever	Steel roller lever
References of assembled devices with 3-pole N.C. + N.C. + N.O. break before make, slow break contact				
With 1/2"-14 NPT cable entry				
	XCSD3710N12 ⊖	**XCSD3702N12** ⊖	**XCSD3718N12** ⊖	**XCSD3719N12** ⊖
With ISO M20 x 1.5 cable entry				
	XCSD3710P20 ⊖	**XCSD3702P20** ⊖	**XCSD3718P20** ⊖	**XCSD3719P20** ⊖
With Pg 13.5 cable entry				
	XCSD3710G13 ⊖	**XCSD3702G13** ⊖	**XCSD3718G13** ⊖	**XCSD3719G13** ⊖
Weight lb (kg)	0.47 (0.215)	0.49 (0.220)	0.56 (0.255)	0.56 (0.255)

Contact functional diagrams



3-pole N.C. + N.C. + N.O. break before make, slow break contact

1,8 3,2(P) 21-22 31-32 13-14 0 3 5mm	3,1(A) 5,6(P) 21-22 31-32 13-14 0 5,2 mm	25˚ 70˚(P) 21-22 31-32 13-14 0 42˚ 90˚	25˚ 70˚(P) 21-22 31-32 13-14 0 42˚ 90˚

Contact operation

■ *contact closed* *(A) = cam displacement*
□ *contact open* *(P) = positive opening point*
⊖ *N.C. contact with positive opening operation*

Additional specifications not shown under General Specifications (page 4/31)

Switch actuation		On end	By 30° cam	
Type of actuation				
Maximum actuation speed		1.64 ft/s (0.5 ms)		4.9 ft/s (1.5 ms)
Minimum force or torque	For tripping	3.72 lb (15 N)	2.70 lb (12 N)	0.89 lb-in. (0.1 N•m)
	For positive opening	10.12 lb (45 N)	8.09 lb (36 N)	2.21 lb-in. (0.25 N•m)
Conduit entry		1 entry tapped M20 x 1.5 mm for ISO cable connector, clamping capacity 7 to 13 mm 1 entry tapped Pg 13.5 for cable connector, clamping capacity 9 to 12 mm 1 entry tapped for 1/2"-14 NPT (USAS B2-1) conduit		

Dimensions *in. (mm)*

XCSD3●18●●●, XCSD3●19●●●



(1) Tapped entry for ISO M20 x 1.5 or Pg 13.5 cable connector or 1/2"-14 NPT conduit.
(2) 2 elongated holes Ø0.17 x .25 in. (Ø4.3 x 6.3 mm) on 0.87 in. (22 mm) centers or 2 holes Ø0.17 in. (Ø4.3 mm) on 0.79 in. (20 mm) centers.
(3) 0.08 x Ø0.12 in. (2 x Ø3 mm) holes for studs, depth . 16 in. (4 mm).

Dual Dimensions: INCHES Millimeters

Introduction: page 4/30 | Specifications: page 4/31 | References: pages 4/32 to 4/35 | Dimensions: pages 4/32 to 4/35

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Compact design, plastic, type XCSP

Type of head	Plunger		Rotary	
				
Type of operator	Metal end plunger	Steel roller plunger	Thermoplastic roller lever	Steel roller lever
References of assembled devices with 3-pole N.C. + N.C. + N.O. snap action contact				
With 1/2"-14 NPT cable entry				
	XCSP3910N12 ⊖	**XCSP3902N12** ⊖	**XCSP3918N12** ⊖	**XCSP3919N12** ⊖
With ISO M20 x 1.5 cable entry				
	XCSP3910P20 ⊖	**XCSP3902P20** ⊖	**XCSP3918P20** ⊖	**XCSP3919P20** ⊖
With Pg 13.5 cable entry				
	XCSP3910G13 ⊖	**XCSP3902G13** ⊖	**XCSP3918G13** ⊖	**XCSP3919G13** ⊖
Weight lb (kg)	0.47 (0.215)	0.49 (0.220)	0.56 (0.255)	0.56 (0.255)

Contact functional diagrams



3-pole N.C. + N.C. + N.O. snap action contact

Contact operation				

contact closed *(A) = cam displacement*
contact open *(P) = positive opening point*
⊖ *N.C. contact with positive opening operation*

Additional specifications not shown under General Specifications (page 4/31)

Switch actuation		On end	By 30° cam	
Type of actuation				
Maximum actuation speed		1.64 ft/s (0.5 ms)		4.9 ft/s (1.5 ms)
Minimum force or torque	For tripping	3.72 lb (15 N)	2.70 lb (12 N)	0.89 lb-in. (0.1 N•m)
	For positive opening	10.12 lb (45 N)	8.09 lb (36 N)	2.21 lb-in. (0.25 N•m)
Conduit entry		1 entry tapped M20 x 1.5 mm for ISO cable connector, clamping capacity 7 to 13 mm 1 entry tapped Pg 13.5 for cable connector, clamping capacity 9 to 12 mm 1 entry tapped for 1/2"-14 NPT (USAS B2-1) conduit		

Dimensions *in. (mm)*

XCSP3●10●●●



XCSP3●02●●●



(1) Tapped entry for ISO M20 x 1.5 or Pg 13.5 cable connector or 1/2"-14 NPT conduit.
(2) 2 elongated holes Ø.17 x .25 in. (Ø4.3 x 6.3 mm) on .87 in. (22 mm) centers or 2 holes Ø.17 in. (Ø4.3 mm) on .79 in. (20 mm) centers.
(3) .08 x Ø.12 in. (2 x Ø3 mm) holes for studs, depth .16 in. (4 mm).

Dual Dimensions: INCHES Millimeters

Introduction: page 4/30 | Specifications: page 4/31 | References: pages 4/32 to 4/35 | Dimensions: pages 4/32 to 4/35

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety limit switches
Compact design, plastic, type XCSP

Type of head	Plunger		Rotary	
				
Type of operator	Metal end plunger	Steel roller plunger	Thermoplastic roller lever	Steel roller lever
References of assembled devices with 3-pole N.C. + N.C. + N.O. break before make, slow break contact				
With 1/2"-14 NPT cable entry				
	XCSP3710N12 ⊖	**XCSP3702N12** ⊖	**XCSP3718N12** ⊖	**XCSP3719N12** ⊖
With ISO M20 x 1.5 cable entry				
	XCSP3710P20 ⊖	**XCSP3702P20** ⊖	**XCSP3718P20** ⊖	**XCSP3719P20** ⊖
With Pg 13.5 cable entry				
	XCSP3710G13 ⊖	**XCSP3702G13** ⊖	**XCSP3718G13** ⊖	**XCSP3719G13** ⊖
Weight lb (kg)	0.47 (0.215)	0.49 (0.220)	0.56 (0.255)	0.56 (0.255)

Contact functional diagrams



3-pole N.C. + N.C. + N.O. break before make, slow break contact

1,8 3,2(P) 21-22 31-32 13-14 0 3 5mm	3,1(A) 5,6(P) 21-22 31-32 13-14 0 5,2 mm	25° 70°(P) 21-22 31-32 13-14 0 42° 90°	25° 70°(P) 21-22 31-32 13-14 0 42° 90°

Contact operation

■ *contact closed* *(A) = cam displacement*
□ *contact open* *(P) = positive opening point*
⊖ *N.C. contact with positive opening operation*

Additional specifications not shown under General Specifications (page 4/31)

Switch actuation		On end	By 30° cam	
Type of actuation				
Maximum actuation speed		1.64 ft/s (0.5 ms)		4.9 ft/s (1.5 ms)
Minimum force or torque	For tripping	3.72 lb (15 N)	2.70 lb (12 N)	0.89 lb-in. (0.1 N•m)
	For positive opening	10.12 lb (45 N)	8.09 lb (36 N)	2.21 lb-in. (0.25 N•m)
Conduit entry		1 entry tapped M20 x 1.5 mm for ISO cable connector, clamping capacity 7 to 13 mm 1 entry tapped Pg 13.5 for cable connector, clamping capacity 9 to 12 mm 1 entry tapped for 1/2"-14 NPT (USAS B2-1) conduit		

Dimensions *in. (mm)*

XCSP3•18•••, XCSP3•19•••



(1) Tapped entry for ISO M20 x 1.5 or Pg 13.5 cable connector or 1/2"-14 NPT conduit.
(2) 2 elongated holes Ø0.17 x 0.25 in. (Ø4.3 x 6.3 mm) on 0.87 in. (22 mm) centers or 2 holes Ø0.17 in. (Ø4.3 mm) on 0.79 in. (20 m) centers.
(3) 0.08 x Ø0.12 in. (2 x Ø3 mm) holes for studs, depth . 16 in. (4 mm).

Dual Dimensions: INCHES Millimeters

Introduction: page 4/30 | Specifications: page 4/31 | References: pages 4/32 to 4/35 | Dimensions: pages 4/32 to 4/35

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety interlock switches with lever or rotary shaft operator
Plastic, double insulated, turret head, types XCSPL, XCSTL, XCSPR, XCSTR

XCSPL with 1 conduit entry

With rotary operating head, with elbowed lever (flush with rear of switch) or straight lever, for hinged covers and guards



Page 4/38

XCSPR with 1 conduit entry

With rotary operating head, with rotary shaft, for hinged covers and guards



Page 4/38

XCSTL with 2 conduit entries

With rotary operating head, with elbowed lever (flush with rear of switch) or straight lever, for hinged covers and guards



Page 4/38

XCSTR with 2 conduit entries

With rotary operating head, with rotary shaft, for hinged covers and guards



Page 4/38

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety interlock switches with lever or rotary shaft operator
Plastic, double insulated, turret head, types XCSPL, XCSTL, XCSPR, XCSTR

Environmental specifications

Conformity to standards	Products	EN/IEC 60947-5-1, EN/IEC 60947-5-4, UL 508, CSA C22-2 n° 14
	Machine assemblies	EN/IEC 60204-1, EN/ISO 14119
Product certifications		UL, CSA, BG
Maximum safety level *(1)*		PL=e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061
Reliability data B_{10d}		50,000,000 (value given for a service life of 20 years, limited by mechanical or contact wear)
Protective treatment		Standard version: **TC** and **TH**
Ambient air temperature	For operation	–13 to +158 °F (–25 to +70 °C)
	For storage	–40 to +158 °F (–40 to +70 °C)
Vibration resistance		50 gn (10–500 Hz) conforming to IEC 60068-2-6
Shock resistance		50 gn (duration 11 ms) conforming to IEC 60068-2-27
Electric shock protection		Class 2 conforming to EN/IEC 60536
Degree of protection		**IP67 conforming to EN/IEC 60529**
Cable entry		**XCSP●**: 1 entry tapped M16 x 1.5 for ISO cable connector (clamping capacity 4.5 to 10 mm) or for n° 11 (Pg 11) cable connector conforming to NF C 68-300 (DIN Pg 11) (clamping capacity 7 to 10 mm) or tapped for 1/2"-14 NPT (USAS B2-1) conduit. **XCST●**: 2 entries tapped M16 x 1.5 for ISO cable connector (clamping capacity 4.5 to 10 mm) or for n° 11 (Pg 11) cable connector conforming to NF C 68-300 (DIN Pg 11) (clamping capacity 7 to 10 mm) or for 1/2"-14 NPT conduit using adapter DE9RA1012 in one of the n° 11 tapped entries and a blanking plug in the other.
Materials		Polyamide PA66 fiberglass impregnated case and stainless steel lever and mountings

Contact block specifications

Rated operational specifications	2 and 3 contact versions slow break	**XCSPL, XCSTL, XCSPR, XCSTR**: ∼ AC-15, A300: Ue = 240 V, Ie = 3 A or Ue = 120 V, Ie = 6 A All models: ⎓ DC-13, Q300: Ue = 250 V, Ie = 0.27 A or Ue = 125 V, Ie = 0.55 A conforming to IEC/EN 60947-5-1
Rated insulation voltage	2 and 3 contact versions	**XCSPL, XCSTL, XCSPR, XCSTR**: Ui = 500 V conforming to IEC/EN 60947-1 Ui = 300 V conforming to UL 508, CSA C22-2 n° 14
Rated impulse withstand voltage	2 and 3 contact versions	**XCSPL, XCSTL, XCSPR, XCSTR**: Uimp = 6 kV conforming to IEC/EN 60947-5-1
Positive operation		N.C. contacts with positive opening operation conforming to EN/IEC 60947-5-1 Section 3
Resistance across terminals		⩽ 30 mΩ conforming to EN/IEC 60947-5-4
Short-circuit protection	2 and 3 contact versions	**XCSPL, XCSTL, XCSPR, XCSTR**: 10 A cartridge fuse type gG (gl)
Connection	2 contact version	**XCSPL, XCSTL, XCSPR, XCSTR**: Clamping capacity, min: 1 x 21 AWG (0.5 mm²), max: 2 x 15 AWG (1.5 mm²) with or without cable end
Minimum actuation speed	3 contact version	0.39 in./s (0.01 ms)

Additional specifications

Tripping angle	5°
Mechanical life	**1 million operating cycles**
Minimum torque	For tripping: 0.07 lb-ft; for positive opening: 0.18 lb-ft (XCSPL and XCSPR), 0.33 lb-ft (XCSTL and XCSTR)

(1) Using an appropriate and correctly connected control system.

Electrical life

- Conforming to EN/IEC 60947-5-1 Appendix C
- Utilization categories AC-15 and DC-13
- Maximum operating rate: 3600 operating cycles/hour
- Load factor: 0.5

AC supply
∼ 50/60 Hz
⎓⎓ inductive circuit

2 and 3 slow break contact versions



DC supply ⎓

Power (in W) broken for 1 million operating cycles

Voltage	**V**	**24**	**48**	**120**
⎓⎓	**W**	13	9	7

The product life expressed is based on average usage and normal operating conditions. Actual operating life will vary with conditions. The above statements are not intended to nor shall they create any express or implied warranties as to product operation or life. For information on the limited warranty offered on this product please refer to the Schneider Electric Conditions of Sale found in the *Digest*.

Introduction: page 4/36 | Specifications: page 4/37 | References: page 4/38 | Dimensions: page 4/39 | Wiring diagrams: page 4/39

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety interlock switches with lever or shaft operator
Plastic, double insulated, turret head, types XCSPL, XCSTL, XCSPR, XCSTR

Type	Elbowed lever (flush with rear of switch)			Straight lever		Shaft
						
Operator	To left	Centered	To right	To right OR to left	Centered	Length 1.18 in. (30 mm) *(2)*
References (⊖ N.C. contact with positive opening operation)						
2-pole N.C. + N.O. break before make slow break	**XCSPL593** ⊖	**XCSPL583** ⊖	**XCSPL573** ⊖	**XCSPL563** ⊖	**XCSPL553** ⊖	**XCSPR553** ⊖
2-pole N.C. + N.C. slow break	**XCSPL793** ⊖	**XCSPL783** ⊖	**XCSPL773** ⊖	**XCSPL763** ⊖	**XCSPL753** ⊖	**XCSPR753** ⊖
Weight lb (kg)	0.21 (0.095)	0.21 (0.095)	0.21 (0.095)	0.21 (0.095)	0.21 (0.095)	0.23 (0.105)

						
Operator	To left	Centered	To right	To right OR to left	Centered	Length 1.18 in. (30 mm) *(2)*
References (⊖ N.C. contact with positive opening operation)						
3-pole N.C. + N.O. + N.O. (2 N.O. break before make) slow break 	–	**XCSTL583** ⊖	–	**XCSTL563** ⊖	**XCSTL553** ⊖	**XCSTR553** ⊖
3-pole N.C. + N.C. + N.O. (N.O. break before make) slow break 	**XCSTL793** ⊖	**XCSTL783** ⊖	**XCSTL773** ⊖	**XCSTL763** ⊖	**XCSTL753** ⊖	**XCSTR753** ⊖
3-pole N.C. + N.C. + N.C. slow break 	–	**XCSTL883** ⊖	**XCSTL873** ⊖	**XCSTL863** ⊖	–	**XCSTR853** ⊖
Weight lb (kg)	0.32 (0.145)	0.32 (0.145)	0.32 (0.145)	0.32 (0.145)	0.32 (0.145)	0.34 (0.155)

Adapter reference: XCSTL or XCSTR with 1/2"-14 NPT conduit

One conduit adapter for 1/2"-14 NPT conduit is included with each device.
For a second conduit adapter when using 2 conduit openings, order an additional conduit adapter: DE9RA1012.

	Threaded for Pg 11 and supplied with a Pg 11 to 1/2"-14 NPT adapter	Sold in lots of 10	**DE9RA1012**
		Weight lb (kg)	0.11 (0.050)

(1) Head adjustable in 90° steps throughout 360°. Switches supplied with 2 additional self-locking screws for positive mounting of the head.
*(2) For switches with 3.15 in. (80 mm) rotary shaft: replace the 2nd number in the reference (5) with **6**. Example: XCSPR5**5**3 becomes XCSPR5**6**3. The weight increases by 1.1 oz. (0.032 kg.)*

The devices listed above are threaded for Pg 11 and supplied with a Pg 11 to 1/2"-14 NPT adapter (using the supplied adapter on the XCST) and are available with metric conduit:

- To order devices tapped for 11 mm cable connector, conforming to NFC 68-300 (DIN Pg 11): Change the last character in the reference to 1. For example: XCSPL593 changes to XCSPL591.
- To order devices tapped for M16 x 1.5 for ISO cable connector: Change the last character in the reference to 2.For example: XCSPL59**3** changes to XCSPL59**2**.

Introduction: page 4/36 | Specifications: page 4/37 | References: page 4/38 | Dimensions: page 4/39 | Wiring diagrams: page 4/39

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Preventa™ safety interlock switches with lever or shaft operator
Plastic, double insulated, turret head, types XCSPL, XCSTL, XCSPR, XCSTR

Operation

Operator displacement

XCSPL•93, PL•73, PL•63



XCSPL•83, PL•53

XCSTL•93, TL•73, TL•63



XCSTL•83, TL•53

XCSPR•53

XCSTR•53

Functional diagrams

XCSPL593, PL573, PL563



XCSPL583, PL553



XCSTL563



XCSTL583, TL553



XCSPR553



XCSTR553



XCSPL793, PL773, PL763



XCSPL783, PL753



XCSTL793, TL773, TL763



XCSTL783, TL753



XCSPR753



XCSTR753



Contact operation

■ contact closed
□ contact open

XCSTL873, TL863



XCSTL883, TL853



XCSTR853



Dimensions *in. (mm)*

XCSPL••3



(1) 1 tapped entry for 1/2"-14 NPT conduit
Ø: 2 elongated holes Ø0.17 x 0.33 in. (4.3 x 8.3 mm) on 0.87 in. (22 mm) centers, 2 holes Ø0.17 in. (4.3 mm) on 0.79 in. (20 mm) centers

XCSTL••3



Dual Dimensions: INCHES / Millimeters

(1) 2 tapped entries for n° 11 cable connector
(2) 2 elongated holes Ø0.17 x 0.33 in. (4.3 x 8.3 mm) on 0.87 in. (22 mm) centers, 2 holes Ø0.17 in. (4.3 mm) on 0.79 in. (20 mm) centers
(3) 22 elongated holes Ø0.21 x 0.52 in. (5.3 x 13.3 mm)

XCSPR••3



(1) 1 tapped entry for 1/2"-14 NPT conduit
Ø: 2 elongated holes Ø0.17 x 0.33 in. (4.3 x 8.3 mm) on 0.87 in. (22 mm) centers, 2 holes Ø0.17 in. (4.3 mm) on 0.79 in. (20 mm) centers
L = 1.18 in. (30 mm) (XCSPR•53)
or 3.15 in. (80 mm) (XCSPR•63)

XCSTR••3



(1) 2 tapped entries for n° 11 cable connector
(2) 2 elongated holes Ø0.17 x 0.33 in. (4.3 x 8.3 mm) on 0.87 in. (22 mm) centers, 2 holes Ø0.17 in. (4.3 mm) on 0.79 in. (20 mm) centers
(3) 2 elongated holes Ø0.21 x 0.52 in. (5.3 x 13.3 mm)
L = 1.18 in. (30 mm) (XCSTR•53)
or 3.15 in. (80 mm) (XCSTR•63)

Wiring diagrams

PL=b, category 1 conforming to EN/ISO 13849-1

Example with cable short-circuit protection fuse



PL=d, category 3 conforming to EN/ISO 13849-1

Example with 3-pole N.C. + N.O. + N.O. contact with mixed redundancy of the contacts and the associated control relays



To activate K1, the lever or spindle must be rotated when the supply is switched on. H1: "lever or spindle displaced from initial position" indicator. When used in conjunction with an XPS safety relay module and another safety switch, the rotary lever or rotary shaft operator safety interlock switch can provide locking protection to PL=d, category 3 or PL=e, category 4 conforming to EN/ISO 13849-1.

Introduction: page 4/36 | Specifications: page 4/37 | References: page 4/38 | Dimensions: page 4/39 | Wiring diagrams: page 4/39

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, double insulated, turret head, types XCSMP, XCSPA, XCSTA
Metal, turret head, types XCSA, XCSB, XCSC

Plastic, types XCSMP, XCSPA, XCSTA

Safety interlock switches with or without locking of the actuator



Pages 4/42 and 4/46

Metal, types XCSA, XCSB, XCSC

Safety interlock switches with or without locking of the actuator



Page 4/50

Environmental specifications

Safety interlock switch type		XCSMP, XCSPA, XCSTA (plastic)	XCSA, XCSB, XCSC (metal)
Conformity to standards	Products	EN/IEC 60947-5-1, UL 508, CSA C22-2 n° 14	
	Machine assemblies	EN/IEC 60204-1, EN/ISO 14119	
Product certifications		UL, CSA (cULus for **XCSMP**)	UL, CSA
Maximum safety level *(1)*		PL=e, Category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061	
Reliability data B_{10d}		5,000,000 (value given for a service life of 20 years, limited by mechanical or contact wear)	
Protective treatment		Standard version: **TC**	
Ambient air temperature	For operation	–13 °F to +158 °F (–25 °C to +70 °C)	
	For storage	–40 °F to +158 °F (–40 °C to +70 °C); –13 °F to +176 °F (–25 °C to +80 °C) for **XCSMP**	
Vibration resistance		5 gn (10–500 Hz) conforming to EN/IEC 60068-2-6. For **XCSMP**: 6 gn (10–55 Hz).	
Shock resistance		10 gn (duration 11 ms) conforming to EN/IEC 60068-2-27. For **XCSMP**: 50 gn (duration 11 ms).	
Electric shock protection		Class 2 conforming to EN/IEC 60536	Class 1 conforming to EN/IEC 60536
Degree of protection		**IP67 conforming to EN/IEC 60529 and EN/IEC 60947-5-1** Live parts of these switches are protected against the penetration of dust and water. However, when installing take all necessary precautions to prevent the penetration of solid bodies, or liquids with a high dust content, into the actuator aperture. Not recommended for use in saline atmospheres	
Cable entry		1 entry (**XCSPA**) or 2 entries (**XCSTA**) tapped for ISO M16 x 1.5 cable connector (clamping capacity 4.5 to 10 mm) or for n° 11 (Pg 11) cable connector, or tapped 1/2" NPT, or for 1/2"-14 NPT (USAS B2-1) conduit using metal adapter DE9 RA1012) for **XCSTA** (other entry fitted with blanking plug).	1 entry tapped ISO M20 x 1.5 (clamping capacity 7 to 13 mm) or tapped for n° 13 (Pg 13.5) cable connector conforming to NFC 68-300 (clamping capacity 9 to 12 mm) or for 1/2"-14 NPT (USAS B2-1) conduit
Connecting cable		Precabled, either 4 x 0.5 mm^2 or 6 x 0.5 mm^2 (**XCSMP**)	–
Materials		XCSMP/PA/TA Polyamide PA66 fibreglass impregnated case	XCSA/B/C Zamak case
		Actuators (all types): steel XC60, surface treated	

(1) Using an appropriate and correctly connected control system.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, double insulated, turret head, types XCSMP, XCSPA, XCSTA
Metal, turret head, types XCSA, XCSB, XCSC

Contact block specifications

Rated operational specifications		2 and 3 contact, slow break	**XCSA**, **XCSB**, **XCSC**, **XCSTA**, **XCSPA**: ∼ AC-15, A300: Ue = 240 V, Ie = 3 A or Ue = 120 V, Ie = 6 A **XCSMP**: ∼ AC-15, C300: Ue = 240 V, Ie = 0.75 A or Ue = 120 V, Ie = 1.5 A All models: ⎓ DC-13, Q300: Ue = 250 V, Ie = 0.27 A or Ue = 125 V, Ie = 0.55 A conforming to EN/IEC 60947-5-1
		2 contact, snap action	**XCSPA**: ∼ AC-15, A300: Ue = 240 V, Ie = 3 A; Ithe = 10 A ⎓ DC-13, Q300: Ue = 250 V, Ie = 0.27 A or Ue = 125 V, Ie = 0.55 A conforming to EN/IEC 60947-5-1
Conventional thermal current in enclosure			**XCSA**, **XCSB**, **XCSC**, **XCSPA** (2 & 3 slow break contact and 2 snap action contact versions) **XCSMP**: Ithe = 2.5 A
Rated insulation voltage			Ui = 500 V conforming to EN/IEC 60947-1; Ui = 300 V conforming to UL 508, CSA C22-2 n° 14
Rated impulse withstand voltage			Uimp = 6 kV conforming to EN/IEC 60947-5-1
Positive operation			N.C. contacts with positive opening operation conforming to EN/IEC 60947-5-1, Section 3
Resistance across terminals			≤ 30 mΩ conforming to EN/IEC 60947-5-4
Short-circuit protection			10 A cartridge fuse type gG (gl)
Connection	Precabled		4 x 20 AWG (0.5 mm²) or 6 x 20 AWG (0.5 mm²) (**XCSMP**), PVC
	Screw clamp terminals	2 contact, snap action	**XCSPA**, **XCSTA**: Clamping capacity, min: 1 x 22 AWG (0.34 mm²), max: 2 x 14 AWG (1.5 mm²)
		2 and 3 contact	**3 contact (XCSA, XCSB, XCSC, XCSTA)**, 2 contact **(XCSPA)**: Clamping capacity, min: 1 x 20 AWG (0.5 mm²), max: 2 x 14 AWG (1.5 mm²) with or without cable end

Electrical durability

Conforming to EN/IEC 60947-5-1 Appendix C.
Utilization categories AC-15 and DC-13.
Maximum operating rate: 3600 operating cycles/hour.
Load factor: 0.5

Only applicable to **XCSMP**:
Conforming to EN/IEC 60947-5-1 Appendix C.
Utilization categories AC-15 and DC-13.
Maximum operating rate: 900 operating cycles/hour.

AC supply
50/60 Hz ∼
⎓ inductive circuit

2 snap action contact version



3 contact version XCSA/B/C/TA and 2 slow break contact version



DC supply ⎓
Power (in W) broken for 5 million operating cycles.

Voltage	**V**	**24**	**48**	**120**
⎓	**W**	10	7	4

Voltage	**V**	**24**	**48**	**120**
⎓	**W**	13	9	7

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, double insulated, fixed head, type XCSMP
Precabled, length 6.6, 16.4, or 32.8 ft (2, 5, or 10 m)

Type of switch	Without locking of actuating key



References of switches without actuating key (⊖ N.C. contact with positive opening operation) *(1)*

Schematic diagrams shown represent the contact states while the operating key is inserted in the head of the switch.

2-pole N.C. + N.O. **break before make, slow break** 6.6 ft (2 m) cable *(2)*		**XCSMP59L2** ⊖
2-pole N.C. + N.C. **slow break** 6.6 ft (2 m) cable *(2)*		**XCSMP79L2** ⊖
3-pole N.C. + N.C. + N.O. **break before make, slow break** 6.6 ft (2 m) cable *(2)*		**XCSMP70L2** ⊖
3-pole N.C. + N.C. + N.C. **slow break** 6.6 ft (2 m) cable *(2)*		**XCSMP80L2** ⊖
Weight lb (kg)		0.24 (0.110)

Additional specifications not shown under General Specifications (pages 4/40 and 4/41)

Actuation speed	Maximum: 59 in./s (1.5 ms), minimum: 2 in./s (0.05 ms)
Resistance to forcible withdrawal of actuating key	1.8 lbs. (8 N)
Connection	Precabled, 4 x 20 AWG (0.5 mm²) or 6 x 20 AWG (0.5 mm²)
Maximum operating rate	For maximum life: 1200 operating cycles per hour
Minimum force for extraction of key	1.8 lbs. (8 N)

References of actuating keys

Description	Straight key	Right-angled key	Pivoting key For right-hand door	Pivoting key For left-hand door
				
For switches XCSMP	**XCSZ81**	**XCSZ84**	**XCSZ83**	**XCSZ85**
Weight lb (kg)	0.03 (0.015)	0.06 (0.025)	0.19 (0.085)	0.19 (0.085)

Spare parts

Description	Unit reference	Weight lb (kg)
Blanking plugs (Sold in lots of 10)	**XCSZ29**	0.01 (0.005)

(1) A blanking plug for the operating head slot is included with the switch.
(2). References shown have a 6.6 ft (2 m) cable. Other cable lengths are available: replace the 2 at the end of the reference with 5 for a 16.4 ft (5m) cable, or with 10 for a 32.8 ft (10 m) cable.
*Example: XCSMP59L**2** becomes XCSMP59L**10** for a switch with a 32.8 ft (10 m) cable.*

Introduction: page 4/40 | Specifications: page 4/40 | References: page 4/42 | Dimensions: page 4/43 | Wiring diagrams: page 4/45

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, double insulated, fixed head, type XCSMP
Precabled, length 6.6, 16.4, or 32.8 ft (2, 5, or 10 m)

Dimensions *in. (mm)*

XCSMP



(1) Ø0.29 in. (7.6 mm); length 6.6, 16.4, or 32.8 ft (2, 5, or 10 m).

XCSZ81



XCSZ84



XCSZ83



(1) 2 elongated holes Ø0.17 x 0.24 in. (4.2 x 6.0 mm).

XCSZ85



(1) 2 elongated holes Ø0.17 x 0.24 in. (4.2 x 6.0 mm).

Dual Dimensions: INCHES / Millimeters

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, double insulated, fixed head, type XCSMP
Precabled, length 6.6, 16.4, or 32.8 ft (2, 5, or 10 m)

Operating radius required for key

XCSZ81



XCSZ84



XCSZ83



XCSZ85



Functional diagrams

XCSMP59●



XCSMP79●



XCSMP70●



XCSMP80●



Contact operation

Contact closed
Contact open

Dual Dimensions: INCHES Millimeters

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, double insulated, fixed head, type XCSMP
Precabled, length 6.6, 16.4, or 32.8 ft (2, 5, or 10 m)

Wiring diagrams *(These wiring diagrams are given as examples only; the designer must refer to the relevant safety standards for guidance.)*

Wiring to PL=b, category 1 conforming to EN/SO 13849-1

Example with 3-pole N.C. + N.C. + N.O. contact and protective fuse to prevent jumpering of the N.C. contact, either by cable damage or by tampering.



Wiring to PL=d, category 3 conforming to EN/ISO 13849-1

Example with 2-pole N.C. + N.O. contact with mixed redundancy of the contacts and the associated control relays.
To activate K1, it is necessary to remove and re-insert the actuator when the supply is switched on.



(1) Signaling contact

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061. Wiring method used in conjunction with Preventa™ safety relay (the keyed safety interlock switch is generally used in conjunction with a safety limit switch)

Method for machines with quick rundown time (low inertia)
Locking or interlocking mechanism uses the principles of redundancy and autocheck.
The safety relays help to ensure these functions.



Locking by actuating key and actuation in positive mode associated with a safety relay module

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, turret head(1), types XCSPA and XCSTA
Conduit entries tapped 1/2"-14 NPT

Type of switch		Without locking of actuator			
					
References of switches without actuating key (⊖ **N.C. contact with positive opening operation**)					
2-pole N.C. + N.O. *(2)* break before make slow break		**XCSPA593**	⊖	–	
2-pole N.O. + N.C. *(2)* make before break slow break		**XCSPA693**	⊖	–	
2-pole N.C. + N.C. *(2)* slow break		**XCSPA793**	⊖	–	
3-pole N.C. + N.O. + N.O. *(2)* (2 N.O. break before make) slow break		–		**XCSTA593**	⊖
3-pole N.C. + N.C. + N.O. *(2)* (N.O. break before make) slow break		–		**XCSTA793**	⊖
3-pole N.C. + N.C. + N.C. *(2)* slow break		–		**XCSTA893**	⊖
Weight lb (kg)		0.24 (0.110)		0.35 (0.160)	

Additional specifications not shown under General Specifications (pages 4/40 and 4/41)

Actuation speed	Maximum: .19.6 in./s (0.5 ms), minimum: 0.39 in./s (0.01 ms)
Resistance to forcible withdrawal of actuator	**XCSPA**, **XCSTA**: 2.3 lbs (10 N) (11.3 lbs [50 N] using actuators **XCSZ12** or **XCSZ13** together with guard retaining device **XCSZ21**)
Maximum operating rate	For maximum life: 600 operating cycles per hour
Minimum force for positive opening	3.4 lbs (15 N)
Cable entry	**XCSPA**: 1 entry tapped for 1/2"-14 NPT (USAS B2-1) conduit. **XCSTA**: 2 entries tapped 11 mm, 1 mounted with metal adapter DE9RA1012 for 1/2"-14 NPT (USAS B2-1) conduit. Second entry fitted with blanking plug.
Materials	Polyamide PA66 fiberglass impregnated case.

References of accessories

XCSZ91



XCSZ200

DE9RA1012

Description	For use with	Unit reference	Weight lb (kg)
Blanking plugs for operating head slot (Sold in lots of 10)	XCSPA, XCSTA	**XCSZ28**	0.11 (0.050)
Padlocking device to prevent insertion of actuator, for up to 3 padlocks (padlocks not included)	XCSPA, XCSTA	**XCSZ91**	0.12 (0.053)
Actuator centering device *(3)* (Mounting screws included)	XCSPA, XCSTA	**XCSZ200**	0.05 (0.022)
1/2"-14 NPT conduit adapter (Sold in lots of 10)	XCSTA	**DE9RA1012**	0.11 (0.050)

(1) Head adjustable in 90° steps throughout 360°. A blanking plug for the operating head slot is included with the switch.
(2) Wiring diagrams shown represent the contact states while the actuating key is inserted in the head of the switch.
(3) Do not use with XCSZ91.

The devices listed above are threaded for 1/2"-14 NPT (using the supplied adapter on the XCSTA), and are available with metric conduit:

- To order devices tapped for an 11 mm cable connector, conforming to NFC 68-300 (DIN Pg 11): Change the last character in the reference to 1. For example: XCSPA59**3** changes to XCSPA59**1**
- To order devices tapped for an M16 x 1.5 for ISO cable connector: Change the last character in the reference to 2. For example: XCSPA59**3** changes to XCSPA59**2**

References: page 4/46 | Specifications: page 4/46 | Dimensions: page 4/47 | Wiring diagrams: page 4/49

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, turret head, types XCSPA and XCSTA
Conduit entries tapped 1/2”-14 NPT

References of actuators and guard retaining device



Description	Straight actuator	Actuator with wide mounting *(1)*		Pivoting actuator	Right-angled actuator	Guard retaining device *(2)*
For safety interlock switches XCS PA, TA	**XCSZ11**	**XCSZ12**	**XCSZ15**	**XCSZ13**	**XCSZ14**	**XCSZ21**
Weight lb (kg)	0.03 (0.015)	0.03 (0.015)	0.03 (0.012)	0.19 (0.085)	0.06 (0.025)	0.18 (0.080)

(1) 2 actuator lengths, XCSZ12: 1.57 in. (40 mm), XCSZ15: 1.14 in. (29 mm).
(2) Only for use with safety interlock switches XCSPA and XCSTA (without actuator centering device XCSZ200) used in conjunction with actuators XCSZ12, XCSZ13 or XCSZ15.

Dimensions *in. (mm)*

XCSPA●91, XCSPA●92



(1) 1 tapped entry for cable connector
Ø: 2 elongated holes Ø0.17 x 0.33 in. (4.3 x 8.3 mm) on 0.87 in. (22 mm) centers, 2 holes Ø0.17 in. (4.3 mm) on 0.79 in. (20 mm) centers

XCSPA●93



(1) 1 tapped entry tapped for 1/2"-14 NPT conduit
Ø: 2 elongated holes Ø0.17 x 0.33 in. (4.3 x 8.3 mm) on 0.87 in. (22 mm) centers, 2 holes Ø0.17 in. (4.3 mm) on 0.79 in. (20 mm) centers

XCSTA●9●



(1) 2 tapped entries for cable connector or 1/2"-14 NPT conduit adapter
(2) 2 elongated holes Ø0.17 x 0.33 in. (4.3 x 8.3 mm) on 0.87 in. (22 mm) centers, 2 holes Ø0.17 in. (4.3 mm) on 0.79 in. (20 mm) centers
(3) 2 elongated holes Ø0.21 x 0.52 in. (5.3 x 13.3 mm)

Actuator centering device XCSZ200



Dual Dimensions: INCHES / Millimeters

1/2"-14 NPT conduit adapter
DE9RA1012



(1) Tapped entry for 1/2"-14 NPT conduit
(2) Pg 11 threaded shank

References: page 4/46 | Specifications: page 4/46 | Dimensions: page 4/47 | Wiring diagrams: page 4/49

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, turret head, types XCSPA and XCSTA

Dimensions (continued) *in. (mm)*

XCSZ11



(1) Adapter (included with actuating key XCSZ11) for replacing, without drilling additional mounting hole, an XCKT with actuating key XCKY01 by a safety interlock switch XCSTA with actuating key XCSZ11.

Ø a: 2 elongated holes Ø0.19 x 0.39 in. (4.7 x 10 mm)

Ø b: 1 elongated hole for M4 or M4.5 screw

XCSZ12, XCSZ15



Ø: 2 elongated holes Ø0.19 x 0.39 in. (4.7 x 10 mm)

L = 1.57 in. (40 mm) (XCSZ12) or 1.14 in. (29 mm) (XCSZ15)

XCSZ13



Ø: 2 elongated holes Ø0.19 x 0.39 in. (4.7 x 10 mm)

XCSZ14



Ø: 1 elongated hole Ø0.19 x 0.39 in. (4.7 x 10 mm)

Operating radius required for actuator

XCSZ11



XCSZ12, XCSZ15



d = 1.81 in. (46 mm) (XCSZ12) or 1.38 in. (35 mm) (XCSZ15)

XCSZ13



XCSZ14



Dual Dimensions: INCHES Millimeters

R = minimum radius

References: page 4/46 | Specifications: page 4/46 | Dimensions: page 4/47 | Wiring diagrams: page 4/49

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Safety interlock switches, actuator operated
Plastic, turret head, types XCSPA and XCSTA

Setup

Functional diagrams

XCSPA5●●



XCSPA6●●



XCSPA7●●



XCSTA5●●



XCSTA7●●



Contact operation

Contact closed Contact open Contacts in transition

Dual Dimensions: INCHES / Millimeters

4

Setup

Functional diagrams

XCSTA8●●



Contact operation

Contact closed
Contact open
Contact in transition

Wiring diagrams

(These wiring diagrams are given as examples only; the designer must refer to the relevant safety standards for guidance.)

Wiring to PL=b, category 1 conforming to EN/ISO 13849-1

Example with 3-pole N.C. + N.O. + N.O. contact and protection fuse to prevent jumpering of the N.C. contact, either by cable damage or by tampering.



(1) Signaling contact

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1

Example with 2-pole N.C. + N.O. contact with mixed redundancy of the contacts and the associated control relays. To activate K1, it is necessary to remove and re-insert the actuator when the supply is switched on.



Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061

Wiring method used in conjunction with safety relay module

(The guard interlock switch should be used in conjunction with a safety limit switch to give electrical/mechanical redundancy.)

Method for machines with quick rundown time (low inertia)

Locking or interlocking device based on the principle of redundancy and self-monitoring.



Locking of actuator and operation in positive mode associated with a safety relay module.

References: page 4/46
Specifications: page 4/46
Dimensions: page 4/47
Wiring diagrams: page 4/49

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Metal, turret head(1), types XCSA, XCSB and XCSC
Conduit entries tapped 1/2"-14 NPT

Type of switch	Without locking of actuator			With locking of actuator, manual unlocking (2)			
							
LED indication on opening of N.C. contacts	Without	1 orange LED ⎓ 24/48 V	1 orange LED ∿ 110/240 V	Without	1 orange LED ⎓ 24/48 V	1 orange LED ∿ 110/240 V	Without

References of switches without actuator (⊖ N.C. contact with positive opening operation)

Schematic diagrams shown represent the contact states while the actuating key is inserted in the head of the switch.

3-pole N.C. + N.O. + N.O. (2 N.O. break before make) slow break 	**XCSA503** ⊖	–	**XCSA523** ⊖	**XCSB503** ⊖	–	–	–
3-pole N.C. + N.C. + N.O. (N.O. break before make) slow break 	**XCSA703** ⊖	**XCSA713** ⊖	**XCSA723** ⊖	**XCSB703** ⊖	**XCSB713** ⊖	**XCSB723** ⊖	**XCSC703** ⊖
3-pole N.C. + N.C. + N.C. slow break 	**XCSA803** ⊖	–	–	**XCSB803** ⊖	–	–	**XCSC803** ⊖
Weight lb (kg)	0.97 (0.440)	0.97 (0.440)	0.97 (0.440)	1.05 (0.475)	1.05 (0.475)	1.05 (0.475)	1.06 (0.480)

Additional specifications not shown under General Specifications (pages 4/40 and 4/41)

Actuation speed	Maximum: 19.7 in./s (0.5 ms), minimum: 0.39 in./s (0.01 ms)
Resistance to forcible withdrawal of actuator	**XCSB** and **XCSC**: 337 lbs. (1500 N)
Maximum operating rate	For maximum life: 600 operating cycles per hour
Minimum force for extraction of actuator	≥ 4.5 lbs (20 N)
Cable entry	**XCSA**, **XCSB**, **XCSC**: 1 conduit entry Entries tapped for 1/2"-14 NPT (USAS B2-1) conduit
Materials	Body: Zamak. Head: Zamak.

References of actuators

				
Description	Straight actuator	Actuator with wide mounting	Pivoting actuator	Latch for sliding doors (Padlockable in open position)
For safety interlock switches XCS A, B, C, E	**XCSZ01**	**XCSZ02**	**XCSZ03**	**XCSZ05**
Weight lb (kg)	0.04 (0.020)	0.04 (0.020)	0.21 (0.095)	1.32 (0.600)

(1) Head adjustable in 90° steps throughout 360°. A blanking plug for the operating head slot is included with switch.
(2) Unlocking by pushbutton for XCSB●●● and by key operated lock for XCSC●●● (2 keys included with switch).

The devices listed above are threaded for 1/2"-14 NPT, and are available with metric conduit:
- To order devices tapped for 13 mm cable connector, conforming to NFC 68-300 (DIN Pg 13.5): Change the last character in the reference to 1. For example: XCSA723 changes to XCSA721.
- To order devices tapped for M20 x 1.5 for ISO cable connector: Change the last character in the reference to 2. For example: XCSA723 changes to XCSA722.
- To order devices with pre-wired connectors, refer to pages 4/78 and 4/79.

References: page 4/50 | Specifications: page 4/50 | Dimensions: page 4/51 | Wiring diagrams: page 4/53

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Metal, turret head, types XCSA, XCSB and XCSC

Separate components



XCSZ3●

Description	For use with	Supply voltage	Reference	Weight lb (kg)
1 orange LED indicator module with cover, seal and 2 mounting screws	XCSA XCSB XCSC	∼ or 24/48 V ⎓	**XCSZ31**	0.09 (0.040)
		110/240 V ∼	**XCSZ32**	0.09 (0.040)

Description	For use with	Reference	Weight lb (kg)
Blanking plugs for operating head slot (Sold in lots of 10)	XCSA, XCSB, XCSC	**XCSZ27**	0.11 (0.050)
Tubular high security keys to manually unlock and open guards (Sold in lots of 10)	XCSB, XCSC	**XCSZ25**	0.22 (0.100)
Padlocking attachment to prevent insertion of actuator, for up to 3 padlocks (padlocks not included) The padlock attachment cannot be used as a lock-out tag-out means.	XCSA, XCSB, XCSC	**XCSZ90**	0.12 (0.055)



XCSZ90

Dimensions *in. (mm)*

Safety interlock switches

XCSA●●●



(1) 1 tapped entry for ISO M20 or Pg 13.5 cable connector or 1/2"-14 NPT
Ø: 2 elongated holes Ø0.21 x 0.29 in. (5.3 x 7.3 mm)

XCSB●●●, XCSC●●●



Dual Dimensions: INCHES Millimeters

(1) 1 tapped entry for ISO M20 or Pg 13.5 cable connector or 1/2"-14 NPT
Ø: 2 elongated holes Ø0.21 x 0.29 in. (5.3 x 7.3 mm)

References: page 4/50 | Specifications: page 4/50 | Dimensions: page 4/51 | Wiring diagrams: page 4/53

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Metal, turret head, types XCSA, XCSB and XCSC

Dimensions (continued) *in. (mm)*

XCSZ01



(1) Adapter (included with actuator XCSZ01) for replacing, without drilling additional mounting holes, a safety interlock switch XCKJ with actuating key ZCKY07 by an XCSA, B, C or E with actuating key XCSZ01.

XCSZ02



Ø: 2 elongated holes Ø0.21 x 0.39 in. (5.3 x 10 mm)

XCSZ03



Mounting axis % related to actuator.

Ø: 2 elongated holes Ø0.21 x 0.39 in. (5.3 x 10 mm)

XCSZ05



Ø: 4 elongated holes Ø0.21 x 0.29 in. (5.3 x 7.3 mm)

Operating radius required for actuator

XCSZ01



XCSZ02



XCSZ03



Dual Dimensions: INCHES / Millimeters

R = minimum radius

References: page 4/50 | Specifications: page 4/50 | Dimensions: page 4/51 | Wiring diagrams: page 4/53

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Metal, turret head, types XCSA, XCSB and XCSC

Setup

Functional diagrams

XCS•5•••



XCS•7•••



XCS•8•••



Contact operation

- Closed
- Open
- Contact in transition

Wiring diagrams Note: These wiring diagrams are given as examples only; the designer must refer to the relevant safety standards for guidance.

Wiring to PL=b, category 1 conforming to EN/SO 13849-1

Example with 3-pole N.C. + N.O. + N.O. contact and protection fuse to prevent jumpering of the N.C. contact, either by cable damage or by tampering.



(1) Signaling contact

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1

Example with 3-pole N.C. + N.O. + N.O. contact with mixed redundancy of the contacts and the associated control relays. To activate K1, it is necessary to remove and re-insert the actuator when the supply is switched on.



H1: Actuator Not Inserted indicator

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061. Wiring method used in conjunction with Preventa safety relay module (The safety interlock switch should be used in conjunction with a safety limit switch to give electrical/mechanical redundancy).

Method for machines with quick rundown time (low inertia)

Locking device based on the principle of redundancy and self-monitoring.
The safety relay modules provide these functions.



Locking of actuator and operation in positive mode associated with a safety relay module.

References: page 4/50
Specifications: page 4/50
Dimensions: page 4/51
Wiring diagrams: page 4/53

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking, turret head
Metal, type XCSLF
Plastic, double insulated, type XCSLE

Metal, type XCSLF

Safety interlock switches with solenoid interlocking of the actuator



Page 4/56

With mushroom-head push button for escape release



Page 4/57

Plastic, type XCSLE

Safety interlock switches with solenoid interlocking of the actuator

Page 4/58

Environmental specifications

Safety interlock switch type		XCSLF (metal)	XCSLE (plastic)
Conformity to standards	Products	EN/IEC 60947-5-1, EN/ISO 13849-1, EN/IEC 62061, UL 508, CSA C22-2 n° 14	
	Machine assemblies	EN/IEC 60204-1, EN/ISO 14119, EN/ISO 12100	
Product certifications		UL, CSA, TÜV (pending)	
Maximum safety level *(1)*		PL=e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061	
Reliability data B_{10d}		5,500,000 (value given for a service life of 20 years, limited by mechanical or contact wear)	
Ambient air temperature	For operation	–13 to +140 °F (–25 to +60 °C)	
	For storage	–13 to +158 °F (–25 to +70 °C)	
Vibration resistance		5 gn (10 to 500 Hz) conforming to EN/IEC 60068-2-6	
Shock resistance		10 gn (duration 11 ms) conforming to EN/IEC 60068-2-27	
Electric shock protection		Class I conforming to EN/IEC 60536	Class II conforming to EN/IEC 60536
Degree of protection		IP66 and IP67 (IP66 for XCSLF●●●●4●● and XCSLF●●●●6●●) conforming to EN/IEC 60529 and EN/IEC 60947-5-1 *(2)*	
Cable entry		3 cable entries tapped M20 x 1.5 for cable connector ISO. Tightening capacity from 7 to 13 mm or entries tapped for 1/2"-14 NPT (USAS B2-1) conduit	
Materials		Zamak case	Polyamide case
		Actuators (all types): steel XC60, surface treated	

(1) With a suitable and properly connected control system.

(2) Live parts of these switches are protected against the penetration of dust and water. However, when installing, take all necessary precautions to prevent the penetration of solid bodies, or liquids with a high dust content, into the actuator aperture. Not recommended for use in saline atmospheres.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking, turret head
Metal, type XCSLF
Plastic, double insulated, type XCSLE

Contact block specifications

Rated operational specifications	~ AC-15, C300: Ue = 240 V, Ie = 0.75 A ⎓ DC-13, R300: Ue = 250 V, Ie = 0.1 A conforming to EN/IEC 60947-5-1
Conventional thermal current in enclosure	Ithe = 4 A (max. total thermal current = <15 A)
Rated insulation voltage	Ui = 250 V degree of pollution 3 conforming to EN/IEC 60947-1 Ui = 300 V conforming to UL 508, CSA C22-2 n° 14
Rated impulse withstand voltage	Uimp = 4 kV conforming to EN/IEC 60947-5-1
Positive operation	N.C. contact(s) with positive opening operation conforming to EN/IEC 60947-5-1, Section 3C
Minimum switching current	10 mA at 20 V
Minimum switching voltage	17 V
Short-circuit protection	4 A cartridge fuse type gG (gl) or 6 A fast acting
Connection	Spring terminals clamping capacity: minimum: 1 x 20 AWG (0.5 mm^2); maximum: 2 x 16 AWG (1.5 mm^2); 0.51 in. (13 mm) stripped end

Supplementary specifications

Actuation speed	Maximum: 19.7 in/s (0.5 ms); minimum: 0.39 in/s (0.01 ms)
Resistance to forcible withdrawal of actuator Fzh 2300 N according to the verification principle GS-ET 19 (Fzh=F max/1.3)	**XCSLF**: F max = 674.4 lb-f (3000 N) **XCSLE**: F max = 314.7 lb-f (1400 N)
Maximum operating rate	For maximum life: 600 operating cycles per hour
Minimum force for extraction of actuator (not locked)	4.5 lbs (20 N)

Electrical life
conforming to EN/IEC 60947-5-1
Appendix C
Rated category AC-15 and DC-13
Maximum operating rate:
3600 operating cycles/hour
Load factor: 0.5

Alternating Current
~ 50/60 Hz
inductive circuit



Direct Current ⎓

Power cut for 1 million operating cycles

Voltage	V	24	48	120
	W	16	28	38

Power of switching
conforming to EN/IEC 60947-5-1
Appendix C
Rated category AC-15 and DC-13

Power of switching **1**:
C300 240 V 0.75 A
R300 250 V 0.1 A

Power of switching **2**:
C300 120 V 1.5 A
R300 125 V 0.22 A



Electrical life
The product life expressed is based on average usage and normal operating conditions. Actual operating life will vary with conditions. The above statements are not intended to nor shall they create any express or implied warranties as to product operation or life. For information on the limited warranty offered on this product please refer to the Schneider Electric Conditions of Sale found in the *Digest*.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Metal, turret head*(1)*, type XCSLF
Three conduit entries

Type of switch	**Locking without power (locking on de-energization of solenoid), unlocking with power** *(2)*



LED indication	Orange LED: means the guard is open. Green LED: means the guard is closed and locked.				
Supply voltage of solenoid and LED indicators	24 V⁓ (50/60 Hz on ⁓) or 24 V⎓				
Type of contact on solenoid	1 N.C. + 1 N.O. break before make	2 N.C. simultaneous	1 N.C. + 2 N.O. break before make	2 N.C. + 1 N.O. break before make	3 N.C. simultaneous

XCSLF: Locking without power (locking on de-energization of solenoid), unlocking with power

Switch contacts	Conduit	Voltage	1 N.C. + 1 N.O.	2 N.C.	1 N.C. + 2 N.O.	2 N.C. + 1 N.O.	3 N.C.
1 N.C. + 1 N.O.	M20 x 1.5	24	XCSLF2525312 *(5)*	—	—	—	—
		240	XCSLF2525342	—	—	—	—
2 N.C.	M20 x 1.5	24	XCSLF2725312 *(5)*	XCSLF2727312 *(5)*	—	—	—
		240	XCSLF2725342	XCSLF2727342	—	—	—
	1/2"-14 NPT	24	—	XCSLF2727313	—	—	—
		120	—	XCSLF2727333	—	—	—
1 N.C. + 2 N.O.	M20 x 1.5	24	—	—	XCSLF3535312 *(6)*	—	—
		120	—	—	XCSLF3535332	—	—
		240	—	—	XCSLF3535342	—	—
	1/2"-14 NPT	24	—	—	XCSLF3535313	—	—
		120	—	—	XCSLF3535333	—	—
		240	—	—	XCSLF3535343	—	—
2 N.C. + 1 N.O.	M20 x 1.5	24	—	—	—	XCSLF3737312 *(6)*	—
		120	—	—	—	XCSLF3737332	—
		240	—	—	—	XCSLF3737342	—
	1/2"-14 NPT	24	—	—	—	XCSLF3737313	—
		120	—	—	—	XCSLF3737333	—
		240	—	—	—	XCSLF3737343	—
3 N.C.	M20 x 1.5	24	—	—	—	—	XCSLF3838312 *(6)*
	1/2"-14 NPT	24	—	—	—	—	XCSLF3838313
		120	—	—	—	—	XCSLF3838333

XCSLF: Locking with power (locking on energization of solenoid), unlocking without power

1 N.C. + 2 N.O.	M20 x 1.5	24	—	—	XCSLF3535512 *(6)*	—	—
	1/2"-14 NPT	24	—	—	XCSLF3535513	—	—
		120	—	—	XCSLF3535533	—	—
2 N.C. + 1 N.O.	M20 x 1.5	24	—	—	—	XCSLF3737512 *(6)*	—
	1/2"-14 NPT	24	—	—	—	XCSLF3737513	—
		120	—	—	—	XCSLF3737533	—
		240	—	—	—	XCSLF3737543	—
3 N.C.	1/2"-14 NPT	24	—	—	—	—	XCSLF3838513
		120	—	—	—	—	XCSLF3838533
Weight oz (kg)			38.80 (1.100)	38.80 (1.100)	38.80 (1.100)	38.80 (1.100)	38.80 (1.100)

Solenoid and LED indicator specifications

Load factor	100%
Rated operational voltage *(4)*	24 V⁓ / V⎓, 120 V⁓, or 230 V⁓
Voltage limits (conforming to EN/IEC 60947-1)	–15%, +10% of the rated operational voltage (including ripple on ⎓)
Power consumption	< 5.4 W at 68 °F (20 °C) and maximum voltage

References of actuators and separate components (see page 4/59)

(1) Head adjustable in 90° steps through 360°. A blanking plug for the operating head slot is included with the switch.
(2) A key operated lock (delivered with 2 keys) enables forced opening of the interlocking mechanism by authorized personnel, allowing withdrawal of the actuating key and subsequent opening of the N.C. safety contacts.
(3) Schematic diagrams shown represent the contact states while the actuating key is inserted in the head of the switch.
(4) Common supply for solenoid and LED indicators.
*(5) To order these devices with a 16 pin M23 connector, replace the **2** at the end of the reference with **M2**. Example: XCSLF2525312 changes to XCSLF252531**M2**.*
*(6) To order these devices with a 19 pin M23 connector, replace the **2** at the end of the reference with **M3**. Example: XCSLF3535312 changes to XCSLF353531**M3**.*
■ Note: Devices with M23 connectors have tamper resistant screws on the front cover of the switch.
■ To order devices pre-wired with 9 pin mini connectors, refer to page 4/79.

Introduction: page 4/54 | Specifications: page 4/55 | References: pages 4/56 to 4/60 | Dimensions: page 4/61 | Wiring diagrams: page 4/63

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Metal, turret head(1), type XCSLF
Three conduit entries

Type of switch	Locking without power (locking on de-energization of solenoid), unlocking with power *(2)*, or by mushroom-head push button for escape release *(3)*	
		
LED indication	Orange LED: signals that the guard is open Green LED: signals that the guard is closed and locked	
Supply voltage of solenoid and LED indicators	24 V~ (50/60 Hz on ~) or 24 V⎓	
Type of contact on solenoid	1 N.C. + 2 N.O. break before make 	2 N.C. + 1 N.O. break before make

XCSLF: Locking without power (locking on de-energization of solenoid), unlocking with power
40 mm mushroom button

Switch contacts	Conduit	Voltage	1 N.C. + 2 N.O.	2 N.C. + 1 N.O.
1 N.C. + 2 N.O.	**M20 x 1.5**	**24**	**XCSLF3535412** *(6)*	—
2 N.C. + 1 N.O.	**M20 x 1.5**	**24**	—	**XCSLF3737412** *(6)*
	1/2"-14 NPT	**24**	—	**XCSLF3737413**
		120	—	**XCSLF3737433**

XCSLF: Locking without power (locking on de-energization of solenoid), unlocking with power
Keyed mushroom button

1 N.C. + 2 N.O.	**M20 x 1.5**	**24**	**XCSLF3535612** *(6)*	—
2 N.C. + 1 N.O.	**M20 x 1.5**	**24**	—	**XCSLF3737612** *(6)*
	1/2"-14 NPT	**24**	—	**XCSLF3737613**
		120	—	**XCSLF3737633**
Weight oz (kg)			43.03 (1.220)	43.03 (1.220)

Solenoid and LED indicator specifications

Load factor		100%
Rated operational voltage *(5)*		24 V~ or V⎓, 120 V~, or 230 V~
Voltage limits	Conforming to EN/IEC 60947-1	–15%, +10% of the rated operational voltage (including ripple on ⎓)
Power consumption		<5.4 W at 68 °F (20 °C) and maximum voltage

References of actuators and separate components (see page 4/59)

(1) Head adjustable in 90° steps through 360°. A blanking plug for the operating head slot is included with the switch.
(2) A key-operated lock (delivered with 2 keys) enables forced opening of the interlocking mechanism by authorized personnel, allowing withdrawal of the actuating key and subsequent opening of the N.C. safety contacts.
(3) Ø40 mm, trigger action, latching mushroom-head push button with resetting by either turn-to-release or key-release (key n° 455).
(4) Wiring diagrams shown represent the contact states while the actuating key is inserted in the head of the switch.
(5) Common supply for solenoid and LED indicators.
*(6) To order these devices with a 19 pin M23 connector, replace the **2** at the end of the reference with **M3**. Example: XCSLF3535412 changes to XCSLF353541**M3**.*
- Note: Devices with M23 connectors have tamper resistant screws on the front cover of the switch.
- To order devices pre-wired with 9 pin mini connectors, refer to page 4/79.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Plastic, double insulated, turret head(1), type XCSLE
Three conduit entries

Type of switch	Locking without power, unlocking with power *(2)*
LED indication	Orange LED: signals that the guard is open Green LED: signals that the guard is closed and locked
Supply voltage of solenoid and LED indicators	24 V⁓ (50/60 Hz on ⁓) or 24 V⎓
Type of contact on solenoid	1 N.O. + 1 N.C. break before make: 33, 41, 34, 42 · 2 N.C. simultaneous: 31, 41, 32, 42 · 1 N.C. + 2 N.O. break before make: 61, 43, 53, 62, 44, 54 · 2 N.C. + 1 N.O. break before make: 41, 51, 63, 42, 52, 64 · 3 N.C. simultaneous: 41, 51, 61, 42, 52, 62

4

XCSLE: Locking without power (locking on de-energization of solenoid), unlocking with power

Switch contacts	Conduit	Voltage	1 N.C. + 1 N.O.	2 N.C.	1 N.C. + 2 N.O.	2 N.C. + 1 N.O.	3 N.C.
1 N.C. + 1 N.O. (13, 21, 14, 22)	M20 x 1.5	24	XCSLE2525312 *(5)*	—	—	—	—
		120	XCSLE2525332	—	—	—	—
		240	XCSLE2525342	—	—	—	—
2 N.C. (11, 21, 12, 22)	M20 x 1.5	24	—	XCSLE2727312 *(5)*	—	—	—
		120	—	XCSLE2727332	—	—	—
	1/2"-14 NPT	24	—	XCSLE2727313	—	—	—
		120	—	XCSLE2727333	—	—	—
1 N.C. + 2 N.O. (21, 13, 33, 22, 14, 34)	M20 x 1.5	24	—	—	XCSLE3535312 *(6)*	—	—
		240	—	—	XCSLE3535342	—	—
	1/2"-14 NPT	24	—	—	XCSLE3535313	—	—
		120	—	—	XCSLE3535333	—	—
		240	—	—	XCSLE3535343	—	—
2 N.C. + 1 N.O. (21, 31, 13, 22, 32, 14)	M20 x 1.5	24	—	—	—	XCSLE3737312 *(6)*	—
		240	—	—	—	XCSLE3737342	—
	1/2"-14 NPT	24	—	—	—	XCSLE3737313	—
		120	—	—	—	XCSLE3737333	—
3 N.C. (11, 21, 31, 12, 22, 32)	M20 x 1.5	24	—	—	—	—	XCSLE3838312 *(6)*
		240	—	—	—	—	XCSLE3838342
	1/2”-14 NPT	24	—	—	—	—	XCSLE3838313
		120	—	—	—	—	XCSLE3838333

XCSLE: Locking with power (locking on energization of solenoid), unlocking without power

1 N.C. + 1 N.O. (13, 21, 14, 22)	M20 x 1.5	24	XCSLE2525512 *(5)*	—	—	—	—
	1/2"-14 NPT	24	XCSLE2525513	—	—	—	—
2 N.C. (11, 21, 12, 22)	M20 x 1.5	24	—	XCSLE2727512 *(5)*	—	—	—
2 N.C. + 1 N.O. (21, 31, 13, 22, 32, 14)	1/2"-14 NPT	24	—	—	—	XCSLE3737513	—
		120	—	—	—	XCSLE3737533	—
3 N.C. (11, 21, 31, 12, 22, 32)	1/2"-14 NPT	24	—	—	—	—	XCSLE3838513
		120	—	—	—	—	XCSLE3838533
Weight oz (kg)			18.70 (0.530)	18.70 (0.530)	18.70 (0.530)	18.70 (0.530)	18.70 (0.530)

Solenoid and LED indicator specifications

Load factor	100%
Rated operational voltage *(4)*	24 V⁓ or V⎓, 120 V⁓, or ⁓ 230 V
Voltage limits (Conforming to EN/IEC 60947-1)	–15%, +10% of the rated operational voltage (including ripple on ⎓)
Power consumption	<5.4 W at 68 °F (20 °C) and maximum voltage

References of actuators and separate components (see page 4/59)

(1) Head adjustable in 90° steps through 360°. A blanking plug for the operating head slot is included with the switch.
(2) A tool delivered with the guard switch enables forced opening of the interlocking mechanism by authorized personnel, allowing withdrawal of the actuating key and subsequent opening of the N.C. safety contacts.
(3) Schematic diagrams shown represent the contact states while the actuating key is inserted in the head of the switch.
(4) Common supply for solenoid and LED indicators.
*(5) To order these devices with a 16 pin M23 connector, replace the **2** at the end of the reference with **M2**. Example: XCSLE2525312 changes to XCSLE252531**M2**.*
*(6) To order these devices with a 19 pin M23 connector, replace the **2** at the end of the reference with **M3**. Example: XCSLE3535312 changes to XCSLE353531**M3**.*
■ Note: Devices with M23 connectors have tamper resistant screws on the front cover of the switch.
■ To order devices pre-wired with 9 pin mini connectors, refer to page 4/79.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking, turret head
Metal, type XCSLF
Plastic, double insulated, type XCSLE

XCSZ01

XCSZ02



XCSZ03



XCSZ05



XCSZ90

References of actuators

Description	For use with	Unit reference	Weight oz (kg)
Straight actuator	XCSLF, XCSLE	**XCSZ01**	0.705 (0.020)
Actuator with wide mounting	XCSLF, XCSLE	**XCSZ02**	0.705 (0.020)
Pivoting actuator	XCSLF, XCSLE	**XCSZ03**	3.351 (0.095)
Latch for sliding doors (Padlockable in open position) The padlock attachment cannot be used as a lock-out tag-out means.	XCSLF, XCSLE	**XCSZ05**	21.164 (0.600)

Separate components

Description	For use with	Unit reference	Weight oz (kg)
Blanking plug for operating head slot (Sold in lots of 10)	XCSLF, XCSLE	**XCSZ30**	1.764 (0.050)
Keys for interlock forced-opening device (Sold in lots of 10)	XCSLF	**XCSZ25**	3.527 (0.100)
Padlocking attachment to prevent insertion of actuating key, for up to 3 padlocks (padlocks not included) The padlock attachment cannot be used as a lock-out tag-out means.	XCSLF, XCSLE	**XCSZ90**	1.940 (0.055)
Tool for forced opening of interlocking device (Sold in lots of 10)	XCSLE	**XCSZ100**	1.764 (0.050)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking, turret head Metal, type XCSLF and plastic, type XCSLE

Cabling accessories

Specifications

Type of connection	Screw threaded (metal clamping ring)
Degree of protection	IP 65 (with clamping ring correctly tightened)
Ambient air temperature	-13… +230° F (-25… +110° C)
Connection	To solder terminals. Maximum conductor c.s.a.: 18 AWG (1.0 mm²) Cable gland: no. 13 metal (Pg 13.5) Clamping capacity: 0.354 to 0.472 in. (9 to 12 mm)
LED signalling	–
Nominal voltage	60 V ∼, 75 V ⎓
Nominal current	7.5 A
Insulation resistance	> 10^{12} Ω
Contact resistance	≤ 5 mΩ

References





Type of connector	Number of contacts	Cable connection	Type	Reference	Weight oz (kg)
Female, M23	16	To solder terminals	Straight	**XZCC23FDM160S**	2.822 (0.080)
			Elbowed	**XZCC23FCM160S**	5.291 (0.150)
	19	To solder terminals	Straight	**XZCC23FDM190S**	2.822 (0.080)
			Elbowed	**XZCC23FCM190S**	5.291 (0.150)

Dimensions

XZCC23FDM160S and **XZCC23FDM190S**



XZCC23FCM160S and **XZCC23FCM190S**



Dual Dimensions: in. (mm)

(1) No. 13 metal cable gland

Connections

XZCC23F●M160S



XZCC23F●M190S



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking, turret head
Metal, type XCSLF
Plastic, double insulated, type XCSLE

Dimensions

Metal key operated switches

XCSLF●●●●●●●



(1) 3 tapped entries for 1/2"-14 NPT
Ø: 2 elongated holes Ø7 x 5.2

XCSLF●●●●●●●, with mushroom-head push button for escape release



(1) 3 tapped entries for 1/2"-14 NPT
Ø: 2 elongated holes Ø7 x 5.2

Plastic key operated switches

XCSLE●●●●●●●



(1) 3 tapped entries for 1/2"-14 NPT
Ø: 2 elongated holes Ø6.2 x 4.2

Dual Dimensions: in. (mm)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking, turret head
Metal, type XCSLF
Plastic, double insulated, type XCSLE

Dimensions

XCSZ01



(1) Adapter (included with actuator XCSZ01) for replacing, without drilling an additional mounting hole, an XCKJ safety interlock switch (ZCKY07 actuating key) with an XCSLF safety interlock switch (XCSZ01 actuating key).

Ø: 2 elongated holes Ø5.3 x 10

XCSZ02



Ø: 2 elongated holes Ø5.3 x 10

XCSZ03



Mounting axis % related to actuator.

XCSZ05



(1) 10 mm deep
Ø: 4 elongated holes Ø5.2 x 8

Operating radius required for actuator

XCSZ01



XCSZ02



XCSZ03



R = minimum radius

Dual Dimensions: in. (mm)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking, turret head
Metal, type XCSLF
Plastic, double insulated, type XCSLE

Functional diagrams

XCSLF/LE25●●●



XCSLF/LE27●●●



XCSLF/LE35●●●



XCSLF/LE37●●●



XCSLF/LE38●●●



Contact operation

■ Contact closed □ Contact open ▭ Contact in transition

Wiring diagrams

Wiring to PL=b, category 1 conforming to EN/ISO 13849-1

Example with 2-pole N.C. + N.O. contact and protection fuse to prevent jumpering of the N.C. contact, either by cable damage or by tampering.



Wiring to PL=d, category 3 conforming to EN/ISO 13849-1

Example with 3-pole 2 N.C. + 1 N.O. contact with redundancy of the contacts and the associated control relays. To activate K1, it is necessary to remove and re-insert the actuating key when the supply is switched on.



Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061. Connection principle with Preventa safety relay module (the guard safety interlock switch should be used in conjunction with a safety limit switch to give electrical/ mechanical redundancy).

Method for machines with long rundown time (high inertia)



Interlocking device for actuator mounted on guard and zero speed detection.

Dual Dimensions: in. (mm)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking, turret head
Metal, type XCSLF
Plastic, double insulated, type XCSLE

Wiring to PL=b, category 1 conforming to EN/ISO 13849-1

Wiring examples with protection fuse to prevent jumpering of the N.C. contact, either by cable damage or by tampering.

Locking without power N.C. + N.O.and N.C. + N.O. auxiliary contacts

XCSLF/LE25253●●



E1-E2: Solenoid supply
13-14: Safety contact, available for redundancy
13-X2/E2: LED (orange): actuator withdrawn
41-X1/E2: LED (green): actuator inserted and locked
22-41: Safety prewiring provided
S1: Manual unlocking button
X: Unlocking signal

Locking with power N.C. + N.O.and N.C. + N.O. auxiliary contacts

XCSLF/LE25255●●



E1-E2: Solenoid supply
13-14: Safety contact, available for redundancy
13-X2/E2: LED (orange): actuator withdrawn
41-X1/E2: LED (green): actuator inserted and locked
22-41: Safety prewiring provided
S: Locking signal *(1)*

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1

Wiring examples with redundancy for the guard safety interlock contacts, without monitoring or redundancy in the power circuit

Locking without power 2 N.C. + N.O. and 2 N.C. + N.O. auxiliary contacts

XCSLF/LE37373●●



E1-E2: Solenoid supply
21-22 and 31-32: Safety contacts, available for redundancy
13-X2/E2: LED (orange): actuator withdrawn
51-X1/E2: LED (green): actuator inserted and locked
22-41 and 32-51: Safety prewiring provided
S1: Manual unlocking button
X: Unlocking signal

Locking with power 2 N.C. + N.O. and 2 N.C. + N.O. auxiliary contacts

XCSLF/LE37375●●



E1-E2: Solenoid supply
21-22 and 31-32: Safety contacts, available for redundancy
13-X2/E2: LED (orange): actuator withdrawn
51-X1/E2: LED (green): actuator inserted and locked
22-41 and 32-51: Safety prewiring provided
S: Locking signal *(1)*

(1) **The locking signal could be lost at any instant (power failure, cable breakage). Do not use safety interlock switches with Locking with Power for applications where the safety of the operator could be jeopardized in the event of the guard opening. For these applications, use safety interlock switches with Locking without Power.**

Introduction: page 4/54 | Specifications: page 4/55 | References: pages 4/56 to 4/60 | Dimensions: page 4/61 | Wiring diagrams: page 4/63

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking, turret head
Metal, type XCSLF
Plastic, double insulated, type XCSLE

Connection by M23 connectors

16-pin M23 connectors

XCSLF/LE2525●●



XCSLF/LE2725●●



XCSLF/LE2727●●



19-pin M23 connectors

XCSLF/LE3535●●



XCSLF/LE3737●●



XCSLF/LE3837●●



XCSLF/LE3838●●



(1) PE connection for XCSLF only.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking
Metal, turret head, type XCSE
Plastic, double insulated, type XCSTE

Metal, type XCSE

Safety interlock switches with locking of the actuator



Page 4/68

Plastic, type XCSTE

Safety interlock switches with locking of the actuator



Page 4/74

Environmental specifications

Safety interlock switch type		XCSE (metal)	XCSTE (plastic)
Conformity to standards	Products	EN/IEC 60947-5-1, UL 508, CSA C22-2 n° 14	
	Machine assemblies	EN/IEC 60204-1, EN/ISO 14119	
Product certifications		UL, CSA	UL, CSA
Maximum safety level *(1)*		PL=e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061	
Reliability data B_{10d}		5,000,000 (value given for a service life of 20 years, limited by mechanical or contact wear)	
Protective treatment		Standard version: **TC**	
Ambient air temperature	For operation	–13 to +104 °F (–25 to +40 °C)	–13 to +140 °F (–25 to +60 °C)
	For storage	–40 to +158 °F (–40 to +70 °C)	
Vibration resistance		5 gn (10–500 Hz) conforming to EN/IEC 60068-2-6	
Shock resistance		10 gn (duration 11 ms) conforming to EN/IEC 60068-2-27	
Electric shock protection		Class I conforming to EN/IEC 60536	Class II conforming to EN/IEC 60536
Degree of protection		**IP67 conforming to EN/IEC 60529 and EN/IEC 60947-5-1** *(2)*	
Cable entry		2 entries tapped ISO M20 x 1.5 (clamping capacity 7 to 13 mm) or tapped for n° 13 (Pg 13.5) cable connector conforming to NFC 68-300 (clamping capacity 8 to 12 mm) or for 1/2"-14 NPT (USAS B2-1) conduit	1 entry tapped M16 x 1.5 (clamping capacity 4.5 to 10 mm) or tapped for n° 11 (Pg 11) cable connector conforming to NFC 68-300 (clamping capacity 7 to 10 mm) or for 1/2"-14 NPT conduit using metal adapter DE9 RA1012 in n° 11 (Pg 11) tapped entry
Materials		Zamak case	Polyamide PA66 fibreglass impregnated case
		Actuators (all types): steel XC60, surface treated	

(1) Using an appropriate and correctly connected control system.

(2) Live parts of these switches are protected against the penetration of dust and water. However, when installing take all necessary precautions to prevent the penetration of solid bodies, or liquids with a high dust content, into the actuator aperture. Not recommended for use in saline atmospheres.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated with solenoid interlocking
Metal, turret head, type XCSE
Plastic, double insulated, type XCSTE

Contact block specifications

Rated operational specifications	2 and 3 contact, slow break	**XCSE**, **XCSTE**: ∿ AC-15, B300: Ue = 240 V, Ie = 1.5 A or Ue = 120 V, Ie = 3 A All models: ⎓ DC-13, Q300: Ue = 250 V, Ie = 0.27 A or Ue = 125 V, Ie = 0.55 A conforming to EN/IEC 60947-5-1
Conventional thermal current in enclosure		**XCSE**, **XCSTE** 2 and 3 slow break contact versions: Ithe = 6 A
Rated insulation voltage	2 and 3 contact	3 contact (**XCSE**), 2 contact (**XCSTE**): Ui = 500 V conforming to EN/IEC 60947-1; Ui = 300 V conforming to UL 508, CSA C22-2 n° 14
Rated impulse withstand voltage	2 and 3 contact	3 contact (**XCSE**), 2 contact (**XCSTE**): Uimp = 6 kV conforming to EN/IEC 60947-5-1
Positive operation		N.C. contacts with positive opening operation conforming to EN/IEC 60947-5-1, Section 3
Resistance across terminals		⩽ 30 mΩ conforming to EN/IEC 60947-5-4
Short-circuit protection	2 and 3 contact	3 contact (**XCSE**), 2 contact (**XCSTE**): 10 A cartridge fuse type gG (gl)
Connection Screw clamp terminals	2 and 3 contact	3 contact **(XCSE)**, 2 contact **(XCSTE)**: Clamping capacity, min: 1 x 20 AWG (0.5 mm²), max: 2 x 14 AWG (1.5 mm²) with or without cable end

Complementary specifications

Actuation speed	Maximum: 19.7 in./s (0.5 ms), minimum: 0.39 in./s (0.01 ms)
Resistance to forcible withdrawal of actuator	**XCSE**: 450 lb (2000 N); **XCSTE**: 112 lb (500 N)
Maximum operating rate	For maximum life: 600 operating cycles per hour
Minimum force for extraction of actuator	⩾ 4.5 lb (⩾ 20 N)
Materials	Body and head: Zamak (**XCSE**) Body and head: polyamide PA66, fibreglass impregnated (**XCSTE**)

Electrical life

Conforming to EN/IEC 60947-5-1 Appendix C.
Utilization categories AC-15 and DC-13.
Maximum operating rate: 3600 operating cycles/hour.
Load factor: 0.5

3 contact XCSE and 2 contact XCSTE version, slow break

AC supply
50/60 Hz ∿
⎓ inductive circuit



DC supply ⎓
Power (in W) broken for 5 million operating cycles.

Voltage	V	24	48	120
⎓	W	13	9	7

Electrical life

The product life expressed is based on average usage and normal operating conditions. Actual operating life will vary with conditions. The above statements are not intended to nor shall they create any express or implied warranties as to product operation or life. For information on the limited warranty offered on this product please refer to the Schneider Electric Conditions of Sale found in the *Digest*.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Solenoid interlocking
Metal, turret head*(1)*, type XCSE
Conduit entries tapped 1/2"-14 NPT

Type of switch	**With interlocking, locking by solenoid**	
		
Type of interlocking	**Locking without power (locking on de-energization of solenoid) and unlocking on energization of solenoid** *(2)*. To order a safety interlock switch with locking with power (locking on energization of solenoid) and unlocking on de-energization of the solenoid, replace the 2nd number *(3)* with **5** in the references shown below. Example: **XCSE5313 becomes XCSE5513**	
LED indication	Orange LED: "guard open" signaling. Green LED: "guard closed and locked" signaling.	
Supply voltage of solenoid	∿ or ⎓ 24 V (50/60 Hz on ∿)	∿ or ⎓ 110/120 V *(3)* (50/60 Hz on ∿)
Type of contact on solenoid	N.C. + N.O.	N.C. + N.O.
References of switches without actuating key (⊖ N.C. contact with positive opening operation)		
3-pole N.C. + N.O. + N.O. (2 N.O. break before make) *(4)* 	**XCSE5313** ⊖	**XCSE5333** ⊖
3-pole N.C. + N.C. + N.O. (N.O. break before make) *(4)* 	**XCSE7313** ⊖	**XCSE7333** ⊖
3-pole N.C. + N.C. + N.C. slow break *(4)* 	**XCSE8313** ⊖ *(5)*	**XCSE8333** ⊖
Weight lb (kg)	2.51 (1.140)	
Solenoid specifications		
Load factor	100 %	
Rated operational voltage	∿ **or** ⎓ **24 V**	∿ **or** ⎓ **110/120 V**
Voltage limits	–20%, +10% of the rated operational voltage (including ripple on ⎓) conforming to IEC/EN 60947-1	
Service life	20,000 hours	
Power consumption	Inrush: 10 VA. Sealed: 10 VA	
LED indicator specifications		
Rated insulation voltage	50 V conforming to IEC/EN 60947-1	250 V conforming to IEC/EN 60947-1
Current power consumption	7 mA	7 mA
Rated operational voltage	∿ **or** ⎓ **24/48 V**	∿ **110/240 V**
Voltage limits	∿ or ⎓ 20–52 V (including ripple)	∿ 95–264 V (including ripple)
Service life	100,000 hours	100,000 hours
Protection against overvoltages	Yes	Yes

(1) Head adjustable in 90° steps throughout 360°. A blanking plug for the operating head slot is included with the switch.
(2) A key operated lock enables forced opening of the interlocking mechanism by authorized personnel, allowing withdrawal of the actuating key and subsequent opening of the N.C. safety contacts.
(3) For use on ⎓ 110/120 V, remove the LED module.
(4) Wiring diagrams shown represent the contact states while the actuating key is inserted in the head of the switch.
(5) Switches supplied with a single green LED.
(6) The N.O. contacts will close after the N.C. contacts open. They do not change state simultaneously.

The devices listed above are threaded for 1/2"-14 NPT, and are available with metric conduit:
- To order devices tapped for a 13 mm cable connector, conforming to NF C 68-300 (DIN Pg 13.5): Change the last character in the reference to 1.
  For example: XCSE7333 changes to XCSE7331
- To order devices tapped for a M20 x 1.5 for ISO cable connector: Change the last character in the reference to 2.
  For example: XCSE7333 changes to XCSE7332
- To order devices pre-wired with mini connectors, refer to pages 4/78 and 4/79.

Introduction: page 4/66 | Specifications: page 4/66 | References: page 4/68 | Dimensions: page 4/70 | Wiring diagrams: page 4/71

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Solenoid interlocking
Metal, turret head, type XCSE

XCSZ01

XCSZ02



XCSZ03



XCSZ05

References of actuators

Description	For use with	Unit reference	Weight oz (kg)
Straight actuator	XCSE	**XCSZ01**	0.705 (0.020)
Actuator with wide mounting	XCSE	**XCSZ02**	0.705 (0.020)
Pivoting actuator	XCSE	**XCSZ03**	3.351 (0.095)
Latch for sliding doors (Padlockable in open position) The padlock attachment cannot be used as a lock-out tag-out means.	XCSE	**XCSZ05**	21.164 (0.600)



XCSZ4●



Separate components

Description	For use with	Supply voltage	Reference	Weight lb (kg)
1 orange LED + 1 green LED indicator module with cover + lock *(1)*, seal and 4 mounting screws (2 keys included for lock)	XCSE73●●	∿ or 24/48 V ⎓	**XCSZ43**	0.39 (0.175)

(1) Lock incorporated as standard on safety interlock switches XCSE: key withdrawal in LOCK and UNLOCK positions.

Description	For use with	Key withdrawal positions from lock	Unit reference	Weight lb (kg)
Blanking plugs for operating head slot (Sold in lots of 10)	XCSE	–	**XCSZ27**	0.11 (0.050)
Tubular high security keys to manually unlock and open guards (Sold in lots of 10)	XCSE	–	**XCSZ25**	0.22 (0.100)
Padlocking attachment to prevent insertion of actuator, for up to 3 padlocks (padlocks not included) The padlock attachment cannot be used as a lock-out tag-out means	XCSE	–	**XCSZ90**	0.12 (0.055)



XCSZ90

Description	For use with	Unit reference	Weight kg
Conduit adapter, M20 to 1/2"-14 NPT (Sold in lots of 5)	XCSE	**DE9RA2012**	0.11 (0.048)

Introduction: page 4/66 | Specifications: page 4/66 | References: page 4/68 | Dimensions: page 4/70 | Wiring diagrams: page 4/71

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Solenoid interlocking
Metal, turret head, type XCSE

Dimensions *in. (mm)*

Safety interlock switches

XCSE●●●●



(1) 1 tapped entry for cable connector.
Ø: 2 elongated holes Ø0.21 x 0.29 in. (5.3 x 7.3 mm)

1/2"-14 NPT conduit adapter

DE9RA2012



Dual Dimensions: INCHES / Millimeters

(1) Tapped entry for 1/2"-14 NPT conduit
(2) M20 x 1.5 threaded shank

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Solenoid interlocking
Metal, turret head, type XCSE

Setup

Functional diagrams

XCS•5•••



XCS•7•••



XCS•8•••



Contact operation



Wiring diagrams *(These wiring diagrams are given as examples only; the designer must refer to the relevant safety standards for guidance.)*

Wiring to PL=b, category 1 conforming to EN/ISO 13849-1

Example with 3-pole N.C. + N.O. + N.O. contact and protection fuse to prevent jumpering of the N.C. contact, either by cable damage or by tampering.



(1) Signaling contact

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1

Example with 3-pole N.C. + N.O. + N.O. contact with mixed redundancy of the contacts and the associated control relays. To activate K1, it is necessary to remove and re-insert the actuator when the supply is switched on.



H1: "actuator not inserted" indicator

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061. Wiring method used in conjunction with Preventa safety relay module (The safety interlock switch should be used in conjunction with a safety limit switch to give electrical/ mechanical redundancy).

Method for machines with long rundown time (high inertia)



Interlocking device for actuator mounted on guard and zero speed detection.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Solenoid interlocking
Metal, turret head, type XCSE

Wiring to PL=b, category 1 conforming to EN/ISO 13849-1

Wiring examples with protective fuse to prevent jumpering of the N.C. contact, either by cable damage or by tampering.

Note: *These wiring diagrams are provided as examples only. The designer must refer to relevant safety standards for guidance.*

Locking without power, N.C. + N.O. + N.O.

XCSE53●●



(1) Solenoid
(2) Auxiliary contact
E1-E2: Solenoid supply
43-44: Solenoid signaling contact
13-14: Safety contact, available for redundancy
33-X1: LED (orange): actuating key withdrawn
51-X1: LED (green): actuating key inserted and locked
21-52: Safety pre-wiring provided

Locking with power, N.C. + N.O. + N.O.

XCSE55●●



(1) Solenoid
(2) Auxiliary contact
E1-E2: Solenoid supply
51-52: Solenoid signaling contact
13-14: Safety contact, available for redundancy
33-X1: LED (orange): actuating key withdrawn
43-X1: LED (green): actuating key inserted and locked
21-44: Safety pre-wiring provided

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Metal, turret head, type XCSE

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1

Wiring examples with redundancy for the switch contacts, without monitoring or redundancy in the power circuit

Locking without power, N.C. + N.C. + N.O.

XCSE73●●



(1) Solenoid
(2) Auxiliary contact
E1-E2: Solenoid supply
43-44: Solenoid signaling contact
21-22 and 31-32: Safety contacts, available for redundancy
13-X1: LED (orange): actuating key withdrawn
51-X1: LED (green): actuating key inserted and locked
21-52: Safety pre-wiring provided

Locking with power, N.C. + N.C. + N.O.

XCSE75●●



(1) Solenoid
(2) Auxiliary contact
E1-E2: Solenoid supply
51-52: Solenoid signaling contact
21-22 and 31-32: Safety contacts, available for redundancy
13-X1: LED (orange): actuating key withdrawn
43-X1: LED (green): actuating key inserted and locked
21-44: Safety pre-wiring provided

Note: *These wiring diagrams are given as examples only; the designer must refer relevant safety standards for guidance.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Solenoid interlocking
Plastic, turret head*(1)*, type XCSTE
Conduit entries tapped Pg 11 with 1/2"-14 NPT adapter

Type of switch	With interlocking, locking by solenoid		
			
Type of interlocking	**Locking without power (locking on de-energization) and unlocking on energization of solenoid** *(2)*. To order a safety interlock switch with locking with power (locking on energization) and unlocking on de-energization of the solenoid, replace the 2nd number *(3)* with **5** in the references shown below. Example: **XCSTE5313** becomes **XCSTE5513.**		
Supply voltage of solenoid	∿ or ⎓ 24 V (50/60 Hz on ∿)	∿ or ⎓ 120 V (50/60 Hz on ∿)	∿ or ⎓ 230 V (50/60 Hz on ∿)
References of switches without actuating key (⊖ N.C. contact with positive opening operation)			
2-pole N.C. + N.O. *(3)* break before make slow break	**XCSTE5313** ⊖	**XCSTE5333** ⊖	**XCSTE5343** ⊖
2-pole N.O. + N.C. *(3)* make before break slow break	**XCSTE6313** ⊖	**XCSTE6333** ⊖	**XCSTE6343** ⊖
2-pole N.C. + N.C. *(3)* slow break	**XCSTE7313** ⊖	**XCSTE7333** ⊖	**XCSTE7343** ⊖
Weight lb (kg)	0.79 (0.360)	0.79 (0.360)	0.79 (0.360)
Solenoid specifications			
Load factor	100 %		
Rated operational voltage	∿ **or** ⎓ **24 V**	∿ **or** ⎓ **120 V**	∿ **or** ⎓ **230 V**
Voltage limits	– 20%, +10% of the rated operational voltage (including ripple on ⎓) conforming to EN/IEC 60947-1		
Service life	20,000 hours		
Power consumption	10 VA max.		

References of actuating keys and guard retaining device






Description	Straight actuator	Actuator with wide mounting *(4)*		Pivoting actuator	Right-angled actuator
For interlock switches XCSPA, TA, TE	**XCSZ11**	**XCSZ12**	**XCSZ15**	**XCSZ13**	**XCSZ14**
Weight lb (kg)	0.03 (0.015)	0.03 (0.015)	0.03 (0.012)	0.19 (0.085)	0.06 (0.025)

References of accessories

809927

XCSZ91


DF523736

XCSZ200

DE9RA1012

Description	For use with	Unit reference	Weight lb (kg)
Blanking plugs for operating head slot (Sold in lots of 10)	XCSTE	**XCSZ28**	0.11 (0.050)
Tool for forced opening of interlocking device (Sold in lots of 10)	XCSTE	**XCSZ100**	0.11 (0.050)
Padlocking device to prevent insertion of actuator, for up to 3 padlocks (padlocks not included). The padlock attachment cannot be used as a lock-out tag-out means.	XCSTE	**XCSZ91**	0.12 (0.053)
Actuator centering device (Mounting screws included)	XCSTE	**XCSZ200**	0.05 (0.022)
1/2"-14 NPT conduit adapter (Sold in lots of 10)	XCSTE	**DE9RA1012**	0.11 (0.050)

(1) Head adjustable in 90° steps throughout 360°. A blanking plug for the operating head slot is included with the switch.
(2) A special tool included with the safety interlock switch enables forced opening of the interlocking mechanism by authorized personnel, allowing withdrawal of the actuating key and subsequent opening of the N.C. safety contacts.
(3) Wiring diagrams shown represent the contact states while the actuating key is inserted in the head of the switch.
(4) 2 actuator lengths, XCSZ12: 1.57 in. (40 mm), XCSZ15: 1.14 in. (29 mm).

The devices listed above are threaded for 1/2"-14 NPT (using the supplied adapter on the XCSTA), and are available with metric conduit:

- To order devices tapped for an 11 mm cable connector, conforming to NFC 68-300 (DIN Pg 11): Change the last character in the reference to 1. For example: XCSTE531**3** changes to XCSTE531**1**
- To order devices tapped for an M16 x 1.5 for ISO cable connector: Change the last character in the reference to 2. For example: XCSTE531**3** changes to XCSTE531**2**.

References: page 4/74 | Specifications: page 4/74 | Dimensions: page 4/75 | Wiring diagrams: page 4/76

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Solenoid interlocking
Plastic turret head, type XCSTE

Dimensions *in. (mm)*

Safety interlock switches
XCSTE●●●●



(1) 1 tapped entry for cable connector
Ø: 2 elongated holes Ø0.17 x 0.33 in. (4.3 x 8.3 mm) on 0.87 in. (22 mm) centers, 2 holes Ø0.17 in. (4.3 mm) on 0.79 in. (20 mm) centers

Actuator centering device
XCSZ200



1/2"-14 NPT conduit adapter
DE9RA1012



(1) Tapped entry for 1/2"-14 NPT conduit
(2) Pg 11 threaded shank

Actuators

XCSZ11



(1) Adapter (included with actuator XCSZ11) for replacing, without drilling additional mounting hole, a safety interlock switch XCKT with actuator XCKY01 by a safety interlock switch XCSTA with actuator XCSZ11.

Ø a: 2 elongated holes Ø0.19 x 0.39 in. (4.7 x 10 mm)
Ø b: 1 elongated hole for M4 or M4.5 screw

XCSZ12, XCSZ15



Ø: 2 elongated holes Ø0.19 x 0.39 in. (4.7 x 10 mm)
L = 1.57 in. (40 mm) (XCSZ12) or 1.14 in. (29 mm) (XCSZ15)

XCSZ13



Ø: 2 elongated holes Ø0.19 x 0.39 in. (4.7 x 10 mm)

XCSZ14



Ø: 1 elongated hole Ø0.19 x 0.39 in. (4.7 x 10 mm)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Safety interlock switches, actuator operated
Solenoid interlocking
Plastic turret head, type XCSTE

Operating radius required for actuator

XCSZ11





XCSZ12, XCSZ15





d = 1.81 in. (46 mm) (XCSZ12) or 1.38 in. (35 mm) (XCSZ15)

XCSZ13





XCSZ14





R = minimum radius

Wiring diagrams

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061

(The safety interlock switch should be used in conjunction with a safety limit switch to give electrical/mechanical redundancy)

Method for machines with long rundown time (high inertia)



Interlocking device for actuator mounted on guard and zero speed detection.

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1

Example with 2-pole N.C. + N.O. contact with mixed redundancy of the contacts and the associated control relays. To activate K1, it is necessary to remove and re-insert the actuator when the supply is switched on.



(1) These wiring diagrams are given as examples only; the designer must refer to the relevant safety standards for guidance.

Setup

Functional diagrams

XCSTE5●●●



XCSTE6●●●



XCSTE7●●●



Contact operation

■ Closed □ Open ▒ Contact in transition

Dual Dimensions: INCHES Millimeters

References: page 4/74 | Specifications: page 4/74 | Dimensions: page 4/75 | Wiring diagrams: page 4/76

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Safety interlock switches, actuator operated
Solenoid interlocking
Plastic turret head, type XCSTE

Wiring diagrams (continued)

Wiring to PL=b, category 1 conforming to EN/ISO 13849-1
Wiring examples with protection fuse to prevent jumpering of the N.C. contact, either by cable damage or by tampering.

Locking without power (on de-energization of solenoid)

N.C. + N.O.
XCSTE53●●



(1) Solenoid
(2) Auxiliary contact
E1-E2: Solenoid supply
13-14: Safety contact, available for redundancy or signaling

Locking with power (on energization of solenoid)

N.C. + N.O.
XCSTE55●●



(1) Solenoid
(2) Auxiliary contact
E1-E2: Solenoid supply
13-14: Safety contact, available for redundancy or signaling

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1
Wiring examples with redundancy for the safety interlock switch contacts, without monitoring or redundancy in the power circuit

Locking without power (on de-energization of solenoid)

N.C. + N.C.
XCSTE73●●



(1) Solenoid
(2) Solenoid auxiliary contact
E1-E2: Solenoid supply
11-12: Safety contact, available for redundancy

Locking with power (on energization of solenoid)

N.C. + N.C.
XCSTE75●●



(1) Solenoid
(2) Solenoid auxiliary contact
E1-E2: Solenoid supply
11-12: Safety contact, available for redundancy

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Safety interlock switches, actuator operated
Pre-wired connector options
Metal, turret head, types XCSA, XCSB, XCSC, XCSE, XCSLE and XCSLF

Pre-wired mini connectors for XCS safety interlocks

The XCS safety interlock switches are available with mini connectors in several different wiring diagrams. Each wiring option shown here and on page 4/79 has a notation of which devices are available with that option. Add the following suffixes to the appropriate XCS reference. Only a small number of the pre-wired options available are listed here and on page 4/79. **Many other connectors and wiring diagrams are available. New wiring diagrams to meet your applications are available upon request; contact the Customer Care Center.**

3-pin



5-pin

6-pin

7-pin

NOTE: Views of connectors shown above are of the male views as installed in the switch.

3-pin: (for all XCS except XCSE, XCSMP, and XCSDM) suffix AA

Switch terminals	Wire color
21	Black
22	White
Ground	Green

5-pin: (for all XCS except XCSE, XCSMP, and XCSDM) suffix CA *(1)*

Switch terminals	Wire color
13	Orange
14	Red
21	White
22	Black
Ground	Green

5-pin: (for XCSE) suffix CC *(1)*

Switch terminals	Wire color
13	Orange
14	Red
E1	White
E2	Black
Ground	Green

5-pin: (for all XCS except XCSE, XCSMP, and XCSDM) suffix CB *(1)*

Switch terminals	Wire color
13	White
14	Black
21	Orange
22	Red
Ground	Green

5-pin: (for XCSE) suffix CD *(1)*

Switch terminals	Wire color
13	White
14	Black
E1	Orange
E2	Red
Ground	Green

6-pin: (for all XCS with LED except for XCSE) suffix DA

Switch terminals	Wire color
13	Orange
14	Blue
21	Red
22	White
X1	Black
Ground	Green

7-pin: (for XCSE) suffix EA *(1)*

Switch terminals	Wire color
13	Orange
14	Red
21	White
22	Black
Ground	Green
E1	Blue
E2	White with black tracer/stripe

7-pin: (for XCSE - locking without power) suffix ED *(1)*

Switch terminals	Wire color
33	White
34	Black
51	Orange
X1	Red
Ground	Green
E1	Blue
E2	White with black tracer/stripe

Jumper between 52 and 21 (installed by Schneider Electric)
Jumper between 22 and X2 (installed by Schneider Electric)
Jumper between 34 and X3 (installed by Schneider Electric)

7-pin: (for XCSE) suffix EB *(1)*

Switch terminals	Wire color
13	White
14	Black
21	Orange
22	Red
Ground	Green
E1	Blue
E2	White with black tracer/stripe

7-pin: (for XCSE) suffix EE

Switch terminals	Wire color
21	Orange
22	Red
51	White
52	Black
Ground	Green
E1	Blue
E2	White with black tracer/stripe

7-pin: (for XCSE - locking without power) suffix EC *(1)*

Switch terminals	Wire color
33	Orange
34	Red
51	White
X1	Black
Ground	Green
E1	Blue
E2	White with black tracer/stripe

Jumper between 52 and 21 (installed by Schneider Electric)
Jumper between 22 and X2 (installed by Schneider Electric)
Jumper between 34 and X3 (installed by Schneider Electric)

7-pin: (for XCSE) suffix EF

Switch terminals	Wire color
21	White
22	Black
51	Orange
52	Red
Ground	Green
E1	Blue
E2	White with black tracer/stripe

(1) Not for XCS devices with all N.C. contacts. The device must have at least 1 N.O. contact.
Note: More available connector versions are listed on page 4/79.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Pre-wired mini connectors for XCS safety interlocks *(continued)*

The XCS safety interlock switches are available with mini connectors in several different wiring diagrams. Each wiring option shown here and on page 4/78 has a notation of which devices are available with that option. Add the following suffixes to the appropriate XCS reference. Only a small number of the pre-wired options available are listed here and on page 4/78. **Many other connectors and wiring diagrams are available. New wiring diagrams to meet your applications are available upon request; contact the Customer Care Center.**

9-pin

1 - Orange
2 - Blue
3 - Red-Blk. Tr.
4 - Green-Blk. Tr.
5 - White
6 - Red
7 - Green
8 - White-Blk. Tr.
9 - Black

NOTE: Views of connectors shown above are of the male views as installed in the switch.

9-pin: (for XCSE) suffix GA *(1)*

Switch terminals	Wire color
13	Orange
14	Red
21	White
22	Black
Ground	Green
51	Red with black tracer/stripe
52	Green with black tracer/stripe
E1	Blue
E2	White with black tracer/stripe

9-pin: (for XCSE) suffix GB *(1)*

Switch terminals	Wire color
13	White
14	Black
21	Orange
22	Red
Ground	Green
51	Red with black tracer/stripe
52	Green with black tracer/stripe
E1	Blue
E2	White with black tracer/stripe

9-pin: (for XCSE) (locking with power) suffix GC

Switch terminal	Wire color
31	Orange
32	Red
21	White
22	Black
Ground	Green
43	Red with black tracer/stripe
44	Green with black tracer/stripe
E1	Blue
E2	White with black tracer/stripe

9-pin: (for XCSE) (locking without power) suffix GD

Switch terminals	Wire color
31	Orange
32	Red
21	White
22	Black
Ground	Green
51	Red with black tracer/stripe
52	Green with black tracer/stripe
E1	Blue
E2	White with black tracer/stripe

9 Pin: (for XCSLE and XCSLF) (locking without power) suffix GJ

Switch terminals	Wire color
11	Red
42	White
21	Orange
52	Blue
X1	Black
Ground	Green/Yellow
E1	Red with Black tracer/stripe
E2	White with Black tracer/stripe
Terminals Jumpered	12 to 41 22 to 51

9 Pin: (for XCSLF) (locking with or without power) suffix GK

Switch terminals	Wire color
21	Red
22	White
13	Orange
14	Blue
X1	Black
Ground	Green/Yellow
E1	Red with Black tracer/stripe
E2	White with Black tracer/stripe

9 Pin: (for XCSLF) (locking with or without power) suffix GL

Switch terminals	Wire color
21	Red
42	White
31	Orange
52	Blue
X1	Black
Ground	Green/Yellow
E1	Red with Black tracer/stripe
E2	White with Black tracer/stripe
Terminals Jumpered	22 to 41 32 to 51

(1) Not for XCS devices with all N.C. contacts. The device must have at least 1 N.O. contact.
Note: More available connector versions are listed on page 4/78.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic switches
Plastic

4

XCSDMC

Rectangular, compact: 2.01 x 0.63 x 0.28 in. (51 x 16 x 7 mm)

Precabled connection	Connector on pigtail connection





Page 4/82

XCSDMP

Rectangular, standard: 3.46 x 0.98 x 0.51 in. (88 x 25 x 13 mm)

Precabled connection	Connector on pigtail connection





Page 4/82

XCSDMR

Cylindrical, diameter: 1.18 in. (30 mm), length: 1.51 in. (38.5 mm)

Precabled connection	Connector on pigtail connection





Page 4/82

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic switches
Plastic

Environment

Conformity to standards		Products		EN/IEC 60204-1, EN/ISO 14119
		Machine assemblies		IEC/EN 60204-1, EN/ISO 12100, EN 1088/ISO 14119 (XCSDM●5●● only)
Product certifications				UL-CSA, BG
Maximum safety level *Using an appropriate and correctly connected control system.*				PL=e, category 4 conforming to EN/ISO 13849-1 and SIL 3 conforming to EN/IEC 61508
Reliability data B_{10d}				50,000,000 (value given for a service life of 20 years, limited by mechanical or contact wear)
Protective treatment				Standard version: **TH**
Ambient air temperature		For operation	**°F (°C)**	–13 to +185 (–25 to +85)
		For storage	**°F (°C)**	–40 to +185 (–40 to +85)
Vibration resistance				10 gn (10–150 Hz) conforming to IEC 60068-2-6
Shock resistance				30 gn (11 ms) conforming to IEC 60068-2-7
Sensitivity to magnetic fields			**mT**	≥ 0.3
Electric shock protection				Class II conforming to IEC 60536
Degree of protection		Conforming to IEC 60529		IP66 and IP67 for coded magnetic switches with precabled connection IP67 for coded magnetic switches with connector on pigtail connection
Materials				Thermoplastic case (PBT) PVC cable (ROHS)

Contact block specifications

Rated operational specifications				Ue: ⎓ 24 V, Ie: 100 mA max.
Rated insulation voltage (Ui)				Ui: ⎓ 100 V
Rated impulse withstand voltage (Uimp)			**kV**	2.5 conforming to EN/IEC 60947-5-1
Resistance across terminals		Contact with LED	Ω	57
		Contact without LED	Ω	10
Protection (not using safety module)				External cartridge fuse: 500 mA gG (gl)
Connection	XCSDMC			Precabled, 4 x 22 AWG, length: 2, 5 or 10 m depending on model or M8 connector on 5.95 in. (0.15 m) pigtail
	XCSDMP	2 contact model		Precabled, 4 x 22 AWG, length: 2, 5 or 10 m depending on model or M12 connector on 5.95 in. (0.15 m) pigtail
		3 contact model		Precabled, 6 x 22 AWG, length: 2, 5 or 10 m depending on model or M12 connector on 5.95 in. (0.15 m) pigtail
	XCSDMR			Precabled, 4 x 22 AWG, length: 2, 5 or 10 m depending on model or M12 connector on 5.95 in. (0.15 m) pigtail
Contact material				Rhodium
Electrical life				1.2 million operating cycles
Maximum switching voltage			**V**	⎓ 100
Switching capacity		Contact with LED	**mA**	5–100
		Contact without LED	**mA**	0.1–100
Insulation resistance			**M**W	1000
Maximum breaking capacity		Contact with LED	**VA**	3
		Contact without LED	**VA**	10
Maximum switching frequency			**Hz**	150

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic switches
Plastic, precabled

Type	Rectangular		Cylindrical
	Compact 2.01 x 0.63 x 0.28 in (51 x 16 x 7 mm)	Standard 3.46 x 0.98 x 0.51 in (88 x 25 x 13 mm)	Diameter: 1.18 in. (30 mm) Length: 1.51 in. (38.5 mm)



References of switches *(1)* must be used in conjunction with XPS safety relay modules, safety controllers, or safety PLCs

Contact states shown are with the magnet positioned in front of the switch

2-pole N.O. + N.C. (N.C. break before make)		**XCSDMC5902**	**XCSDMP5902**	**XCSDMR5902**
2-pole N.C. + N.C. *(2)* (1 N.O. break before make)		**XCSDMC7902**	**XCSDMP7902**	**XCSDMR7902**
3-pole N.O. + N.O. + N.C. (1 N.C. break before make)		–	**XCSDMP5002**	–
3-pole N.O. + N.C. + N.C. *(2)* (1 N.O. break before make)		–	**XCSDMP7002**	–
2-pole N.O. + N.C. *(3)* (N.C. break before make) With LED		**XCSDMC5912**	**XCSDMP5912**	**XCSDMR5912**
2-pole N.C. + N.C. *(2) (3)* (1 N.O. break before make) With LED		**XCSDMC7912**	**XCSDMP7912**	**XCSDMR7912**
3-pole N.O. + N.O. + N.C. *(3)* (1 N.C. break before make) With LED		–	**XCSDMP5012**	–
3-pole N.O. + N.C. + N.C. *(2) (3)* (1 N.O. break before make) With LED		–	**XCSDMP7012**	–
Weight lb (kg)		0.22 (0.101)	0.40 (0.180)	0.32 (0.146)

(1) Magnetic switch + coded magnet (XCSZC●●●●).
Switch precabled with 6.6 ft (2 m) cable. For other cable lengths, replace the last number of the reference (2) with 5 for a 16.4 ft (5 m) cable or with 10 for a 32.8 ft (10 m) cable. Example: XCSDMC5902 rectangular, compact switch with N.C. + N.O. contacts and 10 m cable becomes ***XCSDMC59010****.*
(2) For wiring in conjunction with an XPSAF safety relay module, refer to pages 4/89 and 4/91.
(3) The green LED is lit when the coded magnet is positioned in front of the switch (guard closed).
·N.O. contact PK-GY is to be used as an indicator of the device state, typically to a PLC. It is not to be used for the safety function.

Additional specifications not shown under General Specifications (page 4/81)

Operating zone	Sao: 0.20 in. (5 mm) Sar: 0.59 in. (15 mm)	Sao: 0.31 in. (8 mm) Sar: 0.79 in. (20 mm)	Sao: 0.31 in. (8 mm) 0.79 in. (20 mm)
Approach directions	3 directions	3 directions	1 direction

Accessories (page 4/84)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches

Coded magnetic switches
Plastic, connector on 5.9 in. (151 mm) pigtail

Type	Rectangular		Cylindrical
	Compact 2.01 x 0.63 x 0.28 in (51 x 16 x 7 mm)	Standard 3.46 x 0.98 x 0.51 in (88 x 25 x 13 mm)	Diameter: 1.18 in. (30 mm) Length: 1.51 in. (38.5 mm)
	M8 connector	**M12 connector**	**M12 connector**
			

References of switches *(1)* must be used in conjunction with XPS safety relay modules, safety controllers, or safety PLCs

Contact states shown are with the magnet positioned in front of the switch

2-pole N.O. + N.C. (N.C. break before make)		**XCSDMC590L01M8**	**XCSDMP590L01M12**	**XCSDMR590L01M12**
2-pole N.C. + N.C. *(2)* (1 N.C. break before make)		**XCSDMC790L01M8**	**XCSDMP790L01M12**	**XCSDMR790L01M12**
3-pole N.O. + N.O. + N.C. (1 N.C. break before make)		–	**XCSDMP500L01M12**	–
3-pole N.O. + N.C. + N.C. *(2)* (1 N.O. break before make)		–	**XCSDMP700L01M12**	–
2-pole N.O. + N.C. *(3)* (N.C. break before make) With LED		**XCSDMC591L01M8**	**XCSDMP591L01M12**	**XCSDMR591L01M12**
2-pole N.C. + N.C. *(2) (3)* (1 N.O. break before make) With LED		**XCSDMC791L01M8**	**XCSDMP791L01M12**	**XCSDMR791L01M12**
3-pole N.O. + N.O. + N.C. *(3)* (1 N.C. break before make) With LED		–	**XCSDMP501L01M12**	–
3-pole N.O. + N.C. + N.C. *(2) (3)* (1 N.O. break before make) With LED		–	**XCSDMP701L01M12**	–
Weight lb (kg)		0.22 (0.101)	0.40 (0.180)	0.32 (0.146)

(1) Magnetic switch + coded magnet (XCSZC●●●●).
(2) For wiring in conjunction with an XPSAF safety relay module, refer to pages 4/89 and 4/91.
(3) The green LED is lit when the coded magnet is positioned in front of the switch (guard closed).
N.O. contact PK-GY (6-7) is to be used as an indicator of the device state, typically to a PLC. It is not to be used for the safety function.

Additional specifications not shown under Specifications (page 4/81)

Operating zone	Sao: 0.20 in. (5 mm) Sar: 0.59 in. (15 mm)	Sao: 0.31 in. (8 mm) Sar: 0.79 in. (20 mm)	Sao: 0.31 in. (8 mm) Sar: 0.79 in. (20 mm)
Approach directions	3 directions	3 directions	1 direction

Accessories (page 4/84)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Accessories

Accessories for coded magnetic safety interlock switches	XCSDMC●●●2 XCSDMC●●●L	XCSDMP●●●2 XCSDMP●●●L	XCSDMR●●●2 XCSDMR●●●L
Mounting clamp	–		**XSZB130**
Weight lb (kg)	–		0.18 (0.080)
Additional coded magnet	**XCSZC1**	**XCSZP1**	**XCSZR1**
Weight lb (kg)	0.02 (0.009)	0.11 (0.050)	0.04 (0.018)
Nonmagnetic shims	**XCSZCC** (lot of 2)	**XCSZCP** (lot of 2)	**XCSZCR**
Weight lb (kg)	0.02 (0.008)	0.03 (0.012)	0.004 (0.002)

Pre-wired female connectors for connector version switches
Pre-wired connector specifications

Pre-wired connector type		XZCP0941L●, XZCP1041L●	XZCP29P11L●	XZCP1141L●, XZCP1241L●
Type of connection		Screw threaded (metal clamping ring)	Screw threaded (metal clamping ring)	Screw threaded (metal clamping ring)
Number of conductors/pins		4	8	4
Degree of protection		IP67 (with clamping ring correctly tightened)		
Ambient air temperature	Static	–31 to +194 °F (–35 to +90 °C)	–31 to +194 °F (–35 to +90 °C)	–31 to +194 °F (–35 to +90 °C)
	Dynamic	+23 to +194 °F (–5 to +90 °C)	+23 to +194 °F (–5 to +90 °C)	+23 to +194 °F (–5 to +90 °C)
Cabling		Ø0.205" (5.2 mm) cable, wire c.s.a.: 4 x 22 AWG (0.34 mm²)	Ø0.205" (5.2 mm) cable, wire c.s.a.: 8 x 24 AWG (0.25 mm²)	Ø0.205" (5.2 mm) cable, wire c.s.a.: 4 x 22 AWG (0.34 mm²)
LED signaling		–	–	–
Nominal voltage		∼ 60 V, ⎓ 75 V	∼ 250 V, ⎓ 300 V	∼ 250 V, ⎓ 300 V
Nominal current		4 A	2 A	4 A
Insulation resistance		> 10^9 Ω	> 10^9 Ω	> 10^9 Ω
Contact resistance		⩽ 5 mΩ	⩽ 5 mΩ	⩽ 5 mΩ

References of pre-wired connectors



XZCP0941L●



XZCP1041L●



XZCP29P11L●



XZCP1141L●



XZCP1241L●

Type of connector	Number of pins	For use with	Type	Cable length ft (m)	Reference	Weight lb (kg)
Female, M8	4	XCSDMC●●●L	Straight	6.56 (2)	**XZCP0941L2**	0.18 (0.080)
				16.40 (5)	**XZCP0941L5**	0.40 (0.180)
				32.81 (10)	**XZCP0941L10**	0.79 (0.360)
			Elbowed	6.56 (2)	**XZCP1041L2**	0.18 (0.080)
				16.40 (5)	**XZCP1041L5**	0.40 (0.180)
				32.81 (10)	**XZCP1041L10**	0.79 (0.360)
Female, M12	8	XCSDMP●●●L	Straight	6.56 (2)	**XZCP29P11L2**	0.22 (0.100)
				16.40 (5)	**XZCP29P11L5**	0.64 (0.290)
				32.81 (10)	**XZCP29P11L10**	1.04 (0.470)
Female, M12	4	XCSDMR●●●L/ XCSDMP●●●L	Straight	6.56 (2)	**XZCP1141L2**	0.20 (0.090)
				16.40 (5)	**XZCP1141L5**	0.42 (0.190)
				32.81 (10)	**XZCP1141L10**	0.82 (0.370)
			Elbowed	6.56 (2)	**XZCP1241L2**	0.20 (0.090)
				16.40 (5)	**XZCP1241L5**	0.42 (0.190)
				32.81 (10)	**XZCP1241L10**	0.82 (0.370)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Function diagrams with magnet present (precabled version)

XCSDMC59●●



Color
(N.C.): BN/BU
(N.O.): BK/WH

XCSDMC79●●



Color
(N.C.): BN/BU
(N.C.): BK/WH

XCSDMP50●●



Color
(N.C.): BN/BU
(N.O.): BK/WH
(N.O.): GY/PK

XCSDMP70●●



Color
(N.C.): BN/BU
(N.C.): BK/WH
(N.O.): GY/PK

XCSDMR59●●/XCSDMP59●●



Color
(N.C.): BN/BU
(N.O.): BK/WH

XCSDMR79●●/XCSDMP79●●



Color
(N.C.): BN/BU
(N.C.): BK/WH

Function diagrams with magnet present (connector on pigtail version)

XCSDMC59●●



Pin
(N.C.): 1/3
(N.O.): 4/2

XCSDMC79●●



Pin
(N.C.): 1/3
(N.C.): 4/2

XCSDMP50●●



Pin
(N.C.): 1/3
(N.O.): 4/2
(N.O.): 6/7

XCSDMP70●●



Pin
(N.C.): 1/3
(N.C.): 4/2
(N.O.): 6/7

XCSDMR59●●/XCSDMP59●●



Pin
(N.C.): 1/3
(N.O.): 4/2

XCSDMR79●●/XCSDMP79●●



Pin
(N.C.): 1/3
(N.O.): 4/2

Contact closed

Contact open

Contact in transition

Sao: specified operating distance.
Sar: specified tripping distance.
Conforming to EN/IEC 60947-5-3.

4

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic switches
Plastic

Coded magnetic switches

XCSDMC

Precabled connection



(1) Counterbored: 0.24 x 0.14 in. (Ø6 x 3.5 mm)

Connector on pigtail connection



(1) Counterbored: 0.24 x 0.14 in. (Ø6 x 3.5 mm)
(2) M8 4-pin connector.

Coded magnet for XCSDMC

XCSZC1



(1) Counterbored: 0.24 x 0.14 in. (Ø6 x 3.5 mm)

XCSDMP

Precabled connection



Connector on pigtail connection



(1) 4 or 6-pin M12 connector.

Coded magnet for XCSDMP

XCSZP1



XCSDMR

Precabled connection



Connector on pigtail connection



(1) M12 4-pin connector.

Coded magnet for XCSDMR

XCSZR1



(1) 2 x Ø0.17 (2 x Ø4.3), countersunk: Ø7.5 at 45°.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Accessories

Mounting clamp

XSZB130



(1) 2 elongated holes Ø0.16 x 0.31 in. (4 x 8 mm).

Nonmagnetic shims

XCSZCC



XCSZCP



XCSZCR



Pre-wired female connectors

XZCP0941L●



XZCP1041L●



XZCP1141L●



XZCP1241L●



XZCP29P11L●



Wiring diagrams

M8 pre-wired female connector

XZCP0941L●



M12 pre-wired female connector

XZCP1141L●, XZCP1241L●



XZCP29P11L●



Mounting

XCSDMC



XCSDMP



XCSDMR



XCS	a	b	c	d	e
DMC	1.57 (40)	0.51 (13) min.	–	3.19 x 2.17 (81 x 55)	–
DMP	3.94 (100)	0.39 (10) min.	–	4.65 x 2.17 (118 x 55)	–
DMR	1.57 (40)	0.47 (12) min.	> 0.39 (10)	Ø1.77 (45)	0.79 (20)
		–	> 0.39 (10)	Ø1.77 (45)	0.51 (13)
		0.47 (12) min.	< 0.39 (10)	–	0.79 (20)
		–	< 0.39 (10)	–	0.67 (17)

Nonmagnetic shims	
A	XCSZCC
B	XCSZCP
C	XCSZCR

Dual Dimensions: INCHES / Millimeters

Introduction: page 4/80
Specifications: page 4/81
References: page 4/82
Dimensions: page 4/86
Wiring diagrams: page 4/87

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic switches
Plastic, precabled

XCSDMP5●●● with XPSDMB

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL 3 conforming to EN/IEC 61508.
Example with 3-pole N.O. + N.O. + N.C. (1 N.O. break before make) contact.



ESC: External start conditions.
- Inputs: S11, S12, S13 or S21, S22, S23
- Unused inputs must be jumpered from S_1 to S_3. For example: S21 to S23.
- The order in which the inputs are wired or jumpered will not affect device operation.

XCSDMC5●●●, XCSDMP5●●●, XCSDMR5●●● with XPSDME

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL 3 conforming to EN/IEC 61508. Example with 2-pole N.O. + N.C. (N.O. break before make) contact.



ESC: External start conditions.
- Inputs: S_1, S_2, S_3
- Unused inputs must be jumpered from S_1 to S_3. For example if input S61, S62, S63 is not used, then terminals S61 and S63 must be jumpered.
- The order in which the inputs are wired or jumpered will not affect device operation.

Introduction: page 4/80 | Specifications: page 4/81 | References: page 4/82 | Dimensions: page 4/86 | Wiring diagrams: page 4/87

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Connection of up to 3 coded magnetic switches, with an LED on one input, with XPSDM● *(1)*

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1 and SIL 2 conforming to EN/IEC 61508

Example with 2-pole N.O. + N.C. contact



Example with 3-pole N.O. + N.O. + N.C. contact



(1) Input: S11, S12, S13 or S21, S22, S23.

XCSDM●7●●● with XPSAF

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL 3 conforming to EN/IEC 61508. Example with 2-pole N.C. + N.C. contact



(1) With start button monitoring.
(2) Without start button monitoring.
ESC: External start conditions.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic switches
Plastic, connector on pigtail

XCSDMP5●●● with XPSDMB

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL 3 conforming to EN/IEC 61508.
Example with 3-pole N.O. + N.O. + N.C. (1 N.O. break before make) contact.



ESC: External start conditions.
• Inputs: S11, S12, S13 or S21, S22, S23
• Unused inputs must be jumpered from S_1 to S_3. For example: S21 to S23.
• The order in which the inputs are wired or jumpered will not affect device operation.

XCSDMC5●●●, XCSDMP5●●●, XCSDMR5●●● with XPSDME

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL 3 conforming to EN/IEC 61508. Example with 2-pole N.O. + N.C. (N.O. break before make) contact.



ESC: External start conditions.
• Inputs: S_1, S_2, S_3
• Unused inputs must be jumpered from S_1 to S_3. For example, if input S61, S62, S63 is not used, then terminals S61 and S63 must be jumpered.
• The order in which the inputs are wired or jumpered will not affect device operation.

Introduction: page 4/80 | Specifications: page 4/81 | References: page 4/82 | Dimensions: page 4/86 | Wiring diagrams: page 4/87

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Connection of up to 3 coded magnetic switches, with an LED on one input, with XPSDM● *(1)*

Wiring to PL=d, category 3 conforming to EN/ISO 13849-1 and SIL 2 conforming to EN/IEC 61508

Example with 2-pole N.O. + N.C. contact



Example with 3-pole N.O. + N.O. + N.C. contact



(1) Input: S11, S12, S13 or S21, S22, S23.

XCSDM●7●●● with XPSAF

Wiring to PL=e, category 4 conforming to EN/ISO 13849-1 and SIL 3 conforming to EN/IEC 61508. Example with 2-pole N.C. + N.C. contact



(1) With start button monitoring.
(2) Without start button monitoring.
ESC: External start conditions.

Introduction: page 4/80 | Specifications: page 4/81 | References: page 4/82 | Dimensions: page 4/86 | Wiring diagrams: page 4/87

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic system

Coded magnetic system
Precabled connection

SIL 2/PL=d, category 3 and SIL 3/PL=e, category 4

XCSDM3791●● /XCSDM4801●●



page 4/94

Coded magnetic system
M12 connector connection

SIL 2/PL=d, category 3 and SIL 3/PL=e, category 4

XCSDM3791M12/ XCSDM4801M12



page 4/95

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic system

Coded magnetic type			SIL 2/PL= d, category 3 XCSDM3	SIL 3/PL=e, category 4 XCSDM4
Environment				
Conformity to standards			EN/IEC 60947-5-1; EN/IEC 60947-5-2; EN/IEC 60947-5-3, EN/ISO 14119	
Product certifications			CE, UL, CSA, TÜV	
Maximum safety level *Using an appropriate and correctly connected control system.*			SIL 2 conforming to EN/IEC 61508,PL=d, category 3 conforming to EN/ISO 13849-1	SIL 3 conforming to EN/IEC 61508, PL=e, category 4 conforming to EN/ISO 13849-1
Reliability data B_{10d}			MTTFd = 182 years PFH = $3.94E^{-9}$/ PFD = $1.15E^{-5}$ SFF = 92.5% / HFT = 1	
Ambient air temperature	For operation	**°F (°C)**	–13 to +158 (–25 to +70)	
	For storage	**°F (°C)**	+40 to +185 (–40 to +85)	
Vibration resistance	Conforming to IEC 60068-2-6		10 gn (10–500 Hz)	
Shock resistance	Conforming to IEC 60068-2-7		30 gn, 11 ms	
Sensitivity to magnetic fields		**mT**	≤ 0,5	
Electric shock protection	Conforming to IEC 61140		Class III	
Degree of protection	Conforming to IEC 60529		Precabled version: IP66, IP67 Connector version: IP67	
	Conforming to DIN 40050		Precabled version: IP69K	
Materials			Thermoplastic case (PBT); PVC cable	
Specifications				
Rated operational specifications			Ub : ⎓ 24 V +10% –20%	
Rated insulation voltage (Ui)			Ui : ⎓ 36V	
Rated impulse withstand voltage (Uimp)	Conforming to EN 60947-5-1	kV	2.5	
Integrated output protection			Overload and short-circuit protection	
Connection	Conforming to IEC 60947-5-2-A3 and IEC 61076		Precabled, 6 x 22 AWG (0.25 mm²), length: 6.6, 16.4 or 32.8 ft (2, 5, or 10 m) depending on model or M12 connector (A coding)	Precabled, 8 x 22 AWG (0.25 mm²), length: 6.6, 16.4 or 32.8 ft (2, 5, or 10 m) depending on model or M12 connector (A coding)
Cable diameter		**in. (mm)**	0.24 (6.1 +/- 0.3)	
Cable resistance		**mΩ/m**	90	
Safety outputs (OSSD) **(Output Signal Switching Devices)**			2 PNP type (N.O.) solid-state outputs, 1.5 A (2 A up to 140 °F (60°C)), ⎓ 24 V (short-circuit protected)	
Alarm output			–	1 solid-state output, 0.5 A, ⎓ 24 V, PNP
Signaling			LED (green/red/orange)	
Maximum switching frequency		**Hz**	3	
Activation delay		**ms**	100	
Discordance time		**s**	2	
HFT (Hardware Fault Tolerance)			1	
			Test interval: 12 months	
Tightening torque		**lb-ft (N•m)**	1.327 (1.8) maximum	
Maximum series mounting			32 maximum with 6.6 ft (2 m) cable	–
Functions				
Functions			- LED status signaling	- Auto/Manual start via Start input - Monitoring of external switching devices (EDM: External Devices Monitoring) - Display of operating modes (LED) - Monitoring of the function (open or closed) as well as the response time of the power components.

4

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic system
Plastic, solid-state PNP type output

Type	Coded magnetic system with dedicated transmitter
	Precabled connection



References

Description	Type of connection	SIL 2/PL=d, category 3	SIL 3/PL=e, category 4	Weight lb (kg)
Magnetic system with dedicated transmitter *(1)*	Precabled, 6.6 ft (2 m)	**XCSDM379102**	**XCSDM480102**	0.71 (0.320)
	Precabled, 16.4 ft (5 m)	–	**XCSDM480105**	1.06 (0.480)
	Precabled, 32.8 ft (10 m)	**XCSDM379110**	**XCSDM480110**	1.64 (0.745)

(1) Self-contained system does not require the use of safety module or nonmagnetic shim.

Detection specifications

Assured operating distance	Sao : 0.39 in. (10 mm)
Assured tripping distance	Sar : 0.79 in. (20 mm)
Approach directions	9
Approach speed	0.03 ft/s (0.01 ms) mini

Output status (precabled connection)

Output states shown are with the dedicated transmitter positioned in front of the receiver.

XCSDM3791●●



XCSDM4801●●



Output closed
Output open
Transitional state

Sao : Specified operating distance.
Sar : Specified tripping distance.
Conforming to EN/IEC 60947-5-3

Approach directions







Introduction: page 4/92 | Specifications: page 4/93 | References: page 4/94 | Dimensions: page 4/97 | Wiring diagrams: page 4/98

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic system
Plastic, solid-state PNP type output

Type	Coded magnetic system with dedicated transmitter
	M12 connector connection



References

Description	Type of connection	SIL 2/PL=d, category 3	SIL 3/PL=e, category 4	Weight lb (kg)
Coded magnetic system with dedicated transmitter *(1)*	M12 connector	**XCSDM3791M12**	**XCSDM4801M12**	0.47 (0.215)

1) Self-contained system does not require the use of safety module or nonmagnetic shim.

Detection specifications

Assured operating distance	Sao : 0.39 in. (10 mm)
Assured tripping distance	Sar : 0.79 in. (20 mm)
Approach directions	9
Approach speed	0.03 ft/s (0.01 ms) mini

Output status (precabled connection)

Output states shown are with the dedicated transmitter positioned in front of the receiver.

XCSDM3791M12



XCSDM4801M12



"OFF" = Error

Output closed
Output open
Transitional state

Sao : Specified operating distance.
Sar : Specified tripping distance.
Conforming to EN/IEC 60947-5-3

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Accessories

Description	For use with	Reference	Weight lb (kg)
Replacement dedicated transmitter	XCSDM3/4●●●02/05/10 XCSDM3/4●●●M12	**XCSDMT**	0.22 (0.100)
Arc suppressor (pair)	XCSDM3/4●●●02/05/10 XCSDM3/4●●●M12	**XUSLZ500**	0.04 (0.020)

Pre-wired female connectors for connector version coded magnetic system

Pre-wired connector specifications

Pre-wired connector type			XZ CP29P12L●
Type of connection			Screw threaded (metal clamping ring)
Number of contacts			8
Degree of protection			IP67 (with clamping ring correctly tightened)
Ambient air temperature	Operation	**°F (°C)**	–13 to +158 (–25 to +70)
	Storage	**°F (°C)**	–40 to +185 (–40 to +85)
Cabling	Conforming to EN/IEC 60947-5-2		Ø6.1 mm PUR cable, wire c.s.a.: 8 x 22 AWG (0.25 mm²)
LED signaling			–
Nominal current		**A**	2
Insulation resistance		Ω	> 10^9
Contact resistance		**mΩ**	≤ 5

References of pre-wired connectors



XZCP29P12L●

Type of connector	No. of contacts	For use with	Type	Cable length ft (m)	Reference	Weight lb (kg)
Female, M12 (Coding A)	8	XCSDM3/4●●●02 XCSDM3/4●●●05 XCSDM3/4●●●10	Straight	6.6 (2)	**XZCP29P12L2**	0.22 (0.100)
				16.4 (5)	**XZCP29P12L5**	0.64 (0.290)
				32.8 (10)	**XZCP29P12L10**	1.04 (0.470)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety interlock and limit switches
Coded magnetic system
Plastic

Coded magnetic system

Precabled connection

XCSDM3/4●●●02/05/10



M12 connector (Coding A) connection

XCSDM3/4●●●M12



Accessory

Replacement dedicated transmitter

XCSDMT



Dual Dimensions: INCHES / Millimeters

Pre-wired female connectors

XZCP29P12L●



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Wiring diagram

M12 pre-wired female connector

XZCP29P12L●



Mounting

XCSDM3/DM4







Dual Dimensions: INCHES
Millimeters

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Wiring diagrams

Category 3 (this wiring diagram can achieve SIL 2/PL=d, category 3)

Precabled connection

XCSDM3791●●



M12 connector (A coding) connection

XCSDM3791M12



SIL 3/PL=e, category 4

Precabled connection

XCSDM4801●●



M12 connector (A coding) connection

XCSDM4801M12



Series mounting non-contact safety interlock switches *(2)*

XCSDM3791●●



Wiring to SIL 3/PL=e, category 4 with Preventa safety relay module

Example: XCSDM3●●●●● + XPSAFL5130



(1) Mechanically linked contacts
(2) Maximum series mounting: 32 maximum with 6.6 ft (2 m) cable.
(3) 2A maximum

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtains

Selection guide: Light curtains 5/2

Overview 5/6

Light curtains, type 4

For finger or hand protection
- Optimum light curtains with solid state output, type XUSLB. 5/8
- Universal light curtains with solid state output, type XUSLD 5/8
- Substitution table (Cross-reference from XUSLT to XUSLB and XUSLDM) . . 5/20
- Muting module for XUSLDM universal light curtains, type XPSLCM1 . . . . . 5/22

For body protection
- Compact light curtains with solid-state output, type XUSLP
  - with connector 5/28
  - with terminal block. 5/30

Light curtains, type 2

For hand protection
- Slim, compact light curtains with solid-state output, type XUSLN 5/36

For body protection
- Preventa™ safety modules and single-beam photo-electric sensors, type XPSCM 5/48

Accessories for light curtains types 2 and 4. . . . . 5/40

Safety relay modules

For monitoring 2 to 4 light curtains types 2 and 4
- Preventa™ safety relay modules, type XPSLCD. 5/56

For “muting” function of light curtains types 2 and 4
- Preventa™ safety monitoring modules, type XPSLCM 5/60

Light curtain application and installation

Protection of personnel 5/68

Standards and basic requirements 5/69

Minimum safety distances 5/70
- United States. 5/70
- Europe 5/72
- Special rules for presses 5/72

Prevention of access to hazardous area. 5/73

Light curtain alignment 5/74

Using mirrors 5/75

Minimum object sensitivity (MOS). 5/76

Fixed and floating blanking 5/77

Test procedure for the United States. 5/78

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions
Light curtains

Applications		**Machine tool, material handling, automotive, etc.**	
Functions		**Finger protection: 0.55 in. (14 mm), or hand protection: 1.18 in. (30 mm)**	
Device		Light curtains, type 4	
		Multi-beam, infrared transmission, light curtains (1 transmitter-receiver pair)	
		Optimum Type	Universal Type
Conformity	Product standards	ANSI/RIA R15.06, ANSI B11:19-1990, OSHA 1910.217(C), OSHA 1910.212, EN/IEC 61496-1 and EN/IEC 61496-2 and IEC 61508-1, 2 (Type 4 ESPE)	
	European directives	Machinery directive 2006/42/EC, Work equipment directive 89/655/EEC and EMC directive 89/336 EEC ROHS directive 2002/95/EC	
Product certifications		CE, TUV, UL, CSA	
Degree of protection		IP65	
Cross-section		1.50 x 1.97 in. (38 x 50 mm)	
Protected height	Conforming to EN 999	11–53.5 in. (280–1360 mm) (finger protection) 12.6–83.5 in. (320–2120 mm) (hand protection)	
Nominal sensing distance		1–23 ft (0.3–7 m) (finger protection) 1–65 ft (0.3–20 m) (hand protection)	
Response time		Depending on height protected: 23–41 ms (finger protection) Depending on height protected: 23–32 ms (hand protection)	
Type of outputs	Safety	2 solid-state PNP outputs (N.O.) ⎓ 24 V, ≤ 625 mA Short-circuit protection	
	Auxiliary	1 solid-state 100 mA, ⎓ 24 V, PNP or NPN output depending on the model	
Main functions **Muting function** (inhibition of the light curtain Detection function)		- Auto/manual - Test - EDM (external device monitoring) - Light beam coding	- Auto/manual - Test - EDM (external device monitoring) - Light beam coding - Blanking (fixed and floating) - Cascadable (up to 4 segments) - Muting
Supply voltage		⎓ 24 V ± 20%, 2 A	
References		**XUSLB**	**XUSLD**
Pages		5/10	5/11

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Applications		**Packaging, conveyor systems, material handling, warehousing, stocking, etc.**
Functions		**Body protection 11.8, 15.7, 19.7, 23.6 in (300, 400, 500 and 600 mm) and single beam**
Device		Light curtains, type 4
		1–6 beam light curtains with infrared transmission (1 transmitter-receiver pair)
		Type 4 model, solid-state output

Conformity	Product standards	ANSI/RIA R15.06, ANSI B11:19-1990, OSHA 1910.217(C), OSHA 1910.212, type 4 (ESPE) conforming to IEC 61496-1 and 2
	European directives	Machinery directive 2006/42/EC, Work equipment directive 89/655/EEC and EMC directive 89/336/EEC
Product certifications		CE, TUV, UL, CSA
Degree of protection		IP67
Cross-section		2.05 x 2.17 in. (52 x 55 mm)
Protected height	Conforming to EN 999	29.53–70.87 in. (750–1800 mm) (1–6 light beams)
Nominal sensing distance		2.6–65.5 ft or 2.6–229.7 ft (0.8–20 m or 0.8–70 m) depending on configuration 2.6–26.3 ft (0.8–8 m) for light curtains with passive receiver
Response time		< 16 to < 24 ms, depending on the light beam coding selected
Type of outputs	Safety	2 solid-state PNP outputs (N.O.) ⎓ 24 V, ≤ 650 mA Short-circuit protection
	Auxiliary	1 solid-state 100 mA, ⎓ 24 V PNP output
Main functions **Muting function** (inhibition of the light curtain Detection function)		Functions integrated in the light curtain: Auto/Manual start and manual 1st cycle, - EDM (external devices monitoring), - test input, - 3 light beam codings available, - Muting via external module
Supply voltage		⎓ 24 V ± 20%, 2 A
References		**XUSLP●●●●**
Pages		5/29

5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions
Light curtains

Applications		**Packaging, conveyor systems, material handling, warehousing, stocking, etc.**
Functions		**Hand protection 1.18 in. (30 mm)**
Device		Light curtains, type 2
		Multi-beam light curtains with infrared transmission (1 transmitter-receiver pair)
		Slim, compact model, solid-state output Automatic or manual start

Conformity	Product standards	IEC 61496-1 and IEC 61496-2 type 2 (ESPE)
	European directives	Machinery directive 2006/42/EC, Work equipment directive 89/655/EEC and EMC directive 89/336/EEC
Product certifications		CE, TUV. UL, CSA
Degree of protection		IP65
Cross-section		1.12 x 1.26 in. (28.5 x 32 mm)
Protected height	Conforming to EN 999	5.91–59.06 in. (150–1500 mm) (hand protection)
Nominal sensing distance		0.98–49.21 ft (0.3–15 m)
Response time		14–24 ms
Type of outputs	Safety	2 solid-state PNP outputs (N.O.) ⎓ 24 V, ≤ 500 mA Short-circuit protection
	Auxiliary	1 x 100 mA, ⎓ 24 V PNP alarm output
Main functions		Functions integrated in the light curtain: - automatic or manual start, depending on the version
Muting function (inhibition of the light curtain Detection function)		- Muting via external module
Supply voltage		⎓ 24 V ± 20%, 2 A
References		**XUSLNG5C●●●●, XUSLNG5D●●●●**
Pages		5/37

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Packaging, conveyor systems, material handling, warehousing, stocking, etc.

Body protection

Light curtains, type 2

Single-beam, infrared transmission, light curtains (Preventa safety monitoring module plus 1–4 thru-beam photoelectric sensors)

Type 2 model, relay outputs (N.O.)

IEC 60947-1, EN 61496-1, EN 60825-1, UL 508,
type 2 (ESPE) conforming to IEC 61496-1 and 2

Machinery directive 2006/42/EC, Work equipment
directive 89/655/EEC and EMC directive 89/336/EEC
EN 60825-1 (emission class 1)

CE type approval BIA/Cologne. UL, CSA

IP67

Ø of sensors: 18 mm

29.5–47.2 in. (750–1200 mm) (1–4 light beams)

26.2 ft (8 m)

< 20 ms (sensors + safety module)

Solid-state PNP
Preventa safety module XPSCM outputs
2 guided contact relays, each 1 N.O.
AC-15: C300, 1800 VA inrush, 180 VA maintained
DC-13: ⎓ 24 V/1.5 A, L/R = 50 ms
Maximum thermal current = 2.5 A

⎓ 24 V, 20 mA

Muting integrated in the safety monitoring module XPSCM

Safety module XPSCM: ⎓ 24 V (19–29 V)
Sensors XU2S: ⎓ 24 V (10–30 V)

XU2S●●●●●●● + XPSCM

5/50

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions
Light curtains

Introduction

Protection of personnel

Light curtains are electro-sensitive protection equipment (ESPE) designed to help protect persons operating or working in the vicinity of machinery, by stopping the dangerous movement of parts as soon as one of the light beams is broken.
In particular, they help provide protection for personnel operating dangerous machinery (annex IV of 2006/42/EC) but they are equally suitable for use with many other types of machines. They make it possible to help protect personnel while allowing free access to machines.

The absence of a door or guard makes access easier and reduces the time required for loading, inspection, or adjustment operations.

Directives and standards

Conformity to standards

These light curtains conform to the following:
- European Machinery Safety Directive 2006/42/EC and European Work Equipment Directive 89/655/EEC,
- Low Voltage Directives 73/23/EEC and 93/68/EEC and the Electromagnetic Compatibility Directive 89/336/EEC,
- Standard EN/IEC 61496-1, EN/IEC 61496-2 and IEC 61508 (only XUSLB, XUSLDM and XUSLDS) (electro-sensitive protection equipment: ESPE),
- Standard EN 60825 (emission power),
- Standard EN 999/ISO 13855 (installation positioning).

These light curtains are UL, CSA, and TÜV certified.

Applications

Main applications

- Applications for type 2 products:
  - assembly and packaging lines,
  - conveying and handling lines,
  - warehousing and storage systems,
  - waste disposal skips.

- Types of machine requiring the use of type 4 products:
  - presses (all types), shears, and trimmers,
  - hoisting equipment,
  - saws (all types),
  - machine tools (lathes, milling machines, machining centers),
  - woodworking machines (planing machines, lathes, spindle molding machines, side and face milling cutters),
  - textile machinery (carding machines, weaving looms, steam rooms),
  - assembly machines,
  - assembly robots.

Safety requirements

Detection of anomalies

Detection of anomalies liable to compromise safety, and stopping of the machine

The design of the machine and its control system must be to the same level of safety as that of the light curtain in order to provide the immediate stopping of the machine's dangerous movement as soon as the hazardous zone (protected by the light curtain) is entered.

It must not be possible to enter the protected zone without breaking the protective light beams. The light curtain must therefore be installed in such a manner that the light beams cannot be avoided.
The machine can only be restarted if no danger exists and no personnel are present in the hazardous zone. The risk that persons might be inside the protected zone but out of the protective light beams must be addressed.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Functions

Protection mode
AUTO/MAN (automatic/manual): This is what standard EN/IEC 61496 calls start (or restart) interlock of the light curtain:
- In Auto mode: Upon power-up or after the beams have been cleared, the light curtain resets itself automatically (closing of the OSSD output safety circuits),
- In Manual mode: Upon power-up or after the beams have been cleared, the light curtain keeps its output safety circuits in the Open position. Pressing and releasing the reset button will reset the light curtain and close its OSSD output safety circuits.

Note: In all cases, a general start instruction for the machine will trigger its actual start-up.

Monitoring the external switching devices
Also called EDM (external device monitoring) by standard EN/IEC 61496, this consists of monitoring the state (open or closed) of the machine's power switching components, along with the time taken to reach that state.

Auxiliary output
Where configurable (XUSLP), this is a low power solid-state output for signaling to the automation system. This output closes when the light curtain switches to run mode.

Alarm
This is a low power solid-state output for signaling to the automation system. This output closes when the light curtain switches to alarm mode.

Signaling
LED display of operating modes and alarm.

Alignment aid
Display by visible infrared LED of each beam broken.

Muting (inhibition)
When activated, the Muting function inhibits the Detection function of the light curtain.
Activation (or deactivation) is achieved by means of standard sensors (photoelectric or other). When activated, a signal is sent to the automation system. This function is used to allow objects to access the hazardous zones during the process.
Signaling informs the operator or operators that they are not protected.

Blanking
While the Muting function inhibits *all* beams in the light curtain from detecting objects, the Blanking function inhibits a *selected* group of light beams. This allows objects to be present during process operations. Blanking is adaptable to the size of the objects present.
Blanking effectively increases the Minimum Object Sensitivity (MOS). This imposes a greater safety distance, increasing the minimum distance between the light curtain and the hazard. Also, additional protection on each side of the object present must be provided, in order to prevent any intrusion into the free areas.

Floating blanking
This function makes it possible to inhibit one or two light beams (adjacent or otherwise), anywhere in the light curtain. This configuration is used, for example, for metal plate feeding applications on folding presses or shears.

Blanking plus floating blanking
The Blanking function (fixed inhibition of light beams) and Floating Blanking function (moving inhibition of one or two light beams) can be combined.

Multi-segments
The "multi-segments" enable the protection of zones using a single connection. Only the first segment (XUSLDM…), also called the''master'', has to be connected to the enclosure or control cabinet. This first segment, which can either be for finger or hand detection, can support up to 3 other segments, also called intermediate segments or ''slaves'' which are connected by jumper cables to the M12 connectors located on its top surface. The intermediate segments can be of different detection capacities and heights protected than that of the ''Master''. They are fully dependent on the functions configured in the first segment. Note: the multi-segment system developed can not exceed 256 light beams in total and each intermediate segment must not exceed 128 light beams nor have a jumper cable longer than 10 m between them.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

Optimum XUSLB and Universal XUSLDM with solid-state output

Light curtain type			XUSLBQ6A●●●● XUSLDMQ6A●●●● 0.55 in. (14 mm)	XUSLBR5A●●●● 1.18 in. (30 mm)	XUSLDMY5A●●●●● 1.18 in. (30 mm)
Environmental specifications					
Conformity to standards			ANSI/RIA R15.06, ANSI B11:19-1990, OSHA 1910.217(C), OSHA 1910.212, EN/IEC 61496-1 and EN/IEC 61496-2 and IEC 61508-1, 2 (Type 4 ESPE)		
Certifications			CE, TUV, UL, CSA		
European directives			Machinery directive 2006/42/EC, Work equipment directive 89/655/EEC and EMC directive 89/336 EEC ROHS directive 2002/95/EC		
Maximum safety level *(1)*			PL = e/category 4 conforming to EN/ISO 13849-1 SIL 3 conforming to EN/IEC 61508		
Reliability data			PFH_d = 4.9E^{-6} 1/h conforming to EN/IEC 61508		
Ambient air temperature	Operating	**°F (°C)**	14 to +131 (-10 to +55)		
	Storage	**°F (°C)**	–13 to +167 (–25 to +75)		
Relative humidity			95% maximum, without condensation		
Degree of protection			IP65		
Shock and vibration resistance	Conforming to IEC 61496-1		Shock resistance: 10 gn, impulse 16 ms Vibration resistance: 10–55 Hz, amplitude: 0.35 ±0.05 mm		
Materials			Casing: aluminum with electrostatically applied red (RAL 3000) polyester paint finish; end caps: 20% fiberglass impregnated polycarbonate. Lens: PMMA (polymethyl methacrylate).		
Mounting			End brackets (included)		
Optical specifications					
Minimum detection capacity (MOS)			0.55 in. (14 mm) (finger)	1.18 in. (30 mm) (hand)	
Nominal sensing distance (Sn)		**ft (m)**	1–23 (0.3–7) or 9.8 (3) with PDM *(2)*	1–65.6 (0.3–20) or 26.2 (8) with PDM *(2)*	1–65.6 (0.3–20) or 26.2 (8) with PDM *(2)*
Protected height		**in. (mm)**	11–53.5 (280–1360)	12.6–83.5 (320–2120)	
Effective aperture angle (EAA)			2.5° at 9.8ft (3 m) (3° when used with IP67 protection tube)		
Light source			GaAlAs LED, 880 nm		
Immunity to ambient light			Conforming to IEC/EN 61496-2		
Electrical specifications					
Response time		**ms**	23–41	23–32	
Power supply			⎓ 24 V ± 20% 2 A conforming to EN/IEC 61496 and EN/IEC 60204-1		
	Transmitter	**mA**	285		
	Receiver	**A**	1.8 (with maximum load)		
Maximum current consumption (no-load)	Transmitter	**mA**	285 (SELV: Safety Extra Low Voltage)		
	Receiver	**mA**	450		
Immunity to interference			Conforming to EN 61496-1		
Safety outputs OSSD (output signal switching devices)			2 solid-state PNP (N.O.) outputs ≤ 625 mA, ⎓ 24 V (short-circuit protected)		
Auxiliary output			1 solid-state output 100 mA, ⎓ 24 V, PNP or NPN (depending on the model)		
Monitoring activation of output switching devices (MPCE/EDM)			50 mA, ⎓ 24 V and start/restart 10 mA		
Signaling	Transmitter		1 LED (power supply)		
	Receiver		4 LEDs (stop, run, interlock, ECS/B Blanking or FB Floating Blanking)		
Connections *(3)*					
Light curtains	Transmitter		M12, 5-pin, female connector		
	Receiver		M12, 8-pin, female connector		
Segments XUSLDS	Transmitter/Receiver		M12, 4-pin, female connector on pigtail		
XPSLCM1	Receiver		M12, 4-pin, female connector		
Pre-wired connectors c.s.a.	Transmitter/Receiver		22 AWG (0.32 mm²) conductors with M12, 5-pin, male connector		
	Receiver		22 AWG (0.32 mm²) conductors with M12, 8-pin, male connector		
Jumper cables c.s.a.	Transmitter/receiver		22 AWG (0.32 mm²) conductors with M12, 4-pin, male/female connectors		
Cable resistance of pre-wired connectors	Transmitter/receiver	Ω	0.1686 per ft (0.05531 per m) for 22 AWG (0.32 mm²) conductors		
Cable lengths			Pre-wired connectors with cable lengths of 16.4, 32.8, 49.2, and 98.4 ft (5, 10, 15 and 30 m) are available separately. The maximum cable length is 196.9 ft (60 m), depending on the load current and power supply.		

(1) Using an appropriate and correctly connected control system.
(2) PDM: programming and diagnostic module, available as an option. See page 5/14.
(3) Pre-wired connectors must be ordered separately. See page 5/14.

Specifications: page 5/8 | References: page 5/10 | Dimensions: page 5/16 | Wiring diagrams: page 5/18

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

Optimum XUSLB and Universal XUSLDM with solid-state output

Light curtain type			XUSLB●●●●●●	XUSLDM●●●●●
Functions				
Functions	Accessible by cabling alone *(1)*		◻ Automatic start ◻ Auxiliary output (PNP, status signaling) ◻ Test (MTS: monitoring test signal) ◻ Alignment aid by display of each light beam broken ◻ LED display of operating modes and anomalies	
	Accessible via programming and diagnostic module		◻ Auto/Manual ◻ Monitoring of the external switching devices (EDM: external device monitoring) ◻ Light beam coding (A or B) ◻ Sensing distance (short, long) ◻ Programming and downloading the configuration settings, via programming and diagnostic module (PDM) ◻ Display of operating modes and anomalies by LED or PDM *(2)*	◻ Auto/Manual, manual 1st cycle ◻ Monitoring of the external switching devices (EDM: external device monitoring) ◻ Blanking (ECS/B) ◻ Monitored Blanking ◻ Floating Blanking (FB) ◻ Reduction of resolution ◻ Response time (normal, slow) ◻ Light beam coding (A or B) ◻ Sensing distance (short, long) ◻ Auxiliary output (alarm or status signaling, PNP or NPN) ◻ Start button (N.O. or N.C., 0 V or 24 V) ◻ Muting (see page 5/7) ◻ Cascadable versions with up to 4 segments total (256 light beams max., modular finger/hand) using XUSLDS segments ◻ Programming and downloading the configuration settings, via programming and diagnostic module (PDM) ◻ Display of operating modes and anomalies by LED or PDM *(2)*
Monitoring the external switching devices (EDM: external device monitoring)			Monitoring of the function (open or closed) as well as the response time of the power components.	
Test function			Initiates the stop instruction of the light curtain by opening the contact (simulated intrusion)	
Muting function (inhibition)			◻ With external module XPSLCM1150	◻ Integrated when using connection module XPSLCM1 for connecting sensors and Muting indicator light ◻ or with module XPSLCM1150

(1) Not requiring use of PDM.
(2) PDM: programming and diagnostic module, available as an option. See page 5/14.

5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

Optimum XUSLB with solid-state output

XUSLBQ6A●●●●

XUSLBR5A●●●●

Transmitter-receiver pairs for finger protection *(1)*

Detection capacity: 0.55 in. (14 mm).
Sensing distance: 1–22.9 ft (0.3–7 m), or 9.8 ft (3 m) with PDM.

■ 2 PNP safety outputs

Protected height	Response time	Number of light beams	Auxiliary output	References *(2)*	Weight
in. (mm)	ms				lb (kg)
11 (280)	23	24	PNP	**XUSLBQ6A0280**	3.95 (1.790)
12.6 (320)	23	32	PNP	**XUSLBQ6A0320**	4.34 (1.970)
14.2 (360)	23	36	PNP	**XUSLBQ6A0360**	4.74 (2.150)
17.3 (440)	23	44	PNP	**XUSLBQ6A0440**	5.51 (2.500)
20.5 (520)	23	52	PNP	**XUSLBQ6A0520**	6.33 (2.870)
23.6 (600)	23	60	PNP	**XUSLBQ6A0600**	7.10 (3.220)
28.3 (720)	32	72	PNP	**XUSLBQ6A0720**	8.29 (3.760)
29.9 (760)	32	76	PNP	**XUSLBQ6A0760**	8.69 (3.940)
34.6 (880)	32	88	PNP	**XUSLBQ6A0880**	9.85 (4.470)
36.2 (920)	32	92	PNP	**XUSLBQ6A0920**	10.25 (4.650)
37.8 (960)	32	96	PNP	**XUSLBQ6A0960**	10.65 (4.830)
40.9 (1040)	32	104	PNP	**XUSLBQ6A1040**	11.44 (5.190)
44.1 (1120)	32	112	PNP	**XUSLBQ6A1120**	12.21 (5.540)
47.2 (1200)	32	120	PNP	**XUSLBQ6A1200**	13.01 (5.900)
53.5 (1360)	41	136	PNP	**XUSLBQ6A1360**	13.62 (6.180)

Transmitter-receiver pairs for hand protection *(1)*

Detection capacity: 1.18 in. (30 mm).
Sensing distance: 1–65.6 ft (0.3–20 m), or 26.2 ft (8 m) with PDM.

■ 2 PNP safety outputs

Protected height	Response time	Number of light beams	Auxiliary output	References *(2)*	Weight
in. (mm)	ms				lb (kg)
12.6 (320)	23	16	PNP	**XUSLBR5A0320**	4.34 (1.970)
14.2 (360)	23	18	PNP	**XUSLBR5A0360**	4.74 (2.150)
17.3 (440)	23	22	PNP	**XUSLBR5A0440**	5.51 (2.500)
20.5 (520)	23	26	PNP	**XUSLBR5A0520**	6.33 (2.870)
23.6 (600)	23	30	PNP	**XUSLBR5A0600**	7.10 (3.220)
26.8 (680)	23	34	PNP	**XUSLBR5A0680**	7.89 (3.580)
29.9 (760)	23	38	PNP	**XUSLBR5A0760**	8.69 (3.940)
34.6 (880)	23	44	PNP	**XUSLBR5A0880**	9.85 (4.470)
36.2 (920)	23	46	PNP	**XUSLBR5A0920**	10.25 (4.650)
40.9 (1040)	23	52	PNP	**XUSLBR5A1040**	11.44 (5.190)
47.2 (1200)	23	60	PNP	**XUSLBR5A1200**	13.01 (5.900)
53.5 (1360)	23	68	PNP	**XUSLBR5A1360**	14.59 (6.620)
55.1 (1400)	23	70	PNP	**XUSLBR5A1400**	14.99 (6.800)
59.8 (1520)	32	76	PNP	**XUSLBR5A1520**	16.16 (7.330)
61.4 (1560)	32	78	PNP	**XUSLBR5A1560**	16.53 (7.500)
64.6 (1640)	32	82	PNP	**XUSLBR5A1640**	17.35 (7.870)
67.7 (1720)	32	86	PNP	**XUSLBR5A1720**	18.14 (8.230)
70.9 (1800)	32	88	PNP	**XUSLBR5A1800**	18.94 (8.590)
75.6 (1920)	32	96	PNP	**XUSLBR5A1920**	20.11 (9.120)
83.5 (2120)	32	106	PNP	**XUSLBR5A2120**	22.09 (10.020)

(1) Includes a test rod, 2 sets of 2 brackets with mounting hardware, a user guide with the certificate of conformity on CD-ROM, and 1 arc suppressor set.
Programming and diagnostic module (if required) and pre-wired connectors must be ordered separately. See page 5/14.

*(2) To order a receiver only, add the letter **R** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLBR5A0320 becomes **XUSLBR5A0320R** for the receiver only.*
*To order a transmitter only, add the letter **T** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLBR5A0320 becomes **XUSLBR5A0320T** for the transmitter only.*

Other versions Combining type 4 safety light curtains with external module for Muting function. See page 5/60.

Separate components and accessories: page 5/14

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

Universal XUSLDM with solid-state output

XUSLDMQ●●●●

XUSLDMY●●●●

Transmitter-receiver pairs for finger protection *(1)*

Detection capacity: 0.55 in. (14 mm).
Sensing distance: 1–22.9 ft (0.3–7 m) or 9.8 ft (3 m) with PDM.

■ 2 PNP safety outputs

Protected height	Response time		Number of light beams	Auxiliary output	References *(2)*	Weight
	Normal	Slow				
in. (mm)	ms	ms				lb (kg)
11 (280)	23	38	24	PNP/NPN	**XUSLDMQ6A0280**	3.95 (1.790)
12.6 (320)	23	38	32	PNP/NPN	**XUSLDMQ6A0320**	4.34 (1.970)
14.2 (360)	23	38	36	PNP/NPN	**XUSLDMQ6A0360**	4.74 (2.150)
17.3 (440)	23	38	44	PNP/NPN	**XUSLDMQ6A0440**	5.51 (2.500)
20.5 (520)	23	38	52	PNP/NPN	**XUSLDMQ6A0520**	6.39 (2.900)
23.6 (600)	23	38	60	PNP/NPN	**XUSLDMQ6A0600**	7.10 (3.220)
28.3 (720)	32	53	72	PNP/NPN	**XUSLDMQ6A0720**	8.29 (3.760)
29.9 (760)	32	53	76	PNP/NPN	**XUSLDMQ6A0760**	8.69 (3.940)
34.6 (880)	32	53	88	PNP/NPN	**XUSLDMQ6A0880**	9.85 (4.470)
36.2 (920)	32	53	92	PNP/NPN	**XUSLDMQ6A0920**	10.25 (4.650)
37.8 (960)	32	53	96	PNP/NPN	**XUSLDMQ6A0960**	10.65 (4.830)
40.9 (1040)	32	53	104	PNP/NPN	**XUSLDMQ6A1040**	11.44 (5.190)
44.1 (1120)	32	53	112	PNP/NPN	**XUSLDMQ6A1120**	12.21 (5.540)
47.2 (1200)	32	53	120	PNP/NPN	**XUSLDMQ6A1200**	13.01 (5.900)
53.5 (1360)	41	68	136	PNP/NPN	**XUSLDMQ6A1360**	14.59 (6.620)

Transmitter-receiver pairs for hand protection *(1)*

Detection capacity: 1.18 in. (30 mm).
Sensing distance: 1–65.6 ft (0.3–20 m), or 26.2 ft (8 m) with PDM.

■ 2 PNP safety outputs

Protected height	Response time		Number of light beams	Auxiliary output	References *(2)*	Weight
	Normal	Slow				
in. (mm)	ms	ms				lb (kg)
12.6 (320)	23	38	16	PNP/NPN	**XUSLDMY5A0320**	4.34 (1.970)
14.2 (360)	23	38	18	PNP/NPN	**XUSLDMY5A0360**	4.74 (2.150)
17.3 (440)	23	38	22	PNP/NPN	**XUSLDMY5A0440**	5.51 (2.500)
20.5 (520)	23	38	26	PNP/NPN	**XUSLDMY5A0520**	6.33 (2.870)
23.6 (600)	23	38	30	PNP/NPN	**XUSLDMY5A0600**	7.10 (3.220)
26.8 (680)	23	38	34	PNP/NPN	**XUSLDMY5A0680**	7.89 (3.580)
29.9 (760)	23	38	38	PNP/NPN	**XUSLDMY5A0760**	8.69 (3.940)
34.6 (880)	23	38	44	PNP/NPN	**XUSLDMY5A0880**	9.85 (4.470)
36.2 (920)	23	38	46	PNP/NPN	**XUSLDMY5A0920**	10.25 (4.650)
40.9 (1040)	23	38	52	PNP/NPN	**XUSLDMY5A1040**	11.44 (5.190)
47.2 (1200)	23	38	60	PNP/NPN	**XUSLDMY5A1200**	13.01 (5.900)
53.5 (1360)	23	38	68	PNP/NPN	**XUSLDMY5A1360**	14.59 (6.620)
55.1 (1400)	23	38	70	PNP/NPN	**XUSLDMY5A1400**	14.99 (6.800)
59.8 (1520)	32	53	76	PNP/NPN	**XUSLDMY5A1520**	16.16 (7.330)
61.4 (1560)	32	53	78	PNP/NPN	**XUSLDMY5A1560**	16.53 (7.500)
64.6 (1640)	32	53	82	PNP/NPN	**XUSLDMY5A1640**	17.35 (7.870)
67.7 (1720)	32	53	86	PNP/NPN	**XUSLDMY5A1720**	18.14 (8.230)
70.9 (1800)	32	53	88	PNP/NPN	**XUSLDMY5A1800**	18.94 (8.590)
75.6 (1920)	32	53	96	PNP/NPN	**XUSLDMY5A1920**	20.11 (9.120)
83.5 (2120)	32	53	106	PNP/NPN	**XUSLDMY5A2120**	22.09 (10.020)

(1) Includes a test rod, 2 sets of 2 brackets with mounting hardware, user guide with certificate of conformity on CD-ROM and 1 arc suppressor set.
Programming and diagnostic module (if required) and pre-wired connectors must be ordered separately. See page 5/14.

*(2) To order a receiver only, add the letter **R** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLDMY5A0320 becomes **XUSLDMY5A0320R** for the receiver only.*
*To order a transmitter only, add the letter **T** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLDMY5A0320 becomes **XUSLDMY5A0320T** for the transmitter only.*

Other versions Combining type 4 safety light curtains with external module for Muting function. See page 5/60.

Separate components and accessories: page 5/14

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLDS segments for Universal XUSLDM light curtains

XUSLDM + XUSLDS

Segments for cascadable Universal light curtains

Cascadable versions with up to 4 segments total (256 light beams max., modular finger/hand), using XUSLDS segments

XUSLDS light curtain segments cannot be used separately as stand-alone systems. They must be connected to an XUSLDM light curtain. The XUSLDM is the initial (or base) light curtain, and the first XUSLDS segment is connected to the XUSLDM. Each successive XUSLDS is then connected to the previous XUSLDS

Configuration of XUSLDS segments

Two segments

Number of light beams	Response time ms
0–65	23
66–120	32
121–174	41
175–229	50
230–256	59

Three segments

Number of light beams	Response time ms
0–59	23
60–114	32
115–168	41
169–223	50
224–256	59

Four segments

Number of light beams	Response time ms
0–53	23
54–108	32
109–162	41
163–217	50
218–256	59

Separate components and accessories: page 5/14

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLDS segments for Universal XUSLDM light curtains

XUSLDSQ6A●●●●

XUSLDS light curtain segments cannot be used separately as stand-alone systems. They must be connected to an XUSLDM light curtain. The XUSLDM is the initial (or base) light curtain, and the first XUSLDS segment is connected to the XUSLDM. Each successive XUSLDS in then connected to the previous XUSLDS.

Transmitter-receiver pairs for finger protection *(1)*

Detection capacity: 0.55 in. (14 mm).
Sensing distance: depends on XUSLDM light curtain used.

■ Segments for cascadable Universal light curtains *(2)*

Protected height in. (mm)	Number of light beams	References *(3)*	Weight lb (kg)
11 (280)	24	**XUSLDSQ6A0280**	3.95 (1.790)
12.6 (320)	32	**XUSLDSQ6A0320**	4.34 (1.970)
14.2 (360)	36	**XUSLDSQ6A0360**	4.74 (2.150)
17.3 (440)	44	**XUSLDSQ6A0440**	5.51 (2.500)
20.5 (520)	52	**XUSLDSQ6A0520**	6.33 (2.870)
23.6 (600)	60	**XUSLDSQ6A0600**	7.10 (3.220)
28.3 (720)	72	**XUSLDSQ6A0720**	8.29 (3.760)
29.9 (760)	76	**XUSLDSQ6A0760**	8.69 (3.940)
34.6 (880)	88	**XUSLDSQ6A0880**	9.85 (4.470)
36.2 (920)	92	**XUSLDSQ6A0920**	10.25 (4.650)
37.8 (960)	96	**XUSLDSQ6A0960**	10.65 (4.830)
40.9 (1040)	104	**XUSLDSQ6A1040**	11.44 (5.190)
44.1 (1120)	112	**XUSLDSQ6A1120**	12.21 (5.540)
47.2 (1200)	120	**XUSLDSQ6A1200**	13.01 (5.900)

XUSLDSY5A●●●●

Transmitter-receiver pairs for hand protection *(1)*

Detection capacity: 1.18 in. (30 mm).
Sensing distance: depends on XUSLDM light curtain used.

■ Segments for cascadable Universal light curtains *(2)*

Protected height in. (mm)	Number of light beams	References *(3)*	Weight lb (kg)
12.6 (320)	16	**XUSLDSY5A0320**	4.34 (1.970)
14.2 (360)	18	**XUSLDSY5A0360**	4.74 (2.150)
17.3 (440)	22	**XUSLDSY5A0440**	5.51 (2.500)
20.5 (520)	26	**XUSLDSY5A0520**	6.33 (2.870)
23.6 (600)	30	**XUSLDSY5A0600**	7.10 (3.220)
26.8 (680)	34	**XUSLDSY5A0680**	7.89 (3.580)
29.9 (760)	38	**XUSLDSY5A0760**	8.69 (3.940)
34.6 (880)	44	**XUSLDSY5A0880**	9.85 (4.470)
36.2 (920)	46	**XUSLDSY5A0920**	10.25 (4.650)
40.9 (1040)	52	**XUSLDSY5A1040**	11.44 (5.190)
47.2 (1200)	60	**XUSLDSY5A1200**	13.01 (5.900)
53.5 (1360)	68	**XUSLDSY5A1360**	14.59 (6.620)
55.1 (1400)	70	**XUSLDSY5A1400**	14.99 (6.800)
59.8 (1520)	76	**XUSLDSY5A1520**	16.16 (7.330)
61.4 (1560)	78	**XUSLDSY5A1560**	16.53 (7.500)
64.6 (1640)	82	**XUSLDSY5A1640**	17.35 (7.870)
67.7 (1720)	86	**XUSLDSY5A1720**	18.14 (8.230)
70.9 (1800)	88	**XUSLDSY5A1800**	18.94 (8.590)
75.6 (1920)	96	**XUSLDSY5A1920**	20.11 (9.120)
83.5 (2120)	106	**XUSLDSY5A2120**	22.09 (10.020)

(1) Includes 2 sets of 2 brackets and hardware.
Jumper cables must be ordered separately. See page 5/14.
(2) The segments are to be connected to the M12 4-pin connector on top of the XUSLDM light curtains.
*(3) To order a receiver only, add the letter **R** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLDSY5A0320 becomes **XUSLDSY5A0320R** for the receiver only.*
*To order a transmitter only, add the letter **T** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLDSY5A0320 becomes **XUSLDSY5A0320T** for the transmitter only.*

Separate components and accessories: page 5/14

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

Optimum XUSLB and Universal XUSLDM/LDS
With solid-state output

XUSLPDM



XSZ BCT●●



XSZ BCR●●

Separate components

Power supplies, 90° mirror adapters, protective covers, anti-vibration kit, mounting bases, laser alignment tool

See pages 5/15 and 5/40 to 5/47.

Accessories

Description	For use with	Length ft (m)	References	Weight lb (kg)
Programming and diagnostic module (PDM)	XUSLB/LDM light curtains	–	**XUSLPDM**	0.62 (0.280)
Holder mount	Programming and diagnostic module XUSLPDM	–	**XUSLZPDM**	0.09 (0.040)
Pre-wired connectors for light curtains XUSLB/XUSLDM	Transmitter type	16.4 (5)	**XSZBCT05**	0.86 (0.390)
		32.8 (10)	**XSZBCT10**	1.52 (0.690)
		49.2 (15)	**XSZBCT15**	2.27 (1.030)
		98.4 (30)	**XSZBCT30**	4.25 (1.930)
	Receiver type	16.4 (5)	**XSZBCR05**	0.99 (0.450)
		32.8 (10)	**XSZBCR10**	1.72 (0.780)
		49.2 (15)	**XSZBCR15**	2.43 (1.100)
		98.4 (30)	**XSZBCR30**	5.03 (2.280)
Jumper cables for XUSLDS segments M12 male/female, 4-pin, straight	Transmitter type	1 (0.3)	**XSZDCT003**	0.11 (0.050)
		1.6 (0.5)	**XSZDCT005**	0.15 (0.070)
		3.3 (1)	**XSZDCT010**	0.24 (0.110)
		6.6 (2)	**XSZDCT020**	0.46 (0.210)
		9.9 (3)	**XSZDCT030**	0.66 (0.300)
		16.4 (5)	**XSZDCT050**	1.08 (0.490)
		32.8 (10)	**XSZDCT100**	2.09 (0.950)
	Receiver type	1 (0.3)	**XSZDCR003**	0.11 (0.050)
		1.6 (0.5)	**XSZDCR005**	0.15 (0.070)
		3.3 (1)	**XSZDCR010**	0.24 (0.110)
		6.6 (2)	**XSZDCR020**	0.46 (0.210)
		9.9 (3)	**XSZDCR030**	0.66 (0.300)
		16.4 (5)	**XSZDCR050**	1.08 (0.490)
		32.8 (10)	**XSZDCR100**	2.12 (0.960)
Jumpers for replacing XUSLT light curtains with XUSLB or XUSLDM	Transmitter type male/female 5 pins	1 (0.3)	**XSZTBDMCT003**	0.13 (0.060)
	Receiver type male/female 8 pins	1 (0.3)	**XSZTBDMCR003**	0.13 (0.060)

Description	For use with	References	Weight lb (kg)
Replacement caps for M12 connector **(Sold in lots of 10)**	XUSLDM light curtains and XUSLDS segments	**XUSLZ600**	0.002 (0.001)
Replacement caps for M8 connector (programming and diagnostic module XUSLPDM connection to light curtains) **(Sold in lots of 10)**	XUSLB/LDM light curtains and XUSLDS segments	**XUSLZ610**	0.02 (0.010)
Mounting kit (2 brackets)	XUSLB/LDM light curtains and XUSLDS segments	**XUSLZ228**	0.22 (0.100)
Sliding nuts (4 nuts) for rear or side mounting with XUSLZ228	XUSLB/LDM light curtains	**XUSLZ330**	0.09 (0.040)
Arc suppressor (pair)	All light curtain types	**XUSLZ500**	0.04 (0.020)
IP67 protection tube (see page 5/15)			–
User guide on CD-ROM	All light curtain types	**XUSLZ450**	0.02 (0.010)
Connection module for muting of light curtains (see page 5/22)	XUSLDM light curtains	**XPSLCM1**	0.42 (0.190)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLB/XUSLDM protection tubes for light curtains with solid-state output and XUSLDS segments

IP67 protection tubes for XUSLB/XUSLDM light curtains and XUSLDS segments			XUSLZD7●●●●
Environmental specifications			
Air temperature	Operating	**°F (°C)**	32 to +104 (0 to +40)
	Storage	**°F (°C)**	–13 to +158 (–25 to +70)
Degree of protection			IP67 conforming to IEC 60529
Material			Acrylic
Sensing distance (Sn) **reduction coefficient**			0.90
Environmental chemicals			
Chemical resistance	Aliphatic hydrocarbons		Resistant
	Alkalis		
	Aqueous solutions		
	Detergents and cleaners		
	Inorganic diluted acids		
	Chlorinated or aromatic hydrocarbons		Limited resistance
	Esters		
	Ketones		
Environmental resistance	Adverse weather, sunlight (UV)		Resistant
	Humidity		
	Immersion in water		

References of IP67 protection tubes

XUSLZD7●●●

Description	For use with	Height in. (mm)	References	Weight lb (kg)
IP67 protection tubes for XUSLB/LDM transmitter-receiver pair and XUSLDS●●● segments (0.90 Sn) *(1)* **(Sold in lots of 2)**	XUSL●●6A0280	11.2 (284.4)	**XUSLZD70280**	5.84 (2.650)
	XUSL●●●A0320	12.8 (324.8)	**XUSLZD70320**	6.19 (2.810)
	XUSL●●●A0360	14.4 (364.5)	**XUSLZD70360**	6.53 (2.960)
	XUSL●●●A0440	17.5 (443.9)	**XUSLZD70440**	7.21 (3.270)
	XUSL●●●A0520	20.6 (523.4)	**XUSLZD70520**	7.89 (3.580)
	XUSL●●●A0600	23.8 (604.1)	**XUSLZD70600**	8.58 (3.890)
	XUSL●●5A0680	26.9 (683.6)	**XUSLZD70680**	9.24 (4.190)
	XUSL●●6A0720	28.5 (724)	**XUSLZD70720**	9.59 (4.350)
	XUSL●●●A0760	30 (763)	**XUSLZD70760**	9.92 (4.500)
	XUSL●●●A0880	34.8 (882.8)	**XUSLZD70880**	10.93 (4.960)
	XUSL●●●A0920	36.3 (922.5)	**XUSLZD70920**	11.28 (5.120)
	XUSL●●6A0960	37.9 (963.6)	**XUSLZD70960**	11.62 (5.270)
	XUSL●●●A1040	41.1 (1042.9)	**XUSLZD71040**	12.30 (5.580)
	XUSL●●6A1120	44.2 (1122.3)	**XUSLZD71120**	12.99 (5.890)
	XUSL●●●A1200	47.4 (1203.8)	**XUSLZD71200**	13.67 (6.200)
	XUSL●●●A1360	53.6 (1362)	**XUSLZD71360**	15.01 (6.810)
	XUSL●●5A1400	55.2 (1401.7)	**XUSLZD71400**	15.37 (6.970)
	XUSL●●5A1520	59.9 (1521.5)	**XUSLZD71520**	16.38 (7.430)
	XUSL●●5A1560	61.5 (1563.3)	**XUSLZD71560**	16.71 (7.580)
	XUSL●●5A1640	64.6 (1641.3)	**XUSLZD71640**	17.89 (7.890)
	XUSL●●5A1720	67.7 (1720.8)	**XUSLZD71720**	18.08 (8.200)
	XUSL●●5A1800	71 (1802.9)	**XUSLZD71800**	18.76 (8.510)
	XUSL●●5A1920	75.7 (1922.8)	**XUSLZD71920**	19.78 (8.970)
	XUSL●●5A2120	83.5 (2120.7)	**XUSLZD72120**	21.47 (9.740)

(1) Sensing distance reduction coefficient must be taken into account for each pair of IP67 protection tubes used.

Introduction: page 5/12 | References: page 5/13 | Dimensions: page 5/16 | Wiring diagrams: page 5/18

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

Optimum XUSLB and Universal XUSLDM with solid-state output

Light curtains

XUSLB



XUSLDM



Dual Dimensions: in. (mm)

XUS	b	b1	H	Protected height
LB●●●0280	11.2 (284.4)	16.6 (420.4)	15 (381.7)	11 (280)
LB●●●0320	12.8 (324.8)	18.1 (460.8)	16.6 (422.1)	12.6 (320)
LB●●●0360	14.4 (364.5)	19.7 (500.5)	18.2 (461.8)	14.2 (360)
LB●●●0440	17.5 (443.9)	22.8 (579.9)	21.3 (541.2)	17.3 (440)
LB●●●0520	20.6 (523.4)	26 (659.4)	24.4 (620.7)	20.5 (520)
LB●●●0600	23.8 (604.1)	29.1 (740.1)	27.6 (701.4)	23.6 (600)
LB●●●0680	26.9 (683.6)	32.3 (819.6)	30.7 (780.9)	26.8 (680)
LB●●●0720	28.5 (724)	33.9 (860)	32.3 (821.3)	28.3 (720)
LB●●●0760	30 (763)	35.4 (899)	33.9 (860.3)	29.9 (760)
LB●●●0880	34.8 (882.8)	40.1 (1018.8)	38.6 (980.1)	34.6 (880)
LB●●●0920	36.3 (922.5)	41.7 (1058.5)	40.1 (1019.8)	36.2 (920)
LB●●●0960	37.9 (963.6)	43.3 (1099.6)	41.8 (1060.9)	37.8 (960)
LB●●●1040	41.1 (1042.9)	46.4 (1178.9)	44.9 (1140.2)	40.9 (1040)
LB●●●1120	44.2 (1122.3)	49.5 (1258.3)	48 (1219.6)	44.1 (1120)
LB●●●1200	47.4 (1203.8)	52.7 (1339.8)	51.2 (1301.1)	47.2 (1200)
LB●●●1360	53.6 (1362)	59 (1498)	57.5 (1459.3)	53.5 (1360)
LB●●●1400	55.2 (1401.7)	60.5 (1537.7)	59 (1499)	55.1 (1400)
LB●●●1520	59.9 (1521.5)	65.3 (1657.5)	63.7 (1618.8)	59.8 (1520)
LB●●●1560	61.5 (1563.3)	66.9 (1699.3)	65.4 (1660.6)	61.4 (1560)
LB●●●1640	64.6 (1641.3)	70 (1777.3)	68.4 (1738.6)	64.6 (1640)
LB●●●1720	67.7 (1720.8)	73.1 (1856.8)	71.6 (1818.1)	67.7 (1720)
LB●●●1800	71 (1802.9)	76.3 (1938.9)	74.8 (1900.2)	70.9 (1800)
LB●●●1920	75.7 (1922.8)	81.1 (2058.8)	79.5 (2020.1)	75.6 (1920)
LB●●●2120	83.5 (2120.7)	88.8 (2256.7)	87.3 (2217.3)	83.5 (2120)

XUS	b	b1	H	Protected height
LDM●●0280	11.2 (284.4)	16.6 (420.4)	15 (381.7)	11 (280)
LDM●●0320	12.8 (324.8)	18.1 (460.8)	16.6 (422.1)	12.6 (320)
LDM●●0360	14.4 (364.5)	19.7 (500.5)	18.2 (461.8)	14.2 (360)
LDM●●0440	17.5 (443.9)	22.8 (579.9)	21.3 (541.2)	17.3 (440)
LDM●●0520	20.6 (523.4)	26 (659.4)	24.4 (620.7)	20.5 (520)
LDM●●0600	23.8 (604.1)	29.1 (740.1)	27.6 (701.4)	23.6 (600)
LDM●●0680	26.9 (683.6)	32.3 (819.6)	30.7 (780.9)	26.8 (680)
LDM●●0720	28.5 (724)	33.9 (860)	32.3 (821.3)	28.3 (720)
LDM●●0760	30 (763)	35.4 (899)	33.9 (860.3)	29.9 (760)
LDM●●0880	34.8 (882.8)	40.1 (1018.8)	38.6 (980.1)	34.6 (880)
LDM●●0920	36.3 (922.5)	41.7 (1058.5)	40.1 (1019.8)	36.2 (920)
LDM●●0960	37.9 (963.6)	43.3 (1099.6)	41.8 (1060.9)	37.8 (960)
LDM●●1040	41.1 (1042.9)	46.4 (1178.9)	44.9 (1140.2)	40.9 (1040)
LDM●●1120	44.2 (1122.3)	49.5 (1258.3)	48 (1219.6)	44.1 (1120)
LDM●●1200	47.4 (1203.8)	52.7 (1339.8)	51.2 (1301.1)	47.2 (1200)
LDM●●1360	53.6 (1362)	59 (1498)	57.5 (1459.3)	53.5 (1360)
LDM●●1400	55.2 (1401.7)	60.5 (1537.7)	59 (1499)	55.1 (1400)
LDM●●1520	59.9 (1521.5)	65.3 (1657.5)	63.7 (1618.8)	59.8 (1520)
LDM●●1560	61.5 (1563.3)	66.9 (1699.3)	65.4 (1660.6)	61.4 (1560)
LDM●●1640	64.6 (1641.3)	70 (1777.3)	68.4 (1738.6)	64.6 (1640)
LDM●●1720	67.7 (1720.8)	73.1 (1856.8)	71.6 (1818.1)	67.7 (1720)
LDM●●1800	71 (1802.9)	76.3 (1938.9)	74.8 (1900.2)	70.9 (1800)
LDM●●1920	75.7 (1922.8)	81.1 (2058.8)	79.5 (2020.1)	75.6 (1920)
LDM●●2120	83.5 (2120.7)	88.8 (2256.7)	87.3 (2217.3)	83.5 (2120)

(1) 2 elongated holes, 0.73 x 0.27 in. (18.5 x 6.8 mm).
(2) 4 elongated holes, 0.91 x 0.27 in. (23.2 x 6.8 mm).
(3) M12 male connector on 10.6 in. (0.27 m) pigtail.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLDS segments for Universal XUSLDM light curtains
Protection tube

Cascadable segments

XUSLDS



XUS	b	b1	b2	H	H1	Protected height
LDS●●●0280	11.2 (284.4)	16.6 (420.4)	15.8 (401.5)	15 (381.7)	14.3 (363.1)	11 (280)
LDS●●●0320	12.8 (324.8)	18.1 (460.8)	17.4 (442.3)	16.6 (422.1)	15.9 (403.5)	12.6 (320)
LDS●●●0360	14.4 (364.5)	19.7 (500.5)	19 (482)	18.2 (461.8)	17.4 (443.2)	14.2 (360)
LDS●●●0440	17.5 (443.9)	22.8 (579.9)	22.1 (561.4)	21.3 (541.2)	20.6 (522.6)	17.3 (440)
LDS●●●0520	20.6 (523.4)	26 (659.4)	25.2 (640.9)	24.4 (620.7)	23.7 (602.1)	20.5 (520)
LDS●●●0600	23.8 (604.1)	29.1 (740.1)	28.4 (721.6)	27.6 (701.4)	26.9 (682.8)	23.6 (600)
LDS●●●0680	26.9 (683.6)	32.3 (819.6)	31.5 (801.1)	30.7 (780.9)	30 (762.3)	26.8 (680)
LDS●●●0720	28.5 (724)	33.9 (860)	33.1 (841.5)	32.3 (821.3)	31.6 (802.7)	28.3 (720)
LDS●●●0760	30 (763)	35.4 (899)	34.7 (880.5)	33.9 (860.3)	33.1 (841.7)	29.9 (760)
LDS●●●0880	34.8 (882.8)	40.1 (1018.8)	39.4 (1000.3)	38.6 (980.1)	37.9 (961.5)	34.6 (880)
LDS●●●0920	36.3 (922.5)	41.7 (1058.5)	40.9 (1040)	40.1 (1019.8)	39.4 (1001.2)	36.2 (920)
LDS●●●0960	37.9 (963.6)	43.3 (1099.6)	42.6 (1081.1)	41.8 (1060.9)	41 (1042.3)	37.8 (960)
LDS●●●1040	41.1 (1042.9)	46.4 (1178.9)	45.7 (1160.4)	44.9 (1140.2)	44.2 (1121.6)	40.9 (1040)
LDS●●●1120	44.2 (1122.3)	49.5 (1258.3)	48.8 (1239.8)	48 (1219.6)	47.3 (1201)	44.1 (1120)
LDS●●●1200	47.4 (1203.8)	52.7 (1339.8)	52 (1321.3)	51.2 (1301.1)	50.5 (1282.5)	47.2 (1200)
LDS●●●1360	53.6 (1362)	59 (1498)	58.2 (1479.5)	57.5 (1459.3)	56.7 (1440.7)	53.5 (1360)
LDS●●●1400	55.2 (1401.7)	60.5 (1537.7)	59.8 (1519.2)	59 (1499)	58.3 (1480.4)	55.1 (1400)
LDS●●●1520	59.9 (1521.5)	65.3 (1657.5)	64.5 (1639)	63.7 (1618.8)	63 (1600.2)	59.8 (1520)
LDS●●●1560	61.5 (1563.3)	66.9 (1699.3)	66.2 (1680.8)	65.4 (1660.6)	66.1 (1679.2)	61.4 (1560)
LDS●●●1640	64.6 (1641.3)	70 (1777.3)	69.2 (1758.8)	68.4 (1738.6)	67.7 (1720)	64.6 (1640)
LDS●●●1720	67.7 (1720.8)	73.1 (1856.8)	72.4 (1838.3)	71.6 (1818.1)	70.8 (1799.5)	67.7 (1720)
LDS●●●1800	71 (1802.9)	76.3 (1938.9)	75.6 (1920.4)	74.8 (1900.2)	74.1 (1881.6)	70.9 (1800)
LDS●●●1920	75.7 (1922.8)	81.1 (2058.8)	80.3 (2040.3)	79.5 (2020.1)	78.8 (2001.5)	75.6 (1920)
LDS●●●2120	83.5 (2120.7)	88.8 (2256.7)	88.1 (2237.5)	87.3 (2217.3)	86.6 (2198.7)	83.5 (2120)

(1) Flexible 4.33 in. (0.11 m) cable.

Protection tube for XUSLB/XUSLDM light curtains and XUSLDS segments

XUSLZD7●●●●



XUS	b	b1
LZD70280	11.2 (284.4)	19.8 (502.8)
LZD70320	12.8 (324.8)	21.4 (543.2)
LZD70360	14.4 (364.5)	22.9 (582.9)
LZD70440	17.5 (443.9)	26.1 (662.3)
LZD70520	20.6 (523.4)	29.2 (741.8)
LZD70600	23.8 (604.1)	32.4 (822.5)
LZD70680	26.9 (683.6)	35.5 (902)
LZD70720	28.5 (724)	37.1 (942.4)
LZD70760	30 (763)	38.6 (981.4)
LZD70880	34.8 (882.8)	43.4 (1101.2)
LZD70920	36.3 (922.5)	44.9 (1140.9)
LZD70960	37.9 (963.6)	46.5 (1182)

XUS	b	b1
LZD71040	41.1 (1042.9)	49.7 (1261.3)
LZD71120	44.2 (1122.3)	52.8 (1340.7)
LZD71200	47.4 (1203.8)	56 (1422.2)
LZD71360	53.6 (1362)	62.2 (1580.4)
LZD71400	55.2 (1401.7)	63.8 (1620.1)
LZD71520	59.9 (1521.5)	68.5 (1739.9)
LZD71560	61.5 (1563.3)	70.1 (1781.7)
LZD71640	64.6 (1641.3)	73.2 (1859.2)
LZD71720	67.7 (1720.8)	76.3 (1939.2)
LZD71800	71 (1802.9)	79.6 (2021.2)
LZD71920	75.7 (1922.8)	84.3 (2141.2)
LZD72120	83.5 (2120.7)	92.1 (2338.4)

Dual Dimensions:
in. (mm)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

Optimum XUSLB and Universal XUSLDM with solid-state output

Direct connection with XUSLB/LDM●●●



(1) *For testing prior to installation, you can select MPCE/EDM OFF (factory default setting). In that case, the MPCE/EDM line must be connected to the 0 V line of the system.*
(2) *The auxiliary output connects to a PLC (optional).*
(3) *If remote start is not used, connect the start line to the 0 V line.*
(4) *The K1 and K2 coils must be protected using the arc suppressors included in the documentation kit.*

Note: *Relays K1 and K2 must have mechanically linked contacts.*

5

Connection via a Preventa XPSAFL module



(1) *The auxiliary output connects to a PLC (optional).*
(2) *The light curtain must be configured with MPCE/EDM OFF and with automatic start.*

Note: *Relays K3 and K4 must have mechanically linked contacts.*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

Optimum XUSLB and Universal XUSLDM with solid-state output

Transmitter

Transmitter connector



(1) Light curtain test input.

Transmitter status indicator



1 Yellow LED

Receiver

Receiver connector



Receiver status indicator



1 Blanking: Orange LED
2 Interlock or Alarm: Yellow LED
3–4 Machine run: Green LED
Machine stop: Red LED

Programming and diagnostic module

Description and connection to XUSLB/XUSLDM light curtains

XUSLPDM



1 Screen
2 Navigation button for displaying menus and selecting functions

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

Optimum XUSLB and Universal XUSLDM with solid-state output

Optimum light curtains	
Detection capacity: 0.55 in. (14 mm)	
Old light curtain	**New light curtain**
XUSLTQ6A0260, XUSLTQ6B0260	**XUSLBQ6A0280**
XUSLTQ6A0350, XUSLTQ6B0350	**XUSLBQ6A0320, XUSLBQ6A0360**
XUSLTQ6A0435, XUSLTQ6B0435	**XUSLBQ6A0440**
XUSLTQ6A0520, XUSLTQ6B0520	**XUSLBQ6A0520**
XUSLTQ6A0610, XUSLTQ6B0610	**XUSLBQ6A0600**
XUSLTQ6A0700, XUSLTQ6B0700	**XUSLBQ6A0720**
XUSLTQ6A0785, XUSLTQ6B0785	**XUSLBQ6A0760**
XUSLTQ6A0870, XUSLTQ6B0870	**XUSLBQ6A0880, XUSLBQ6A0920**
XUSLTQ6A0955, XUSLTQ6B0955	**XUSLBQ6A0960**
XUSLTQ6A1045, XUSLTQ6B1045	**XUSLBQ6A1040**
XUSLTQ6A1130, XUSLTQ6B1130	**XUSLBQ6A1120**
XUSLTQ6A1215, XUSLTQ6B1215	**XUSLBQ6A1200**
XUSLTQ6A1305, XUSLTQ6B1390, XUSLTQ6A1390, XUSLTQ6B1390	**XUSLBQ6A1360**
Detection capacity: 1.18 in. (30 mm)	
Old light curtain	**New light curtain**
XUSLTR5A0350, XUSLTR5B0350	**XUSLBR5A0320, XUSLBR5A0360, XUSLBR5A0440**
XUSLTR5A0520, XUSLTR5B0520	**XUSLBR5A0520, XUSLBR5A0600**
XUSLTR5A0700, XUSLTR5B0700	**XUSLBR5A0680, XUSLBR5A0760**
XUSLTR5A0870, XUSLTR5A0870,	**XUSLBR5A0880, XUSLBR5A0920**
XUSLTR5A1045, XUSLTR5B1045	**XUSLBR5A1040**
XUSLTR5A1215, XUSLTR5B1215	**XUSLBR5A1200, XUSLBR5A1360**
XUSLTR5A1390, XUSLTR5B1390	**XUSLBR5A1400, XUSLBR5A1520**
XUSLTR5A1570, XUSLTR5B1570	**XUSLBR5A1560, XUSLBR5A1640**
XUSLTR5A1745, XUSLTR5B1745	**XUSLBR5A1720, XUSLBR5A1800**
XUSLTR5A1920, XUSLTR5B1920	**XUSLBR5A1920**
XUSLTR5A2095, XUSLTR5B2095	**XUSLBR5A2120**

Note: The specifications of the ranges (optics, connections, dimensions, mounting, functions, etc.) are not exactly the same.
Please refer to the detailed specifications of the XUSLB●●●●●●● and XUSLD●●●●●●● ranges and associated accessories when replacing a light curtain from the XUSLT●●●●●●● range.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Universal light curtains	
Detection capacity: 1.18 in. (30 mm)	
Old light curtain	**New light curtain**
XUSLTY5A0350, XUSLTY5B0350	**XUSLDMY5A0320, XUSLDMY5A0360, XUSLDMY5A0440**
XUSLTY5A0520, XUSLTY5B0520	**XUSLDMY5A0520, XUSLDMY5A0600**
XUSLTY5A0700, XUSLTY5B0700	**XUSLDMY5A0680, XUSLDMY5A0760**
XUSLTY5A0870, XUSLTY5B0870	**XUSLDMY5A0880, XUSLDMY5A0920**
XUSLTY5A1045, XUSLTY5B1045	**XUSLDMY5A1040**
XUSLTY5A1215, XUSLTY5B1215	**XUSLDMY5A1200, XUSLDMY5A1360**
XUSLTY5A1390, XUSLTY5B1390	**XUSLDMY5A1400, XUSLDMY5A1520**
XUSLTY5A1570, XUSLTY5B1570	**XUSLDMY5A1560, XUSLDMY5A1640**
XUSLTY5A1745, XUSLTY5B1745	**XUSLDMY5A1720, XUSLDMY5A1800**
XUSLTY5A1920, XUSLTY5B1920	**XUSLDMY5A1920**
XUSLTY5A2095, XUSLTY5B2095	**XUSLDMY5A2120**

Note: The specifications of the ranges (optics, connections, dimensions, mounting, functions, etc.) are not exactly the same.
Please refer to the detailed specifications of the XUSLB●●●●●●● and XUSLD●●●●●●● ranges and associated accessories when replacing a light curtain from the XUSLT●●●●●●● range.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ connection module XPSLCM1

for Muting function on XUSLDM light curtains



Operating principle

Universal XUSLDM light curtains have an integrated Muting function that is configurable using the XUSLPDM programming and diagnostic module. This function allows for the automatic passage of parts for machining or loaded pallets, without interrupting the transportation movement within the zone protected by the electro-sensitive protection equipment (ESPE) system. In addition to the safety light curtain, an XPSLCM1 connection module, which is connected directly to the top of the light curtain receiver, allows for the cabling of 2–4 muting sensors as well as an indicator light. In the event of a sequence error, the muting indicator light flashes (1 second interval); turning the Start key switch off and on restarts the system.

When the system is switched on by the start command, and the light curtain protection not interrupted, the main circuit is closed by the safety outputs of the XUSLDM light curtain (solid-state safety outputs). In addition to the safety outputs, the light curtain incorporates signaling LEDs and an auxiliary output (alarm or status signaling) for sending system status information to the PLC. Four LEDs on the light curtain and one on the front face of the XPSLCM1 connection module provide information on the safety circuit status.

An interruption of the protection field monitored by the electro-sensitive protection equipment causes instantaneous opening of the safety outputs; the process PLC receives a stop command, and the LED display mounted on the front face indicates the change of state of the safety circuits. The Open state is maintained until the light beams are unobstructed, and the Start key switch is operated (if included in the light curtain configuration).

The Muting function cannot be activated by energizing the muting sensors unless the safety outputs have been closed beforehand. To trigger the Muting function, the muting devices must be activated within the configurable time interval (50 ms to 5 seconds, in increments of 50 ms). During the activated muting phase, materials can be transported through the protection field without deactivating the safety outputs. In the event of intrusion into the hazardous zone, a person cannot activate the muting sensors in the same way, and the system stops.

During the muting operation process, a light indicating the muting state is controlled by the XPSLCM1 module. The indicator light comes on when a muting signal is generated, and indicates the inhibition of the protection function. An indicator light error (short-circuit, open-circuit) will be recognized, and will deactivate the Muting function.



ESPE: electro-sensitive protection equipment (light curtain)
A, B, D, C: muting sensors
m: trolley length
dM: distance between A, B and D, C

Conditions to be observed for the Muting function

- The muting sensors must either be either:
  - thru-beam: XUK0ARCTL2 (sensing distance 98.4 ft / 30 m) + XUK0ARCTL2T,
  - polarized reflex: XUK0ARCTL2 (sensing distance 16.4 ft / 5 m) + reflector XUZC50,
  - mechanical limit switches with hard contacts.
- dM ≤ m to obtain continuous validation of the Muting function.
- Avoid the intrusion of persons during the muting phase. This phase is indicated by the indicator light connected to the muting indicator output of the XPSLCM1 connection module.
- A materials trolley must generate the muting signal before entering the protection field, and discontinue the muting signal on exiting once it has cleared all the sensors of the protection field.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ connection module XPSLCM1

for Muting function on XUSLDM light curtains

Specifications

Connection module type			XPSLCM1
Maximum achievable safety level *(1)*			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Conformity to standards			ANSI/RIA R15.06, ANSI B11:19-1990, OSHA 1910.217(C), OSHA 1910.212, EN/IEC 61496-1 and EN/IEC 61496-2 and IEC 61508-1, 2 (Type 4 ESPE)
Certifications			CE, TÜV, CSA, UL
Product designed for max. use in safety related parts of control systems	Conforming to EN 954-1/ISO 13849-1		Category 4
Ambient air temperature	Operating	**°F (°C)**	32 to +131 (0 to +55)
	Storage	**°F (°C)**	–13 to +167 (–25 to +75)
Degree of protection conforming to IEC 529	Terminals		IP 20
	Enclosure		IP 20
Power supply by XUSLDM light curtain	Voltage	**V**	⎓ 24 (±20**%**)
	Maximum current	**mA**	30
Maximum consumption		**W**	0.7
Rated insulation voltage (Ui)		**V**	500
Rated impulse withstand voltage (Uimp)		**kV**	1.1
Shock resistance	Conforming to IEC 68-2-6	**gn**	6 (10–55 Hz)
Vibration resistance	Conforming to IEC 68-2-29	**gn**	10 (16 ms)
Number of light curtains that can be connected			1 transmitter-receiver pair
Inputs for muting sensors - number of inputs to be monitored			2–4 per Muting function
- supply voltage of sensors		**V**	⎓ 24
- output current of each sensor		**mA**	< 20
Type of muting sensors			Thru-beam, polarized reflex or sensors with hard contacts
Synchronization time of muting sensors		**ms**	50–500 (configurable in XUSLDM light curtain in increments of 50 ms)
Maximum muting time		**min**	2 or unlimited
Safety outputs	Number and type		2 PNP (terminals 1 and 2)
	Breaking capacity of outputs	**mA**	30 V/100
Muting indicator light	Output		1 NPN
	Power	**W**	1–7 max.
	Type		LED or filament bulb
Signaling			1 LED
Connection	Type		Captive screw clamp terminals, nonremovable
1-wire connection	Without cable end		Solid or flexible cable: 26–14 AWG (0.14–2.5 mm^2)
	With cable end		Without bezel, flexible cable: 24–14 AWG (0.25–2.5 mm^2)
	With cable end		With bezel, flexible cable: 24–16 AWG (0.25–1.5 mm^2)
2-wire connection	Without cable end		Without bezel, flexible cable: 24–18 AWG (0.25–1.0 mm^2)
	Without cable end		Double, with bezel, flexible cable: 22–16 AWG (0.5–1.5 mm^2)

(1) Using an appropriate and correctly connected control system.

5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ connection module XPSLCM1

for Muting function on XUSLDM light curtains



Description

XPSLCM1

To aid diagnostics, the connection module has 1 LED on the front face **1**.

References

Connection module

Description	Type of terminal block connection	Muting indicator light output	Supply	References	Weight oz (kg)
Connection module for Muting function	Nonremovable	1 NPN	⎓ 24 V	**XPSLCM1**	6.70 (0.190)

Connection cables

Description	Length ft (m)	References	Weight lbs (kg)
Pre-wired connectors for connection between the XPSLCM1 module and the XUSLD receiver	32.81 (10)	**XPSDCRM10**	1.521 (0.690)
	49.21 (15)	**XPSDCRM10**	2.271 (1.030)
	98.43 (30)	**XPSDCRM10**	4.255 (1.930)

Spare parts

Description	Power W	References	Weight oz (kg)
Muting indicator light kit *(1)*	5	**XSZCM01**	0.42 (0.012)
Replacement bulbs for muting indicator light kit consisting of one lot of 10 replacement bulbs and 1 removal/insertion tool XBF X13	1–7	**XSZCM02**	0.56 (0.016)

(1) XVB or XVD with steady light LED or filament bulb can also be used.

Dimensions

XPSLCM1

Mounting on 35 mm rail





Muting indicator light kit XSZCM01





(1) Faston® connector 4.7.

Dual Dimensions: in. (mm)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ connection module XPSLCM1

for Muting function on XUSLDM light curtains

Connection of XUSLDM light curtains with connection module XPSLCM1

Example configuration with XUSLDM light curtains



(1) For testing prior to installation, you can select MPCE/EDM OFF (factory default setting). In that case, the MPCE/EDM line must be connected to the 0 V line of the system.
(2) The auxiliary output connects to a PLC (optional).
(3) If remote start is not used, connect the start line to the 0 V line.
(4) The K1 and K2 coils must be protected using the arc suppressors included in the documentation kit.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Functional diagram of XUSLDM light curtain with connection module XPSLCM1

Start/Restart Interlock mode with 2 sensors



(1) Press the Start button.

Override function



Principle: page 5/22 | Specifications: page 5/23 | References: page 5/24 | Dimensions: page 5/24 | Wiring diagrams: page 5/25

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Functional diagram of XUSLDM light curtain with connection module XPSLCM1

Start/Restart Interlock mode with 4 sensors



(1) Press the Start button.

Override function



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLP compact light curtains with solid-state output

Light curtain type			XUSLP●●●●
Environmental specifications			
Conformity to standards			ANSI/RIA R15.06, ANSI B11:19-1990, OSHA 1910.217(C), OSHA 1910.212, EN/IEC 61496-1-2 for type 4 ESPE
Certifications			CE, TUV, UL, CSA
European directives			Machinery directive 2006/42/EC, Work equipment directive 89/655/EEC and EMC directive 89/336 EEC
Maximum safety level *(1)*			PL = e/category 4 conforming to EN/ISO 13849-1 SIL 3 conforming to EN/IEC 61508
Reliability data			PFH_d = 2.7E^{-9} 1/h conforming to EN/IEC 61508
Ambient air temperature	Operating	**°F (°C)**	+32 to +131 (0 to +55)
	Storage	**°F (°C)**	–13 to +167 (–25 to +75)
Relative humidity			95% maximum, without condensation
Degree of protection			IP65 and IP67
Shock and vibration resistance	Conforming to IEC 61496-1		Shock resistance: 10 gn, impulse 16 ms, Vibration resistance: 10–55 Hz, amplitude: 0.35 ±0.05 mm
Materials			Casing: aluminum with electrostatically applied red (RAL 3000) polyester paint finish; end caps: 20% fiberglass impregnated polycarbonate. Front cover: acrylic.
Mounting			End brackets (included)
Optical specifications			
Minimum detection capacity		**in. (mm)**	11.8, 15.7, 19.7, 23.6 (300, 400, 500, 600) and single beam (Body protection)
Nominal sensing distance (Sn)		**ft (m)**	2.6–65.5 or 2.6–229.7 (0.8–20 or 0.8–70), depending on the configuration; and 2.6–26.2 (0.8–8) for light curtains with passive receiver
Protected height			Depends on the number of light beams. See the table on page 5/33.
Effective aperture angle (EAA)			2.5° at 9.8 ft (3 m)
Light source			GaAlAs LED, 850 nm
Immunity to ambient light			Conforming to EN/IEC 61496-2
Electrical specifications			
Response time		**ms**	< 16 to < 24, depending on the light beam coding selected
Power supply			⎓ 24 V ± 20% 2 A conforming to EN/IEC 61496 and EN/IEC 60204-1
	Transmitter	**mA**	100 (SELV: Safety Extra Low Voltage)
	Receiver	**A**	1.6 (with maximum load)
Maximum current power consumption (no-load)	Transmitter	**mA**	100
	Receiver	**mA**	300
Immunity to interference			Conforming to EN/IEC 61496-1
Safety outputs OSSD (output signal switching devices)			2 solid-state PNP (N.O.) outputs ≤ 650 mA, ⎓ 24 V (short-circuit protected)
Auxiliary output			1 solid-state output 100 mA, ⎓ 24 V, PNP
Monitoring activation of output switching devices (MPCE/EDM)			50 mA, ⎓ 24 V
Signaling	Transmitter		1 LED (power supply)
	Receiver		3 LEDs (stop, run, interlock) and a 2-digit display for diagnostics
Connections *(2)*	Transmitter		M12, 5-pin, male connector or terminal block
	Receiver		M12, 8-pin, male connector or terminal block
Conductor	Transmitter/receiver pre-wired connector	**AWG (mm²)**	22 (0.35), tinned wires.
Cable resistance	Transmitter/receiver	Ω	0.016 per ft (0.055 per m) for 22 AWG (0.35 mm²) wire
Cable lengths		**ft (m)**	Pre-wired connectors with cable lengths of 16.4, 32.8, 49.2 and 98.4 ft (5,10, 15, and 30 m) are available separately. The maximum cable length is 394 ft (120 m), depending on the load current and power supply.
Functions			
Functions			Start: - Auto/Manual, manual 1st cycle - Monitoring of the external switching devices (EDM: external device monitoring) - Test (MTS: monitoring test signal) for XUSLPZ only - Alignment aid by display of each broken light beam - Display of operating modes and alarm by LEDs and 2-digit display Selection of Auto/Manual, relay monitoring, alarm or auxiliary output functions, light beam coding and selection of sensing distance using configuration switches.
Monitoring the external switching devices (EDM = external device monitoring)			Monitoring of the function (open or closed) as well as the response time of the power components. Parameters can be set using configuration switches.
Test function			Initiates the stop instruction of the light curtain by opening the contact (simulated intrusion)
Muting function (inhibition)			Possible with external module **XPSLCM1150**

(1) Using an appropriate and correctly connected control system.

(2) Pre-wired female connectors must be ordered separately. See page 5/31.

Specifications: page 5/28 | References: page 5/29 | Dimensions: page 5/32 | Wiring diagrams: page 5/34

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLP compact light curtains with solid-state output, with connector

XUSLPZ1AM

XUSLPZ3A●●●●M

Transmitter-receiver pairs for body protection *(1)*

Detection capacity: 11.8, 15.7, 19.7, 23.6 in. (300, 400. 500. 600 mm) and single beam.
Sensing distance: 2.6–65.5 ft or 2.6–229.7 ft (0.8–20 m or 0.8–70 m) (depending on the configuration).

■ 2 PNP safety outputs

Detection capacity *(3)*	Response time Light beam coding A	B	C	Number of light beams	Auxiliary output	References *(2)*	Weight
in. (mm)	ms	ms	ms				lb (kg)
–	< 24	< 20	< 16	1	PNP	**XUSLPZ1AM**	9.92 (4.500)
19.69 (500)	< 24	< 20	< 16	2	PNP	**XUSLPZ2A0500M**	13.89 (6.300)
23.62 (600)	< 24	< 20	< 16	2	PNP	**XUSLPZ2A0600M**	14.77 (6.700)
15.75 (400)	< 24	< 20	< 16	3	PNP	**XUSLPZ3A0400M**	15.87 (7.200)
19.69 (500)	< 24	< 20	< 16	3	PNP	**XUSLPZ3A0500M**	18.96 (8.600)
11.81 (300)	< 24	< 20	< 16	4	PNP	**XUSLPZ4A0300M**	18.08 (8.200)
11.81 (300)	< 24	< 20	< 16	5	PNP	**XUSLPZ5A0300M**	20.94 (9.500)
11.81 (300)	< 24	< 20	< 16	6	PNP	**XUSLPZ6A0300M**	22.93 (10.400)

(1) Includes 2 sets of 2 brackets with mountings and a user guide with certificate of conformity.
Pre-wired female connectors must be ordered separately. See page 5/31.
*(2) To order a receiver only, add the letter **R** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLPZ2A0600M becomes **XUSLPZ2A0600MR** for the receiver only.*
*To order a transmitter only, add the letter **T** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLPZ2A0600M becomes **XUSLPZ2A0600MT** for the transmitter only.*
(3) Detection capacity (also known as MOS) is the smallest diameter object that the light curtain is capable of detecting. The protected height of a light curtain depends on the detection capacity and the number of beams in the light curtain. Refer to pages 5/32 and 5/33 for dimensions and for determination of protected height.

XUSLPB2●●

Transmitter-receiver pairs for body protection, with passive receiver (reflector) *(1)*

Detection capacity: 19.7 and 23.6 in. (500 and 600 mm).
Sensing distance: 2.6–26.3 ft (0.8–8 m).

■ 2 PNP safety outputs
■ The **XUSLPB** system integrates the transmitter and receiver into one assembly (transceiver), which is mated with a passive reflector unit. The passive reflector unit does not require electrical connections.

Detection capacity *(3)*	Response time Light beam coding A	B	C	Number of light beams	Auxiliary output	References *(2)*	Weight
in. (mm)	ms	ms	ms				lb (kg)
19.69 (500)	< 24	< 20	< 16	2	PNP	**XUSLPB2A500M**	13.89 (6.300)
23.62 (600)	< 24	< 20	< 16	2	PNP	**XUSLPB2A600M**	14.77 (6.700)

(1) Includes 2 sets of 2 brackets with mountings and a user guide with certificate of conformity.
Pre-wired female connectors must be ordered separately. See page 5/31.
*(2) To order a passive receiver (reflector), replace the letter **M** with the letter **P** at the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLPB2A500M becomes **XUSLPB2A500P** for the passive receiver (reflector).*
*To order a transmitter-receiver (transceiver) only, add the letter **R** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLPB2A600M becomes **XUSLPB2A600MR** for the transmitter-receiver (transceiver) only.*
(3) Detection capacity (also known as MOS) is the smallest diameter object that the light curtain is capable of detecting. The protected height of a light curtain depends on the detection capacity and the number of beams in the light curtain. Refer to pages 5/32 and 5/33 for dimensions and for determination of protected height.

Other versions Combining type 4 light curtains with an external module for the Muting function. See page 5/60.

Separate components and accessories: page 5/31

Specifications: page 5/28 | References: page 5/29 | Dimensions: page 5/32 | Wiring diagrams: page 5/34

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLP compact light curtains with solid-state output, with terminal block *(3)*

XUSLPZ1AB

XUSLPZ3A ●●●●B

Transmitter-receiver pairs for body protection *(1)*

Detection capacity:
11.8, 15.7, 19.7, 23.6 in. (300, 400. 500. 600 mm) and single beam.
Sensing distance:
2.6–65.5 ft or 2.6–229.7 ft (0.8–20 m or 0.8–70 m), depending on the configuration

- 2 PNP safety outputs

Detection capacity *(4)*	Response time Light beam coding			Number of light beams	Auxiliary output	References *(2)*	Weight
	A	B	C				
in. (mm)	ms	ms	ms				lb (kg)
–	< 24	< 20	< 16	1	PNP	**XUSLPZ1AB**	9.92 (4.500)
19.69 (500)	< 24	< 20	< 16	2	PNP	**XUSLPZ2A0500B**	13.89 (6.300)
23.62 (600)	< 24	< 20	< 16	2	PNP	**XUSLPZ2A0600B**	14.77 (6.700)
15.75 (400)	< 24	< 20	< 16	3	PNP	**XUSLPZ3A0400B**	15.87 (7.200)
19.69 (500)	< 24	< 20	< 16	3	PNP	**XUSLPZ3A0500B**	18.96 (8.600)
11.81 (300)	< 24	< 20	< 16	4	PNP	**XUSLPZ4A0300B**	18.08 (8.200)
11.81 (300)	< 24	< 20	< 16	5	PNP	**XUSLPZ5A0300B**	20.94 (9.500)
11.81 (300)	< 24	< 20	< 16	6	PNP	**XUSLPZ6A0300B**	22.93 (10.400)

(1) Includes 2 sets of 2 brackets with mountings and a user guide with certificate of conformity.
*(2) To order a receiver only, add the letter **R** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLPZ2A0600B becomes **XUSLPZ2A0600BR** for the receiver only.*
*To order a transmitter only, add the letter **T** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLPZ2A0600B becomes **XUSLPZ2A0600BT** for the transmitter only.*
(3) Terminal block versions provide 3 conduit openings with M20 thread. When installing light curtain, use an M20 threaded cable gland (liquid tight cable strain relief fitting), or a DE9RA1220 conduit adapter for use with ½" NPT. The DE9RA1220 is not supplied with the light curtain and must be ordered separately. A micro style connector may also be used.
(4) Detection capacity (also known as MOS) is the smallest diameter object that the light curtain is capable of detecting. The protected height of a light curtain depends on the detection capacity and the number of beams in the light curtain. Refer to pages 5/32 and 5/33 for dimensions and for determination of protected height.

Other versions Combining type 4 light curtains with an external module for the Muting function. See page 5/60.

Separate components and accessories: page 5/31

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLP accessories for compact light curtains



XSZ PCT●●



XSZ PCR●●

Separate components

Power supplies, 90° mirror adapters, protective covers, anti-vibration kit, mounting bases

See pages 5/40 to 5/47.

Accessories

Description	Usage	Length ft (m)	References	Weight lb (kg)
Mounting kit (2 brackets)	For XUSLP light curtains	–	**XUSLZ219**	0.99 (0.450)
Pre-wired female connectors	Transmitter type	16.40 (5)	**XSZPCT05**	0.77 (0.350)
		32.81 (10)	**XSZPCT10**	1.54 (0.700)
		49.21 (15)	**XSZPCT15**	2.25 (1.020)
		98.43 (30)	**XSZPCT30**	4.45 (2.020)
	Receiver type	16.40 (5)	**XSZPCR05**	0.77 (0.350)
		32.81 (10)	**XSZPCR10**	1.54 (0.700)
		49.21 (15)	**XSZPCR15**	2.25 (1.020)
		98.43 (30)	**XSZPCR30**	4.45 (2.020)
Sliding nuts for side mounting (4 nuts)	–	–	**XUSLZ320**	0.99 (0.450)
User guide on CD-ROM	All light curtain types	–	**XUSLZ450**	0.04 (0.020)
Arc suppressor (pair)	All light curtain types	–	**XUSLZ500**	0.04 (0.020)

Power supplies: page 5/40

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLP compact light curtains with solid-state output

Light curtains

XUSLPZ●●●



XUS	b in. (mm)	b1 in. (mm)	G in. (mm)
LPZ1A●	9.12 (231.6)	–	8.69 (220.7)
LPZ2A0500●	28.80 (731.6)	19.69 (500)	28.37 (720.7)
LPZ2A0600●	32.74(831.6)	23.62 (600)	32.31 (820.7)
LPZ3A0400●	40.61 (1031.6)	15.75 (400)	40.19 (1020.7)
LPZ3A0500●	48.49 (1231.6)	19.69 (500)	48.06 (1220.7)
LPZ4A0300●	44.93 (1141.1)	11.81 (300)	44.12 (1120.7)
LPZ5A0300●	56.36 (1431.6)	11.81 (300)	55.56 (1411.2)
LPZ6A0300●	68.17 (1731.6)	11.81 (300)	67.37 (1711.2)

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtains
XUSLPB●●●



Dual Dimensions:
in. (mm)

XUS	b in. (mm)	b1 in. (mm)	G in. (mm)
LPB2A500M	30.75 (781.1)	19.69 (500)	29.95 (760.7)
LPB2A600M	34.69 (881.1)	23.62 (600)	33.89 (860.7)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 4

XUSLP compact light curtains with solid-state output

Direct connection with XUSLP●●●



(1) For testing prior to installation, you can select MPCE/EDM OFF (factory default setting). In that case, the MPCE/EDM line must be connected to the 0 V line of the system.
(2) The auxiliary output connects to a PLC (optional).
(3) If remote start is not used, connect the start line to the 0 V line.

Connection via a Preventa XPSAFL module



(1) The auxiliary output connects to a PLC (optional).
(2) The light curtain must be configured with MPCE/EDM OFF and with automatic start.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XUSLPZ/LPB●

Transmitter

Pre-wired connector of transmitter (XUSLPZ)



Transmitter status indicator



1 Yellow LED

Configuration indicator XUSLPZ



Configuration indicator XUSLPB



Receiver

Pre-wired connector of receiver (XUSLPZ) and pre-wired connector of transmitter-receiver (XUSLPB)



Receiver status indicator



1 Interlock or Alarm yellow LED
2 Machine stop red LED
3 Machine run green LED
4 2-digit display

Configuration indicator XUSLPZ and XUSLPB



Connection to terminal block



Connection to M12 connector





5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 2

XUSLN slim, compact light curtains with solid-state output

Light curtain type			XUSLNG●●●● 1.18 in. (30 mm)
Environmental specifications			
Conformity to standards			IEC 61496-1 and IEC 61496-2 (Type 2 ESPE)
Certifications			CE, TUV, UL, CSA
European directives			Machinery directive 2006/42/EC, Work equipment directive 89/655/EEC and EMC directive 89/336 EEC
Maximum safety level *(1)*			PL = c/category 2 conforming to EN/ISO 13849-1 SIL 2 conforming to EN/IEC 61508
Reliability data			PFH_d = 2.29E^{-7} 1/h conforming to EN/IEC 61508
Ambient air temperature	Operating	**°F (°C)**	+32 to +131 (0 to +55)
	Storage	**°F (°C)**	–13 to +167 (–25 to +75)
Relative humidity			95% maximum, without condensation
Degree of protection			IP65
Shock and vibration resistance	Conforming to IEC 61496-1		Shock resistance: 10 gn, impulse 16 ms, Vibration resistance: 10–55 Hz, amplitude: 0.35 ±0.05 mm
Materials			Casing: aluminum with electrostatically applied red (RAL 3000) polyester paint finish; end caps: 30% fiberglass impregnated nylon; front cover: acrylic.
Mounting			End brackets (included)
Optical specifications			
Minimum detection capacity		**in. (mm)**	1.18 (30) (Hand)
Nominal sensing distance (Sn)		**ft (m)**	1–49.3 (0.3–15)
Protected height		**in. (mm)**	5.29–57.87 in. (150–1500 mm)
Effective aperture angle (EAA)			5° at 3 m conforming to IEC 61496-1 and IEC 61496-2 (Type 2 ESPE)
Light source			GaAlAs LED, 880 nm
Immunity to ambient light			Conforming to IEC/EN 61496-2
Electrical specifications			
Response time		**ms**	14–24
Power supply			⎓ 24 V ± 20% 2 A conforming to IEC 61496 and IEC 60204-1 (–10% using the EDM function)
	Transmitter	**mA**	50 (SELV: Safety Extra Low Voltage)
	Receiver	**A**	1.09 (with maximum load)
Maximum current power consumption (no-load)	Transmitter	**mA**	50
	Receiver	**mA**	90
Immunity to interference			Conforming to EN 61496-1 and EN 61496-2
Safety outputs OSSD (output signal switching devices)			2 solid-state PNP (N.O.) outputs ≤ 500 mA, ⎓ 24 V (short-circuit protection)
Signaling	Transmitter		2 LEDs (power supply and diagnostic)
	Receiver		4 LEDs (stop, run, top alignment, and bottom alignment)
Connections *(2)*	Transmitter		M12, 4-pin, male connector
	Receiver		M12, 5-pin, male connector
Pre-wired connectors	Transmitter/Receiver	**AWG (mm²)**	22 (0.25) tinned wires.
Cable resistance	Transmitter/Receiver	Ω	0.028 Ω/ft (0.093 Ω/m) for 22 AWG (0.25 mm²) wire
Cable lengths		**ft (m)**	Pre-wired connectors with cable lengths of 9.84, 32.81, and 98.43 ft (3, 10, and 30 m) are available separately. The maximum cable length is 164 ft (50 m), depending on the load current and power supply.
Functions			
Functions			■ Start: □ Automatic: model **XUSLNG5C** □ Manual: model **XUSLNG5D** ■ Alignment aid using 2 LEDs ■ LED display of operating modes ■ Monitoring of the external switching devices EDM/MPCE
Muting function (inhibition)			Possible with external module **XPSLCM1150**

(1) Using an appropriate and correctly connected control system.
(2) Pre-wired female connectors must be ordered separately. See page 5/37.

5

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Light curtains, type 2

XUSLN slim, compact light curtains with solid-state output

XUSLNG5●●●●●

Transmitter-receiver system for hand protection *(1)*

Detection capacity: 1.18 in. (30 mm). Sensing distance: 0.89–49.21 ft (0.3–15 m).

■ 2 PNP safety outputs—Automatic start

Protected height	Response time	Number of light beams	Alarm output	References *(2)*	Weight
in. (mm)	ms				lb (kg)
5.91 (150)	14	7	PNP	**XUSLNG5C0150**	5.95 (2.700)
11.81 (300)	15	14	PNP	**XUSLNG5C0300**	6.39 (2.900)
17.72 (450)	16	21	PNP	**XUSLNG5C0450**	7.05 (3.200)
23.62 (600)	17	28	PNP	**XUSLNG5C0600**	7.50 (3.400)
29.53 (750)	18	35	PNP	**XUSLNG5C0750**	7.94 (3.600)
35.43 (900)	19	42	PNP	**XUSLNG5C0900**	8.60 (3.900)
41.34 (1050)	20	49	PNP	**XUSLNG5C1050**	9.04 (4.100)
47.24 (1200)	21	56	PNP	**XUSLNG5C1200**	9.48 (4.300)
53.15 (1350)	22	63	PNP	**XUSLNG5C1350**	9.92 (4.500)
59.06 (1500)	23	70	PNP	**XUSLNG5C1500**	10.58 (4.800)

■ 2 PNP safety outputs—Manual start

Protected height	Response time	Number of light beams	Alarm output	References *(2)*	Weight
in. (mm)	ms				lb (kg)
5.91 (150)	14	7	PNP	**XUSLNG5D0150**	5.95 (2.700)
11.81 (300)	15	14	PNP	**XUSLNG5D0300**	6.39 (2.900)
17.72 (450)	16	21	PNP	**XUSLNG5D0450**	7.05 (3.200)
23.62 (600)	17	28	PNP	**XUSLNG5D0600**	7.50 (3.400)
29.53 (750)	18	35	PNP	**XUSLNG5D0750**	7.94 (3.600)
35.43 (900)	19	42	PNP	**XUSLNG5D0900**	8.60 (3.900)
41.34 (1050)	20	49	PNP	**XUSLNG5D1050**	9.04 (4.100)
47.24 (1200)	21	56	PNP	**XUSLNG5D1200**	9.48 (4.300)
53.15 (1350)	22	63	PNP	**XUSLNG5D1350**	9.92 (4.500)
59.06 (1500)	23	70	PNP	**XUSLNG5D1500**	10.58 (4.800)

(1) Includes a test rod, 2 sets of 2 brackets with mountings, and a user guide with certificate of conformity and 1 arc suppressor set.
***Pre-wired female connectors must be ordered separately**. See below.*

*(2) To order a transmitter only, replace the letter C or D with **E** and add the letter **T** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLNG5C0150 becomes **XUSLNG5E0150T** for the transmitter only.*
*To order a receiver only, add the letter **R** to the end of the catalog number for the corresponding transmitter-receiver pair.*
*Example: XUSLNG5C0150 becomes **XUSLNG5C0150R** for the receiver only.*

Other versions

Combining type 4 light curtains with an external module for the Muting function. See page 5/60.

Accessories

Description		For use with	Length ft (m)	References	Weight oz (kg)
Mounting kit (2 brackets)		XUSLN light curtains	–	**XUSLZ218**	0.99 (0.450)
Pre-wired female connectors	Transmitter type	XUSLN light curtains	9.84 (3)	**XSZ NCT03**	1.50 (0.680)
			32.81 (10)	**XSZ NCT10**	2.01 (0.910)
			98.43 (30)	**XSZ NCT30**	3.00 (1.360)
	Receiver type	XUSLN light curtains	9.84 (3)	**XSZ NCR03**	1.50 (0.680)
			32.81 (10)	**XSZ NCR10**	2.01 (0.910)
			98.43 (30)	**XSZ NCR30**	3.00 (1.360)
Arc suppressor (pair)		All types of light curtains	–	**XUSLZ500**	0.04 (0.020)
User guide on CD-ROM		All types of light curtains and accessories	–	**XUSLZ450**	0.04 (0.020)



XSZ NCT●●



XSZ NCR●●

Separate components

Power supplies, 90° mirror adapters, anti-vibration kit, and mounting bases

See pages 5/40 to 5/47.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Dimensions

Slim, compact light curtains

XUSLN●●●



XUS	b in. (mm)	b1 in. (mm)	H in. (mm)	Protected height in. (mm)
LN●●●0150	5.79 (147)	10.71 (272)	9.67 (245.6)	5.91 (150)
LN●●●0300	11.57 (294)	16.50 (419)	15.46 (392.6)	11.81 (300)
LN●●●0450	17.36 (441)	22.28 (566)	21.24 (539.5)	17.72 (450)
LN●●●0600	23.15 (588)	28.07 (713)	27.03 (686.6)	23.62 (600)
LN●●●0750	28.94 (735)	33.86 (860)	32.82 (833.6)	29.53 (750)
LN●●●0900	34.72 (882)	39.65 (1007)	38.61 (980.6)	35.43 (900)
LN●●●1050	40.51 (1029)	45.43 (1154)	44.39 (1127.6)	41.34 (1050)
LN●●●1200	46.30 (1176)	51.22 (1301)	50.18 (1274.6)	47.24 (1200)
LN●●●1350	52.09 (1323)	57.01 (1448)	55.97 (1421.6)	53.15 (1350)
LN●●●1500	57.87 (1470)	62.80 (1595)	61.76 (1568.6)	59.06 (1500)

(1) 1 elongated hole Ø0.27 x 0.66 in. (Ø6.75 x 16.75 mm.)
(2) M12 male connector.

Connections

Transmitter

Pre-wired connector of transmitter XSZ NCT



Transmitter status indicator



1 Interlock or Alarm
yellow LED
2 Switch-on/Machine run
green LED

Receiver

Pre-wired connector of receiver XSZ NCR



Receiver status indicator



1 Top alignment
yellow LED
2 Bottom alignment
yellow LED
3 Stop
red LED
4 Run
green LED

Specifications: page 5/36
References: page 5/37
Dimensions: page 5/38
Wiring diagrams: page 5/38

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Wiring diagrams (continued)

Direct connection with XUSLNG5D●●●



(1) The K1 and K2 coils must be protected using the arc suppressors included in the documentation kit.
(2) For the EDM function, contactors LC1D●●BD and control relays CAD●●BD, CA4KN●●BW3, and CA3KN●●BD are recommended

5

Connection of XUSLN5C●●● light curtain via a Preventa XPSAFL module



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions
Accessories for safety light curtains types 2 and 4



XUSZM/ZA●●●●

90° mirror adapter for light curtains

Glass mirror (0.88 Sn) *(1)*

Description	For use with light curtains			Height *(2)*	References	Weight
	XUSLB/LDM	XUSLP	XUSLN	in. (mm)		lb (kg)
90° mirror adapter with rotatable mounting	–	XUSLPZ1A●	–	5.5 (140)	**XUSZM0102**	2.3 (1.040)
	–	–	–	7.5 (191)	**XUSZM0152**	2.9 (1.300)
	XUSLB/LDM0280	–	XUSLN●●●0150	13.5 (343)	**XUSZM0305**	4.2 (1.900)
	XUSLB/LDM0320 XUSLB/LDM0360	–	XUSLN●●●0300	19.5 (495)	**XUSZM0457**	5.5 (2.500)
	XUSLB/LDM0440	–	XUSLN●●●0450	21.5 (546)	**XUSZM0508**	6.2 (2.800)
	XUSLB/LDM0520	XUSLP●2A500●	–	25.5 (648)	**XUSZM0610**	7.1 (3.200)
	XUSLB/LDM0600/0680	XUSLP●2A0600●	XUSLN●●●0600	29.5 (749)	**XUSZM0711**	8.2 (3.700)
	XUSLB/LDM0720	–	–	31.5 (800)	**XUSZM0762**	8.4 (3.800)
	XUSLB/LDM0760	–	XUSLN●●●0750	33.5 (851)	**XUSZM0813**	8.8 (4.000)
	XUSLB/LDM0880	XUSLPZ3A0400●	–	37.5 (953)	**XUSZM0914**	9.9 (4.500)
	XUSLB/LDM0920/0960		XUSLN●●●0900	41.5 (1054)	**XUSZM1016**	11 (5.000)
	XUSLB/LDM1040	XUSLPZ3A0500●	–	43.5 (1105)	**XUSZM1067**	11.5 (5.200)
	XUSLB/LDM1120	XUSLPZ4A0300●	XUSLN●●●1050	49.5 (1257)	**XUSZM1219**	13 (5.900)
	XUSLB/LDM1200	XUSLPZ5A0300●	XUSLN●●●1200	53.5 (1359)	**XUSZM1321**	13.9 (6.300)
	XUSLB/LDM1360	–	XUSLN●●●1350	55.5 (1410)	**XUSZM1372**	14.3 (6.500)
	XUSLB/LDM1400	–	–	57.5 (1461)	**XUSZM1422**	14.8 (6.700)
	XUSLB/LDM1520	–	XUSLN●●●1500	61.5 (1562)	**XUSZM1524**	15.9 (7.200)
	XUSLB/LDM1560	XUSLPZ6A0300●	–	65.5 (1664)	**XUSZM1626**	16.8 (7.600)
	XUSLB/LDM1640/1720	–	–	73.5 (1867)	**XUSZM1830**	18.7 (8.500)
	XUSLB/LDM1800	–	–	73.5 (1867)	**XUSZM1830**	18.7 (8.500)
	XUSLB/LDM1920/2120	–	–	85.5 (2172)	**XUSZM2134**	21.6 (9.800)

Stainless steel mirror (0.82 Sn) *(1)*

Description	For use with light curtains			Height *(2)*	References	Weight
	XUSLB/LDM	XUSLP	XUSLN	in. (mm)		lb (kg)
90° mirror adapter with rotatable mounting	–	XUSLPZ1A●	–	5.5 (140)	**XUSZA0102**	2.4 (1.090)
	–	–	–	7.5 (191)	**XUSZA0152**	2.9 (1.300)
	XUSLB/LDM0280	–	XUSLN●●●0150	13.5 (343)	**XUSZA0305**	4.4 (2.000)
	XUSLB/LDM0320 XUSLB/LDM0360	–	XUSLN●●●0300	19.5 (495)	**XUSZA0457**	6 (2.700)
	XUSLB/LDM0440	–	XUSLN●●●0450	21.5 (546)	**XUSZA0508**	6.6 (3.000)
	XUSLB/LDM0520	XUSLP●2A500●	–	25.5 (648)	**XUSZA0610**	7.7 (3.500)
	XUSLB/LDM0600/0680	XUSLP●2A0600●	XUSLN●●●0600	29.5 (749)	**XUSZA0711**	8.6 (3.900)
	XUSLB/LDM0720	–	–	31.5 (800)	**XUSZA0762**	9.3 (4.200)
	XUSLB/LDM0760	–	XUSLN●●●0750	33.5 (851)	**XUSZA0813**	9.7 (4.400)
	XUSLB/LDM0880	XUSLPZ3A0400●	–	37.5 (953)	**XUSZA0914**	9.9 (4.500)
	XUSLB/LDM0920/0960		XUSLN●●●0900	41.5 (1054)	**XUSZA1016**	11.9 (5.400)
	XUSLB/LDM1040	XUSLPZ3A0500●	–	43.5 (1105)	**XUSZA1067**	12.3 (5.600)
	XUSLB/LDM1120	XUSLPZ4A0300●	XUSLN●●●1050	49.5 (1257)	**XUSZA1219**	14.1 (6.400)
	XUSLB/DM1200	XUSLPZ5A0300●	XUSLN●●●1200	53.5 (1359)	**XUSZA1321**	15 (6.800)
	XUSLB/LDM1360	–	XUSLN●●●1350	55.5 (1410)	**XUSZA1372**	15.4 (7.000)
	XUSLB/LDM1400	–	–	57.5 (1461)	**XUSZA1422**	16.1 (7.300)
	XUSLB/LDM1520	–	XUSLN●●●1500	61.5 (1562)	**XUSZA1524**	17.2 (7.800)
	XUSLB/LDM1560	XUSLPZ6A0300●	–	65.5 (1664)	**XUSZA1626**	18.3 (8.300)
	XUSLB/LDM1640/1720	–	–	73.5 (1867)	**XUSZA1830**	20.3 (9.200)
	XUSLB/LDM1800	–	–	73.5 (1867)	**XUSZA1830**	20.3 (9.200)
	XUSLB/LDM1920/2120	–	–	85.5 (2172)	**XUSZA2134**	23.4 (10.600)

(1) Sensing distance reduction coefficient must be taken into account for each 90° mirror adapter used.
(2) Usable reflective height.

Accessories

Description	Usage	References	Weight lb (kg)
Laser alignment tool	XUSLB, XUSLD, XUSLP, XUSLN	**XUSLAT1**	0.75 (0.340)

ABL8RPS24050

Power supplies for XUSL● light curtains

Input voltage	Secondary			Reset	Conforming to standard EN 61000-3-2	References	Weight lb (kg)
	Output voltage	Nominal power	Nominal current				
Single phase (N-L1) or 2-phase (L1-L2) connection							
100–120 / 200–500 V~ –15 %,+10 % 50/60 Hz	24–28.8 V⎓	72 W	3 A	Auto/manual	Yes	**ABL8RPS24030**	0.7 (0.300)
		120 W	5 A	Auto/manual	Yes	**ABL8RPS24050**	1.5 (0.700)
		240 W	10 A	Auto/manual	Yes	**ABL8RPS24100**	2.2 (1.000)

References: page 5/40
Dimensions: pages 5/44 and 5/47
Wiring diagrams: page 5/47

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Protective covers for light curtains XUSLB/XUSLDM/XUSLP			**XUSZWS●●●●**
Environmental specifications			
Air temperature	Operating	**°F (°C)**	32 to +131 (0 to +55)
	Storage	**°F (°C)**	–13 to +158 (–25 to +70)
Material			polycarbonate
Sensing distance (Sn) **reduction coefficient**			0.91 *(1)*
Environmental chemicals			
Chemical resistance	Acids, aliphatic hydrocarbons		Resistant
	Alcohols, alkalis		Limited resistance
	Detergents and cleaners		
	Greases and oils		
	Silicone oils and greases not containing alkaline products		
	Amines		Not resistant
	Aromatic hydrocarbons		
	Detergents and cleaners containing alkaline		
	Esters		
	Halogenated hydrocarbons		
	Ketones		
	Silicone oils and greases containing alkaline products		

References of protective covers



XUSLZWB●●●●



XUSZWSP

Description	For use with	Height in. (mm)	References	Weight lb (kg)
Polycarbonate protective covers for transmitter-receiver pair (0.91 Sn) *(1)* (Sold in sets of 2)	XUSLB/DM280	12.2 (310)	**XUSLZWB0280**	0.6 (0.282)
	XUSLB/DM320	13.8 (350)	**XUSLZWB0320**	0.7 (0.318)
	XUSLB/DM360	15.4 (390)	**XUSLZWB0360**	0.8 (0.354)
	XUSLB/DM440	18.5 (470)	**XUSLZWB0440**	0.9 (0.426)
	XUSLB/DM520	21.7 (550)	**XUSLZWB0520**	1.1 (0.497)
	XUSLB/DM600	24.8 (630)	**XUSLZWB0600**	1.3 (0.569)
	XUSLB/DM680	28 (710)	**XUSLZWB0680**	1.4 (0.641)
	XUSLB/DM720	29.5 (750)	**XUSLZWB0720**	1.5 (0.677)
	XUSLB/DM760	31.1 (790)	**XUSLZWB0760**	1.6 (0.713)
	XUSLB/DM880	35.8 (910)	**XUSLZWB0880**	1.8 (0.821)
	XUSLB/DM920	37.4 (950)	**XUSLZWB0920**	1.9 (0.857)
	XUSLB/DM960	39 (990)	**XUSLZWB0960**	2.0 (0.893)
	XUSLB/DM1040	42.1 (1070)	**XUSLZWB1040**	2.1 (0.965)
	XUSLB/DM1120	45.3 (1150)	**XUSLZWB1120**	2.3 (1.037)
	XUSLB/DM1200	48.4 (1230)	**XUSLZWB1200**	2.4 (1.108)
	XUSLB/DM1360	54.7 (1390)	**XUSLZWB1360**	2.8 (1.252)
	XUSLB/DM1400	56.3 (1430)	**XUSLZWB1400**	2.8 (1.288)
	XUSLB/DM1520	61 (1550)	**XUSLZWB1520**	3.1 (1.396)
	XUSLB/DM1560	62.6 (1590)	**XUSLZWB1560**	3.2 (1.432)
	XUSLB/DM1640	65.7 (1670)	**XUSLZWB1640**	3.3 (1.504)
	XUSLB/DM1720	68.9 (1750)	**XUSLZWB1720**	3.5 (1.576)
	XUSLB/DM1800	72 (1830)	**XUSLZWB1800**	3.6 (1.648)
	XUSLB/DM1920	76.8 (1950)	**XUSLZWB1920**	3.9 (1.756)
	XUSLB/DM2120	84.6 (2150)	**XUSLZWB2120**	4.3 (1.935)

Description	For use with	Height in. (mm)	References	Weight lb (kg)
Polycarbonate protective covers for single beam device (0.91 Sn) *(1)* (Sold in sets of 2)	XUSLP	2.5 (62.48)	**XUSZWSP**	2.2 (0.100)

(1) Sensing distance reduction coefficient must be taken into account for each pair of polycarbonate protective covers used.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Anti-vibration kit

Selection according to weight and application

Weight classes

Light curtain type	Height in. (mm)	Weight class 1	2	3	4
XUSLN	5.9–23.6 (150–600)	•			
	29.5–59.1 (750–1500)		•		
XUSLB/LDMQ/LDSQ	11–40.9 (280–1040)		•		
	44.1–53.5 (1120–1360)			•	
XUSLBR/LDMY/LDSY	12.6–40.9 (320–1040)		•		
	44.1–83.5 (1120–2120)			•	
XUSLPZ1A	–			•	
XUSLPZ2A0500 and XUSLPZ2A0600	–			•	
XUSLPZ3A0400	–			•	
XUSLPZ3A0500	–				•
XUSLPZ4A0300	–			•	
XUSLPZ5A0300 and XUSLPZ6A0300	–				•
XUSLPB2A500 and XUSLPB2A600	–			•	

Type of mirror adapters	Height in. (mm)	Weight class 1	2	3	4
XUSZM *(1)*	4 (102)	•			
	12–18 (305–457)		•		
	20–28 (508–711)			•	
	32–40 (813–1016)				•
XUSZA	4 (102)	•			
	12–42 (305–1067)		•		
	48–64 (1219–1626)			•	
	72–84 (1830–2134)				•

(1) Use of the anti-vibration kit is not recommended for mirror adapters greater than 40 in. (1016 mm) in height.

Applications

Weight class	Anti-shock applications *(1)* Shear mounted: Number of mountings per head *(3)*	References	Anti-shock applications *(1)* Compression mounted: Number of mountings per head *(3)*	References	Anti-vibration applications *(2)* Shear mounted: Number of mountings per head *(3)*	References	Anti-vibration applications *(2)* Compression mounted: Number of mountings per head *(3)*	References
1	2	XSZSMK	Not recommended		2 or 4	XSZSMK	2	XSZSMK1
	2	XSZSMK1			2 or 4	XSZSMK1		
2	2 or 4	XSZSMK	2	XSZSMK1	2 or 4	XSZSMK	2	XSZSMK
	2 or 4	XSZSMK1			2 or 4	XSZSMK1	2 or 4	XSZSMK1
					2	XSZSMK2		
3	4	XSZSMK	2	XSZSMK	2 or 4	XSZSMK	2 or 4	XSZSMK
	4	XSZSMK1	2 or 4	XSZSMK1	4	XSZSMK1	4	XSZSMK1
	2 or 4	XSZSMK2			2 or 4	XSZSMK2		
4	4	XSZSMK	2	XSZSMK	4	XSZSMK	2	XSZSMK
	4	XSZSMK1	4	XSZSMK1	4	XSZSMK1	4	XSZSMK1
	2	XSZSMK2			2 or 4	XSZSMK2		

(1) Low frequency, high amplitude applications, such as punching presses, where a powerful shock can exist.
(2) High frequency, low amplitude applications, such as offset printing machines, where constant vibration can exist.
(3) Head: transmitter, receiver, or mirror.

Shock absorber specifications

Specifications per shock absorber		Compression mounted: Maximum load lb (kg)	Torque lb•in (N•m)	Natural frequency Hz	Shear mounted: Maximum load lb (kg)	Torque lb•in (N•m)	Natural frequency Hz
For anti-vibration kit	**XSZSMK**	18.0 (8.16)	222.5 (25.16)	11	3.0 (1.36)	27.7 (3.13)	9.5
	XSZSMK1	4.8 (2.177)	96.1 (10.86)	14	2.5 (1.13)	20.7 (2.34)	9
	XSZSMK2	55.0 (24.94)	949.7 (107.39)	13	23.0 (10.43)	132.2 (14.94)	7.5

References of anti-vibration kits



XSZSMK•



XUSLZ227

Description	For use with	References	Weight lb (kg)
Anti-vibration kit consisting of 8 shock absorbers, stud mounting. 16 washers and 16 nuts included with kit.	All light curtain types and 90° mirror adapters	**XSZSMK**	0.07 (0.030)
		XSZSMK1	0.04 (0.020)
		XSZSMK2	0.1 (0.045)
Mounting kit for XUSLN (2 brackets)	Anti-vibration kit	**XUSLZ227**	1.0 (0.450)

Specifications: page 5/42
References: page 5/42
Dimensions: page 5/45

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Mounting base for light curtains and mirrors			**XUSZC●●●●**
Environmental specifications			
Ambient air temperature	Operating	**°F (°C)**	–13 to +158 (–25 to +70)
	Storage	**°F (°C)**	–13 to +158 (–25 to +70)
Materials			Mounting base: steel End protection: black polycarbonate, 20% fiberglass

References



XUSZC●●●●

Mounting bases

Designation	For use with			Protected height	Catalog number	Weight
	Light curtains Height	Mirrors Height	IP67 tube Height			
	in. (mm)	in. (mm)	in. (mm)	in. (mm)		lb (kg)
Mounting base XUSZC●●●●	5.9 –35.4 (150–900)	7.2 –35.2 (182–894)	19.8 –38.6 (503–981)	47.2 (1200)	**XUSZC1200**	25 (11.340)
	36.2 –59.1 (920–1500)	39.2 –59.2 (995–1503)	43.4 –63.8 (1102–1620)	70.9 (1800)	**XUSZC1800**	35 (15.880)
	59.8 –70.9 (1520–1800)	63.2 –67.2 (1605–1706)	68.5 –76.3 (1740–1939)	82.7 (2100)	**XUSZC2100**	45 (20.410)
	75.6 –82.5 (1920–2095)	75.2 (1910)	79.6 –84.3 (2021–2141)	94.5 (2400)	**XUSZC2400**	60 (27.220)
	–	88.2 (2240)	92 (2336)	122 (3100)	**XUSZC3100**	66 (29.940)

Accessories

Description	For use with	Catalog number	Weight lb (kg)
Mounting kit (sold in lots of 2)	Mounting base XUSZC●●●●	**XUSZCA**	1.0 (0.450)
Floor mounting kit Consisting of: 4 bolts, 4 rawplugs, 12 washers, 8 standard nuts, 4 lock nuts, 4 rubber insulators, 4 spacers (tube)	Mounting base XUSZC●●●●	**XUSZCB**	1.0 (0.450)

5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Accessories for safety light curtains types 2 and 4

90° mirror adapters + Mounting clamps

XUSZM●●●●/XUSZA●●●●



XUS Glass	Stainless steel	b in. (mm)	H in. (mm)
ZM0102	ZA102	5.5 (140)	0.7 (182)
ZM0152	ZA152	7.5 (191)	9.2 (233)
ZM0305	ZA0305	13.5 (343)	15.2 (386)
ZM0457	ZA0457	19.5 (495)	21.2 (538)
ZM0508	ZA0508	21.5 (546)	23.2 (589)
ZM0610	ZA0610	25.5 (648)	27.2 (690)
ZM0711	ZA0711	29.5 (749)	31.2 (792)
ZM0762	ZA0762	31.5 (800)	33.2 (843)
ZM0813	ZA0813	33.5 (851)	35.2 (894)
ZM0914	ZA0914	37.5 (953)	39.2 (995)
ZM1016	ZA1016	41.5 (1054)	43.2 (1097)
ZM1067	ZA1067	43.5 (1105)	45.2 (1148)
ZM1219	ZA1219	49.5 (1257)	51.2 (1300)
ZM1321	ZA1321	53.5 (1359)	55.2 (1402)
ZM1372	ZA1372	55.5 (1410)	57.2 (1452)
ZM1422	ZA1422	57.5 (1461)	59.2 (1503)
ZM1524	ZA1524	61.5 (1562)	63.2 (1605)
ZM1626	ZA1626	65.5 (1664)	67.2 (1706)
ZM1830	ZA1830	73.5 (1867)	75.2 (1910)
ZM2134	ZA2134	85.5 (2172)	87.2 (2214)

Mounting clamp (quantity 2)



Dual Dimensions: Inches / Millimieters

Protective cover

XUSZW●●● for XUL B/D



XUS	b in. (mm)
LZWB0280	12.2 (310)
LZWB0320	13.8 (350)
LZWB0360	15.4 (390)
LZWB0440	18.5 (470)
LZWB0520	21.7 (550)
LZWB0600	24.8 (630)
LZWB0680	28 (710)
LZWB0720	29.5 (750)
LZWB0760	31.1 (790)
LZWB0880	35.8 (910)
LZWB0920	37.4 (950)
LZWB0960	39 (990)
LZWB1040	42.1 (1070)
LZWB1120	45.3 (1150)
LZWB1200	48.4 (1230)
LZWB1360	54.7 (1390)
LZWB1400	56.3 (1430)
LZWB1520	61 (1550)
LZWB1560	62.6 (1590)
LZWB1640	65.7 (1670)
LZWB1720	68.9 (1750)
LZWB1800	72 (1830)
LZWB1920	76.8 (1950)
LZWB2120	84.6 (2150)

XUSZWSP for XUSLP



Specifications: pages 5/40 and 5/41
References: pages 5/40 and 5/41
Dimensions: page 5/44

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Anti-vibration kits *(1)*

XSZSMK



XSZSMK1



XSZSMK2



(1) The anti-vibration kit consists of 8 shock absorbers, 16 washers, and 16 nuts.

Mounting brackets for anti-vibration kit

XUSLZ227 and XUSLN



Dual Dimensions: Inches / Millimeters

(1) 2 elongated holes Ø0.2 x 0.7 in. (Ø5.10 x 16.75 mm).
(2) 1 elongated hole Ø0.3 x 0.7 in (Ø6.75 x 16.75 mm).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Mounting base
XUSZC●●●●





XUS	b in. (mm)
ZC1200	47.3 (1200)
ZC1800	70.9 (1800)
ZC2100	82.7 (2100)
ZC2400	94.5 (2400)
ZC3100	122 (3100)

Floor mounting kit (quantity 4) for mounting base XUSZC●●●●
XUSZCB

Scale 2.5



1 Bolt
2 1 lock nut
3 3 washers
4 Rubber insulator
5 Spacer (tube)
6 2 standard nuts
7 Rawplug

Dual Dimensions: Inches / Millimieters

5

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Dimensions

ABL8RPS24●●●
common side view



ABL8	a in. (mm)	b in. (mm)
RPS24030	4.7 (120)	1.7 (44)
RPS24050	4.7 (120)	2.2 (56)
RPS24100	5.5 (140)	3.3 (85)

Dual Dimensions: Inches
Millimieters

Internal wiring diagrams

ABL8RPS24030



ABL8RPS24050



ABL8RPS24100



5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ XPSCM safety modules and XU2S single-beam photoelectric sensors

With a test input associated with a built-in “muting” function

Operating principle

XPSCM safety relay modules, when combined with XU2S single-beam photoelectric sensors (periodically tested), form a category 2 light curtain conforming to standards IEC/EN 61496 parts 1 and 2 and EN 60825-1.
The connection of 1–4 pairs of XU2S photoelectric sensors makes it possible to create a protected space up to 47.2 in. (1200 mm) high, conforming to EN 999/ ISO 13855, and 26.2 ft (8 m) long.

The built-in “muting” function allows the automatic passage of parts for machining or loaded pallets, without interrupting the transportation movement within the zone protected by the electro-sensitive protection equipment (ESPE).
When the system is switched on by the start command, and the light protection is not interrupted, the main circuit is closed by the two safety relays of the XPSCM module.

An interruption of the protection field causes the safety outputs to open instantaneously, and the process PLC receives a stop command. The LED on the XPSCM front panel changes from green to red. The Open state is maintained until the module is restarted using the start button.

The “muting” function allows the light protection to be inhibited (muted). This function allows a trolley transporting materials to pass through without triggering the main circuit. The Muting function cannot be activated by energizing the inhibition devices unless the safety outputs have been switched on beforehand.

To trigger the “muting” function, the inhibition devices (muting sensors) must be activated within the 3-second interval. This synchronization time for the two inhibition inputs can be deactivated by connecting two configuration terminals. The muting cycle has a maximum duration of 60 seconds. During this period, materials can be transported through the protection field without deactivating the safety outputs. The 60 second limit value of the muting cycle may be made infinite by connecting two configuration terminals.

During the muting operation process, a light indicating the muting state is controlled by the XPSCM module. The indicator light comes on when a muting signal is generated, and indicates the inhibition of the protection function. An indicator light error (short-circuit, open-circuit) will be recognized, and will deactivate the Muting function.



D1, D2, D3, D4: monitoring photoelectric sensors
MA1, MB1, MA2, MB2: muting photoelectric sensors
m = trolley length
dM = distance between MA1/MB1 and MA2/MB2

Conditions to be observed for the “muting” function

- “Muting” sensors must be of the XU2 M18PP340 thru-beam or XU9 M18PP340 polarized reflex type, or mechanical limit switches with contacts.
- *dM* ≤ *m* to obtain continuous validation of the Muting function.
- Avoid the intrusion of persons during the muting phase. This phase is indicated by an indicator light connected to the muting indicator output of the XPSCM module.
- A materials transportation trolley (i.e.: AGV) must generate the muting signal before it enters the protection field, and discontinue the muting signal on exiting once it has cleared all the sensors of the protection field.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ XPSCM safety modules and XU2S single-beam photoelectric sensors

With a test input associated with a built-in “muting” function

Specifications of safety modules

Module type			XPSCM1144	XPSCM1144P
Maximum achievable safety level *(1)*			PL c/Category 2 conforming to EN/ISO 13849-1, SILCL 1 conforming to EN/IEC 62061	
Reliability data	Mean Time To dangerous failure ($MTTF_d$)	**Years**	16.6	
	Diagnostic Coverage (DC)	**%**	95.5	
	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	3.12×10^{-7}	
Conformity to standards			EN/IEC 61496-1, EN/IEC 61496-2, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1,	
Product certifications			UL, CSA, IFA	
Ambient air temperature		**°F (°C)**	Operation: +14 to +131 (-10 to +55). Storage: –13 to +185 (–25 to +85)	
Degree of protection conforming to IEC 529			Terminals: IP 20, enclosure: IP 40	
Supply voltage		**V**	⎓ 24, voltage limits: ±20%	
Maximum power consumption		**W**	< 15, with thru-beam photoelectric sensors and muting signaling	
Module fuse protection			Internal, electronic	
Rated insulation voltage (Ui)		**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 and 2)	
Rated impulse withstand voltage (Uimp)		**kV**	4 (overvoltage category 3, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 and 2)	
Inputs for sensors	Number of inputs to be monitored		4 (terminals Z1, Z2, Z3, Z4)	
	Input voltage	**V**	⎓ 24	
	Supply voltage of sensors	**V**	⎓ 24 (terminal U+/U-)	
	Supply current of sensors	**mA**	< 200	
Inputs for the Muting function	Number of muting inputs		2 (terminals MA, MB)	
	Input voltage	**V**	⎓ 24 (terminal U+/U-)	
	Maximum current	**mA**	< 200	
	Synchronization time for the activation of the MA/MB muting signal	**s**	3 (±20%) for activation of the MA/MB “muting” signal	
	Muting maximum duration	**s**	60 (–10 to +30%)	
Single-beam thru-beam photoelectric sensors for input monitoring Z1-Z2-Z3-Z4 -sensors authorized for the protection field (max. 4)			XU2S18PP340●●● (infrared)	
-muting sensors			XU2 M18PP340●●● or XU9 M18PP340●●● photoelectric sensors or XC limit switches	
-sensor supply resistivity		Ω	10 max.	
Safety outputs -number and type			2 N.O. (terminals 13-14, 23-24), hard contacts	
-solid-state output breaking capacity			4 N.O. 24 V/20 mA, (Y33-Y34, Y33-Y44, Y33-Y54, Y33-Y64)	
-breaking capacity in AC-15		**VA**	C300: inrush 1800, maintained 180	
-breaking capacity in DC-13			24 V/1.5 A, L/R = 50 ms	
-maximum thermal current (Ithe)		**A**	5.6	
-sum of maximum thermal current		**A**	11	
-minimum current (volt-free contact)		**mA**	10	
-minimum voltage (volt-free contact)		**V**	17	
-short-circuit protection		**A**	4 gG or 6 fast-acting fuse cartridge, conforming to EN/IEC 60947-5-1 and DIN VDE 0660 part 200	
Muting signaling sensors for incandescent lamp			Number 1 (terminal H1), maximum power: 6.5 W/⎓ 24 V, minimum power: 4 W/⎓ 24 V	
Response time on input change of state		**ms**	< 25	
Electrical life			See page 2/172 of the *Machine Safety Products* catalog, MKTED208051EN-US.	
Display			4 LEDs	
Connection	Type		Captive screw clamp terminals	Captive screw clamp terminals, separate, removable terminal block
1-wire connection	Without cable ends		Solid or flexible cable: 26-14 AWG ($0.14 – 2.5\ mm^2$)	Solid or flexible cable: 24-14 AWG ($0.2 – 2.5\ mm^2$)
	With cable ends, without bezel		Flexible cable: 24-14 AWG ($0.25 – 2.5\ mm^2$)	Flexible cable: 24-14 AWG ($0.25 – 2.5\ mm^2$)
	With cable ends, with bezel		Flexible cable: 24-16 AWG ($0.25 – 1.5\ mm^2$)	Flexible cable: 24-14 AWG ($0.25 – 2.5\ mm^2$)
2-wire connection	Without cable ends		Solid or flexible cable: 26-18 AWG ($0.14 – 0.75\ mm^2$)	Solid cable: 24-18 AWG ($0.2 – 1.0\ mm^2$), Flexible cable: 24-16 AWG ($0.2 – 1.5\ mm^2$)
	With cable ends, without bezel		Flexible cable: 24-18 AWG ($0.25 – 1.0\ mm^2$)	Flexible cable: 24-18 AWG ($0.25 – 1.0\ mm^2$)
	With cable ends, double with bezel		Flexible cable: 22-14 AWG ($0.5 – 1.5\ mm^2$)	Flexible cable: 22-14 AWG ($0.5 – 1.5\ mm^2$)

(1) Using an appropriate and correctly connected control system.

5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Specifications of photoelectric sensors

Conformity to standards			IEC 61496-1 and IEC 61496-2 (Type 2 ESPE)
Maximum safety level *(1)*			PL=c/category 2 conforming to EN/ISO 13849-1
Reliability data	Probability of dangerous Failure per Hour (PFH_d)	**1/h**	PFH_d=4.6E^{-7} conforming to EN/IEC 61508 PFH_d=5.5E^{-7} conforming to EN/IEC 61508, with “muting” function
Ambient air temperature		**°F (°C)**	Operation: –13 to +131 (–25 to +55) (infrared transmission sensors), Storage: –40 to +158 (–40 to +70)
Vibration resistance			7 gn (10–55 Hz), conforming to EN/IEC 60068-2-6
Shock resistance			30 gn, 3 axes: 3 times, conforming to EN/IEC 60068-2-27
Degree of protection			IP 67 conforming to EN/IEC 60529
Connection	Pre-cabled		PVC cable, diameter 0.20 in. (5 mm), 16.4 ft (5 m) long wire: 4 x 22 AWG (0.34 mm²) for thru-beam transmitter
	Connector		M12 male connector, 4-pin (suitable jumper cables and female connectors M12, 4-contact. See the "Machine Cabling" section.)
Materials			Case: nickel-plated brass (infrared transmission sensors). Lenses: PMMA
Nominal sensing distance		**ft (m)**	26.2 (8) (infrared transmission sensors)
Rated supply voltage		**V**	⎓ 12–24 (with protection against reverse polarity)
Voltage limits		**V**	⎓ 10–30 V (including ripple)
Switching capacity (sealed)		**mA**	≤ 100 mA (with overload and short-circuit protection)
Voltage drop, closed state		**V**	≤ 1.5
Current power consumption, no-load		**mA**	≤ 35
Maximum switching frequency		**Hz**	500
Delays		**ms**	Response: ≤ 1; recovery: ≤ 1

(1) Using an appropriate and correctly connected control system.

5

***XPS**CM1144●*

Safety modules

Description	Type of terminal block connection	Number of safety circuits	Additional outputs	Supply	References	Weight oz (kg)
Safety modules for monitoring single-beam photoelectric sensors, with a test input associated with a built-in “muting” function	Integrated in module	2	4	⎓ 24 V	**XPSCM1144**	12.35 (0.350)
	Separate, can be removed from module	2	4	⎓ 24 V	**XPSCM1144P**	12.35 (0.350)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ XPSCM safety modules and XU2S single-beam photoelectric sensors

With a test input associated with a built-in “muting” function

XU2S18●P340L5

XU2S18●P340WL5

XU2S18KP340L5T

XU2S18KP340WL5T

XU2S18PP340DR

XU2S18PP340WL5R

Single-beam photoelectric sensors with a test input

Description	Transmission type	Line of sight	Connection	References	Weight oz (kg)
PNP thru-beam pair (transmitter + receiver) Light or dark programmable switching	Infrared Sensing distance: 26.2 ft (8 m)	Along case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18PP340L5**	17.11 (0.485)
			M12 connector	**XU2S18PP340D**	5.47 (0.155)
		90° to case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18PP340WL5**	17.11 (0.485)
			M12 connector	**XU2S18PP340WD**	5.47 (0.155)
Thru-beam transmitter alone (for XPSCM1144●)	Infrared	Along case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18KP340L5T**	8.29 (0.235)
			M12 connector	**XU2S18KP340DT**	2.65 (0.075)
		90° to case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18KP340WL5T**	8.29 (0.235)
			M12 connector	**XU2S18KP340WDT**	5.47 (0.155)
PNP thru-beam receiver alone (for XPSCM1144●)	Infrared	Along case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18PP340L5R**	8.82 (0.250)
			M12 connector	**XU2S18PP340DR**	2.82 (0.080)
		90° to case axis	Pre-cabled 16.4 ft (5 m)	**XU2S18PP340WL5R**	8.82 (0.250)
			M12 connector	**XU2S18PP340WDR**	2.82 (0.080)

5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ XPSCM safety modules and XU2S single-beam photoelectric sensors

With a test input associated with a built-in “muting” function

Functional diagram of XPSCM module



Functional diagram of the XPSCM module with “muting” function



Key to LEDs



1 A1-A2 supply voltage, electronic internal fuse status (Green)
2 Signaling for restarting (Yellow)
3 Safety output closed (Green)
4 Safety output open (Red)

Principle: page 5/48
Specifications: page 5/49
References: page 5/50
Dimensions: page 5/53
Wiring diagrams: page 5/53

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ XPSCM safety modules and XU2S single-beam photoelectric sensors

With a test input associated with a built-in “muting” function

Operation

	Light switching		Dark switching	
	No object in beam	Object in beam	No object in beam	Object in beam
Output state (PNP) indicator, yellow LED (illuminated when sensor output is on)				

Curves

Infrared detection curve



Functional check



Dimensions

XU2S18PP340L5, XU2S18PP340L5L



(1) LED

(2) Potentiometer

XU2S18PP340D



Mounting nut tightening torque: 17.7 lb-ft (24 N•m)

Connector tightening torque: 1.5 lb-ft (2 N•m)

XU2S18PP340WL5



(1) LED

(2) Potentiometer

XU2S18PP340WD



Dual Dimensions: Inches / Millimeters

Mounting nut tightening torque: 17.7 lb-ft (24 N•m)

Connector tightening torque: 1.5 lb-ft (2 N•m)

Wiring diagrams (3-wire ⎓)

Cable connection

Transmitter



Receiver

Light switching (no object present). PNP output



Receiver

Dark switching (no object present). PNP output



Plug-in connector

Transmitter



Receiver

Light switching (no object present). PNP output



Receiver

Dark switching (no object present). PNP output



Cable connections

(–)	BU	(Blue)
(+)	BN	(Brown)
(OUT)	BK	(Black) (receiver)
(Prog.)	OG	(Orange) (receiver)
(Test)	VI	(Violet) (transmitter)

Connector diagrams

Sensor connector pin view

Transmitter Receiver



Beam break test (for transmitter only)

Beam made Beam broken



Principle: page 5/48 | Specifications: page 5/49 | References: page 5/50 | Dimensions: page 5/53 | Wiring diagrams: page 5/53

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ XPSCM safety modules and XU2S single-beam photoelectric sensors

With a test input associated with a built-in “muting” function

Wiring diagrams (continued)

Connection of XPSCM module with 4 pairs of XU2S single-beam sensors

(Connection of 1 to 4 pairs of XU2 S single-beam sensors to XPS CM, see page 5/55)



XU2S sensors can be programmed for light switching or dark switching (dark switching with sensors 1 and 3 and light switching with sensors 2 and 4, for example).
ESC: external start conditions
Y1-Y2: feedback loop.
STM: for stopping time measurement.

(1) Protection field sensors

(2) Muting sensors

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety detection solutions

Preventa™ XPSCM safety modules and XU2S single-beam photoelectric sensors

With a test input associated with a built-in “muting” function

Wiring diagrams (continued)

Connection of XPSCM module with 1 pair of XU2S sensors

(dark switching)



Connection of XPSCM module with 2 pairs of XU2S sensors

(dark switching)



Connection of XPSCM module with 3 pairs of XU2S sensors

(2 for dark switching, 1 for light switching)



Connection of XPSCM module with 4 pairs of XU2S sensors

(2 for dark switching, 2 for light switching)



5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety relay modules type XPSLCD

For monitoring 2 to 4 light curtains types 2 and 4

Operating principle

The safety monitoring module XPSLCD1141 enables independent monitoring of 2 to 4 light curtains type 2 and type 4.
Each output of the light curtain is separately connected to the inputs of the safety monitoring module, which either authorises or prevents activation of its two safety outputs.
The module manages starting and EMD/MPCE functions and therefore, the light curtains connected to it must be configured for automatic start and the EDM/MPCE function deactivated. The safety monitoring module XPSLCD1141 provides the supply and also manages, in addition to its own auxiliary outputs (1 PNP and 1 NPN), the auxiliary outputs of the light curtains.
At the slightest intrusion through one or more light beams of any of the light curtains, the outputs of the safety monitoring module open. This also applies in the event of any internal fault or output relay(s) fault (subject to the EDM/MPCE configuration on the module).
The light curtain system conforms to the standard EN/IEC 61496-1 (type 4).
The Preventa™ safety monitoring module XPSLCD1141 incorporates removable terminal blocks, thus optimizing machine maintenance.
To aid diagnostics, the safety monitoring module has 9 LEDs and a 2-digit display on the front cover which provide information on the monitoring circuit status.

Environmental specifications

Safety monitoring module type			**XPSLCD1141**
Maximum achievable safety level *(1)*			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Conformity to standards			EN/IEC 61496-1, EN/IEC 61496-2, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1
Certifications			CE, TÜV, CSA, UL
Ambient air temperature		**°F (°C)**	Operation: 0…+ 55; storage: - 25…+ 75
Relative humidity			95% maximum, without condensation
Degree of protection			IP 20
Shock and vibration resistance	Conforming to EN/IEC 61496-1		Shock resistance: 10 gn, impulse 16 ms. Vibration resistance: 5…55 Hz max. on all 3 axes
Materials			ABS thermoplastic enclosure
Mounting			35 mm rail

Electrical specifications

Power supply		**V**	⎓ 24 ± 10%
Current		**A**	10 max.
Response time		**ms**	< 1
Safety outputs			2 solid-state PNP outputs (N.O.), 625 mA on ⎓ 24 V
Alarm or auxiliary output			1 solid-state PNP (N.O.), 500 mA on ⎓ 24 V, and 1 solid-state NPN (N.O.),100 mA on ⎓ 24 V, output
Monitoring activation of output switching devices (EDM/MPCE)		**mA**	50 ± 20% on ⎓ 24 V
Signalling			9 LEDs plus 2-digit display
Functions			- Auto/Manual, manual 1st cycle, - Monitoring of external switching devices (EDM: External Devices Monitoring), - Restart request indicator light, - Display of operating modes and alarm by 9 LEDs and 2-digit display. Selection of Auto/Manual, blanking relay monitoring, floating/blanking and blanking + floating/ blanking relay monitoring using configuration switches behind front cover of module. - Independent monitoring of 2 to 4 light curtains.
Monitoring of external switching devices (EDM = External Devices Monitoring)			Monitoring of the function (open or closed) as well as the response time of the power components. Selectable by using configuration switches.
Start input		**mA**	50 at 24 V
Connection	Type		Captive screw clamp terminals, removable terminal block
1-wire connection	Without cable end		Solid cable: 14 AWG (1.63 mm²)
	Without cable end		Flexible cable: 26-16 AWG (0.14...1.5 mm²)
	With cable end		Without bezel, flexible cable: 26-16 AWG (0.14…1.5 mm²)
2-wire connection	Without cable end		Solid cable: 26-16 AWG (0.14...1.5 mm²)
	Without cable end		Flexible cable: 26-16 AWG (0.14...1.5 mm²)

(1) Using an appropriate and correctly connected control system.

Principle: page 5/56 | Specifications: page 5/56 | References: page 5/57 | Dimensions: page 5/57 | Wiring diagrams: page 5/58

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety relay modules type XPSLCD

For monitoring 2 to 4 light curtains types 2 and 4

References

XPSLCD1141

Description	Type of terminal block connection	Number of safety circuits	Additional outputs	Supply	References	Weight
				V		oz (kg)
Safety module for monitoring 2 to 4 light curtains type 2 and type 4	Removable from module	2 PNP	5 (4 PNP + 1 PNP or NPN)	⎓ 24 V	**XPSLCD1141**	26.455 (0.750)

Dimensions

Safety monitoring module

XPSLCD1141

Mounting on 35 mm rail



Rear view



(1) 2 elongated holes Ø 4 x 5.7.

LED details

The safety monitoring module XPSLCD has 9 LEDs and a 2-digit display on the front cover.



Dual Dimensions: INCHES Millimeters

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety relay modules type XPSLCD

For monitoring 2 to 4 light curtains types 2 and 4

Connection via the safety monitoring module XPSLCD1141

Example: configuration with light curtains XUSLB/XUSLDM, XUSLP and XUSLN



(1) Arc suppressor.
(2) Restart request indicator light.
(3) When module XPSLCD1141 is used with a type 2 light curtain (example: XUSLN), the entire protection system is downgraded to category 2.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Functional diagram of module XPSLCD1141

Automatic start and restart mode



Manual start and restart mode



(1) Start button.

Principle: page 5/56 | Specifications: page 5/56 | References: page 5/57 | Dimensions: page 5/57 | Wiring diagrams: page 5/58

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety monitoring module XPSLCM

For “muting” function of light curtains types 2 and 4

Operating principle

Safety modules XPSLCM are used with type 4 light curtains conforming to EN/IEC 61496-1 to provide a system inhibiting the light curtain protection, i.e. “muting”. This function enables the automatic passage of parts for machining or loaded pallets, without interrupting the transportation movement within the zone protected by the electro-sensitive protection equipment (ESPE) system. In addition to the electro-sensitive protection and safety relay modules XPSLCM, the system consists of 4 to 8 inhibition sensors, 2 indicator lights and a key switch to reset the system to the initial state in the event of a sequence error.

When the system is switched on by the start command and the light curtain protection not interrupted, the main circuit is closed by the safety outputs of the XPSLCM modules (solid-state safety outputs). In addition to safety outputs, the modules incorporate signalling outputs for sending system status information to the PLC. Either 5 or 14 LEDs and a 2-digit display, mounted on the front cover of the module, provide information on the safety circuit status.

An interruption of the protection field monitored by the electro-sensitive protection equipment causes instantaneous opening of the safety outputs; the process PLC receives a stop command and the LED display mounted on the front cover indicates the change of state of the safety circuits. The “open” state is maintained until the module is restarted using the Start button.

The “muting” function cannot be activated by supplying the inhibition sensors unless the safety outputs have been switched on beforehand. To trigger the “muting” function, the inhibition devices must be activated within the 3 second time interval. During the activated “muting” phase, materials can be transported through the protection field without deactivating the safety outputs. In the event of intrusion into the hazardous zone, a person cannot activate the inhibition sensors in the same way and the system stops.

During the muting operation process, a light indicating the muting state is controlled by the XPSLCM module. The indicator light comes on when a muting signal is generated, and indicates the inhibition of the protection function. An indicator light error (short-circuit, open-circuit) will be recognized, and will deactivate the Muting function.



ESPE: electro-sensitive protection equipment (light curtain).
A, B, D, C: “muting” sensors.
m: trolley length and dM = distance between A, B and D, C.

Conditions to be observed for the “muting” function

- The “muting” sensors must either be thru-beam type XUB0BPSNL2 + XUB0BKSNL2T, polarized reflex type XUB0BPSNL2 + XUCZ50 or mechanical limit switches with contacts.
- dM ≤ m to obtain continuous validation of the “muting” function.
- Avoid the intrusion of persons during the “muting” phase. This phase is indicated by the indicator light connected to the “muting” indicator output of the XPSLCM module.
- A materials trolley must provide the “muting” signal before entering the protection field and cease it once it has cleared all the sensors of the protection field on exiting.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety monitoring module XPSLCM

For “muting” function of light curtains types 2 and 4

Specifications

Module type			XPSLCM1150
Maximum achievable safety level *(1)*			PL e/Category 4 conforming to EN/ISO 13849-1, SILCL 3 conforming to EN/IEC 62061
Conformity to standards			EN/IEC 61496-1, EN/IEC 61496-2, EN/IEC 60204-1, EN/IEC 60947-1, EN/IEC 60947-5-1
Certifications			CE, TÜV, CSA, UL
Ambient air temperature	For operation	**°F (°C)**	0…+ 55
	For storage	**°F (°C)**	- 25…+ 75
Degree of protection conforming to IEC 529	Terminals		IP 20
	Enclosure		IP 20
Power supply	Voltage	**V**	⎓ 24
	Voltage limits		- 10…+ 10%
Maximum power consumption		**W**	< 150
Rated insulation voltage (Ui)		**V**	300 (degree of pollution 2 conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 and 2)
Rated impulse withstand voltage (Uimp)		**kV**	4 (overvoltage category III, conforming to EN/IEC 60947-5-1, DIN VDE 0110 parts 1 and 2)
Number of light curtains monitored			1 or 2 transmitter-receiver pairs
Inputs for “muting” sensors	Number of inputs to be monitored		2 to 4 per “muting” function
	Supply voltage of sensors	**V**	24
	Output current of each sensor	**mA**	< 20
Type of “muting” sensors			Thru-beam, polarised reflex or sensors with relay hard contacts
Synchronization time of “muting” sensors		**s**	3 or unlimited
Maximum “muting” time		**min**	2 or unlimited
Safety outputs			
- number and type			2 PNP (terminals 1 and 2), 0.625 A at 24 V
- max. thermal current (Ithe)	1 output	**A**	–
	2 outputs	**A**	2 x 0.108
	3 outputs	**A**	–
	3 contacts	**A**	–
Auxiliary outputs 1 PNP (terminal 5) + 1 NPN (terminal 6)	Breaking capacity of solid-state PNP outputs	**mA**	24 V/500
	Breaking capacity of solid-state NPN outputs	**mA**	24 V/100
“Muting” indicator light power		**W**	1 to 7 max.
Response time on input change of state		**ms**	1
Signalling			14 LEDs plus 2-digit display
Connection	Type		Captive screw clamp terminals, removable terminal block
1-wire connection	Without cable end		Solid cable: 14 AWG (1.63 mm²)
	Without cable end		Flexible cable: 26-16 AWG (0.14...1.5 mm²)
	With cable end		Without bezel, flexible cable: 26-16 AWG (0.14…1.5 mm²)
2-wire connection	Without cable end		Solid cable: 26-16 AWG (0.14...1.5 mm²)
	Without cable end		Flexible cable: 26-16 AWG (0.14...1.5 mm²)

(1) Using an appropriate and correctly connected control system.

5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety monitoring module XPSLCM

For “muting” function of light curtains types 2 and 4

XPSLCM1150

References

Safety module

Description	Type of terminal block connection	Number of safety circuits	Auxiliary outputs	Supply	References	Weight
						oz (kg)
Safety module for “muting” function	Removable from module	2 PNP	1 PNP + 1 NPN	⎓ 24 V	**XPSLCM1150**	23.281 (0.660)

Spare parts

Description	Power	References	Weight
	W		oz (kg)
“Muting” indicator light kit	5	**XSZCM01**	0.423 (0.012)
Replacement bulbs for “muting” indicator light kit consisting of one lot of 10 replacement bulbs and 1 removal/insertion tool XBF-X13	1 to 7	**XSZCM02**	0.564 (0.016)

LED details

XPSLCM1150

To aid diagnostics, the safety monitoring module has 14 LEDs and a 2-digit display on the front cover which provide information on the monitoring circuit status.



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety automation system solutions

Preventa™ safety monitoring module XPSLCM

For “muting” function of light curtains types 2 and 4

Dimensions

XPSLCM1150

Mounting on 35 mm rail





Rear view



(1) 2 elongated holes Ø 4 x 5.7

“Muting” indicator light kit XSZCM01



(1) Faston connector 4.7.

Dual Dimensions: INCHES / Millimeters

5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Connection via the safety monitoring module XPSLCM1150

Example: configuration with light curtains XUSLB/XUSLDM



(1) Arc suppressor.
(2) Inhibition activation/deactivation key switch.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Connection via the safety monitoring module XPSLCM1150

Example: configuration with 2 light curtains XUSLP and XUSLN



(1) Arc suppressor.
(2) Inhibition activation/deactivation key switch.
(3) When module XPSLCM1150 is used with a type 2 light curtain (example: XUSLN), the entire protection system is downgraded to category 2.

Principle: page 5/60 | Specifications: page 5/61 | References: page 5/62 | Dimensions: page 5/63 | Wiring diagrams: page 5/64

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Functional diagram of safety monitoring module XPSLCM1150

“Start/restart interlock” mode with 2 sensors



(1) Press Start button.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Functional diagram of safety monitoring module XPSLCM1150

“Start/restart interlock” mode with 4 sensors



(1) Press Start button.

5

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

Protection of personnel

Protection of Personnel

Safety light curtains are electro-sensitive protective equipment (ESPE) designed to help protect personnel operating or working around industrial machinery, by sending stop signals to the machine control to stop the hazardous movement as soon as one of the light beams is broken.

In particular, they help provide protection for personnel operating hazardous machinery, but they are equally suitable for use with many other types of machines. They make it possible to help protect personnel while allowing free access to machines.

The absence of a door or guard makes access easier and reduces the time required for loading, inspection, or adjustment operations.

Directives and Standards—These Safety Light Curtains Conform to:

- European Machinery Safety Directive 2006/42/EC and European Work Equipment Directive 89/655/EEC,
- Low Voltage Directives 73/23/EEC and 93/68/EEC and also, the Electromagnetic Compatibility Directive 89/336/EEC,
- Standard EN/IEC 61496-1, EN/IEC 61496-2 and IEC 61508 (only XUS LB, XUS LDM and XUS LDS) (electro-sensitive protection equipment: ESPE),
- Standard EN 60825 (emission power),
- Standard EN 999/ISO 13855 (installation conditions)
- These light curtains are UL, CSA and TÜV certified.

Applications—The Main Applications Are:

For Type 2 Light Curtains:

- Packaging and Assembly Plants
- Conveyor and Mechanical Handling Systems
- Warehousing and Storage Systems
- Waste Disposal Skips
- Robot Areas

For Type 4 Light Curtains

- Presses (all types), Shears and Trimmers
- Hoisting Equipment
- Saws (all types)
- Machine Tools (lathes, milling machines, machining centers)
- Woodworking Machines (truing, lathes, spindle molding machines, side and face milling cutters)
- Textile Machinery (carding machines, weaving looms, steam rooms)
- Assembly Machines
- Assembly Robots

Safety Requirements—Detection of Anomalies that May Jeopardize Machine Safety and Stopping

The machine design and its controls must have the same level of safety as that of the safety light curtain, to ensure that the machine is able to immediately stop its hazardous movement if something enters the zone protected by the safety light curtain.

It must be impossible to enter the protected zone without breaking the protective light beams. The safety light curtain must therefore be installed so that the light curtain cannot be avoided.

The restarting of the machine must only be possible when there is no hazard present and when there is no one in the hazardous zone.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

Standards and basic requirements

Safety Systems

Safety systems consist of many components. No one safety component will ensure the safety of the system. The design of the complete safety system should be considered before you begin. It is very important to follow applicable safety standards when installing and wiring these components.

Standards to be Followed—United States

Standards listed below refer to presses and other metal working and general equipment. This is not a complete listing of all applicable standards to be catalog numberd when using light curtains. There may be other OSHA, ANSI, ANSI/RIA, NEC, NFPA, national, state, and local codes that may include requirements for installation of light curtains on machinery.

- OSHA 1910.211
- OSHA 1910.212
- OSHA 1910.217
- ANSI B11.1
- ANSI B11.19
- ANSI B11.20
- ANSI/RIA R15.06

Directives and Standards to be Followed—Europe

Standards listed below refer to general machinery. This is not a complete listing of all applicable standards to be catalog numberd when using light curtains. There may be other European and local codes that may include requirements for installation of light curtains on machinery.

- (NF) E09-010
- DIN 31001
- BS 5304
- EN 294
- EN 811
- EN 999
- EN 954-1
- EN 61496-1

Light Curtains in the United States—Basic Requirements

- This device must be installed, set up, and serviced only by authorized personnel. ANSI defines Authorized Personnel in ANSI B30.2.
- The user must follow all applicable codes, standards, and regulations. Standards specifically catalog numberd in this document must be followed: ANSI B11.1 through B11.20, OSHA 29 CFR 1910 standards, and ANSI/RIA R15.06 standard. There may be other national and local standards that also must be followed.
- Do not alter or modify this equipment.
- Light curtains must be securely mounted to a rigid surface using the provided mounting brackets.
- The machine must be capable of stopping immediately at any place in its stroke after receiving a stop signal.
- Light curtains must not be used with single stroke (full revolution clutched) machinery.
- Read and understand the sections on Calculating Minimum Safety Distances of this catalog for important details regarding standards, spacings and safe operating distances, and stopping times before beginning installation.
- Light curtains must not be used as a lockout device to meet OSHA lock-out/tag-out requirements.
- Light curtains will not protect machine operators and other personnel from liquids, gases, chips, hot surfaces, and other debris from point of operation.
- Light curtains must be sized and installed so that the machine operator cannot reach over, under, or around the sensing field to reach the point of operation.
- Light curtains must be installed so that machine operators cannot position themselves between the hazardous area (pinch point) and the light curtain.
- Light curtains currently cannot be used as PSDI devices to initiate machine movement on mechanical power presses. For PSDI, refer to OSHA 29 CFR 1910.217 (h), the various appendices catalog numberd on PSDI, and OSHA mandatory regulations requiring third party approval.

  Using the light curtain to initiate a machine after an object is removed from the sensing area is called Presence Sensing Device Initiation (PSDI). Use of PSDI places additional requirements on the guarding and safety controls. It can restrict advanced light curtain features such as floating blanking and exact channel selection (ECS) blanking. Contact your local sales office for further information. Other sources of catalog numbers for PSDI include: ANSI RIA 15.06, OSHA 1910.217(h), and ANSI B11.2.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

Minimum safety distances

Minimum Safety Distance

Light Curtains in the United States (Vertical Mount)

The basic formulas for calculating minimum safety distances for light curtains mounted vertically are listed below. These formulas apply to ALL light curtains, including perimeter and point of operation light curtains. ANSI B11.1 is listed first, OSHA 29 CFR 1910.217 listed next.

ANSI B11.1:

This formula applies specifically to the guarding of mechanical power presses, but it is typically used for other applications as well.

$D_s = K \times (T_s + T_c + T_r + T_{bm}) + D_{pf}$

D_s = Minimum safe distance between the light curtain sensing area to the nearest point of operation potential hazard.

K = Hand speed constant of 63 in./s. This is the standard minimum accepted value for both ANSI and OSHA. ANSI recognizes that this constant may not be optimal, and that the user should consider all factors before deciding on the value of the K factor to use in the above formula.

T_s = Stop time of the machine (press), as measured from the final control element. It is measured at the maximum velocity of the press, usually at 90° of press rotation on the downstroke.

T_c = Response time of the control circuit to activate the braking system.

NOTE: T_s and T_c are usually measured as one value by a stop time measurement device.

T_r = Response time of the light curtain.

T_{bm} = Additional time allowed for the brake monitor to compensate for wear and variations in the stopping time. Brake monitors will stop the machine (press) when the stop time of the machinery exceeds a pre-set limit.

NOTE: If a brake monitor is not installed on the machine, a factor must be added to the measured stop time to include brake wear. Generally, brake monitors add approximately 20–25% additional stop time. To determine the actual factor to be used, contact the machine manufacturer.

D_{pf} = Penetration depth factor, to provide for possible penetration through the sensing field by fingers or hands before detection occurs. This value is determined by the Penetration Depth Factor Chart from ANSI B11.1 (see Penetration Depth Factor graph below). Alternately, the following ANSI formula can be used: $D_{pf} = 3.4 (S-0.276)$, where S = minimum object sensitivity.

Example: For devices with minimum object sensitivity of 0.55 in. (14 mm):

$D_{pf} = 3.4 \times (0.55-0.276) = 0.94$ in. (23.88 mm)

For devices with minimum object sensitivity of 1.18 in. (30 mm):

$D_{pf} = 3.4 \times (1.18-0.276) = 3.07$ in. (77.98 mm)

Penetration Depth Factor





Vertical Mount

A = Finger Protection 0.55 in. (14 mm) has a D_{pf} of 0.94 in. (23.88 mm)
B = Hand Protection 1.18 in. (30 mm) has a D_{pf} of 3.07 in. (77.98 mm)

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

Minimum safety distances *(continued)*

Minimum Safety Distance *(continued)*

OSHA: CFR 1910.217 (c)(3)(iii)(e)

This formula applies specifically to the guarding of mechanical power presses, but it is typically used for other applications as well.

D_s = 63 in./s x T_s

Where:

D_s = Minimum safety distance (inches)

63 in./s = hand speed constant

T_s = Stopping time of the press measured at approximately 90° position of the crankshaft rotation (seconds).

Stop time of the machine (press), as measured from the final control element. It is measured to determine worst case time and maximum velocity of the press, usually at 90° of press rotation on the downstroke.

In addition to the formula above, we recommend that OSHA 1910.217 Table O-10 be followed. Per OSHA, the table below shows the maximum width of openings allowed for a guard based on the distance from the guard (light curtain) to the point of operation hazard. The maximum width of opening in the table below corresponds to the minimum object sensitivity for a light curtain.

Example:

Using the formula: D_s = 63 in./s x T_s

if T_s = 0.10 sec

D_s = 63 in. X 0.10 = 6.3 in.

- For an XUSL light curtain with a minimum object sensitivity of 0.55 in.:
  - Using the example above, the separation distance from the point of operation hazard to the light curtain would be 6.3 in. plus a minimum distance (from table O-10) of 3.5 in., for a total separation distance of 9.8 in. The 3.5 in. was chosen from Table O-10 as the additional distance because the opening (minimum object sensitivity) is 0.55 in. Since 0.55 in. is larger than 0.50 in., the values for 0.50 in. cannot be used. Therefore the next larger opening, 0.625 in., must be used and the distance corresponding to the 0.625 in. opening is 3.5 in.
- For an XUSL light curtain with a minimum object sensitivity of 1.18 in.:
- Using the example above, the separation distance from the point of operation hazard to the light curtain would be 6.3 in. plus a minimum distance (from table O-10) of 7.5 in., for a total separation distance of 13.8 in.
- The 7.5 in. was chosen from Table O-10 as the additional distance because the opening (minimum object sensitivity) is 1.18 in. Since 1.18 in. is larger than 0.875 in., the values for 0.875 in. cannot be used. Therefore the next larger opening, 1.25, must be used, and the distance corresponding to the1.25 opening is 7.5 in.

NOTE: 3.5 in. = 89 mm, and 7.5 in. = 191 mm.

OSHA 1910.217 Table O-10

Distance of Opening from Point of Operation Hazard (in.)	Maximum Width of Opening (in.)
1/2 to1-1/2	1/4
1-1/2 to 2-1/2	3/8
2-1/2 to 3-1/2	1/2
3-1/2 to 5-1/2	5/8
5-1/2 to 6-1/2	3/4
6-1/2 to 7-1/2	7/8
7-1/2 to 12-1/2	1-1/4
12-1/2 to 15-1/2	1-1/2
15-1/2 to 17-1/2	1-7/8
17-1/2 to 31-1/2	2-1/8

NOTE: If the light curtain is to be used on machinery that will be standardized throughout North America and Europe, then all minimum distance formulas in "Calculating Minimum Safety Distances" on pages 5/70 through 5/75 must be calculated, and the largest separation distance must be used.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

Minimum safety distances *(continued)*

Light Curtains in Europe (Vertical Mount)—Minimum Safety Distance (XUSL multi-beam)

The minimum safety distance S must be calculated using the following General Formula:

$S \geq K (t_1 + t_2) + C$

- S = Minimum safety (separation) distance between the hazardous area and the light curtain.
- K = Accepted general approach speed of a body or parts of the body. Generally accepted values are: 78.7 in./s (2000 mm/s).
- t_1 = Response time of the light curtain in seconds. This is the total time from detection of a beam broken to the switching of the outputs of the light curtain.
- t_2 = The time (in seconds) needed to stop all hazardous movements of the machine. This information is provided by the machine manufacturer. It is the time between the stop instruction of the light curtain and the actual stop of the hazardous machine components.
- C = Additional safety distance. Generally accepted values are:
  0 in. (0 mm) for 0.55 in. (14 mm) minimum object sensitivity
  5.04 in. (128 mm) for 1.18 in. (30 mm) minimum object sensitivity



Vertical Mount

Using Individual Beam Sensors (XPSCM and XU2S Perimeter Light Curtain)

The formula above is modified from a security light curtain where the light beams are all mounted in the same enclosure. Typically, for a system with individual beam sensors, up to 4 photoelectric sensors are used.

General Formula: $S \geq K (t_1 + t_2) + C$

- S = Minimum safety (separation) distance between the hazardous area and the light curtain.
- K = Accepted general approach speed of a body or parts of the body. Generally accepted values are: 63 in./s (1600 mm/s).
- t_1 = Response time of the light curtain in seconds. This is the total time from detection of a broken beam to the switching of the outputs of the light curtain.
- t_2 = The time (in seconds) needed to stop all hazardous movements of the machine. This information is provided by the machine manufacturer. It is the time between the stop instruction of the light curtain and the actual stop of the hazardous machine components.
- C = Additional safety distance. Generally accepted values are:
  33.5 in. (850 mm) when using several individual photoelectric beams
  47.3 in. (1200 mm) when using a single photoelectric beam

Special Rules for Presses

The use of safety light curtains and mechanical guards on metal working presses is governed by specific standards and rules. The standards specify that only safety light curtains or mechanical guards must be used as safety devices so that, if a person enters the protective field while the dangerous movement is in progress, the machine stops as quickly as possible. “Quick stopping” means stopping of the ram before the operator can reach the hazardous zone, taking into account their speed of movement.

The continuous self-monitoring function of safety light curtains is essential for metal working press applications. If an anomaly occurs in the safety device, the potentially dangerous machine must be stopped automatically.

Once the protected zone is clear, the movement which was started and then interrupted by entry into the zone must not resume its normal travel, even after a Reset button has been pressed. Resetting must restart the movement from the beginning of the cycle. **The safety light curtain must only allow starting of a dangerous movement if its correct operation has been proved** (by pushing a test rod into the hazardous zone, or by means of an automatic device) and if a Reset button (start interlock) has been activated.

The safety distance S is calculated in a special way for:

- mechanical presses: refer to **EN 692**,
- hydraulic presses, pneumatic folding machines, shears, bending and shaping machines: refer to **EN 693**.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

Prevention of access to hazardous area

Prevention of access over the top of the light curtain



Without additional safety device: insufficient degree of protection



With additional device: light beams broken, the machine stops

Prevention of access from beneath the light curtain



Without additional safety device: insufficient degree of protection



With additional device: light beams broken, the machine stops

Prevention of access from the back of the light curtain



Without additional safety device: insufficient degree of protection



With additional device: light beams broken, the machine stops



Addition of solid protection to the light curtain when using channel selection

Prevention of Access to Hazardous Area

Security light curtains can only be used on machines on which the movement of working components may be s*topped at any time during the hazardous operation phase of the machine*.

These light curtains provide a stop signal, not a control instruction. This stop signal must be stored.

The clearing of the light curtain must not result in the restarting of moving parts or hazardous operation.

Subsequent restarting must only be possible by means of deliberate operation of the appropriate control device, or a start-up procedure after having checked that there is no longer any hazard.

Electrical interfacing between the security light curtain and the machine circuits must meet all applicable codes where the machine will be used.

Where security light curtains do not provide an adequate degree of protection due to their location, additional suitable safety devices, guards, or additional security light curtains must be used to prevent operators from entering the protective light curtain and reaching the hazardous zone (EN 294/ISO 13852, EN 811/ISO 13853), or from remaining in the area between the hazardous zone and the security light curtain (EN 999/ISO 13855).

The position and size of these additional safety devices must be such that it is *impossible for operators to reach the hazardous zone* in any way whatsoever (over the top, from beneath, from behind or from the side) *without breaking the beams of the light curtain*.

These additional safety devices must be:

- Either fixed
  (if possible, screwed or welded to the machine),
- Or moving
  (with continuous monitoring of their position if they have to open).

It must be impossible for operators to disconnect or turn off the switching circuits for these additional safety devices.

Protection for Blanking, Floating blanking or Monitored blanking functions

The Blanking (inhibition of light beams), Floating blanking (floating inhibition of light beams) or Monitored blanking (fixed and floating inhibition/disinhibition of light beams) functions create non protected areas in the detection field. These non-protected areas are required for some applications. If an obstruction does not completely fill these unprotected areas, one of two actions must be implemented:

- an increase of safety distance to take into account a larger opening in the light curtain,
- the area not filled by an obstruction must be guarded by a solid protection method (mechanical barrier: metal plate or unfolded structure).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

Alignment and mutual interference

Light Curtain Alignment

Light curtains need to be firmly and securely mounted to the machine. The diagrams below show correct and incorrect mounting. Incorrect mounting as shown below will not allow correct alignment.



Installation Near Reflective Surfaces

The devices must be installed such that the transmitter and associated receiver are mounted facing each other and correctly aligned for both height and angle.

The effective aperture angle of the optics and transmitter/receiver alignment is 2.5° maximum > 3 m (9.8 ft).

Reflective surfaces located near areas protected by light curtains could interfere with the proper operation of the light curtain. Reflective surfaces may include painted metal, shiny sheet metal, stainless steel, or plastic. These reflective surfaces may allow unwanted stray light rays to “go around” objects entering the sensing area of the light curtain. It is necessary to take into account a minimum distance D between the axes of the nearest beam and the reflective surface. This distance is measured from the mid-point between the transmitter and receiver.

European Standards EN 50100-1 and 2 and EN/IEC 61496-1 specify a minimum distance D where:

for 0 < L < 9.84 ft (3 m), D = 5.16 in. (131 mm)

for L > 9.84 ft (3 m), D = (0.035 x L) + 0.2 in. (5 mm), with a minimum value for D of 5.16 in. (131 mm)

D = minimum distance between the light curtain and reflective surface

L = sensing distance of the security light curtain.





Mutual Interference

Certain configurations may require the installation of 2 (or more) security light curtains side by side.

The products in the XUSL range are designed to provide maximum operating safety (coded infrared light beams).

Setup as illustrated to the left is recommended for maximum performance and safety.

Environments Subject to Interference

Industrial applications sometimes place products in extreme operating conditions, due in particular to:

- Electromagnetic interference generated by the close proximity of variable speed controllers, welding machines or walkie-talkies. The products in the XUSL range are designed to be immune to such interference. They conform to:
  - level 3 conforming to EN 61496-1 (fast transient/burst interference)
  - resistance to interference caused by variable speed controllers
- Light interference at a low angle of incidence in relation to the optical axis. The products in the XUSL range are resistant in accordance with IEC 61496-2

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

Using mirrors

Using Mirrors

It is important to comply with the minimum safety distances throughout the protected area, and around the perimeter where the light curtain beams are being reflected by the mirrors. The distances relating to reflective surfaces must also be calculated and observed.

The use of mirrors will significantly reduce the sensing distance of any light curtain. Each mirror used will further reduce the sensing distance.

Reminder: any contamination on the mirror surfaces, such as dust or dirt, will further reduce the sensing distance. This should be considered when installing a light curtain with mirrors in an area where there will be dust, dirt, or other contaminants. More frequent cleaning of the light curtain lenses and the mirrors may be required.

Mirror Configurations



The total nominal range between the transmitter (XUSL•T) and the receiver (XUSL•R) will be reduced according to the number of deflecting mirrors.

Recommended Maximum Range for Glass Mirrors—XUSLB/XUSLD

No. of Mirrors	XUSLB/XUSLDM Range			
	3 m (9.84 ft)	7 m (21.34 ft)	8 m (26.25 ft)	20 m (60.96 ft)
1	2.6 m (8.66 ft)	6.2 m (18.78 ft)	7.0 m (23.50 ft)	17.6 m (53.64 ft)
2	2.3 m (7.61 ft)	5.4 m (16.52 ft)	6.2 m (20.30 ft)	15.4 m (46.94 ft)
3	2.0 m (6.69 ft)	4.8 m (14.54 ft)	5.5 m (17.90 ft)	13.6 m (41.45 ft)
4	1.8 m (5.91 ft)	4.2 m (12.80 ft)	4.8 m (15.75 ft)	12 0 m (36.58 ft)

Recommended Maximum Range for Stainless Steel Mirrors—XUSLB/XUSLD

No. of Mirrors	XUSLB/XUSLDM Range			
	3 m (9.84 ft)	7 m (21.34 ft)	8 m (26.25 ft)	20 m (60.96 ft)
1	2.5 m (8.07 ft)	5.7 m (17.50 ft)	6.6 m (21.50 ft)	16.4 m (49.99 ft)
2	2.0 m (6.63 ft)	4.7 m (14.35 ft)	5.4 m (17.60 ft)	13.4 m (40.84 ft)
3	1.7 m (5.41 ft)	3.9 m (11.76 ft)	4.9 m (14.50 ft)	11.0 m (33.53 ft)
4	1.4 m (4.46 ft)	3.2 m (9.65 ft)	3.6 m (11.90 ft)	9.0 m (23.43 ft)

Note: When mirrors are used, the effects of vibration will be more noticeable. Proper alignment may require more time in the setup of the light curtain and the associated mirrors. The mirrors must be firmly and securely mounted and be protected from shock, vibration, and other physical damage.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

MOS and protected height



Minimum Object Sensitivity (MOS)

This is the smallest object diameter which a Type 4 security light curtain is capable of detecting.

d = P + e

d: minimum object sensitivity

P: distance between the axes of 2 adjacent beams

e: diameter of the beams

XUSL range	P in. (mm)	e in. (mm)	d in. (mm)
Finger protection	0.39 in. (10 mm)	0.13 in. (3.3 mm)	0.55 in. (14 mm)
Hand protection	0.79 in. (20 mm)	0.35 in. (9 mm)	1.18 in. (30 mm)



Protected Height (HP)

According to EN 50100-2, this is the zone (or height) within which an object of equal diameter to the minimum object sensitivity **d** is always detected.

Test Rod

A test rod is included with each XUSL light curtain for the purpose of periodically testing the light curtain for proper operation. The test rod is the appropriate diameter for testing the light curtain it was shipped with.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation
Blanking

Blanking

ECS (Blanking)

The blanking feature, or *exact channel select* (ECS), can be used as an option to disable selected beams or channels in the safety light curtain's sensing field. This feature is used when stationary objects, such as fixtures, conveyors, or tooling, obstruct fixed areas of the sensing field. Once the specific beams or channels have been blocked and the blanking feature has been activated, the selected beams must remain blocked. If the obstruction is removed, the light curtain will transmit a stop signal to the machine.

Floating Blanking

Floating blanking is an option for use with ECS (blanking) or as a stand alone feature. Floating blanking provides the ability for up to two beams or channels to be disabled at any position in the sensing field. The two beams or channels disabled with this feature are not fixed at a single position; they are allowed to float through the sensing field.

It is important to follow the instruction manual provided with the safety light curtain when using the ECS (blanking) and floating blanking optional features together.

If the ECS (blanking) or floating blanking feature is active, the minimum safe distance is affected by an increase in the light curtain's minimum object sensitivity (MOS). According to the ANSI safety distance formula, if the object sensitivity of the light curtain increases, the minimum safe distance must increase.

Protection for the Functions of Blanking and Floating Blanking

The functions of ECS/blanking and floating blanking create "holes" in the detection zone. These holes are required for certain applications. If an obstruction does not completely fill these holes one of two actions will be required:

- The safe mounting distance will need to be increased to account for the larger opening in the detection zone.
- The area not filled by an obstruction must be guarded, typically by some method of hard guarding.

Hard guarding refers to mechanical barriers such as sheet or expanded metal.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light curtain application and installation

Test procedure



Testing Protected Area of Light Curtain

Test Procedure

Test Procedure for the United States

The tests below must be performed by qualified personnel (per ANSI B30.2—1993) at or after the following:

- After installation and before the machine is commissioned
- At regular inspections determined by the employer
- After any maintenance, adjustment, or modification to the light curtain or machine
- After tooling or fixture changes
- We also recommend that the following test procedure be performed daily or at each shift change.

Test procedure:

1. Turn off the machine. Turn on the light curtain.
2. Check the machine to make sure that all guarding is firmly in place, operates properly, and the only access to the hazardous area is through the area protected by the light curtain.
3. Check that light curtain mounting meets or exceeds the minimum safety distance from the nearest hazardous area (pinch point). Verify that the light curtain is mounted securely to a rigid mounting surface.
4. Check for damage to mounting brackets, mounting surface, wiring, or mirrors (if used). If any damage is found, the machine should be locked out ▲ until it is repaired.
5. Verify that operators cannot position themselves between the hazardous area (pinch point) and the light curtain. If this is possible, additional guarding must be installed.
6. Check the distance between the hazardous area and the light curtain sensing area to verify that it meets or exceeds the minimum safety distance.
7. Insert the test rod (the round rod included with each XUSL light curtain) into the protected (sensing) area and move the test rod throughout the entire protected area (top, bottom, sides, vertically up and down in the middle of the sensing area).
8. Remove the test rod and start up the machine. With the machine running, insert the test rod into the sensing area and verify that the machine stops immediately.
9. With the test rod still in the sensing area, verify that the machine cannot be restarted.
10. Remove the test rod from the sensing area and verify that the machine cannot be restarted except when the proper start-up sequence has been followed.
11. Check the stopping mechanisms (including brakes) to verify proper working condition.
12. If any of the above tests do not give the indicated results, the machine should be locked out ▲ until it is repaired. Then run the above tests again.

▲ Follow OSHA 1910.147 for lock-out/tag-out procedures.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Cable pull switches

Selection guide: Cable pull switches 6/2

Cable pull switches, XY2

- General information. 6/3
- Specifications 6/4
- References 6/5
- Accessories. 6/8
- Dimensions 6/11
- Operating principles 6/12
- Application 6/14
- Wiring diagrams 6/16

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety dialog solutions
Cable pull switches, XY2

Applications	**Cable Pull switches for:** - conveyor systems - material handling - machine tools - electrical testing stations - woodworking machinery - textile machinery		
Features	For cable lengths up to 230 ft (70 m). Can be tripped by the operator at any point in the work zone.	For cable lengths up to 98 ft (30 m). Can be tripped by the operator at any point in the work zone.	For cable lengths up to 98 ft (30 m). Can be tripped by the operator at any point in the work zone.
Conformity to standards			
Products	EN/IEC 60947-5-5, EN/ISO 13850:2006, UL 508 and CSA C22-2 n° 14 (with H7)	EN/IEC 60947-5-5, EN/ISO 13850:2006, UL 508 and CSA C22-2 n° 14 (with H7)	EN/IEC 60947-5-5, EN/ISO 13850:2006, UL 508 and CSA C22-2 n° 14 (with H7)
Machine assemblies	EN/IEC 60204-1, Machinery directive: 2006/42/EC, Work equipment directive: 89/655/EEC	EN/IEC 60204-1, Machinery directive: 2006/42/EC, Work equipment directive: 89/655/EEC	EN/IEC 60204-1, Machinery directive: 2006/42/EC, Work equipment directive: 89/655/EEC
Protective treatment	Special version, "TK" with silicone bellows	Special version, "TK" with silicone bellows	—
Ambient temperature			
Operating	–13 to +158 °F (–25 to +70 °C), Standard version –40 to +158 °F (–40 to +70 °C), "TK" version	–13 to +158 °F (–25 to +70 °C), Standard version –40 to +158 °F (–40 to +70 °C), "TK" version	–13 to +158 °F (–25 to +70 °C), Standard version
Storage	–40 to +158 °F (–40 to +70 °C)	–40 to +158 °F (–40 to +70 °C)	–40 to +158 °F (–40 to +70 °C)
Electric shock protection conforming to EN/IEC 61140	Class I	Class I	Class I
Degree of protection	**XY2CE**: IP65 conforming to EN/IEC 60529	**XY2CH**: IP65 conforming to EN/IEC 60529	**XY2CJ:** IP66 and IP67 conforming to EN/IEC 60529
Positive operation conforming to EN/IEC 60947-5-1 Section 3	N.C. contacts with positive opening operation ⊖	N.C. contacts with positive opening operation ⊖	N.C. contacts with positive opening operation ⊖
Rated insulation voltage			
2-pole contacts	Ui = 500 V degree of pollution 3 conforming to EN/IEC 60947-1, Ui = 300 V conforming to UL 508, CSA C22-2 n° 14	Ui = 500 V degree of pollution 3 conforming to EN/IEC 60947-1, Ui = 300 V conforming to UL 508, CSA C22-2 n° 14	Ui = 500 V degree of pollution 3 conforming to EN/IEC 60947-1, Ui = 300 V conforming to UL 508, CSA C22-2 n° 14
3-pole contacts	Ui = 400 V degree of pollution 3 conforming to EN/IEC 60947-1, Ui = 300 V conforming to UL 508, CSA C22-2 n° 14	Ui = 400 V degree of pollution 3 conforming to EN/IEC 60947-1, Ui = 300 V conforming to UL 508, CSA C22-2 n° 14	Ui = 400 V degree of pollution 3 conforming to EN/IEC 60947-1, Ui = 300 V conforming to UL 508, CSA C22-2 n° 14
Rated impulse withstand voltage			
2-pole contacts	Uimp = 6 kV conforming to EN/ IEC 60947-1	Uimp = 6 kV conforming to EN/ IEC 60947-1	Uimp = 6 kV conforming to EN/ IEC 60947-1
3-pole contacts	Uimp = 4 kV conforming to EN/ IEC 60947-1	Uimp = 4 kV conforming to EN/ IEC 60947-1	Uimp = 4 kV conforming to EN/ IEC 60947-1
References	**XY2CE**	**XY2CH**	**XY2CJ**
Pages	6/5	6/6	6/7

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety dialog solutions
Cable pull switches, XY2

XY2CE1A296H7

XY2CH13250H7

XY2CJR19H7

Operating Principle

XY2 cable pull switches provide for a stop or emergency stop to be signaled at any point along a cable up to 230 feet (70 m) in length. This is many times preferred to installing many individual stop or emergency stop push button stations along a conveyor or around the machine, providing a more cost effective solution. Typical applications include conveyor systems, packaging, textiles, transfer machines, presses, woodworking equipment, paint lines, and test laboratories.

The cable pull switch is typically mounted at one end of a machine or conveyor, and the operating cable is routed along the conveyor or around the machine and secured at the other end. The operation of the XY2 is based on the taut cable principle—the cable must be tight and have appropriate tension applied to set or reset the switch. Once cable tension has been set, the device will open the N.C. control contacts if the cable is pulled or if it becomes slack due to stretching or breakage of the cable. Once the switch is tripped, it must be manually reset. The XY2C devices are for use with tensioned stranded steel cables only (refer to "Cable specifications" on page 14. The use of hemp or polymer ropes in place of multi-stranded steel cables is not permissable due to the excessive elasticity of the ropes.

Two versions are available:

- Emergency stop versions have positive opening N.C. contacts that latch upon tripping (positive opening) and must be manually reset.
- Normal stop versions are used where a momentary, non-emergency signal is required at any point along a cable. These devices have snap acting contacts and are non-latching devices.

Features Include:

- 3 cable entries 1/2"-14 NPT (XY2CE and XY2CH)
- 1 cable entry 1/2"-14 NPT (XY2CJ)
- Positive latching (no teasing)
- Slow-make slow-break for emergency stop
- Snap action contacts for momentary switch
- Works properly even if spring is broken
- Padlock attachments available
- Doesn't reset if out of adjustment
- Manual tripping force adjustment (XY2CE)
- Adjustment indicator
- UL Listed and CSA certified
- XY2CH and XY2CJ for applications up to 98 feet (30 m)
- XY2CH has 2 viewing windows to aid in setting and adjusting the switch
- XY2CE for applications up to 230 feet (70 m)
- Positive opening N.C. contacts meet the IEC and EN requirements for positive opening contacts according to IEC/EN 60947-5-1 section 3, and meet NEMA ICS-5, part 6 (direct opening action).

The use of an end spring is strongly advised when using cable pull devices on continuous duty mechanical handling equipment and systems.

The following standards allow the use of cable pull (pull cord) devices in e-stop circuits:

- IEC 60204-1: 10.7 AND 10.8
- ISO 13850
- NFPA 79



Interior View of XY2CE

Note:
These devices are designed for use in tensioned cable pull applications. They are not suitable for use as slack rope pull devices.

6

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Specifications

Conformity to Standards Approvals	ANSI A 17.1, EN/IEC 60947-5-5, EN/ISO 13850: 2006, Machine Directive: 2006/42/EC, NFC 79-130, NFC 63144, VDE 0660-207. **XY2CE/XY2CH/XY2CJ**: UL 508 & CSA C22-2 no 14 (H7 version), UL (NISD), CCC *(1)*
Maximum safety level *(2)*	PL e, category 4 conforming to EN/ISO 13849-1 and SIL CL3 conforming to EN/IEC 62061
Reliability data B_{10d}	**XY2CE**: 50,000 **XY2CH**: 5,000,000 **XY2CJ**: 500,000 (data values for a service life of 20 years: can be limited by contact and mechanical wear)
Ambient Temperature *(3)*	**Operation:** -13 to +158 °F (-25 to +70 °C) for standard devices; -40 to 158 °F (-40 to +70 °C) for TK versions (corrosion resistant). **Storage**: from -40 to +158 °F (-40 to +70 °C) for all devices.
Vibration Resistance	**XY2CE**: 10 gn (10–300 Hz). **XY2CH, XY2CJ**: 10 gn (10–150 Hz), conforming to EN/IEC 60068-2-6
Shock Resistance	50 gn, duration 11 ms, conforming to EN/IEC 600068-2-27
Electric Shock Protection	UL 508, 19-1, Class I conforming to IEC 61140 and NF C 20-030.
Enclosure Rating	**XY2CE, XY2CH**: IP65 conforming to IEC 60529, IP657 conforming to NF C 20-010 (IP 667 with booted push button). **XY2CJ**: IP 66 and IP 67 conforming to IEC 60529.
Mechanical Life	**XY2CE**: 10,000 operating cycles **XY2CH**: 800,000 operating cycles **XY2CJ**: 100,000 operating cycles
Cable Entry	**XY2CE**: 3 plain holes with 1/2"-14 NPT gland (H7) or ISO M20 x 1.5 gland (H29) or Pg 13.5 **XY2CH**: 3 tapped cable entries for 1/2"-14 NPT conduit (H7) or ISO M20 x 1.5 (H29) or Pg 13.5 **XY2CJ**: 1 tapped cable entry for 1/2"-14 NPT conduit (H7) or ISO M20 x 1.5 (H29) or Pg 13.5
Operating Position	All positions.
Length of Protected Area	**XY2CE**: maximum 230 ft (70 m). **XY2CH, XY2CJ**: maximum 98 ft (30 m)

(1) Only products XY2CH without pilot light are CCC and UL-CSA approved.
(2) Using an appropriate and correctly connected control system.
(3) The minimum temperatures listed are based on the absence of freezing moisture or water. Care should be taken to avoid sub-freezing temperatures where dripping or splashing water is present and to avoid bringing a cold device into a humid atmosphere and then back into sub-freezing temperatures. The water or moisture may freeze around internal or external components and prevent it from performing as intended.

Electrical Specifications

Rated operational characteristics	2-pole contact	**XY2CJ, XY2CH, XY2CE**: AC-15: A300 or Ue = 240 V, Ie = 3 A; DC-13: Q300 or Ue = 250 V, Ie = 0.27 A, conforming to EN/IEC 60947-5-1 Appendix A
	3-pole contact	**XY2CJ, XY2CH**: AC-15: B300 or Ue = 240 V, Ie = 1.5 A; DC-13: R300 or Ue = 250 V, Ie = 0.1 A, conforming to EN/IEC 60947-5-1 Appendix A
Nominal thermal current	2-pole contact	10 A
	3-pole contact	6 A
Rated insulation voltage	2-pole contact	**XY2CJ, XY2CH, XY2CE**: Ui = 500 V degree of pollution 3 conforming to EN/IEC 60947-1, Ui = 300 V conforming to UL 508, CSA C22-2 no. 14
	3-pole contact	**XY2CJ, XY2CH**: Ui = 400 V degree of pollution 3 conforming to EN/IEC 60947-1, Ui = 300 V conforming to UL 508, CSA C22-2 no. 14
Rated impulse withstand voltage	2-pole contact	**XY2CJ, XY2CH, XY2CE**: Uimp = 6 kV conforming to EN/IEC 60947-1
	3-pole contact	**XY2CJ, XY2CH**: Uimp = 4 kV conforming to EN/IEC 60947-1
Positive operation		NC contact with positive opening operation conforming to EN/IEC 60947-5-1 Section 3
Resistance across terminals		⩽ 25 mΩ conforming to NF C 93-050 method A or EN/IEC 60255-7 category 3
Terminal referencing		Conforming to CENELEC EN 50013
Short Circuit Protection *(1)*		In U.S. use fast action fuse 10 A type SC; form I Class J, H or equivalent. 10 A cylindrical fuses type g1 or N conforming to IEC 337-1B- and VDE 0660-200 (2 pole contacts)
Rated operational power (Electrical durability)		**XY2CJ, XY2CH, XY2CE** Conforming to EN/IEC 60947-5-1 Appendix C. Utilization categories AC-15 and DC-13 Frequency: 3600 operating cycles/hour. Load factor: 0.5

AC supply ∿ 50/60 Hz
Inductive circuit

2-pole contact



3-pole contact



DC supply ⎓
Power broken in W for 1 million operating cycles.
Inductive circuit

Voltage	V	**24**	**48**	**120**
	W	13	9	7

Voltage	V	**24**	**48**	**120**
	W	4	3	2

Contact connection	Screw clamp terminals **2 contacts**: clamping capacity, min. 1 wire: 20 AWG (0.5 mm²), max. 2 wires: 16 AWG (1.5 mm²). **3 contacts:** clamping capacity, min. 1 wire: 22 AWG (0.34 mm²), max. 1 wire: 18 AWG (1 mm²) or 2 wires: 20 AWG (0.75 mm²). Minimum tightening torque: 7.1 lb-in. (0.8 N.m). Maximum tightening torque: 10.6 lb-in. (1.2 N.m).

(1) The use of the recommended fuse is mandatory for emergency stop applications. Without a fuse to protect the circuit, the contacts may develop a weld significant enough that the positive opening contact mechanism may not be able to break through the weld.

The product life expressed above is based on average usage and normal operating conditions. Actual operating life will vary with conditions. The above statements are not intended to nor shall they create any express or implied warranties as to product operation or life. For information on the limited warranty offered on this product refer to the Schneider Electric Conditions of Sale found in the Digest.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety dialog solutions
Cable pull switches, XY2

Right Cable Mount:

XY2CE1A150H7

XY2CE1A296H7

Left Cable Mount:

XY2CE2A250H7

XY2CE2A196H7

XY2CE Cable Pull for up to 230 ft (70 m) cable length

Cable and accessories must be selected and ordered separately from pages 6/8 and 6/10.

Emergency Stop

Emergency Stop (Latching contact—reset by push button—positive opening contacts) *(3)*
Available only with slow break contacts.
The N.O. contacts close after the N.C. contacts open. They do not change state simultaneously.

*Only the N.C. contacts should be used in the safety control circuit. The N.O. contacts are provided solely for signaling—**NOT** for safety functions.*

In category 3 or 4 safety architectures, to conform with ISO 13850 and the European Union Machinery Directive, safety circuits must use emergency stop devices with 2 N.C. contacts. Using devices with 1 N.O. and 1 N.C. contact will not allow the system to meet category 3 or 4 as it would not meet the requirements for redundancy. Cable pull switches with 1 N.O. and 1 N.C. contact would be suitable for Category 1 or 2 safety architectures. XY2 cable pull switches are ideal choices for use with Preventa™ XPS safety relays.

Cable mount	Contacts	Pilot light (available only on 2 N.O.—2 N.C. devices)	Reference
Right cable mount			
Standard push button	N.O. + N.C.	No	**XY2CE1A150H7**
Booted push button *(1)*	N.O. + N.C.	No	**XY2CE1A250H7**
Standard push button	2 N.O. + 2 N.C.	No	**XY2CE1A190H7**
Standard push button	2 N.O. + 2 N.C.	Yes *(2)*	**XY2CE1A196H7**
Booted push button *(1)*	2 N.O. + 2 N.C.	No	**XY2CE1A290H7**
Booted push button *(1)*	2 N.O. + 2 N.C.	Yes *(2)*	**XY2CE1A296H7**
Left cable mount			
Standard push button	N.O. + N.C.	No	**XY2CE2A150H7**
Booted push button *(1)*	N.O. + N.C.	No	**XY2CE2A250H7**
Standard push button	2 N.O. + 2 N.C.	No	**XY2CE2A190H7**
Standard push button	2 N.O. + 2 N.C.	Yes *(2)*	**XY2CE2A196H7**
Booted push button *(1)*	2 N.O. + 2 N.C.	No	**XY2CE2A290H7**
Booted push button *(1)*	2 N.O. + 2 N.C.	Yes *(2)*	**XY2CE2A296H7**

(1) Recommended for outdoor applications where icy conditions are likely.
(2) Includes LED Module 24–120 V. For 220 V LED module, change tenth digit to 7 (for example, XY2CE1A296H7 becomes XY2CE1A297H7).
(3) Positive opening N.C. contacts meet the IEC and EN requirements for positive opening contacts according to IEC/EN 60947-5-1, and meet NEMA ICS-5, part 6 (direct opening action).

Normal Stop

Normal stop (momentary action, no reset, no positive opening contact) *(2)*
Available only with snap action contacts. Not for use in safety related circuits.

	Contacts	Pilot Light (only available on 2 N.O.–2 N.C. devices)	Reference
Right cable mount	N.O.+N.C.	No	**XY2CE3A010H7**
	2 N.O.+2 N.C.	No	**XY2CE3A020H7**
	2 N.O.+2 N.C.	Yes *(1) (3)*	**XY2CE3A026H7**
Left cable mount	N.O.+N.C.	No	**XY2CE4A010H7**
	2 N.O.+2 N.C.	No	**XY2CE4A020H7**
	2 N.O.+2 N.C.	Yes *(1) (3)*	**XY2CE4A026H7**

(1) Includes LED Module 240–120 V. For 220 V LED module, change tenth digit to 7 (for example, XY2CE3A026H7 becomes XY2CE3A027H7). See spare parts list on page 6/10.
(2) Positive opening N.C. contacts meet the IEC and EN requirements for positive opening contacts according to IEC/EN 60947-5-1, and meet NEMA ICS-5, part 6 (direct opening action).
(3) These devices or components are not UL/CSA.

Options for XY2CE

Description	Designator
Corrosion resistant (only available on devices with booted push button on Emergency Stop devices and all Normal Stop devices) Not available on key operated emergency stop reset nor mushroom head reset versions. The enclosure color is olive-blue instead of red.	Provides a silicone boot, special finish, and copper/brass eyelet. -**For non-pilot-light devices**: 1. Add suffix TK to the part number 2. Change A to C Example: XY2CE1A250H7 changes to XY2CE1C250H7TK -**For pilot light devices**: 1. Add suffix TK to the part number 2. Change A to E Example: XY2CE1A296H7 changes to XY2CE1E296H7TK
Low Temperature -40 °F (-40 °C) The minimum temperatures listed are based on the absence of freezing moisture or water.	**Non-pilot-light versions** -Change A to C: silicone boot Ex: XY2CE1A150H7 changes to XY2CE1C150H7 **Pilot light versions** -Change A to E: silicone boot Ex: XY2CE1A196H7 changes to XY2CE1E196H7
N.C. + N.C. contact	-Change the 9th digit to 7 (for emergency stop only) Ex: XY2CE1A150H7 changes to XY2CE1A170H7
Mushroom head reset (Ø 30 mm)	-Change the 8th digit to 3 Ex: XY2CE1A150H7 changes to XY2CE1A350H7
Key operated emergency stop reset (Uses Ronis key No. 421)	-Change the 8th digit to 4. Ex: XY2CE1A150H7 changes to XY2CE1A450H7

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XY2CH13150H7

XY2CH13250H7

XY2CH13350H7

XY2CH13450H7

XY2CH Cable Pull for up to 98 ft (30 m) cable length

Cable and accessories must be selected and ordered separately from pages 6/8 and 6/10.

Emergency Stop

Emergency Stop (Latching contact—reset by push button—positive opening contacts) *(2)*
Available only with slow break contacts.

The N.O. contacts close after the N.C. contacts open. They do not change state simultaneously.

*Only the N.C. contacts should be used in the safety control circuit. The N.O. contacts are provided solely for signaling—**NOT** for safety functions.*

In category 3 or 4 safety architectures, to conform with ISO 13850 and the European Union Machinery Directive, safety circuits must use emergency stop devices with 2 N.C. contacts. Using devices with 1 N.O. and 1 N.C. contact will not allow the system to meet category 3 or 4 as it would not meet the requirements for redundancy. Cable pull switches with 1 N.O. and 1 N.C. contact would be suitable for Category 1 or 2 safety architectures. XY2 cable pull switches are ideal choices for use with Preventa™ XPS safety relays.

Reset	Contacts	Pilot Light	Reference
Standard push button	N.O. + N.C.	No	**XY2CH13150H7**
	1 N.O. + 2 N.C.	No	**XY2CH13190H7**
Booted push button *(1)*	N.O. + N.C.	No	**XY2CH13250H7**
	1 N.O. + 2 N.C.	No	**XY2CH13290H7**
Mushroom head push button	N.O. + N.C.	No	**XY2CH13350H7**
	1 N.O. +2 N.C.	No	**XY2CH13390H7**
Key operated emergency stop (uses Ronis Key No. 421)	N.O. + N.C.	No	**XY2CH13450H7**

Normal Stop

Normal stop *(3)* (momentary action, no reset, no positive opening contacts) *(2)*
Available only with snap action contacts. Not for use in safety related circuits.

Reset	Contacts	Pilot Light	Reference
No Reset Required	N.O. + N.C.	No	**XY2CH33010H7**

(1) Booted push button recommended for outdoor applications where icy conditions are likely.
(2) Positive opening N.C. contacts meet the IEC and EN requirements for positive opening contacts according to IEC/EN 60947-5-1, and meet NEMA ICS-5, part 6 (direct opening action).
(3) Normal stop devices are not UL/CSA.

Options for XY2CH

Description	Designator
Corrosion resistant (only available on devices with booted push button on Emergency Stop devices and all Normal Stop devices). Not available on key operated emergency stop reset or mushroom-head reset versions. The enclosure color is olive-blue instead of red.	Provides a silicone boot and special finish: 1. Add suffix TK to the reference 2. Change the seventh character to 4 Example: XY2CH13250H7 changes to XY2CH14250H7TK
Silicone bellows	- Change the 7th digit to 4 Ex: XY2CH13150H7 changes to XY2CH14150H7
N.C. + N.C. contact	- Change the 9th digit to 7 (for emergency stop only) Ex: XY2CH13150H7 changes to XY2CH13170H7
Pilot light (not UL/CSA) Bulb is included, replacement bulbs available on page 6/8	- For 24 V, change the 10th digit to 3 - For 48 V, change the 10th digit to 4 - For 120 V, change the 10th digit to 5 - For 230 V, change the 10th digit to 7 Ex: XY2CH13150H7 changes to XY2CH13153H7

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XY2CJS19H7

XY2CJR19H7



XY2CJL19H7

XY2CJ Cable Pull for up to 98 ft (30 m) cable length

Cable and accessories must be selected and ordered separately from pages 6/8 and 6/10.

Emergency Stop

Emergency Stop (Latching contact—reset by push button—positive opening contacts) *(2)*
Available only with slow break contacts.

The N.O. contacts close after the N.C. contacts open. They do not change state simultaneously.

*Only the N.C. contacts should be used in the safety control circuit. The N.O. contacts are provided solely for signaling—**NOT** for safety functions.*

In category 3 or 4 safety architectures, to conform with ISO 13850 and the European Union Machinery Directive, safety circuits must use emergency stop devices with 2 N.C. contacts. Using devices with 1 N.O. and 1 N.C. contact will not allow the system to meet category 3 or 4 as it would not meet the requirements for redundancy. Cable pull switches with 1 N.O. and 1 N.C. contact would be suitable for Category 1 or 2 safety architectures. XY2 cable pull switches are ideal choices for use with Preventa™ XPS safety relays.

Type	Cable Length (max.)	Contacts	Reference
Straight	65 ft. (20 m)	2 N.C. + 1 N.O.	**XY2CJS19H7**
Right cable mount	98 ft. (30 m)	2 N.C. + 1 N.O.	**XY2CJR19H7**
Left cable mount	98 ft. (30 m)	2 N.C. + 1 N.O.	**XY2CJL19H7**

The devices listed above are threaded for 1/2"-14 NPT, and are available with metric conduit:
- *To order devices tapped for 13 mm cable connector, conforming to NFC 68-300 (DIN Pg 13.5), remove the H7 at the end of the part number. For example: XY2CJS19H7 changes to XY2CJS19.*
- *To order devices tapped for M20 x 1.5 for ISO threaded cable entry, change H7 to H29 at the end of the part number. For example: XY2CJS19H7 changes to XY2CJS19H29.*

The XY2CJ devices are not available with pilot lights.

Enclosure materials:
***XY2CJS**: polyamide head, Zamak red RAL 3000 body, treated steel cover.*
***XY2CJR and XY2CJL**: Zamak red RAL 3000 head and body, treated steel cover*

6

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety dialog solutions
Cable pull switches, XY2
Accessories and spare parts


XY2CZ203


XY2CZ210


XY2CZ402

XY2CZ503

XY2CZ524

XY2CZ601

XY2CZ602


XY2CZ705

XY2CZ708

XY2CZ701


XY2CZ702

Separate components

Description	For use with	Diameter in. (mm)	Length ft (m)	Reference	Weight lb (kg)
Galvanized cables with red sheath	XY2CH, XY2CJ and XY2CE	0.13 (3.2)	34.4 (10.5)	**XY2CZ301**	0.617 (0.280)
			50.9 (15.5)	**XY2CZ3015**	0.904 (0.410)
			60.7 (18.5)	**XY2CZ3018**	1.080 (0.490)
			83.7 (25.5)	**XY2CZ302**	1.521 (0.690)
			100.1 (30.5)	**XY2CZ303**	1.829 (0.830)
			165.7 (50.5)	**XY2CZ305**	2.300 (1.360)
			329.7 (100.5)	**XY2CZ310**	5.952 (2.700)
	XY2CE	0.20 (5)	50.9 (15.5)	**XY2CZ1015**	1.874 (0.850)
			83.7 (25.5)	**XY2CZ102**	3.086 (1.400)
			165.7 (50.5)	**XY2CZ105**	6.062 (2.750)
			231.3 (70.5)	**XY2CZ107**	8.532 (3.870)
			329.7 (100.5)	**XY2CZ110**	12.125 (5.500)

Description	Type	For use with	Sold in lots of	Unit reference	Weight lb (kg)
Tensioner (included in mounting kit XY2CZ917)	–	XY2CE	1	**XY2CZ203**	0.198 (0.090)
Turnbuckles	M6 x 60 + locknut	All models *(1)*	1	**XY2CZ402**	0.132 (0.060)
	M8 x 70 + locknut	All models *(1)*	1	**XY2CZ404**	0.220 (0.100)
Tensioner for XY2CJ	–	XY2CJ	1	**XY2CZ210**	0.110 (0.510)
Cable grips	Single	Cable Ø3–5 mm	10	**XY2CZ503**	0.015 (0.007)
	Double	Cable Ø3–5 mm	10	**XY2CZ513**	0.035 (0.016)
	Clamp	Cable Ø3.2 mm	10	**XY2CZ523**	0.110 (0.050)
		Cable Ø5 mm	10	**XY2CZ524**	0.176 (0.080)
Cable supports	Fixed	All models	10	**XY2CZ601**	0.066 (0.030)
	Swiveling	All models	1	**XY2CZ602**	0.287 (0.130)
	Pulley support	All models	1	**XY2CZ705**	0.132 (0.060)
Pulley	Cable Ø5 mm max.	All models	1	**XY2CZ708**	0.004 (0.002)
Cable end protectors	–	Cable Ø3.2 mm	10	**XY2CZ701**	0.004 (0.002)
		Cable Ø5 mm	10	**XY2CZ704**	0.022 (0.010)
End springs *(2)*	–	XY2CH and XY2CJ	1	**XY2CZ703**	0.077 (0.035)
		XY2CE	1	**XY2CZ702**	0.176 (0.080)
Padlock attachment (Yellow) - Contains padlock attachment and two tamper proof cover mounting screws with special key. The padlock attachment cannot be used as a lock-out tag-out means.		XY2CH	1	**XY2CZ916**	0.202 (0.100)

(1) Emergency stop cable pull switches XY2CH13●●● and XY2CH14●●● incorporate a cable tensioner as standard. There is no need to order a turnbuckle.
(2) The use of an end spring is strongly recommended, especially when using longer lengths of cable.

Note: For the maximum cable length, we recommend using
• 3.2 mm diameter galvanized cables for the XY2CH range • 5 mm diameter galvanized cables for the XY2CE range

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety dialog solutions
Cable pull switches, XY2
Accessories and spare parts



XY2CZ917

Mounting kits

Contents	For use with	Cable diameter in. (mm)	Length of cable ft (m)	Reference	Weight lb (kg)
1 tensioner + 1 bracket	XY2CE	–	–	**XY2CZ917**	1.349 (0.612)
1 spring tensioner + 1 notched washer + 1 circlip	XY2CH	–	–	**XY2CZ918**	0.022 (0.010)
1 galvanized cable + 1 cable grip **XY2CZ523** + 1 end spring **XY2CZ703** *(1)*	XY2CH and XY2CJ	0.13 (3.2)	32.8 (10)	**XY2CZ9310**	0.915 (0.415)
			49.2 (15)	**XY2CZ9315**	1.179 (0.535)
			60.7 (18.5)	**XY2CZ9318**	1.280 (0.580)
1 galvanized cable + 4 cable grips **XY2CZ523** + 1 turnbuckle **XY2CZ404** + 1 cable support **XY2CZ601** + 3 cable end protectors **XY2CZ701** + 1 end spring **XY2CZ702** *(1)*	XY2CE, XY2CH, and XY2CJ	0.13 (3.2)	82.0 (25)	**XY2CZ9325**	2.756 (1.250)
			98.4 (30)	**XY2CZ9330**	2.866 (1.300)
	XY2CE	0.13 (3.2)	164.0 (50)	**XY2CZ9350**	4.365 (1.980)
1 galvanized cable + 4 cable grips **XY2CZ524** + 1 turnbuckle **XY2CZ404**, + 1 cable support **XY2CZ601** + 3 cable end protectors **XY2CZ704** + 1 end spring **XY2CZ702** *(1)*	XY2CE	0.20 (5)	82.0 (25)	**XY2CZ9525**	4.200 (1.905)
			164.0 (50)	**XY2CZ9550**	7.231 (3.280)
			230 (70)	**XY2CZ9570**	8.180 (4.000)

(1) The use of an end spring is strongly recommended, especially when using longer lengths of cable.

Note: For the maximum cable length, we recommend using
- *3.2 mm diameter galvanized cables for the XY2CH range*
- *5 mm diameter galvanized cables for the XY2CE range*

6

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety dialog solutions
Cable pull switches, XY2
Accessories and spare parts



XY2CZ805



XY2CZ●●●●

Replacement parts

Description	For use with	Type	Reference	Weight lb (kg)
Reset push button (blue), spring return	XY2CH	Flush with “R” marked on push	**ZB5AA639**	0.066 (0.030)
		Booted	**ZB5APA6**	0.055 (0.025)
		Mushroom head, Ø30	**ZB5AC64**	0.099 (0.045)
	XY2CE	Flush with “R” marked on push	**ZB5AA639**	0.040 (0.018)
		Booted	**ZB5AP6S**	0.046 (0.021)
		Mushroom head, Ø30	**ZB5AC64**	0.060 (0.027)
Key switch	XY2CH and XY2CE	With key n° 421	**ZB5AG612R26**	0.141 (0.064)
		With key n° 455	**ZB5AG6R26**	0.141 (0.064)
Keys for reset button	All types of Emergency stop	N° 421	**ZBG421E**	0.013 (0.006)
		N° 455	**ZBG455**	0.013 (0.006)
Pilot light head assembly	XY2CE	Orange	**XY2CZ800**	0.033 (0.015)
		Red	**XY2CZ801**	0.033 (0.015)
Pilot light lens	XY2CE	Orange	**ZBV0153**	0.007 (0.003)
		Red	**ZBV0143**	0.007 (0.003)
Set of 5 cover gaskets	XY2CE	–	**XY2CZ805**	0.269 (0.122)
Mounting nut, plastic, gray	XY2CH and XY2CE	–	**ZB5AZ901**	0.004 (0.002)
Mounting nut tightening key, plastic, gray	XY2CH and XY2CE For mounting nut ZB5AZ901		**ZB5AZ905**	0.035 (0.016)

Description	For use with	Voltage ~/⎓	Sold in lots of	Unit reference	Weight lb (kg)
Pilot lights With bulb DL1AA●●● included	XY2CH Color: orange	24 V	1	**XY2CZ0024** *(1)*	0.077 (0.035)
		48 V	1	**XY2CZ0048** *(1)*	0.077 (0.035)
		130 V	1	**XY2CZ0130** *(1)*	0.077 (0.035)
		230 V	1	**XY2CZ0230** *(1)*	0.077 (0.035)
Supply on LED	XY2CE Color: red	24 V	1	**ZALVB4**	0.033 (0.015)
		130 V	1	**ZALVG4**	0.033 (0.015)
		230–240 V	1	**ZALVM4**	0.033 (0.015)
	XY2CE Color: orange	24 V	1	**ZALVB5**	0.033 (0.015)
		130 V	1	**ZALVG5**	0.033 (0.015)
		230–240 V	1	**ZALVM5**	0.033 (0.015)
Incandescent bulbs, screw base fitting	XY2CH	24 V, 6 W	10	**DL1AA024**	0.009 (0.004)
		130 V, 6 W	10	**DL1AA127**	0.009 (0.004)
		230 V, 6 W	10	**DL1AA220**	0.009 (0.004)
Packet of 5 collars	For mounting DL1AA127 and DL1AA220 bulbs in pilot lights XY2CZ●●●	–	5	**XY2CZ908**	0.040 (0.018)

(1) Only for use as replacement parts for switches prefitted with pilot lights. CCC and UL-CSA approvals no longer apply if an XY2CZ●●● pilot light is mounted on XY2CH Emergency stops.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

XY2CH

Without pilot light



With pilot light (not CSA/UL approved)



(1) Maximum extension.
(2) H7 version tapped for 1/2"-14 NPT conduit entry. For ISO M20, replace H7 with H29. For Pg 13.5, remove H7 from the part number.
(3) 4.76 in. (121 mm): 24 V and 48 V versions. 5.16 in. (131 mm): 130 V and 230 V versions.

XY2CE

XY2CE●A●●●, XY2CE●C●●●



XY2CE●A●●● + XY2CZ917 (tensioner + bracket)



(1) H7 version comes with three plain holes and one 1/2"-14 NPT conduit adapter. For plain holes for use with M20 cable gland, replace H7 with H29. For plain holes for use with Pg 13.5 cable gland, remove H7 from the part number.
(2) Maximum extension.
Ø: 4 elongated holes Ø0.24 in. (6 mm).

XY2CJ

XY2CJS●●



XY2CJR●● (with anchor point on RH side)



(1) H7 version tapped for 1/2" NPT. For ISO M20, replace the H7 with H29. For Pg 13.5 cable gland, remove H7 from the part number.
(2) Maximum extension.

Accessories

XY2CZ705



XY2CZ708



Dual Dimensions: Inches / Millimeters

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety dialog solutions
Cable pull switches, XY2
Operating principles and adjustment

XY2CE Operating Principles

Normal Position

The cable *(1)* is tightened by the turnbuckle *(2)* and held in a normal position by the spring *(3)*. As the turnbuckle is turned, the cam *(4)* moves from left to right, and allows the actuator *(5)* to be positioned according to the particulars of the desired setting (see page 14).

The mechanical latch is unlocked when the N.C. contact is in the locked position.



Note: An end spring (8) is recommended at the far end of the cable (1) allowing the cable to be moved right or left, especially for cables 80 ft or longer. The use of an end spring is strongly advised when using the cable pull devices on continuous duty mechanical handling equipment and systems.

Tripping the Device

Operating or breaking the cable results in the cam shifting position.

The active part of the cam presses down the actuator *(5)*, simultaneously causing the N.C. contact *(7)* to open and the mechanical latch *(6)* to maintain it in its open position. Cable supports ensure the transmission of the cable tension into the axis of the switch cam.

Definitions



F–Tripping force: The value of the **tension** (F) **along the cable** which trips the switch.

F1–Operating tripping force: The value of the **traction force** (F1) applied by the operation **perpendicular to the cable** which trips the switch.

f–Operating travel: The distance (f) traveled by the operator (that is, the operator's hand), between the normal position and the tripping point.

General Purpose Adjustment Method

XY2CE—Cable Traction Force

Adjust either directly when mounting the cable or using a turnbuckle positioned near the switch but **after the first cable support.** For standard adjustment the **tension indicator should be in the middle of the range.**

Operating Travel



Position A



Position F

The tripping point is adjusted by the rotating cam marked by letters A to F. Position A corresponds to the minimum travel. Position F corresponds to the maximum travel.

NOTE: The switches are delivered from the factory in position A.

XY2CH

XY2CH has two viewing windows to aid in adjusting cable tension and resetting the switch. When the cable tension indicator is in mid-range in its viewing window, the reset button should be pushed to reset the device. When the device is reset, a green indicator is visible in the contact viewing window. When the switch is tripped, a yellow indicator is visible in the contact viewing window and the cable tension indicator is at the edge of its viewing window.

Standards

Preventa™ cable pull switches XY2CH, XY2CJ and XY2CE meet all the requirements of the harmonized European standard **EN/ISO 13850**, relating to Emergency stop devices. All the cable pull switches are CE marked and come with an EC declaration of conformity.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety dialog solutions
Cable pull switches, XY2
Operating principles and adjustment

Adjustment Values (with end spring)

For Preventa™ XY2CE Emergency stop cable pull switches: the adjustment values depend on the positions of the cam located inside the switch. Adjustment is made by rotating the cam after the switch has been installed.

Each notched position of the cam is referenced by the letters A to F, and the selected letter is visible through a viewing port.

The use of an end spring is strongly advised. You can see the references in the table below regarding each type:

Type	Cam position	Maximum cable length: ft. (m)	End spring
XY2CJS	–	65.6 (20)	XY2CZ703
XY2CJR and XY2CJL	–	98.4 (30)	XY2CZ703
XY2CH	–	98.4 (30)	XY2CZ703
XY2CE	A, B, C, D, E, F	229.7 (70)	XY2CZ702

XY2CH



With the graph above, if we consider an ambient temperature variation of 77 °F (25 °C), for example from 32 °F to 77 °F (0 °C to + 25 °C), the table gives us a maximum cable length of 98.4 ft. (30 m).

XY2CE



With the graph above, if we consider an ambient temperature variation of 95 °F (35° C), for example from -14 °F to 77° F (-10 °C to +25 °C), the table gives us a maximum cable length of

- 131.2 ft. (40 m) with cam A adjustments
- 229.7 ft. (70 m) with cam F adjustments

Cable specifications: length = 229.7 ft (70 m); maximum elongation of cable must be no more than 0.00834 in./ft (0.7 mm/m), equivalent to a maximum co-efficient of expansion of 0.07%, based on a 108 °F (60 °C) temperature variance.

XY2CJ



With the graphs above, if we consider an ambient temperature variation of 77 °F (25 °C), for example from 32 °F to 77 °F (0 °C to + 25 °C), the table gives us a maximum cable length of 65.6 ft. (20 m) for XY2CJS and 98.4 ft. (30 m) for XY2CJR and XY2CJL.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Safety dialog solutions
Cable pull switches, XY2

Setup

XY2CH



XY2CE



XY2CE + XY2CZ917



Recommended distance between cable supports (XY2CZ601 or XY2CZ705) is 16.4 ft. (5 m).

Application and Installation Recommendations

The XY2 cable pull switches are based on the taut cable principle, which means the cable must be tight and have a tension applied to allow the switch to be reset and work properly. This is different from slack cable switches where the cable is normally slack and is only tight when pulled. The benefit of the taut cable principle is that the operator knows that if the cable is taut, the machine can be shut down. If slack cable switches are used, the operator is not assured the cable is affixed properly at the switch and may be unsure that when the cable is pulled the machine will stop.

The distance an operator must pull the cable on a slack cable switch depends on the operator's distance from the switch and the amount of slack in the cable. An operator close to the switch needs to take up much less slack in the cable before tripping the switch than an operator at the far end of the installation. With a taut cable switch, the operating force and distance the cable needs to be pulled is the same throughout the installation. The taut cable style of device is more reliable in an emergency situation.

Effects of Friction

To operate properly, the cable must be tight with tension on it, and the cable must have a minimum of friction. Care must be taken in the machine design to ensure that the system avoids ANY friction between the cable on the machine parts or components, and moving parts on the machine or material handling system.

- The cable must be free of motion on its supports. It should not lay against the supports nor rub on them except when the cable is pulled by an operator.
- The cable must not have weights attached nor applied to it as a standard part of the application.
- The application must be designed to reduce friction as low as possible. This is accomplished by using reduced friction pulleys and guides.
- The cables should never be run through conduit or tubing.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Cornering

The operating cable should be installed so that the cable run is straight, but this cable can also be routed around corners using pulleys. If the cable deviates from a straight line, pulleys **must** be used. The effects of friction could be more noticeable if the cable is not installed correctly and with a minimum of friction.

- **Do not** allow the cable to turn corners or change direction using only cable supports.
- A pulley **must** be used when routing cable around corners, regardless of the angle. Use a pulley whenever direction is changed even slightly. The pulley must have freedom of movement on its mounting to maintain the self-alignment of the cable.
- If a fixed pulley is used, a cable support should be positioned within 4 in. (10 cm) of both sides of the pulley.
- The total sum of the angles for the cable bends or turns should be no more than 180°.
  - qty of two 90-degree angle turns is acceptable.
  - qty of three 60-degree angle turns is acceptable.
  - qty of three 90-degree angle turns is not acceptable.

Temperature

Note:
*Routing the cable through both hot and cold production areas with the same cable could require more frequent adjustment and **may** not allow proper adjustment throughout the production cycle.*

Example:
A cable pull switch on a production line where the product is cooked and then flash frozen in a short distance. Some sections of the cable could be very hot, and other sections very cold, and other sections at room temperature. Temperature variations in any of these areas could affect the overall adjustment of the cable. Where such variations occur, we recommend the use of multiple cable pulls.

Temperature variations in the area where the cable pull switch is installed can affect the adjustment of the switch. The cable expands (becomes longer) when temperature increases, and contracts (shrinks) when temperature decreases. Wide temperature variations should be avoided where possible. If temperature variations are significant, the adjustment of the cable and switch must be checked at regular intervals. If the switch is not adjusted properly during installation, temperature variations could affect cable length and trip the switch without operator intervention. If this occurs, the switch needs to be readjusted.

Temperature variances can come from any of the following:

- Seasonal temperature changes in non-climate controlled areas.
- Freezers and refrigeration equipment which are cold during production but are brought to room temperature for cleaning.
- Equipment that is used to heat treat or cook material during production but is brought to room temperature for cleaning.
- Equipment which is at room temperature (or lower temperatures) for production but is cleaned with hot water or steam.
- Equipment placed near windows and large glass areas: sunlight could cause an expansion of the cable where an overcast day may cause a contraction of the cable.

General Guidelines

- Be sure the cable remains accessible and visible to the operators for its entire length.
- The switch, cable supports, and other hardware must be rigidly mounted on the machine or application. If these mountings are not secure and rigid, the tension on the cable could be changed and the switch will trip. Mounting points must not move when the cable is pulled.
- Supports are not to be placed on moveable parts of the application.
- Cable lengths used must not exceed maximum lengths listed for the particular cable pull switch.
- The turnbuckle allows for the proper adjustment of the switch, and must be mounted close to the switch to ease and simplify adjustment of the system.
- The turnbuckle locknuts should be tightened securely.
- The first cable support should be within 4 in. (10 cm) of the switch.
- The sheath around the end of the cable must be removed when inserted into the cable clamps to assure metal-to-metal contact. Failure to remove sheathing could cause the cable to slip, thus reducing cable tension, and switches may not perform to published specifications.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Wiring Diagrams

For the versions with two contact blocks, the left one is identified as A, and the right one is identified as B. The markings are permanently inscribed on the mounting fixture above the contact blocks. Ex. B 21-22 is the normally closed contact of the right contact block.



Note: When the emergency stop switch operates in conjunction with solid-state controls (for example, PLCs), the supply for the safety functions must be disconnected independently of the PLC.

Operating instructions



Indicator Displays

The indicators define the maximum cable tension adjustment zone. The cable tension is adjusted via the turnbuckle. **The device will not function outside this zone.**
For general purpose adjustment, the indicator should be in the middle of the window.



Adjustment Limits for Effective Operating

In a normal position, adjustments must be made so that there is play (J) between the actuator and the conical parts of the cam.



Cable Supports

It is recommended that you space supports along the entire length of the cable at 6–16 ft (2–5 m) intervals. **Cable supports ensure the transmission of the cable tension in the axis of the switch cam. The first one after the switch is mandatory for correct operation** (4.0 in., 100 mm). Also, if pulleys are used to change the direction of the cable, **cable supports at 4 in. (100 mm) before and after the pulley are mandatory**.

Use supports with 0.8 in. (20 mm) maximum height H with respect to the product mounting surface.

Cable Specifications

Recommended minimum cable diameter is 1/8 in. (3.2 mm). However, any galvanized steel cable (aircraft type) less than 9/32 in. (7 mm) diameter can be used, provided it meets the following criteria: Maximum elongation of cable to be no more than 0.00834 in. per ft. (0.7 mm/m), which is equivalent to a maximum co-efficient of expansion of 0.07%, based on a 140 °F (60 °C) temperature variance.

Temperature variations likely to be encountered in the protected area will cause the cable to expand or contract. For the maximum cable length, considering ambient temperature variations, we recommend using:

- 3.2 mm diameter galvanized cables for the XY2CH and XY2CJ ranges
- 5 mm diameter galvanized cables for the XY2CE range

The XY2C device series are for use with tensioned stranded steel cables only. The use of hemp or polymer ropes in place of multi-stranded steel cables is not permissable due to the excessive elasticity of the ropes.

Note:
These devices are designed for use in tensioned cable pull applications. They are not suitable for use as slack rope pull devices.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Introduction - European legislation *7/2*

Industrial accidents *7/3*

European legislation and the standards *7/4*

Standards to be applied *7/6*

Assessment of machinery related risk *7/8*

Standard to be applied according to the design selected for the machine control system *7/10*

Standard EN/ISO 13849-1
Machinery safety - Safety-related parts of control systems (SRP/CS) *7/12*

Standard EN/IEC 62061
Machine Safety - Safety-related electrical control systems (SRECS) *7/16*

Certification and CE marking *7/20*

Relays and contactors for use in safety control circuits *7/22*

Additional EU information *7/26*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards
Introduction - European legislation



Safety and process reliability

Introduction

Safety has become a key issue for businesses. Social developments in association with technological progress have had a profound impact on legislation and on regulations for the use of building electrical automation equipment.

Social issues

The safety-conscious nature of our western societies has led the legislature to increase the number of requirements and establish stricter rules, while the high cost of accidents has prompted companies to make efforts in the same direction.

Technological issues

■ Increasing levels of automation have led to new restrictions. In some case it is difficult, if not dangerous, to stop a machine suddenly and it is necessary to perform a safe shut down sequence before allowing personnel to enter into a production cell.

■ The increasingly widespread use of electronics and software has required a different approach to the solutions adopted; empirical rules are no longer enough. Selection includes a reliability calculation to determine the behavior of the system.

In this context, the specification and design phase are crucial. Studies show that more than two-thirds of all incidents are due to bad design and inadequate specifications. At this stage it is therefore necessary to estimate potential risks and select the most appropriate solutions to reduce their consequences. Standards are available to assist and guide the designer.
Manufacturers of components and solutions help their customers by offering complete, ready-to-use functions which, when combined in accordance with the regulations, satisfy the customer's needs and meet legislative requirements.

In this chapter, we will present a simplified process. To make a choice, the customer will then be able to refer to the safety functions chapter and to the safety products chapters.

European legislation

European legislation requires that preventive action be taken to preserve and protect the quality of the environment and human health. To achieve these objectives, European Directives have been prepared which must be applied by plant operators and by manufacturers of equipment and machines. It also assigns responsibility for possible accidents.

■ Notwithstanding the constraints, machine safety has the following positive repercussions:
- prevention of industrial accidents,
- protection of workers and personnel by means of suitable safety measures that take into account the machine's application and the local environment.

■ This makes it possible to reduce direct and indirect related costs:
- by reducing physical harm,
- by reducing insurance premiums,
- by reducing production losses and possible delay penalties,
- by limiting damages and costs for maintenance.

■ Safe operation involves two principles: safety and reliability of the process:
- safety is the ability of a device to keep the risk incurred by persons within acceptable limits,
- reliability of operation is the ability of a system or device to perform its function at any moment in time and for a specified duration.

■ Safety must be taken into account right from the beginning of the design stage and kept in place throughout all stages of a machine's life cycle: transport, installation, commissioning, maintenance, dismantling.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards
Industrial accidents

Industrial accidents

An industrial accident occurs through work or in the workplace and causes minor to serious injury to a person using a machine, feeding it or carrying out special work on it (fitter, operator, and maintenance personnel).

Causes of accidents in the workplace

■ Human-related factors (designers, users):
- poor grasp of machine design,
- over-familiarity with danger through habit and failure to take dangerous situations seriously,
- underestimation of hazards, causing people to ignore safe working procedure,
- loss of concentration on tasks to be performed (e.g. fatigue),
- failure to comply with procedures,
- stressful working conditions (noise, and/or work rates),
- uncertainty of employment which can lead to inadequate training,
- inadequate or bad maintenance, generating unsuspected hazards.

■ Machine-related factors:
- inadequate guards,
- inherent machine hazards (e.g. reciprocal motion of a machine, unexpected starting or stopping),
- machines not suited to the application or environment (e.g. sound alarms deadened by the noise of surrounding machinery).

■ Plant-related factors:
- movement of personnel from machine to machine (automated production line),
- machinery from different manufacturers and using different technologies,
- flow of materials or products between machines.

Consequences

- Risk of varying degrees of physical injury to the user,
- stoppage of the machine involved,
- stoppage of similar machine installations for inspection, for example by health and safety inspectors,
- if necessary, modifications to make machinery safe,
- change of personnel and training new personnel for the job,
- damage to the company brand image.

Conclusion

Damages for physical injuries are equivalent to about 20 thousand million euro paid out each year in the European Union. Decisive action is required to reduce the number of accidents in the workplace. The first essentials are adequate company policies and efficient organization.
Reducing the number of industrial accidents and injuries depends on the safety of machines and equipment.

Types of potential hazard

The potential hazards of a machine can be classified into three main groups, as illustrated below:



Mechanical hazards

Puncturing, cutting, shearing, fractures, severing	*Catching, entanglement, drawing in, trapping*	*Impact*	*Crushing*



Electrical hazards **Physical and chemical hazards**

Electric shock, electrocution, burns	*Discharge of dangerous substances*	*Burns*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards
European legislation and the standards

European legislation and the standards

The main purpose of the Machinery Directive 2006/42/EC is to compel manufacturers to guarantee a minimum safety level for machinery and equipment sold within the European Union. This version has replaced the 98/37/EC version since January 2010.

To allow free circulation of machinery within the European Union, the CE marking must be applied to the machine and an EC declaration of conformity is issued to the purchaser. This directive came into effect in January 1995 and has been enforced since January 1997 for all machines.

The user has obligations defined by the Use of Work Equipment directive 89/655/EEC which can in most cases be met by using machinery compliant with relevant standards.
These standards are complex. After a brief presentation of the structure of the standards system, we will provide the reader with a practical guide to the typical standards to be applied according to the selected control system design.

Standards

The harmonized European safety standards establish technical specifications which comply with the minimum safety requirements defined in the related directives. Compliance with all applicable harmonized European standards **can be assumed to ensure** compliance with the related directives. The main purpose is to guarantee a minimum safety level for machinery and equipment sold within the EU market and allow the free circulation of machinery within the European Union.

The 3 groups of European standards



■ Type **A** standards
Basic safety standards which specify the basic concepts, design principles and general aspects valid for all types of machine: e.g. PrEN/ISO 12100.

■ Type **B** standards
Standards relating to specific aspects of safety or to a particular device that can be used on a wide range of machines.

□ Type **B1** standards
Standards relating to specific safety aspects of machines: e.g. EN/IEC 60204-1 Electrical equipment of machines.

□ Type **B2** standards
Standards relating to specific products such as two-hand control stations (EN 574), guard switches (EN 1088/ISO 14119), and emergency stops (EN/ISO 13850).

■ Type **C** standards
Standards relating to various families or groups of machines (e.g.: hydraulic presses EN 693, and robots) and giving detailed applicable requirements.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

European legislation and the standards *(continued)*

European legislation and the standards *(continued)*

A selection of standards

Standards	Type	Subject
PrEN/ISO 12100	A	Machinery safety - General principles for design, risk assessment and risk reduction
EN 574	B	Two-hand control devices - Functional aspects and design principles
EN/ISO 13850	B	Emergency stop - Principles for design
EN/IEC 62061	B	Functional safety of safety-related electrical, electronic and electronic programmable control systems
EN/ISO 13849-1 (EN 954-1)	B	Machinery safety - Safety-related parts of control systems - Part 1 general principles for design
EN 349	B	Minimum gaps to avoid crushing parts of the human body
EN 294	B	Safety distances to prevent hazardous zones being reached by upper limbs
EN 811	B	Safety distances to prevent hazardous zones being reached by lower limbs
EN/IEC 60204-1	B	Machinery safety - Electrical equipment of machines - Part 1: general requirements
EN 999/ISO 13855	B	Positioning of protective equipment in respect of approach speeds of body parts
EN 1088/ISO 14119	B	Interlocking devices associated with guards - Principles for design and selection
EN/IEC 61496-1	B	Electro-sensitive protective equipment
EN/IEC 60947-5-1	B	Electromechanical control circuit devices
EN 842	B	Visual danger signals - General requirements, design and testing
EN 1037	B	Prevention of unexpected start-up
EN 953	B	General requirements for the design and construction of fixed and movable guards
EN 201	C	Machinery for plastics and rubber - Injection moulding machines - Safety requirements
EN 692	C	Mechanical presses - Safety requirements
EN 693	C	Hydraulic presses - Safety requirements
EN 289	C	Machinery for plastics and rubber - Presses - Safety requirements
EN 422	C	Blow moulding machines for producing hollow parts - Design and construction requirements
EN/ISO 10218-1	C	Manipulating industrial robots - Safety requirements
EN 415-4	C	Safety of packaging machines - Part 4: palletisers and depalletisers
EN 619	C	Safety and EMC requirements for equipment for mechanical handling of unit loads
EN 620	C	Safety and EMC requirements for fixed belt conveyors for bulk material
EN 746-3	C	Industrial thermo processing equipment - Part 3: safety requirements for the generation and use of atmosphere gases

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards
Standards to be applied



Standards to be applied for the design of machines

Standards to be applied
The process

European Machinery Directive 2006/42/EC
Compliance with the following standards ensure compliance with the Machinery Directive (this new version of the Machinery Directive 2006/42/EC has replaced 98/37/EC since January 2010).

PrEN/ISO 12100 :2009: General principles for design, risk assessment and risk reduction.
See page 7/7.
The purpose of this standard is to provide designers with an overall framework and guidance to enable them to produce machines that are safe for their intended use.

Standards to be apply according to the design selected for the safety-related machine control system.
See page 7/10.

Remarks:
The use of one of these 2 standards gives presumption of conformity to the new 2006/42/EC directive.

EN/IEC 60204-1: Electrical equipment of machines
Standard EN/IEC 60204-1 completes the safety standards by giving setting-up rules for each component of a machine's electrical functions.
It specifies, among other things:
- the type of connection terminals and disconnection and breaking devices,
- the type of electric shock protection,
- the type of control circuits,
- the type of conductors and wiring rules,
- the type of motor protection.

See page 7/21.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards
Standards to be applied *(continued)*



Reduction of risk to an acceptable level

Standards to be applied (continued)

Risk and safety

Safety is the absence of risks which could cause injury to or damage the health of persons. Functional safety is a part of safety that depends on the correct operation of safety functions.

According to the requirements of standard PrEN/ISO 12100 :2009, the machine designer's job is to reduce all risks to a value lower than the acceptable risk.
For more details concerning the sources of accidents and risk prevention, the reader is referred on page 7/3.

This standard recognizes two sources of hazardous phenomena:
- moving transmission parts,
- moving parts contributing to the work.

It gives guidelines for the selection and installation of devices which can be used to protect persons and identifies those measures that are implemented by the machine designer and those dependent on its user.



Selection of the protection system (PrEN/ISO 12100 :2009)

The measures taken by the machine designer may be:
- inherent in the design,
- selection of guards and additional measures, including control systems,
- information for the user.

The measures taken by the user may be (non-exhaustive list):
- organization and procedures,
- personal protective equipment,
- training.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com



Definition of risk

Assessment of machinery related risk

European legislation

■ Machines are sources of potential risk and the Machinery Directive requires a risk assessment to ensure that any potential risk is reduced to less than the acceptable risk.

Standard PrEN/ISO 12100 :2009 defines risk as follows: risk is the severity multiplied by the possibility of occurrence. It defines an iterative process for achieving machine safety, which states that the risks for each potential hazard can be determined in four stages. This method provides the basis for the requisite risk reduction.



Logic steps for risk analysis

Risk assessment

Risk assessment consists of a series of logic steps which make it possible to systematically analyze and evaluate machinery-related risks.

Risk assessment is followed, whenever necessary, by a reduction of the risk. This definition taken from standard PrEN/ISO 12100 :2009 is based on an iterative process represented in the diagram opposite.

Determination of machine limits

Risk assessment starts by determining the limits of the machine at all stages of its life cycle:
- transport, assembly, installation,
- commissioning,
- use,
- de-commissioning, dismantling.

The use limitations must then be specified:
- operating modes,
- level of training required,
- space limits (amplitude, movement),
- time limits (life cycle, frequency of maintenance).

Identification of the potential hazard

If a potential hazard exists, a hazardous phenomenon will cause harm if measures are not taken. All the tasks associated with the machine's life cycle must be identified, such as:
- assembly, transport and installation,
- adjustment, testing,
- learning, programming,
- tool changing,
- feeding, removal of product from the machine,
- starting, stopping,
- emergency stops, restarting after an unexpected stop,
- maintenance and cleaning.

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Assessment of machinery related risk *(continued)*



Elements of the risk

Assessment of machinery related risk (continued)

Risk assessment (continued)

Risk estimation

The risk is a function of the severity of the harm and the probability that this harm will occur.

■ The severity of the harm takes into account:
- the severity of injuries (slight, serious, death),
- the extent of the harm (number of persons).

■ The probability of the harm occurring takes into account:
- exposure to the hazard (nature of access, time spent in the hazardous zone, number of persons exposed, frequency of access),
- the occurrence of a hazardous event (accident history, comparison of risks),
- the possibility of avoiding or limiting the harm (experience, awareness of the risk).

Risk evaluation

On the basis of the risk assessment, the designer has to define the safety related control system. To achieve that, the designer will chose one of the two standards appropriate to the application:
- either standard EN/ISO 13849-1, which defines performance levels (**PL**),
- or standard EN/IEC 62061, which defines safety integrity levels (**SIL**).



λ rate of control system failures
λ_D rate of dangerous failures
λ_{DU} rate of undetected dangerous failures
λ_{DD} rate of detected dangerous failures
λ_S rate of safe failures
λ_{SU} rate of undetected safe failures
λ_{SD} rate of detected safe failures

Breakdown of the probability of failures

Risk reduction

The process of risk reduction for dangerous events starts by:
- intrinsic prevention (inherently safe design),
- definition of the appropriate protective means (guards, carters, fix fences),
- personal training.

If the selected preventive measure depends on a safety related control system, the designer has to perform an iterative process for the design of the safety relative control system.

■ The first stage is to define the necessary safety-related control functions:
- either through the choice of components,
- or by adapting the control system architecture. Redundancy (double circuit components), for example, significantly increases the reliability of the solution.

■ Once the limits of available technologies have been reached, it will not be possible to further reduce the rate of dangerous failures. To achieve the required level of safety, it will be necessary to use a diagnostic system that allows dangerous failures to be detected.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard to be applied according to the design selected for the safety-related machine control system

Standard to be applied according to the design selected for the safety-related machine control system

Safety standards to be applied according to type of architecture selected

Based on the generic definition of the risk, the standards classify necessary safety levels in different discrete levels corresponding for each one to a probability of dangerous failure per hour:

- PL (Performance Level) for standard EN/ISO 13849-1,
- SIL (Safety Integrity Level) for standard EN/IEC 62061.

The table below gives **the relationship** between the performance level (PL) and the Safety Integrity Level (SIL).

PL	SIL	Probability of dangerous failures per hour 1/h
a	No correspondance	$\geq 10^{-5} \ldots < 10^{-4}$
b	1	$\geq 3 \times 10^{-6} \ldots < 10^{-5}$
c	1	$\geq 10^{-6} \ldots < 3 \times 10^{-6}$
d	2	$\geq 10^{-7} \ldots < 10^{-6}$
e	3	$\geq 10^{-8} \ldots < 10^{-7}$

In order to be able to select the applicable standard, a common table in both standards gives indications which are summarized in the table below:

	EN/ISO 13849-1	EN/IEC 62061
Technology used	**max. PL**	**max. SIL**
Non electric only, for example hydraulic	e	Not covered
Including some electromechanical, for example relays and/or non complex electronics	e *(1)*	3
Including complex electronics, for example programmable	d	3

(1) For designated architectures only.

For building specific complex sub-systems or for higher level requirements including software, standard EN/IEC 61508 relating to systems must be used.

7

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard to be applied according to the design selected for the safety-related machine control system *(continued)*

Standard to be applied according to the design selected for the control system *(continued)*

Designing a safety-related control system taking into account the requirements of safety standards may seem rather complex. We will guide the reader through this process by presenting:

- the basis and development of the standards,
- the safety standards to be applied according to the type of architecture selected,
- machine equipment and wiring.

Basis and development of the standards

In a complex system, such as a refinery, it is no longer sufficient to consider only the sub-systems to ensure protection; failure of a sub-system could be catastrophic for persons and the environment.
The approach is therefore more global.Taking into account the whole safety life cycle, standard EN/IEC 61508 deals with safety-related control systems, and includes safety rules, technical specifications, management and training of personnel.

The use of more complex saftey-related control systems based on electronics and software highlights the weaknesses of standard EN 954-1:

- the reliability of components is not taken into account,
- insufficient requirements for programmable products,
- combining components with a category certification is not enough to "guarantee" the required level of risk reduction.

Based on experience gained with systems, the standards body has, in line with standard EN/IEC 61508, developed standard EN/IEC 62061 which applies the principles of functional safety to the design of safety-related control systems for machinery.
This standard offers two important advantages:

- it incorporates the new electronic and electronic programmable technologies to provide the safety functions,
- it is consistent with the basic standard EN/IEC 61508 and is therefore being specified more and more for machines by users.

At the same time, standard EN/ISO 13849-1, effective since 2006, has completely replaced the standard EN 954-1 since January 2010, which brings several improvements and, above all, is consistent with safety standards in general.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard EN/ISO 13849-1

Machinery safety - Safety-related parts of control systems (SRP/CS)



Application example selected

Standard EN/ISO 13849-1
Machinery safety - Safety-related parts of control systems

Standard EN/ISO 13849-1 is a development of standard EN 954-1. For clarity, only a simplified analysis of this new version will be presented here.

Field of application of the standard

This standard gives safety requirements and advice relating to principles for the design and integration of safety-related parts of control systems (SRP/CS), including software design. For these parts, it specifies the characteristics, including the performance level, needed to achieve these safety functions. It applies to the SRP/CS of all types of machine, regardless of the technology and type of energy used (electric, hydraulic, pneumatic, and mechanical).

Process

Risk assessment as defined in standard PrEN/ISO 12100 :2009 (see page 7/6.) leads to decisions on risk reduction measures. If these measures depend on a control system, then PrEN/ISO 12100 :2009 can apply. It defines a 6-stage design process.

1 - Selection of the essential safety functions that SRP/CS must perform. For each safety function, specify the required characteristics.
2 - Determine the required performance level (PLr).
3 - Design and technical creation of safety functions: identify the parts that perform the safety function.
4 - Evaluate the performance level PL for each safety-related part.
5 - Check that the performance level PL achieved is greater than or equal to the required level (PLr).
6 - Check that all requirements are satisfied.

We will now illustrate these stages, taking as an example a safety function that stops operation of a machine motor when a safety guard is opened. The machine is potentially dangerous, there is a risk of the operator's arm being amputated if there is no guard.



Representation of the safety function

Stage 1 - Selection of safety functions
The diagram opposite shows a safety function which consists of several parts:
- the input actuated by opening of the guard (SRP/CS*a*),
- the control logic, limited in this example to opening or closing of a contactor coil (SRP/CS*b*),
- the power output that controls the motor (SRP/CS*c*),
- the connections (I*ab*, I*bc*).

Stage 2 - Estimation of required performance level (PLr)
For our safety function, this is estimated using the risk graph.

The parameters to be considered are:
- □ **S** severity of the injury
  - **S1** slight injury, normally reversible,
  - **S2** Serious, normally irreversible, including death.
- □ **F** frequency and/or duration of exposure to the hazardous phenomenon.
  - **F1** rare to fairly frequent and/or short duration of exposure,
  - **F2** frequent to permanent and/or long duration of exposure.
- □ **P** possibility of avoiding the hazardous phenomena or limiting the harm.
  - **P1** possible under certain circumstances,
  - **P2** virtually impossible.

The result of the estimation (in blue on the drawing on the next page) gives a required performance level PLr = e.



Risk analysis

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard EN/ISO 13849-1

Machinery safety - Safety-related parts of control systems (SRP/CS) *(continued)*



Estimation of required performance level

1	Starting point for estimation
L	Low contribution to risk reduction
PLr	Performance Level required
H	High contribution to risk reduction
→	Estimation

Key:

*i*m	Interconnecting means
c	Cross monitoring
I, I1, I2	Input device, e.g. sensor
L, L1, L2	Logic
m	Monitoring
O, O1, O2	Output device, e.g. main contactor
TE	Test equipment
OTE	Output of TE

Standard EN/ISO 13849-1
Machinery safety - Safety-related parts of control systems
(continued)

Process *(continued)*

Stage 3 - Design and creation of the safety functions

At this point, we need to describe the PL calculation method.
The PL is defined in terms of the probability of a dangerous failure per hour:

PL	Probability of a dangerous failure per hour
a	$\geq 10^{-5} \ldots < 10^{-4}$
b	$\geq 3 \times 10^{-6} \ldots < 10^{-5}$
c	$\geq 10^{-6} \ldots < 3 \times 10^{-6}$
d	$\geq 10^{-7} \ldots < 10^{-6}$
e	$\geq 10^{-8} \ldots < 10^{-7}$

For a SRP/CS (or a combination of SRP/CS) designed according to the requirements of the article 6, PL could be estimated with the figure shown on page 7/14, after estimation of several factors such as :
- hardware and software system structure (categories),
- mechanism of failures, diagnostic coverage (DC),
- components reliability, Mean Time To dangerous Failure ($MTTF_d$),
- Common Cause Failure (CCF).

■ Categories (Cat.) and designated architectures

The table below summarizes system behavior in the event of a failure and the principles used to achieve the safety, for the 5 categories defined:

Cat.	System behavior	Designated architectures
B	A fault can lead to loss of the safety function	
1	As for category B but the probability of this occurence is lower than for the category B	
2	A fault can lead to loss of the safety function between two periodic inspections and loss of the safety function is detected by the control system at the next test.	
3	For a single fault, the safety function is always ensured. Only some faults will be detected. The accumulation of undetected faults can lead to loss of the safety function.	
4	When faults occur, the safety function is always ensured. Faults will be detected in time to prevent loss of the safety function	

■ $MTTF_d$ (Mean Time To dangerous Failure)

The value of the $MTTF_d$ of each channel is given in 3 levels (see table below) and shall be taken into account for each channel (e.g. single channel, each channel of a redundant system) individually.

Reliability levels of components	
Index	**Range**
Low	3 years ≤ $MTTF_d$ < 10 years
Medium	10 years ≤ $MTTF_d$ < 30 years
High	30 years ≤ $MTTF_d$ < 100 years

A $MTTF_d$ of less than 3 years should never be found, because this would mean that after one year in operation, 30% of all those components in use would have failed to a dangerous state. The maximum value is limited to 100 years because devices dealing with a significant risk should not depend on the reliability of a single component. Additional measures such as redundancy and tests are required.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard EN/ISO 13849-1

Machinery safety - Safety-related parts of control systems (SRP/CS) *(continued)*

Standard EN/ISO 13849-1
Machinery safety - Safety-related parts of control systems
(continued)

Process *continued)*

Stage 3 - Design and creation of the safety functions *(continued)*

■ Diagnostic coverage: this term is expressed as a percentage and quantifies the ability to diagnose a dangerous failure.
For example, in the event of welding of a N/C contact in a relay, the state of the N/O contact could incorrectly indicate the opening of the circuit, unless the relay has mechanically linked N/O and N/C contacts, when the fault can be detected.
The standard recognizes four levels:

Diagnostic coverage	
Denotation	**Range**
Nil	DC < 60%
Low	60% ⩽ DC < 90%
Medium	90% ⩽ DC < 99%
High	99% ⩽ DC

■ Relationship between Categories, DC and $MTTF_d$ of each channel and the PL



□ In our example, to reach the PL = e, the solution will therefore have to correspond to category 4 with redundant circuit; the function scheme is shown opposite with two channels in parallel,
□ a high diagnostic capability,
□ a high $MTTF_d$.

For our application, we could suggest a redundant relay scheme but it is nowadays easier to use safety function blocks.
The solution is illustrated below.



Functional diagram of the example



Application scheme of the example

The process suggested by the standard is iterative and a few estimations are therefore necessary in order to obtain the expected result. In view of the required performance level, we have chosen a solution with redundant circuit.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard EN/ISO 13849-1

Machinery safety - Safety-related parts of control systems (SRP/CS) *(continued)*

Standard EN/ISO 13849-1
Machinery safety - Safety-related parts of control systems
(continued)

Process *(continued)*

Stage 4 - Evaluate the performance level PL for each safety-related part
Based on the information in the supplier's catalog and Annex E of the standard, we obtain the following values:

Example	B_{10} (number of operations) / % dangerous failure	$MTTF_d$	DC
SRP/CS_a: Safety limit switches	10.000.000 / 20% dangerous failure	7,102	99%
SRP/CS_b: XPS AK safety module	-	154.5	99,99%
SRP/CS_c: LCK contactor	1.000.000 / 73% dangerous failure	194	99%

For electromechanical products,
the $MTTF_d$ is calculated on the basis of the total number of operations that the product can perform, using $\mathbf{B_{10d}}$ values:
In our case, the machine operates for 220 days per year, 8 hours per day with a cycle of 90 s.
N = 220 x 8 x (3600 / 90) = 70,400 operations/year
$MTTF_d = B_{10d} / (0.1 \times N)$ and $B_{10d} = B_{10} / \%$ dangerous failure.

For the safety switches,
the $MTTF_d$ = (1 / 0.20 x 10 000 000) / (0.1) x 70,400 = 7,102 years
For the contactors,
the $MTTF_d$ = (1 / 0.73 x 1 000 000) / (0.1) x 70,400 = 194 years
The $MTTF_d$ for each channel will then be calculated using the formula:

$$\frac{1}{MTTF_d} = \frac{1}{MTTF_{da}} + \frac{1}{MTTF_{db}} + \frac{1}{MTTF_{dc}}$$

i.e. 85 years for each channel.
A similar formula is used to calculate the diagnostic capability

$$DC_{avg} = \frac{\frac{DC_a}{MTTF_{da}} + \frac{DC_b}{MTTF_{db}} + \frac{DC_c}{MTTF_{dc}}}{\frac{1}{MTTF_{da}} + \frac{1}{MTTF_{db}} + \frac{1}{MTTF_{dc}}}$$

The result of the calculation in our example gives a value of 99%

Stage 5 - Checking that required performance level is achieved
The result of the above calculations is summarized below:
- a redundant architecture: category 4,
- a mean time to failure > 30 years: high $MTTF_d$,
- a diagnostic capability of 99%: high DC.

Looking at this table, we confirm that **PL** level **e** is achieved:



Checking the PL

Stage 6 - Validation of the required performance level
The design of SRP/CS must be validated and must show that the combination of SRP/CS performing each safety function satisfies all the applicable requirements of EN/ISO 13849.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard EN/IEC 62061

Machinery safety - Safety-related electrical control systems (SRECS)

Standard EN/IEC 62061
Machinery safety - Safety-related electrical control systems (SRECS)

Functional Safety of safety-related electrical, electronic and electronic programmable control systems

Field of application of the standard

Safety-related electrical control systems in machines (**SRECS**) are playing an increasing role in ensuring the overall safety of machines and are more and more frequently using complex electronic technology.

This standard is specific to the machine sector within the framework of EN/IEC 61508. It gives rules for the integration of sub-systems designed in accordance with EN/ISO 13849. It does not specify the operating requirements of non-electrical control components in machines (for example: hydraulic, pneumatic).

Functional approach to safety

As with EN/ISO 13849-1, the process starts with analysis of the risks (PrEN/ISO 12100 :2009) in order to be able to determine the safety requirements. **A particular feature of this standard is that it prompts the user to make a functional analysis of the architecture, then split it into sub-functions and analyze their interactions before deciding on a hardware solution for them (the SRECS)**.

■ A functional safety plan must be drawn up and documented for each design project. It must include:

□ a specification of the safety requirements for the safety functions (**SRCF**) that is in two parts:

- a description of the functions and interfaces, operating modes, function priorities, and frequency of operation.
- specification of the safety integrity requirements for each function, expressed in terms of **SIL** (Safety Integrity Level).

The table below gives the target maximum failure values for each level.

SIL	Probability of a dangerous failure per hour (PFHd)
3	$\geq 10^{-8} ... < 10^{-7}$
2	$\geq 10^{-7} ... < 10^{-6}$
1	$\geq 10^{-6} ... < 10^{-5}$

□ The structured and documented design process for electrical control systems (**SRECS**),

□ the procedures and resources for recording and maintaining appropriate information,

□ the process for management and modification of the configuration, taking into account organization and authorized personnel,

□ the verification and validation plan.

■ Functional safety

The decisive advantage of this approach is that of being able to offer a failure calculation method that incorporates all the parameters that can affect the reliability of electrical systems, whatever the technology used.

The method consists of assigning a SIL to each function, taking into account the following parameters:

- the probability of a dangerous failure of the components (**PFH**d),
- the type of architecture; with or without redundancy, with or without diagnostic device making it possible to avoid some of the dangerous failures,
- common cause failures (power cuts, overvoltage, and loss of communication network) (**CCF**),
- the probability of a dangerous transmission error where digital communication is used,
- electromagnetic interference (**EMC**).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard EN/IEC 62061

Machinery safety - Safety-related electrical control systems (SRECS) *(continued)*



Risk assessment parameters



***Stage 1**: Basic structure of the electrical control system*

Standard EN/IEC 62061
Machinery safety - Safety-related electrical control systems (SRECS) *(continued)*

Process

Designing a system is split into 5 stages after having drawn up the functional safety plan:
1 - based on the safety requirements specification (**SRS**), assign a safety level (**SIL**) and identify the basic structure of the electrical control system (**SRECS**), describe each related function (**SRCF**),
2 - break down each function into a function block structure (**FB**),
3 - list the safety requirements for each function block and assign the function blocks to the sub-systems within the architecture,
4 - select the components for each sub-system,
5 - design the diagnostic function and check that the specified safety level (**SIL**) is achieved.
We will retain the previous example which consists of stopping the operation of a motor when the safety guard is opened. In the event of an incident, there is a risk of an harm being amputated or fracture of a limb.

■ **Stage 1** - Assign a safety integrity level (**SIL**) and identify the structure of the **SRECS**
Based on the risk assessment performed in accordance with standard PrEN/ISO 12100 :2009, estimation of the required **SIL** is performed for each hazardous phenomenon and is broken down into parameters, see illustration opposite.

□ Severity **Se**
The severity of injuries or damage to health can be estimated by taking into account reversible injuries, irreversible injuries and death.
The classification is shown in the table below.

Consequence	Severity Se
Irreversible: death, loss of an eye or an arm	4
Irreversible: shattered limb, loss of a finger	3
Reversible: requires the attention of a medical practitioner	2
Reversible: requires first aid	1

□ Probability of the harm occurring
Each of the three parameters **Fr**, **Pr**, **Av** must be estimated separately using the most unfavourable case. It is strongly recommended that a task analysis model be used in order to ensure that estimation of the probability of the harm occurring is correctly taken into account.
- Frequency and duration of exposure **Fr**

The level of exposure is linked to the need to access the hazardous zone (normal operation and maintenance) and the type of access (manual feeding and adjustment). It must then be possible to estimate the average frequency of exposure and its duration.
The classification is shown in the table below:

Frequency of dangerous exposure	Fr
≤ 1 hour	5
>1 hour... ≤ 1 day	5
> 1 day... ≤ 2 weeks	4
2 weeks... ≤ 1 year	3
> 1 year	2

- Probability of occurrence of a hazardous event **Pr**.

Two basic concepts must be taken into account:
- the predictability of the dangerous components in the various parts of the machine in its various operating modes (normal, maintenance, troubleshooting), paying particular attention to unexpected restarting,
- behavior of the persons interacting with the machine, such as stress, fatigue, and inexperience.

Probability of occurrence of a dangerous event	Pr
Very high	5
Probable	4
Possible	3
Almost impossible	2
Negligible	1

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard EN/IEC 62061

Machinery safety - Safety-related electrical control systems (SRECS) *(continued)*

Standard EN/IEC 62061
Machinery safety - Safety-related electrical control systems (SRECS) *(continued)*

Process *(continued)*

■ **Stage 1** - ***(continued)***

- Probability of avoiding or limiting the harm **Av**.

This parameter is linked to the design of the machine. It takes into account the suddenness of the occurrence of the hazardous event, the nature of the dangerous component (cutting, temperature, electrical) and the possibility for a person to identify a hazardous phenomenon.

Probability of avoiding or limiting the harm	Av
Impossible	5
Almost impossible	3
Probable	1

□ Assignment of the **SIL**

Estimation is made with the help of the table below.
In our example, the degree of severity is 3 because there is a risk of a finger being amputated; this value is shown in the first column of the table.
All the other parameters must be added together in order to select one of the classes (vertical columns in the table below), which gives us:
Fr = 5 accessed several times a day
Pr = 4 hazardous event probable
Av = 3 probability of avoiding almost impossible
Therefore a class Cl = 5 + 4 + 3 = 12
A level of SIL 2 must be achieved by the safety-related electrical control system(s) (**SRECS**) on the machine.

Estimation of the SIL

Se	Class Cl				
	3-4	5-7	8-10	11-13	14-15
4	SIL 2	SIL 2	SIL 2	SIL 3	SIL 3
3	-	-	SIL 1	SIL 2	SIL 3
2	-	-	-	SIL 1	SIL 2
1	-	-	-	-	SIL 1

□ Basic structure of the **SRECS**

Without going into detail about the hardware components to be used, the system is broken down into sub-systems. In our case, we find the 3 sub-systems that will perform the input, processing and output functions. The figure opposite illustrates this stage, using the terminology given in the standard.

■ **Stage 2** - Break down each function into a function block structure (**FB**)

A function block (**FB**) is the result of a detailed break down of a safety-related function.
The function block structure gives an initial concept of the SRECS architecture. The safety requirements of each block are deduced from the specification of the safety requirements of the system's function.

■ **Stage 3** - List the safety requirements for each function block and assign the function blocks to the sub-systems within the architecture

Each function block is assigned to a sub-system in the SRECS architecture. A failure of any sub-system will lead to the failure of the safety-related control function. More than one function block may be assigned to each sub-system. Each sub-system may include sub-system elements and, if necessary, diagnostic functions in order to ensure that anomalies can be detected and the appropriate action taken.
These diagnostic functions (D) are considered as separate functions; they may be performed within the sub-system, by another internal or external sub-system.

SRECS
Objective SIL 2



***Stage 2**: Break down into function blocks*

SRECS



***Stage 3**: Assignment of function blocks*

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Standard EN/IEC 62061

Machinery safety - Safety-related electrical control systems (SRECS) *(continued)*



***Stage 4**: Component selection*



Types of sub-system architecture



***Stage 5**: Design of the diagnostic function*

Standard EN/IEC 62061
Machinery safety - Safety-related electrical control systems (SRECS) *(continued)*

Process *(continued)*

■ **Stage 4** - Select the components for each sub-system

The products shown in the illustration opposite are selected. If the sensors and contactors are the same as in the previous example, a safety module XPS AK will be chosen. In this example, we take a cycle of 450s which means the duty cycle **C** is 8 operations per hour.

As the safety integrity level required for the entire system is SIL 2, each of the components must achieve this level.
The manufacturer's catalog gives the following values:
Safety limit switches 1 and 2: B_{10} = 10 000 000 operations, the proportion of dangerous failures is 20%, lifetime is 10 years.

- Safety module: $PFH_d = 7.389\ 10^{-9}$
- Contactors 1 and 2: B_{10} = 1 000 000 operations, the proportion of dangerous failures = 73%, lifetime is 20 years.

■ **Stage 5** - Design the diagnostic function

The SIL of the sub-system depends not only on the components, but also on the architecture selected. For our example, we will choose architectures B and D of the standard.
In our architecture, the safety module performs diagnostics not only on itself, but also on the safety limit switches.

We have three sub-systems for which the safety levels must be determined:

- □ SS1: two redundant safety limit switches in a sub-system with a type D architecture,
- □ SS2: a SIL 3 safety module (obtained on the basis of the PFH provided by the manufacturer),
- □ SS3: two redundant contactors built in accordance with a type B architecture.

The calculation method is quite complex, so we will only give the final result. This method takes into account the following parameters:

- **B_{10}**: number of operations at which 10% of the population fail
- **C**: Duty cycle (number of operations per hour)
- λ_D: rate of dangerous failures ($\lambda_D = \lambda$ x portion of dangerous failures in %)
- β: common cause failure coefficient, which is 10 % here and 10% is the worst case: see Annex F.
- **T1**: Proof Test Interval or life time whichever is smaller, as provided by the supplier
- **T2**: diagnostic test interval
- **DC**: Diagnostic coverage rate = λ_{DD}/λ_D, ratio between the rate of detected failures and the rate of dangerous failures.

We obtain:

- for SS1 $PFH_d = 1.6\ E^{-9}$
- for SS3 $PFH_d = 1.06\ E^{-7}$

The total probability of dangerous failures per hour is:

- $\mathbf{PFH_{DSRECS} = PFH_{DSS1} + PFH_{DSS2} + PFH_{DSS3}}$
- $\mathbf{PFH_{DSRECS}} = 1.6\ 10^{-9} + 7.38\ 10^{-9} + 1.06\ E^{-7} = 1.15\ E^{-7}$

Which corresponds to the expected result (table below) of a SIL = 2 .
Comment: A level of SIL 3 could have been achieved by using mirror contacts to create a feedback loop on the contactors, i.e. a sub-system architecture type D.

Checking the required SIL	
SIL	**Probability of dangerous failures per hour (PFHd)**
3	$\geq 10^{-8} \ldots < 10^{-7}$
2	**$\geq 10^{-7} \ldots < 10^{-6}$**
1	$\geq 10^{-6} \ldots < 10^{-5}$

7

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards
Certification and CE marking

Certification and CE marking

There are 6 stages in the process for certification and afmounting of the CE marking on machines:
1 - apply all the relevant directives,
2 - conform to the essential health and safety requirements,
3 - draw up the technical documentation,
4 - if applicable proceed with the conformity examination,
5 - draw up the Declaration of Conformity,
6- affix the CE marking.

The Machinery Directive

The Machinery Directive is an example of the “New approach” for the harmonization of products in terms of technical specifications and standards. It is based on:
- essential health and safety requirements which must be complied with before the machine is put on the market,
- a voluntary harmonization process of standards undertaken by the European Standards Committee (CEN) and the European committee for electro-technical standardisation (CENELEC).
- conformity of evaluation procedures adapted to the types of risk and associated with machine types,
- the CE marking, affixed by the manufacturer to indicate that the machine conforms to the applicable directives; machines bearing this marking can circulate freely within the European Union.

The directive has considerably simplified the multiple national legislations which were in force and has therefore removed many barriers which made trading difficult in the European Union. This has also made it possible to reduce the social cost of accidents. The directives do not apply to pre-existing machines within the EU unless they are substantially modified.
A list of the machines requiring special attestation procedures can be found in the Machinery Directive Annex 4.

The essential requirements

Annex I of the Machinery Directive groups together the essential health and safety requirements, for putting machines and safety components on the market and into service in Europe.
It follows that:
- if all the requirements of the directive are complied with, no member state of the European Union can oppose circulation of this product.
- if the requirements of the directive are not complied with, putting the product on the market may be prohibited or withdrawal of the product from the market may be required.

In the European Union, this concerns not only manufacturers or their distributors, but also importers and resellers who import these machines or put them into service. Second-hand machines within the EU are not covered, but used machines that have been modified or refurbished can be considered to be new machines.

The harmonized standards

The simplest way to demonstrate conformity with the directives is to conform to the European Harmonized Standards. When, for a product listed in Annex 4 of the Machinery Directive, there is no harmonized standard, or the existing standards are not relevant to cover the essential health and safety requirements, or if the manufacturer considers that these standards are not applicable to their product, they can apply for approval by an outside Notified Body.

These bodies are approved by the Member States after having shown that they have the recognized expertise to give such an opinion (TÜV, BGIA, INRS, and BSI Product Services.

Although the Notified Body has a certain number of responsibilities under the Directive, it is always the manufacturer or their representative who remain responsible for conformity of the product.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards
Certification and CE marking *(continued)*

Certification and CE marking *(continued)*

Declaration of conformity

In accordance with Article 1 of the Machinery Directive, the manufacturer or their authorized representative established in the European Union must draw up a European Declaration of Conformity for each machine (or safety component). This is in order to certify that the machine or safety component conforms to the Directive.
Before putting a product on the market, the manufacturer or their representative must be able to prepare a technical file.

CE marking

Finally, the CE mark must be affixed to the machine by the manufacturer or their authorized representative in the European Union. This marking has been obligatory since 1st January 1995 and can only be affixed if the machine conforms to all the applicable directives, such as:

- the Machinery Directive 2006/42/EC,
- the Electromagnetic Compatibility (EMC) directive 2004/108/EC,
- the Low Voltage Directive 2006/95/EC.

There are other directives such as the protection of persons, lifts, and medical equipment, which may also be applicable.

The CE marking is the machine's passport in the European Union, which allows it to be marketed in all countries within the Union without taking into account regulations in each individual country.

CE marking procedure



Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Relays and contactors for use in safety control Circuits with Preventa™ safety relays

Category (architecture) requirements for relays and contactors

The overall category (architecture) of a safety circuit depends on the components used in the circuit and the method of wiring. The actual maximum category possible for the safety control circuit may be reduced based on the components chosen. The relays or contactors used in a safety circuit, as well as how they are wired, can significantly affect the overall category. Relays and contactors used in the safety circuits must use linked contacts. While there are many relays and contactors available with linked contacts, a majority of them are suitable for use only in category 3 safety circuits – they are not suitable for category 4 circuits (per EN/ISO 13849-1). It is recommended that customers use relays and contactors suitable for use in category 4 circuits as these devices can be used in any safety circuit and eliminate any concern about the devices suitability for the safety circuit desired, whether Category 3 or 4.

All of the relays and contactors referenced on these pages are suitable for category 4 safety circuits.

The wiring of the safety circuit also affects the overall safety level of the installation. The following needs to be considered when designing a safety circuit:

To meet the requirements of Category 3 per EN/ISO 13849-1 (this standard deals with safety related parts of control systems), the output devices must be redundant - meaning there must be two relays or contactors in series controlling the load which can cause a hazardous movement. Using only one relay or contactor will reduce the control system to a maximum Category 2.

To meet the requirements of Category 4 per EN/ISO 13849-1, the requirements for Category 3 need to be met, plus one of the N.C. auxiliary contacts from each of the two relays or contactors in series must be wired in series in the feedback loop. Without both of these N.C. contacts wired in series in the feedback loop, the control system is reduced to a maximum Category 3. The auxiliary contacts of the relays or contactors also need to be linked contacts in conjunction with the power contacts of the relay or contactor to be suitable for Category 4. Even if there are two relays or contactors wired in series and a feedback loop is wired to the safety relay, if the contacts in the feedback loop are not linked contacts with the contacts wired to the load, the maximum category of the safety circuit is now reduced to a maximum Category 3.

The TeSys IEC contactors and 8501 Type X relays shown on the next few pages are suitable for use in safety circuits to category 4 per EN/ISO 13849-1 in the configurations listed. This is a brief listing and many more devices that meet category 4 are available. The TeSys contactors should be your first choice in any application, as they can be used for both standard control and safety related applications - for no additional cost.



Maximum Category 2 only



Meets Category 3 requirements for output portion of circuit



Meets Category 4 requirements for output portion of circuit

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Relays and contactors for use in safety control Circuits with Preventa™ safety relays *(continued)*

TeSys IEC contactors for category 4 safety circuits per EN/ISO 13849-1

Below is a listing of just some of the devices suitable for category 4 safety circuits, many more devices are available. Contact us for additional devices for your application.

Devices with mirrored auxiliary contacts:

- TeSys™ K contactors
- TeSys D contactors (up to 65 amps)
- TeSys F contactors
- TeSys N contactors

Devices with mechanically linked contact pairs:

- TeSys D contactors
- TeSys N (Sizes 00-2 only)

Examples of TeSys D devices

All TeSys D contactors (including AC and standard DC) have mechanically-linked power contacts and are suitable for use in safety circuits through Category 3 per EN/ISO 13849-1. When used with LADN•• auxiliary contacts, the combination of contactor and auxiliary contacts below meet the requirements of IEC 60947-5-1 and are suitable for use in safety circuits through Category 4 per EN/ISO 13849-1:

LC1D•••• plus LADN••
LC2D•••• plus LADN••

On contactors up to 32 A, the use of the internal auxiliary N.C. contact on the devices below also meet IEC 60947-5-1 and are suitable for use in safety circuits through Category 4 per EN/ISO 13849-1:

LC1D••••••
LC2D••••••

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Relays and contactors for use in safety control Circuits with Preventa™ safety relays *(continued)*

TeSys IEC relays for category 4 safety circuits per EN/ISO 13849-1

Below is a listing of just some of the devices suitable for category 4 safety circuits, many more devices are available. Contact us for additional devices for your application.

TeSys D Relays
TeSys D 10 amp 600 volt industrial control relays are available in fixed contact arrangements up to 9 poles. Two or four pole adder decks in a combination of N.O. and N.C. contacts can be snapped on to the basic five pole relay. TeSys D relays are built to a design specification of 30,000,000 mechanical operations.

TeSys D

The contacts of the relays below meet IEC 60947-5-1 and are suitable for use in safety circuits through Category 4 per EN/ISO 13849-1:

CADN32••
CADN50••

These relays can also be used with the following auxiliary contact blocks and all of the resulting contacts also meet the requirements of IEC 60947-5-1 and are suitable for use in safety circuits through Category 4 per EN/ISO 13849-1:

LADN••

7

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards

Relays and contactors for use in safety control Circuits with Preventa™ safety relays *(continued)*

NEMA type relays for category 4 safety circuits per EN/ISO13849-1

Type X Relays

Class 8501 Type X relays combine a rugged, heavy duty design with modular construction for greater flexibility. They are ideal for those applications where long life, high reliability and ease of maintenance are important. The Type X family offers a complete line of relays and accessories for all control applications. The basic relay has room for up to 4 convertible contact cartridges. It can be expanded to 6 or 8 poles by installing an adder deck. A 10 or 12 pole relay can be built by adding a second adder deck.

All Type X relays and adder blocks have mechanically-linked power contacts. When a Type X relay is used with any of the adder blocks, the combination of relay and additional contacts meet the requirements of IEC 60947-5-1:

Type X AC Relays

AC control relays below meet the requirements of IEC 60947-5-1 and are suitable for use in safety circuits through Category 4 per EN/ISO 13849-1:

XO00••
XO20••
XO30••
XO40••
XO60••
XO80••
XO1000••
XO1200••

AC Master relays meet IEC 60947-5-1 and are suitable for use in safety circuits through Category 4 per EN/ISO 13849-1:

XMO20••
XMO40••
XMO60••

The above Type X relays can be used with either the 8501 Type XB20 or XB40 adder decks and meet the requirements of IEC 60947-5-1. Logic reed contact blocks can be mounted to the above relays, but the contacts from these auxiliary logic reed contact blocks do not meet the requirements of IEC 60947-5-1

Type X DC Relays

DC control relays below meet the requirements of IEC 60947-5-1 and are suitable for use in safety circuits through Category 4 per EN/ISO 13849-1:

XDO00••
XDO20••
XDO40••
XDO60••
XOD80••

DC utility relays below meet IEC 60947-5-1 and are suitable for use in safety circuits through Category 4 per EN/ISO 13849-1:

XUDO40••
XUDO04••
XUDO80••
XUDO1200••
XUDO0012••

NOTE: The catalog numbers of the 8501 Type X shown above are basic offerings and include all normally open contacts. Since this product line is extremely flexible, the possible contact configurations from normally open (N.O.) and normally closed (N.C.) are far too long for this document. Refer to the catalog or Digest for a complete listing of N.O./N.C. combinations and ordering information. However, each of the contact cartridges are easily field convertible to N.C..

Overlapping contacts are available on many of the relays above by ordering Forms 1591, 1592, 1593, and 1594. Overlapping contacts are not suitable for use in safety circuits and therefore these forms should not be used where safety is concerned.

The •• indicate positions for voltage codes. Refer to the Square D Digest for complete catalog numbers.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Additional information on EU safety standards

There are many sources of information on the EU, EU standards, and directives, below is a partial list of these sources. This information has been taken from literature, personal contacts, and from the internet. While we believe this information to be correct, there may have been changes in phone numbers and addresses from when we acquired this information. If you need any additional information regarding the EU, directives or standards, please contact any of the sources listed below:

American National Standards Institute (ANSI)

(for IEC/CENELEC/CEN /ISO Standards)
1899 L Street, NW, 11th floor, Washington, DC 20036
Phone: 202-293-8020
Fax: 202-293-9287
http://web.ansi.org

American Society for Quality

600 North Plankinton Ave, Milwaukee, WI 53203
Phone: 800-248-1946
http://www.asq.org

British American Chamber of Commerce

Orlando Fashion Square Mall, 3201 E. Colonial Drive, Suite A-20, Orlando, FL 32803
Phone: 407-266-7251
http://www.britishamericanchamberorlando.com

Compliance Engineering

11444 W. Olympic Blvd., Los Angeles, CA 90064
Phone: 310-445-4200
Fax: 310-445-4299
http://www.ce-mag.com

Delegation of the European Commission

2175 K Street, Washington DC 20037
Phone: 202-862-9500
Fax: 202-429-1766
http://www.euintheus.org

European Committee for Standardization (CEN)

Avenue Marnix 17, B-1000, Brussels
Phone: 32-2-550-08-11
Fax: 32-2-550-08-19
https://www.ce.eu

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Additional information on EU safety standards *(continued)*

European Telecommunication Standards Institute (ETSI)
650 route de Lucioles, F-06291 Sophia-Antipolis Cedex, France
Phone: 33-92-94-42-00
Fax: 33-93-65-47-16
http://www.etsi.org

Global Engineering Documents
15 Inverness Way East, Englewood, Colorado 80112
Phone: 800-854-7179
Fax: 303-397-2740
http://global.ihs.com

Information Handling Services (IHS)
321 Iverness Way East, Englewood, CO 80150
http://www.ihs.com

International Electrotechnical Commission (IEC)
rue de Varembe 3, PO Box 131, CH-1211 Geneva 20, Switzerland
Phone: 41-22-919-0211
Fax: 41-22-919-0330
http://www.iec.ch

International Standards Organization (ISO)
ISO 1, ch. de la Voie-Creuse, Case postale 56, 1, CH-1211 Geneva 20, Switzerland
Phone: 41-22-749-0111
Fax: 41-22-733-3430
http://www.iso.ch

National Center for Standards and Certification Information
NCSCI
Global Standards and Information Group
National Institute of Standards and Technology
100 Bureau Drive, Stop 2100, Gaithersburg, MD 20899-2100
Phone: 301-975-4040
Fax: 301-926-1559
http://ts.nist.gov/standards/information/index.cfm

Underwriters Laboratories Inc.
333 Pfingsten Road, Northbrook IL 60062-2096
Phone: 847-272-8800
http://www.ul.com

Techstreet Inc.
Phone: 800-699-9277
http://www.techstreet.com

University of Wisconsin (Seminars on EU compliance)
University of Wisconsin, Engineering Professional Development
432 North Lake Street, Madison, WI 53706
Phone: 800-462-0876
http://epdwww.engr.wisc.edu

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

International safety standards
Additional EU information *(continued)*

Additional information on EU safety standards *(continued)*

Internet sites:

CORDIS

Information on EU research and development programs
http://cordis.europa.eu/

EUROPA

The main server for all institutions
http://europa.eu.int

EUROPARL

Information on the European Parliament's activities
http://www.europarl.europa.eu/

EUROPEAN ENVIRONMENT AGENCY

Information on the mission, products and services, and organization and staff of the EEA
http://www.eea.europa.eu

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Contents ***chapter 8***

US safety standards

Introduction *8/2*

OSHA, ANSI, and other standards *8/2*

Topics of interest *8/5*

Individual products and emergency stop *8/7*

Stop categories *8/9*

Safety relays *8/9*

Safety controllers and safety PLCs *8/9*

Guards, barriers and interlocking *8/10*

Light curtains *8/11*

Foot switches *8/12*

Summary *8/13*

Additional information on US safety standards *8/14*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
Introduction and OSHA

Introduction

There are many organizations and standards that affect safety in the United States. Some are legally required (such as OSHA regulations) and others are consensus standards guidelines by various associations. The most significant of the legally required standards are OSHA and the related ANSI standards. The OSHA standards, however, are the minimum legally required standards in the United States. Many companies have adopted ANSI and NFPA (as well as others) as part of their corporate standards, and this trend is increasing as interest in improved safety is growing. The most pertinent standards dealing with machinery and machine safety are listed below. We have not attempted to provide details on these standards since there are volumes of additional information available from OSHA, ANSI, and NFPA as well as other sources. There are other codes and standards that also need to be referenced and followed such as the National Electrical Code (NEC - NFPA 70), as well as regional and local requirements.

This section provides information from the referenced standards from OSHA, ANSI and NFPA. This material is provided to help users better understand some of the issues that need to be taken into consideration when designing new applications or upgrading current applications when the safety of personnel is concerned. The complete versions of the referenced standards must be used, read, and referenced whenever designing safety solutions, as more detailed information and additional information is provided in the complete versions of these standards.

Hazards to Personnel

When considering potential safety hazards for personnel, it is easy for everyone to recognize examples of some safety hazards, such as presses or saws, because they are easy to visualize. Some hazards that are often overlooked but are no less dangerous to personnel are:

- Chemical
- Thermal - both heat and cold
- Electrical and shock
- Magnetic
- Toxicity
- Hydraulic
- Pneumatic
- Mechanical
- Kinetic
- Movement of mechanical components, whether related to the equipment under consideration or not
- Plus many more

OSHA 29 CFR1910 Occupational Safety and Health Standards

OSHA began as the Occupational Safety and Health Act of 1970, passed as an act of Congress “to assure so far as possible every working man and woman in the Nation safe and healthful working conditions and to preserve our national resources.” This act is mandatory and legally binding in the United States.

The Occupational Safety and Health Administration (OSHA) standards cover a number of topics regarding safety and health, from A to Z, including Work Surfaces, Hazardous Materials, Personal Protective Equipment, as well as many others.

While OSHA does cover a great deal of topics and areas of safety, there are other organizations that are not government agencies that have developed standards for various industries or situations. OSHA has, in many cases, chosen to use existing consensus standards instead of developing new ones. Many of these existing standards are referenced in OSHA 1910, and according to 1910.6, these “organizations which are not agencies of the U.S. Government which are incorporated by reference in this part, have the same force and effect as other standards in this part”. OSHA has incorporated the standards of two primary standards groups, the American National Standards Institute (ANSI) and the National Fire Protection Association (NFPA), into its set of standards.

Subpart O of 1910 deals with Machinery and Machinery Guarding. Subpart R deals with Special Industries. The topics for Subpart O and R are listed below; followed by Subparts J and S which are of interest to anyone involved with machinery.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
OSHA

OSHA 29 CFR1910 Occupational Safety and Health Standards (continued)

OSHA 1910, Subpart O, Machinery and Machine Guarding

1910.211 Definitions

1910.212 General Requirements for all Machines

1910.213 Woodworking Machinery Requirements

1910.214 Cooperage Machinery

1910.215 Abrasive Wheel Machinery

1910.216 Mills and Calenders in the Rubber and Plastics Industries

1910.217 Mechanical Power Presses

1910.218 Forging Machines

1910.219 Mechanical Power Transmission Apparatus

1910.220 Effective Dates

1910.221 Source of Standards

1910.222 Standards Organizations

OSHA 1910, Subpart R, Special Industries

1910.261 Pulp, Paper, and Paperboard Mills

1910.262 Textiles

1910.263 Bakery Equipment

1910.264 Laundry Machinery and Operations

1910.265 Sawmills

1910.266 Logging Operations

1910.267 Agricultural Operations

1910.268 Telecommunications

1910.269 Electric Power Generation, Transmission, and Distribution

1910.272 Grain Handling Facilities

OSHA 1910 Subpart J, General Environmental Controls

1910.147 Control of Hazardous Energy (also known as Lockout/Tagout)

This standard was effective as of January 2, 1990. It was adopted to help safeguard personnel from hazardous energy while maintaining or servicing equipment. Before maintenance is performed, the hazardous energy must be turned off to the machine, and an energy-isolating device must be used to either lockout or tagout the machine.

This energy source can be electrical, mechanical, hydraulic, pneumatic, chemical, thermal, or other forms of energy. Multiple energy sources may need to be locked out/tagged out before service or maintenance can be performed on the equipment. Section (b) of this standard states “Push buttons, selector switches, and other control circuit type devices are not energy isolating devices.” This would include limit switches, safety interlock switches, cable pull switches, and other types of control equipment. 1910.147 may be the most far reaching standard OSHA has adopted, covering virtually all equipment in use today.

The lockout/tagout is similar in principle to the European Machinery Directive 98/37/EC, Annex 1, Isolation of Energy Sources.

OSHA 1910 Subpart S, Electrical

This subpart addresses electrical safety requirements that are necessary for the practical safeguarding of employees in their workplaces.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
ANSI

The American National Standards Institute (ANSI)

The American National Standards Institute (ANSI) is a private, nonprofit membership organization supported by a diverse constituency of private and public sector organizations, founded in 1918. ANSI does not develop standards, but acts as a facilitator in establishing voluntary consensus standards with various groups. They promote US standards internationally and encourage the adoption of international standards as national standards. ANSI was a founding member of the ISO, and is still active in governing it. They are also strong members of the IEC.

ANSI B11.19, Performance Criteria for Safeguarding

Of the many ANSI standards available, the ANSI B11 Series standards are the most pertinent to machines and machine safety. One of the most pertinent of these standards for general industrial use is: “ANSI B11.19, Performance Criteria for Safeguarding”

B11.1 Mechanical Power Presses – Safety Requirements for Construction, Care and Use

B11.2 Hydraulic Power Presses – Safety Requirements for Construction, Care and Use

B11.3 Safety Requirements for Power Press Brakes

B11.4 Safety Requirements for Shears

B11.5 Iron Workers - Safety Requirements for Construction, Care and Use

B11.6 Safety Requirements for Manual Turning Machines

B11.7 Cold Headers and Cold Formers - Safety Requirements for Construction, Care and Use

B11.8 Safety Requirements for Manual Milling, Drilling and Boring Machines

B11.9 Safety Requirements for Construction, Care and Use of Grinding Machines

B11.10 Safety Requirements for Metal Sawing Machines

B11.11 Safety Requirements for Gear and Spline Cutting Machines

B11.12 Safety Requirements for Roll Forming and Roll Bending Machines

B11.13 Automatic Screw/Bar and Chucking Machines – Safety Requirements for Construction, Care and Use

B11.14 Coil Slitting Machines – Safety Requirements for Construction, Care and Use

B11.15 Safety Requirements for Pipe, Tube, and Shape Bending Machines

B11.16 Safety Requirements for Powder/Metal Compacting Presses

B11.17 Safety Requirements for Horizontal Hydraulic Extrusion Presses

B11.18 Safety Requirements for Machines Processing or Slitting Coiled or Non-Coiled Metal

B11.19 Performance Criteria for Safeguarding

B11.20 Safety Requirements for Integrated Manufacturing Systems

B11.21 Safety Requirements for Machine Tools Using Lasers for Processing Materials

B11.22 Safety Requirements for Turning Centers and Automatic, Numerically Controlled Turning Machines

B11.23 Safety Requirements for Machining Centers and Automatic, Numerically Controlled Milling, Drilling and Boring Machines

B11.24 Safety Requirements for Transfer Machines.

Technical Reports and Explanatory Information

B11.TR1 Ergonomic Guidelines for the Design, Installation and Use of Machine Tools

B11.TR2 Mist Control Considerations for the Design, Installation and Use of Machine Tools Using Metalworking Fluids

B11.TR3 Risk Assessment and Risk Reduction – A guide to estimate, evaluate and reduce risks associated with machine tools

B11.TR4 Selection of Programmable Electronic Systems (PES/PLC) for Machine Tools

B11.TR5 Sound Level Measurement Guidelines – A guide for measuring, evaluating, documenting and reporting sound levels emitted by machinery

B11.TR6 Safety Control Systems for Machine Tools

B11.TR7 Designing for Safety and Lean Manufacturing – A guide on integrating safety and lean manufacturing principles in the use of machinery

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
Additional standards and topics of interest

Additional Standards

Industrial Robots and Robot System Safety

OSHA has recommended

• That robots comply with ANSI/RIA R15.06 (1999), Manufacturing, Remanufacture and Rebuild of Robots. Some of the sections of this standard deal with: manufacture, remanufacture, and rebuild of robots (section 4), performance requirements of safeguarding devices (section 5), installation of robots and robot systems (section 6), safeguarding of personnel (section 7, 8, and 9). In addition, robots and robot systems must comply with OSHA 1910.333 and 1910.147.

• This recommendation is a part of OSHA instruction TED 1.15, September 1995, from the Office of Science and Technology Assessment.

National Fire Protection Association (NFPA)

The NFPA has developed many standards covering a wide variety of subjects over the past 100 years. While they began out of a need to standardize on automatic sprinkler system standards, they grew to become the major recognized group in fire protection in the United States, and are recognized internationally as well.

NFPA 79 began in 1941, with an NFPA subcommittee. It appeared as a supplement to the 1940 NEC in Article 670 - Machine Tools, and remained in Article 670 through the 1959 edition of the NEC. It was officially adopted as a stand alone standard in 1962, but continues to be referenced in Article 670 of the NEC. NFPA 79 – Electrical Standard for Industrial Machinery, as its title indicates, covers all industrial machinery in the US and should be a frequently referred to standard in all industrial facilities.

Topics of interest

Several topics on safety have generated significant interest over the past few years, and these topics are discussed below for general industrial applications. There are standards specific to particular industries in the various standards, and these need to be consulted separately. There are also standards specific to certain types of machinery, and these need to be consulted separately as well. Below are topics that are of the most interest for general industrial machinery.

Similarities between the US standards are noted, as well as similarities to European EN and IEC standards. There has been significant interest in the European and IEC standards recently, and it is interesting to note the similarities between the European standards and US nationally accepted consensus standards and OSHA. As many of the various standards evolve, the US, IEC, and EN standards are becoming more similar, resulting in fewer differences than just a decade ago. Companies doing business globally are already familiar with the EN and IEC standards and their requirements.

References to these standards are provided in the sections below for reference only. The complete versions of the referenced standards must be used, read, and referenced whenever designing safety solutions, as more detailed information and additional information is provided in the complete versions of these standards.

Safety systems and qualified persons

Safety systems are comprised of many components. No one safety component will insure the safety of the system. The design of the complete safety system should be considered before you begin. It is very important to follow applicable safety standards when installing and wiring these components. OSHA has a similar definition of safety systems in their standards. OSHA and ANSI have also defined an “authorized (qualified) person” to perform tasks, and that the authority is given by the employer to this person. This person has also received training on the hazards involved in the tasks they are to perform. It important that appropriately trained and qualified personnel design, develop and maintain safety equipment and systems to provide an appropriate safety level for all personnel.

OSHA 1910.211 Definitions - Safety System

(d) (60) (d) (62) “Safety system” means the integrated total system, including the pertinent elements of the press, the controls, the safeguarding, and any required supplemental safeguarding, and their interfaces with the operator, and the environment, designed, constructed, and arranged to operate together as a unit, such that a single failure or single operating error will not cause injury to personnel due to point of operation hazards.

OSHA 1910.211 Definitions – Authorized Person

(d) (63) “Authorized person” means one to whom the authority and responsibility to perform a specific assignment has been given by the employer.

NFPA 79 – Definitions: Qualified Person.

One who has skills and knowledge related to the construction and operation of the electrical equipment and installations and has received safety training on the hazards involved.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
Topics of interest

Topics of interest *(continued)*

User's Responsibilities

The user (employer) is responsible for ensuring the safeguarding equipment is installed and maintained correctly, and that the various personnel are trained in the operation and maintenance of the safeguarding

ANSI B11.19 defines a user as:

- An entity that utilizes machines, systems, and related equipment.
- An individual, corporation, partnership, or other legal entity or form of business that employs individuals to operate and maintain manufacturing systems/cells.

ANSI B11.19 states the user's responsibilities include:

- The user shall be responsible for ensuring that safeguarding is provided, integrated, installed, maintained, and used in accordance with the requirements of this standard.
- The user shall be responsible for ensuring that supervisors, operators, maintenance and service personnel are trained in the proper installation, adjustment, operation and maintenance of the safeguarding, within the scope of their work activity.

Control Reliability

The sections identified below for control reliability are very similar to the intent of Category 3 and 4 as defined in European Harmonized Standard EN/ISO 13849-1. In all cases, if a single component fails, it shall not prevent the normal stopping action of the machine, and it does prevent the machine from re-starting.

It stands to reason that if a single component fails, there must be a similar component available to complete the stopping action, and that there must be some type of checking circuit to acknowledge that single component failure and prevent a re-start of the machine. This would suggest some type of redundancy of the various components and self checking circuitry would be required if a circuit is to be control reliable.

OSHA 1910.217 (b) (13) Control Reliability

The control system shall be constructed so that a failure within the system does not prevent the normal stopping action from being applied to the press when required, but does prevent initiation of a successive stroke until the failure is corrected. The failure shall be detectable by a simple test, or indicated by the control system. This requirement does not apply to those elements of the control system which have no effect on the protection against point of operation injuries.

ANSI B11.19 and ANSI/RIA 15.06 both provide a definition of Control Reliability similar to the one below:

The control system shall be designed, constructed, and installed such that a single control component failure within the system does not prevent stopping action from taking place but will prevent successive system cycles until the failure has been corrected.

Electrical Equipment

Many standards require conformance to NFPA 79 for electrical equipment and emergency stop devices. Two such standards are ANSI B11.19 and ANSI B11.20.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Requirements for individual products

There are many products used in control systems for safety, and each of these products perform different functions in their application, either as emergency stopping or for guarding personnel. The various safety standards have specific requirements for each of these devices, and a summary of some of these requirements are listed in the following sections. Some of the requirements listed here have been in the US standards for a long time, while many of the requirements have changed over the past few years. As these standards evolve, it is important to keep up to date on the changes as they will affect the design of your equipment.

The information listed here is intended to help make the reader aware of some of the US safety requirements. The complete versions of the referenced standards must be used, read, and referenced whenever designing safety solutions, as more detailed information and additional information is provided in the complete versions of these standards.

Emergency Stop

This section is divided into 5 different groups, due to the amount of information available and to make it easier to locate the information required. Most of the references in this section are from NFPA 79, since ANSI B11.19 states that Stop and emergency stop devices shall meet the requirements of NFPA 79.

General Emergency Stop Requirements

Listed below are highlights of the requirements for emergency stop devices per NFPA 79. For full details, please refer to NFPA 79.

- Emergency stop devices must have absolute priority over all other functions.
- Must have stop or emergency stop capability at each operator workstation and other locations where emergency stop is required.
- Every machine must have a category 0 emergency stop or category 1 emergency stop.
- Emergency stop devices shall include push button, pull-cord (cable pull) or foot switch (without cover).
- Emergency stop switches shall not be flat switches or graphic representations based on software applications.
- Must have self latching means (i.e.: pull to release or rotate).
- Shall be initiated by a single human action.
- Must be manually reset.
- Resetting of the e-stop shall not restart the machinery but only permit restarting.
- Must have positive/direct opening contacts.
- RED actuator with a YELLOW background.
- The emergency stop devices must be continuously operable and readily accessible.

ANSI has some additional information on emergency stops as follows:

ANSI B11.19: STOP AND EMERGENCY STOP DEVICES

Stop and emergency stop devices are not safeguarding devices. They are complimentary to the guards, safeguarding devices, awareness barriers, signals and signs, safeguarding methods and safeguarding procedures.

Stop and emergency stop devices must meet the requirements of ANSI/ NFPA 79.

ANSI/RIA R15.06 also states that the emergency stop shall be fully compliant to NFPA 79.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Emergency Stop *(continued)*

1. Emergency Stop Color

Actuators of emergency stop devices shall be red and the background around these devices shall be yellow. Visibility and recognition of emergency stop devices is the primary concern. The red and yellow color combination shall only be used for emergency stop applications.

OSHA 1910.144: Safety color code for marking physical hazards.

(a)(1)(iii) Stop. Emergency stop bars on hazardous machines such as rubber mills, wire blocks, flat work ironers, etc., shall be red. Stop buttons or electrical switches which letters or other markings appear, used for emergency stopping of machinery shall be red.

2. Emergency Stop Device Types

Emergency stop devices include mushroom head push buttons, pull cord (cable pull), push bar (bumper guards), and foot switches (without mechanical guards). Mushroom head push buttons shall be self latching and have positive opening contacts.

Push button-type devices for emergency stop shall be of the self-latching type and shall have direct opening operation.

Emergency stop switches shall not be flat switches or graphic representations based on software applications.

3. Emergency Stop Function

- Emergency stop devices shall override all other controls.
- They shall be hard wired into the emergency stop circuit.
- Where emergency stop or emergency switching off is used, it shall be initiated by a single human action, and must be manually re-set.
- Resetting of the emergency stop device shall not start, restart, nor cause any hazardous motion or condition.

4. Emergency Stop Location

Emergency stop devices shall be at every operator workstation and other locations where required; continuously operable; readily accessible; and easily distinguishable from other controls.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards

Stop categories, safety relays, safety controllers and PLCs

Stop Categories

The NFPA 79 Stop Category 0, 1 and 2 identified below are very similar to the same Stop Categories in IEC/EN 60204-1. There are no similar stop categories identified in OSHA 1910. The choice of stop category to use is determined by the type of machine and control circuit used, plus the hazards available to personnel.

The three categories of stop functions shall be as follows:

1. Category 0 is an uncontrolled stop by immediately removing power to the machine actuators.
2. Category 1 is a controlled stop with power to the machine actuators available to achieve the stop then remove power when the stop is achieved.
3. Category 2 is a controlled stop with power left available to the machine actuators.

All machines shall have a Category 0 stop.

Safety Relays

Safety relays and their use are now referenced as such in US standards (i.e.: ANSI B11.9).

ANSI B11 also states: A safety (relay) interface module usually consists of monitored, multiple, force-guided captive contact relays, or other devices. A single discrete force-guided captive contact relay does not meet the requirements of this standard.

Safety Controllers and Safety PLCs

Control Systems Incorporating Software and Firmware based Controllers are referenced in NFPA 79.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
Guards, barriers and interlocking



Guards, Barriers and Interlocking

There are many ways to protect personnel: guards and barriers, two hand controls, light curtains, and sometimes distance. These methods are discussed in this section. Guards will be discussed first.

Guards need to prevent personnel from being in the hazardous zones when the machine is operating, and machinery cannot be operated with the guards open. It is clear that the responsibility for these guards falls on the employer per OSHA.

General Requirements

Some of the requirements of guards and interlocks are as follows:

- Guards or interlocks shall be difficult to defeat.
- Devices used in safety related functions shall have positive (direct) opening contacts.
- Closing of the guard or interlock shall not initiate machine motion or any hazardous condition
- When doors or guards are opened and open, no hazardous motion or condition can exist
- Machinery is allowed to start and run only when gates and guards are closed.
- Switches and interlocks shall be installed so they will not be damaged on over-travel.
- Guards and safeguarding devices must be positioned so that personnel cannot reach the hazard prior to the hazardous condition being eliminated (i.e.: hazardous motion stopped)
- The guard shall be designed and installed so that personnel cannot reach over, under, around, or through the guard.

When guards, barriers, light curtains or other safeguarding is used to protect personnel, there is always a minimum safety distance required to protect personnel from harm. With hard guards or barriers, this distance may be determined by the size of the openings in the guard and using a table or chart for the correct minimum safety distance, i.e.: OSHA 1910.217 Table O-10. Other safeguarding devices, such as light curtains or two hand control devices, need to be located a minimum distance away from the hazard such that the hazardous situation can be eliminated before an individual can be injured. ANSI B11.19, Annex on Safety Distance is an excellent resource for determining these minimum safety distances. It covers a wide variety of safeguarding techniques and methods to determine the minimum safety distances and the factors that need to be considered.

Standards References

OSHA 1910.212 General Requirements for all Machines
(a) (1) Types of guarding. One or more methods of machine guarding shall be provided to protect the operator and other employees in the machine area from hazards such as those created by point of operation, ingoing nip points, rotating parts, flying chips, and sparks. Examples of guarding methods are: barrier guards, two-hand tripping devices, and electronic safety devices.

OSHA 1910.212 General Requirements for all Machines
(a) (3) (ii) The point of operation of machines whose operation exposes an employee to injury, shall be guarded. The guarding device shall be in conformity with any appropriate standards therefore, or, in the absence of applicable specific standards, shall be so designed and constructed as to prevent the operator from having any part of his body in the danger zone during the operating cycle.

OSHA 1910.217 Mechanical Power presses
(c) (1) (i) It shall be the responsibility of the employer to provide and ensure the usage of “point of operation guards” or properly applied and adjusted point of operation devices on every operation performed on a mechanical power press. See Table O-10.

OSHA 1910.217 Table O-10 identifies the minimum distance from the barrier or guard to the point of operation hazard based on the size of the opening. If there are any openings in the guard, such as holes or openings in a mesh guard, the maximum dimensions of these openings are used as the basis for use with Table O-10

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Light Curtains

The application, use, and installation of light curtains is covered in much greater detail in Chapter 5 of this catalog. The safety distance formulas in Chapter 5 must be used to determine the minimum safety distance a light curtain must be mounted away from the hazardous activity, based on the particular machine and light curtain used. Listed below are some highlights from ANSI B11.19 regarding light curtains.

The presence sensing device shall incorporate visual means to indicate that the device is detecting an individual within the sensing field of the device.

Exposure to the hazard(s) shall not be possible by reaching over, under or around the sensing field of the device. Additional guards or safeguarding devices shall be provided to protect these areas.

The effective sensing field shall be of adequate height, width and depth so that entry of the individual into the hazard area is detected.

If individuals can place themselves between the sensing field and the hazard area, additional safeguarding should be used in conjunction with the device to prevent the individual from exposure to the hazard.

The presence sensing device shall be installed at a location so that the effective sensing field prevents individuals from reaching the hazard(s) during the hazardous portion of the machine cycle

The presence-sensing device shall protect individuals from hazards by initiating an immediate stop command to the machine control system when the sensing field of the device is interrupted during the hazardous portion of the machine cycle. It shall require re-initiation of the normal actuating means prior to the start or continuation of the motion of the machine

When an individual can pass through the sensing field of the presence-sensing device, the device shall initiate an immediate stop command to the machine control system and shall require that the device be manually reset before hazardous motion can occur.

The reset device shall be located outside of the safeguarded area such that it cannot be reached from the safeguarded area. Reset of the device or machine control shall not occur until verification that the safeguarded area is clear of individuals.

The operator should ensure that no individual is in the safeguarded area before re-setting the device or machine control and initiating hazardous motion.

An additional item of interest regarding light curtains is the Presence Sensing Device Initiation (PSDI): See OSHA 1910.217 (h)

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
Foot switches

Foot Switches

Foot switches are not considered to be safety products, but they have been used to keep personnel out of reach of a hazard. An example is the operator of a machine using the foot switch to start and run the machine. When an operator removes their foot from the foot switch, the machine stops. The foot switch needs to be located a sufficient distance away from the machine to keep the operator out of harm's way.

The references below indicate that foot switches need to be protected from accidental operation from falling objects and unintended operation. Foot switches used for emergency stop need to be unguarded.

OSHA 1910.217(b)(7)(x) MECHANICAL POWER PRESSES
Foot operated tripping controls, if used, shall be protected so as to prevent operation from falling or moving objects, or from unintended operation by accidental stepping onto the foot control.

OSHA 1910.218(b)(2) MECHANICAL POWER PRESSES
Foot operated devices. All foot operated devices (i.e., treadles, pedals, bars, valves, and switches) shall be substantially and effectively protected from unintended operation.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
Summary

Summary

Safety systems are comprised of many components. No one safety component will insure the safety of the system. The design of the complete safety system should be considered before you begin. It is very important to follow applicable safety standards when installing and wiring these components.

This appendix provides portions of the references standards from OSHA, ANSI and NFPA. This material is provided to help users better understand some of the issues that need to be taken into consideration when designing new applications or upgrading current applications when the safety of personnel is concerned. The complete versions of the referenced standards must be used, read, and referenced whenever designing safety solutions, as more detailed information and additional information is provided in the complete versions of these standards.

Reprinted with permission from NFPA 79, Electrical Standard for Industrial Machinery Copyright © 2002, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.

This material is reproduced from American National Standard ANSI B11.19 copyright 2003 and ANSI B11.20 copyright 1996 with permission of the American National Standards Institute. No part of this material may be copied or reproduced in any form, electronic retrieval system or otherwise or made available on the Internet, a public network, by satellite or otherwise without the prior written consent of the American National Standards Institute. Copies of this standard may be purchased from the American National Standards Institute, 11 West 42nd Street, New York, NY 10036.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
Additional information

Additional information on US Safety Standards

There are many sources of information on US safety standards, and below is a partial list of these sources. This information was taken from literature, personal contacts, and from the internet. While we believe this information to be correct, there may have been changes in phone numbers and addresses from when we acquired this information. If you need any additional information regarding the US safety standards, please contact any of the sources listed below:

American National Standards Institute (ANSI)
1899 L Street, NW, 11th Floor, Washington, DC 20036
Phone: 202-293-8020
Fax: 202-293-9287
http://web.ansi.org

American Society of Mechanical Engineers (ASME)
Two Park Avenue, New York, NY 10016-5990
Phone: 800-843-2763 (U.S/Canada)
http://www.asme.org

American Society for Testing and Materials (ASTM)
100 Barr Harbor Drive, West Conshohocken, Pennsylvania, USA 19428-2959
http://www.astm.org

Association for Manufacturing Technology (AMT)
7901 Westpark Dr., McLean, VA 22102-4206
Phone: 703-893-2900
Fax: 703-893-1151
http://www.mfgtech.org

IHS
15 Inverness Way East, Englewood, Colorado 80112
Phone: 800-854-7179
Fax: 303-397-2740
http://global.ihs.com

Institute of Electrical and Electronics Engineers (IEEE)
Operations Center, 445 Hoes Lane, Piscataway, New Jersey 08854-5997
Phone: 732-981-0060
http://www.ieee.org

National Fire Protection Association (NFPA)
1 Batterymarch Park, Quincy, MA 02169-7471
Phone: 617-770-3000
Fax: 617-770-0700
http://www.nfpa.org

National Institute for Occupational Safety and Health (NIOSH)
1600 Clifton Rd. Atlanta, GA 30333
Phone: 800-232-4636
http://www.cdc.gov/niosh/

National Safety Council
1121 Spring Lake Dr., Itasca, IL 60143-3201
Phone: 800-621-7615
http://www.nsc.org

NEMA
1300 N. 17th Street, Suite 900, Arlington, VA, 22209.
Phone: 703-841-3200
Fax: 703-841-5900,
http://www.nema.org

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

US safety standards
Additional information

Additional information on US Safety Standards *(continued)*

NIST (National Institute of Standards and Technology)
100 Bureau Drive, Stop 2100, Gaithersburg, MD 20899-2100
Phone: 301-975-2020
http://www.nist.gov/

Occupational Safety and Health Administration (OSHA)
http://www.osha.gov

Precision Metalforming Association (PMA)
6363 Oak Tree Blvd., Independence, Ohio 44131-2500
Phone: 216-901-8800 ---- Fax: 216-901-9190
http://www.pma.org

Robotic Industries Association
900 Victors Way, Suite 140, Ann Arbor, Michigan 48106
Phone: 313-994-6088
http://www.robotics.org

Society of Automotive Engineers (SAE)
400 Commonwealth Drive, Warrendale, PA 15096-0001
Phone: 724-776-4841
http://www.sae.org

Underwriters Laboratories Inc.
333 Pfingsten Rd., Northbrook, IL 60062
Phone: 847-272-8800
http://www.ul.com

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Technical information

Product standards and certifications *9/2*

Degrees of protection provided by enclosures

IP code *9/4*
IK code *9/5*

Contact design and operation *9/6*

Glossary *9/10*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Technical information
Product standards and certifications

Standardization

Conformity to standards

Telemecanique brand products satisfy, in the majority of cases, national (for example: BS in Great Britain, NF in France, DIN in Germany), European (for example: CENELEC) or international (IEC) standards. These product standards precisely define the performance of the designated products (such as IEC 60947 for low voltage equipment). When used correctly, as designated by the manufacturer and in accordance with regulations and correct practices, these products will allow users to build equipment, machine systems or installations that conform to their appropriate standards (for example: IEC 60204-1, relating to electrical equipment used on industrial machines). Schneider Electric is able to provide proof of conformity of its production to the standards it has chosen to comply with, through its quality assurance system.

On request, and depending on the situation, Schneider Electric can provide the following:

- a declaration of conformity,
- a certificate of conformity (ASEFA/LOVAG),
- a homologation certificate or approval, in the countries where this procedure is required or for particular specifications, such as those existing in the merchant navy.

Code	Certification authority		Country
	Name	Abbreviation	
ANSI	American National Standards Institute	ANSI	USA
BS	British Standards Institution	BSI	Great Britain
CEI	Comitato Elettrotecnico Italiano	CEI	Italy
DIN/VDE	Verband Deutscher Electrotechniker	VDE	Germany
EN	Comité Européen de Normalisation Electrotechnique	CENELEC	Europe
GOST	Gosudarstvenne Komitet Standartov	GOST	Russia
IEC	International Electrotechnical Commission	IEC	Worldwide
JIS	Japanese Industrial Standard	JISC	Japan
NBN	Institut Belge de Normalisation	IBN	Belgium
NEN	Nederlands Normalisatie Institut	NNI	Netherlands
NF	Union Technique de l'Electricité	UTE	France
SAA	Standards Association of Australia	SAA	Australia
UNE	Asociacion Española de Normalizacion y Certificacion	AENOR	Spain

European EN standards

These are technical specifications established in conjunction with, and with approval of, the relative bodies within the various CENELEC member countries (European Union, European Free Trade Association and many central and eastern European countries having "member" or "affiliated" status). Prepared in accordance with the principle of consensus, the European standards are the result of a weighted majority vote. Such adopted standards are then integrated into the national collection of standards, and contradictory national standards are withdrawn. European standards incorporated within the French collection of standards carry the prefix NF EN. At the 'Union Technique de l'Electricité' (Technical Union of Electricity) (UTE), the French version of a corresponding European standard carries a dual number: European reference (NF EN …) and classification index (C …). Therefore, the standard NF EN 60947-4-1 relating to motor contactors and starters, effectively constitutes the French version of the European standard EN 60947-4-1 and carries the UTE classification C 63-110. This standard is identical to the British standard BS EN 60947-4-1 or the German standard DIN EN 60947-4-1. Whenever reasonably practical, European standards reflect the international standards (IEC). With regard to automation system components and distribution equipment, in addition to complying with the requirements of French NF standards, Telemecanique brand components conform to the standards of all other major industrial countries.

Regulations

European Directives

Opening up of European markets assumes harmonization of the regulations pertaining to each of the member countries of the European Union. The purpose of the European Directive is to eliminate obstacles hindering the free circulation of goods within the European Union, and it must be applied in all member countries. Member countries are obliged to transcribe each Directive into their national legislation and to simultaneously withdraw any contradictory regulations. The Directives, in particular those of a technical nature which concern us, only establish the objectives to be achieved, referred to as "essential requirements". The manufacturer must take all the necessary measures to ensure that his products conform to the requirements of each Directive applicable to his production. As a general rule, the manufacturer certifies conformity to the essential requirements of the Directive(s) for his product by affixing the CE mark. The CE mark is affixed to Telemecanique brand products concerned, in order to comply with French and European regulations.

Significance of the CE mark

- The CE mark affixed to a product signifies that the manufacturer certifies that the product conforms to the relevant European Directive(s) which concern it; this condition must be met to allow free distribution and circulation within the countries of the European Union of any product subject to one or more of the E.U. Directives.
- The CE mark is intended solely for national market control authorities.
- The CE mark must not be confused with a conformity marking.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

European Directives (continued)

For electrical equipment, only conformity to standards signifies that the product is suitable for its designated function, and only the guarantee of an established manufacturer can provide a high level of quality assurance. For Telemecanique brand products, one or several Directives are likely to be applicable, depending on the product, and in particular:

- the Low Voltage Directive 2006/95/EC: the CE mark relating to this Directive has been compulsory since January 16, 2007.
- the Electromagnetic Compatibility Directive 89/336/EEC, amended by Directives 92/31/EEC and 93/68/EEC: the CE mark on products covered by this Directive has been compulsory since January 1, 1996

ASEFA-LOVAG certification

The function of ASEFA (Association des Stations d'Essais Française d'Appareils électriques - *Association of French Testing Stations for Low Voltage Industrial Electrical Equipment*) is to carry out tests of conformity to standards and to issue certificates of conformity and test reports. ASEFA laboratories are authorized by the French authorization committee (COFRAC). ASEFA is now a member of the European agreement group LOVAG (Low Voltage Agreement Group). This means that any certificates issued by LOVAG/ASEFA are recognized by all the authorities which are members of the group and carry the same validity as those issued by any of the member authorities.

Quality labels

When components can be used in domestic and similar applications, it is sometimes recommended that a "Quality label" be obtained, which is a form of certification of conformity.

Code	Quality label	Country
CEBEC	Comité Electrotechnique Belge	Belgium
KEMA-KEUR	Keuring van Electrotechnische Materialen	Netherlands
NF	Union Technique de l'Electricité	France
ÖVE	Österreichischer Verband für Electrotechnik	Austria
SEMKO	Svenska Electriska Materiel Kontrollanatalten	Sweden

Product certifications

In some countries, the certification of certain electrical components is a legal requirement. In this case, a certificate of conformity to the standard is issued by the official test authority. Each certified device must bear the relevant certification symbols when these are mandatory:

Code	Certification authority	Country
CSA	Canadian Standards Association	Canada
UL	Underwriters Laboratories	USA
CCC	China Compulsory Certification	China

Note on certifications issued by the Underwriters Laboratories (UL). There are two levels of approval:

"Recognized" ( ) The component is fully approved for inclusion in equipment built in a workshop, where the operating limits are known by the equipment manufacturer and where its use within such limits is acceptable by the Underwriters Laboratories.
The component is not approved as a "Product for general use" because its manufacturing characteristics are incomplete or its application possibilities are limited.
A "Recognized" component does not necessarily carry the certification symbol.

"Listed" (UL) The component conforms to all the requirements of the classification applicable to it and may therefore be used both as a "Product for general use" and as a component in assembled equipment. A "Listed" component must carry the certification symbol.

Marine classification societies

Prior approval (= certification) by certain marine classification societies is generally required for electrical equipment which is intended for use on board merchant vessels.

Code	Classification authority	Country
BV	Bureau Veritas	France
DNV	Det Norske Veritas	Norway
GL	Germanischer Lloyd	Germany
LR	Lloyd's Register	Great Britain
NKK	Nippon Kaiji Kyokaï	Japan
RINA	Registro Italiano Navale	Italy
RRS	Register of Shipping	Russia

Note

For further details on a specific product, please refer to the "Specifications" pages in this catalog or consult your Regional Sales Office.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Technical information

Degrees of protection provided by enclosures

IP code

Degrees of protection against the penetration of solid bodies, water and personnel access to live parts

The European standard EN 60529 dated October 1991, IEC publication 529 (2nd edition - November 1989), defines a coding system (IP code) for indicating the degree of protection provided by electrical equipment enclosures against accidental direct contact with live parts and against the ingress of solid foreign objects or water. This standard does not apply to protection against the risk of explosion or conditions such as humidity, corrosive gasses, fungi or vermin.
Certain equipment is designed to be mounted on an enclosure which will contribute towards achieving the required degree of protection (for example: control devices mounted on an enclosure).
Different parts of an equipment can have different degrees of protection (for example: enclosure with an opening in the base).
Standard NF C 15-100 (December 2002 edition), section 512, table 51 A, provides a cross-reference between the various degrees of protection and the environmental conditions classification, relating to the selection of equipment according to external factors.
Practical guide UTE C 15-103 shows, in the form of tables, the characteristics required for electrical equipment (including minimum degrees of protection), according to the locations in which they are installed.

IP ●●● code

The IP code comprises **2 characteristic numerals** (e.g. **IP 55**) and may include **an additional letter** when the actual protection of personnel against direct contact with live parts is better than that indicated by the first numeral (e.g. IP 20C).
Any characteristic numeral which is unspecified is replaced by an X (e.g. IP XXB).

1st characteristic numeral:

corresponds to protection of the equipment against penetration of solid objects and protection of personnel against direct contact with live parts.

	Protection of the equipment		Protection of personnel
0	Non-protected		Non-protected
1		Protected against the penetration of solid objects having a diameter greater than or equal to 50 mm	Protected against direct contact with the back of the hand (accidental contacts).
2		Protected against the penetration of solid objects having a diameter greater than or equal to 12.5 mm.	Protected against direct finger contact.
3		Protected against the penetration of solid objects having a diameter greater than or equal to 2.5 mm.	Protected against direct contact with a Ø 2.5 mm tool.
4		Protected against the penetration of solid objects having a diameter > 1 mm.	Protected against direct contact with a Ø 1 mm wire.
5		Dust protected (no harmful deposits).	Protected against direct contact with a Ø 1 mm wire.
6		Dust tight.	Protected against direct contact with a Ø 1 mm wire.

2nd characteristic numeral:

corresponds to protection of the equipment against penetration of water with harmful effects.

0	Non-protected	
1		Protected against vertical dripping water, (condensation).
2		Protected against dripping water at an angle of up to 15°.
3		Protected against rain at an angle of up to 60°.
4		Protected against splashing water in all directions.
5		Protected against water jets in all directions.
6		Protected against powerful jets of water and waves.
7		Protected against the effects of temporary immersion.
8		Protected against the effects of prolonged immersion under specified conditions.

Additional letter:

corresponds to protection of personnel against direct contact with live parts.

A	With the back of the hand.
B	With the finger.
C	With a Ø 2.5 mm tool.
D	With a Ø 1 mm wire.

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Technical information

Degrees of protection provided by enclosures

IK code

Degrees of protection against mechanical impact

The European standard EN 62262 dated February 2002 defines a coding system (IK code) for indicating the degree of protection provided by electrical equipment enclosures against external mechanical impact.
Standard NF C 15-100 (December 2002 edition), section 512, table 51 A, provides a cross-reference between the various degrees of protection and the environmental conditions classification, relating to the selection of equipment according to external factors.
Practical guide UTE C 15-103 shows, in the form of tables, the characteristics required for electrical equipment (including minimum degrees of protection), according to the locations in which they are installed.

IK ●● code

The IK code comprises **2 characteristic numerals** (e.g. **IK 05**).

2 characteristic numerals:

corresponding to a value of impact energy.

		h (cm)	Energy (J)
00	Non-protected		
01		7.5	0.15
02		10	0.2
03		17.5	0.35
04		25	0.5
05		35	0.7
06		20	1
07		40	2
08		30	5
09		20	10
10		40	20

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Technical information
Contact design and operation

Safety Systems

Safety systems are comprised of many components. No one safety component will insure the safety of the system. The design of the complete safety system should be considered before you begin. It is very important to follow applicable safety standards when installing and wiring these components.

Terminal Identification

European (IEC) Contact Terminal Markings: Each terminal is marked with 2 digits. The first digit indicates the pole (circuit). The second digit indicates the type of contact: _1 - _2 is N.C., _3 - _4 is N.O. i.e., 11-12, 21-22 are N.C. and 13-14, 23-24 are N.O.

Example of European Terminal Markings:

For switch elements without isolated contacts:

- 11-12 Is the N.C. contact of Pole No. 1
- 13-14 Is the N.O. contact of Pole No. 1

For switch elements with isolated contacts:

- 21-22 Is the N.C. contact of Pole No. 2
- 13-14 Is the N.O. contact of Pole No. 1

Make-before-break (overlapping) SPDT: the normally open contact closes before the normally closed contact opens.

Break-before-make (offset) SPDT: the normally closed contact opens before the normally open contact closes. They do not change state simultaneously.

Concurrent make and break - SPDT: the normally closed contact opens at the same time as the normally open contact closes.

Contact Open Contact Closed

Slow Break Contacts



Snap Action Contacts



Unactuated state **Approach travel**



Contact change of state **Positive opening**

Positive Opening Contact Operation

The diagrams to the left show the operation of both slow make and break contacts, and snap action contacts. Positive opening N.C. contacts meet the IEC and EN requirements for positive opening contacts per IEC 60947-5-1, EN 60947-5-1, and NEMA ICS-5, part 6 (direct opening action).

Slow Make-and-Break Contacts

The speed of transfer of the moveable contacts is dependent on the speed of the operator. The amount of travel of the moveable contacts is also dependent on the amount of travel by the operator. Slow make and break contacts have the same trip and reset points, and do not have the differential travel common to snap switches.

Snap Action Contacts

The speed of transfer of the moveable contacts is not dependent on the speed of the operator. The amount of travel of the moveable contacts is also not dependent on the amount of travel by the operator. The movement of the moveable contacts are determined by a preset travel, after this point is reached, the contacts will trip. Snap action contacts have different trip and reset points, the difference is identified as “differential”.

Snap Action with Positive Opening Contacts

The snap action contacts operate the same as snap action contacts above but with a mechanical component to forcibly open the N.C. contacts if they did not open during the snap action part of the actuator travel. The actuator travel for snap acting contact opening is different (shorter) than the actuator travel to the point of positive opening. If this difference is not designed into the application, the actuator may not be operated far enough to invoke the positive opening function in the event of a contact weld or other failure. Positive opening slow make and break contacts are therefore preferred in safety circuits.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Operation in negative mode and in positive mode

Operation in negative mode

The mechanical system for machine protection must be properly designed

For this, it is recommended that the protection system should work in positive mode, as described below.

The two hazardous anomalies represented in positive mode can be cleared by preventive maintenance; this is not the case with those represented in negative mode (the negative mode anomalies are internal and therefore difficult to detect).



Machine operating | **Machine Stopped** | **Hazard: the machine continues to operate**

Operation in positive mode



Machine operating | **Machine Stopped** | **Hazard: the machine continues to operate**

If there is only one switch, it must be wired in positive mode

Operation in combined mode

Combined positive and negative mode

To clear anomalies due to positive mode, use combined mode.

Combined mode makes it possible to clear anomalies due to use of positive mode only. Negative mode is only acceptable if it is combined with a switch in positive mode; combination of the two modes by means of a positive mode switch used in conjunction with a negative mode switch avoids the risk of common mode anomalies (same anomaly on both switches).



Machine operating | **Guard closed: Machine operating** | **Guard open: machine stopped**

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Positive Opening Operation of Electrical Contacts

Per EN 60947-5-1, Positive Opening Contacts are defined as:

"A control switch having one or more break contact elements coupled to the switch via non-resilient members so that full contact opening of the break contact element(s) is obtained when the actuator is moved through the positive-opening travel by applying the force stated by the manufacturer".

"For the part of the travel that separates the contacts, there shall be a positive drive with no resilient members (I.e.: springs) between the moving contacts and the point of the actuator to which the actuating force is applied". This is almost identical to the definition in NFPA 79.

Operation cannot be relied on solely through the use of conventional snap switches which inherently do have springs or other "resilient members".

Positive Opening Slow-Make Slow Break Contacts



Unactuated State

Actuated State
N.C. Contacts Forced Open

Snap Acting Contacts with Positive Opening Mechanisms



Unactuated State

Approach State

Snap Action
Contact Change of State

Positive Opening

Positive Opening Slow-Make Slow-Break vs. Snap Acting With Positive Opening Contacts

Traditionally, Positive Opening Contacts have been slow-make slow-break type. There are now contact units which are snap action type that have positive opening mechanisms which force the NC contacts open to meet EN 60947-5-1. Either type is suitable (and required) for use in safety applications.

The actuator travel to the snap acting contact opening is different than the actuator travel to the point of positive opening of the N.C. contacts. If this difference is not designed into the application, the actuator may not be operated far enough to invoke the positive opening function in the event of a contact weld or other anomaly.

Slow-make slow-break positive opening construction is overwhelmingly PREFERRED in safety related circuits.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Mechanically Linked Electrical Contacts

Definition

Mechanically linked contacts are contacts which have:

- A mechanical link between the contacts.
- A minimum distance between the points of an open contact in the event of a closed contact being welded.

Linked contacts are contacts which are mechanically linked in such a way as to ensure that the normally closed and normally open contacts can never be closed at the same time.



Mechanical guiding (forced guiding)

If a normally closed contact becomes welded, it must be impossible for the normally open contacts to close when the coil is energized.

If a normally open contact becomes welded, it must be impossible for the normally closed contacts to close when the coil is de-energized.



(1) Suitable distance providing resistance to electrical shorts

If an anomaly occurs: contact A welded: then contact B stays open

Electrical auxiliary contact, mechanically linked to the power poles

Definition

An electrical auxiliary contact mechanically linked to the power poles is an N.C. auxiliary contact which can never be closed at the same time as the power poles.

If one of the power pole contacts becomes welded, the mechanical link prevents the N.C. auxiliary contact from closing when the coil is de-energized

The N.C. auxiliary contact present in TeSys K and D contactors meets this definition.



(1) Distance required to ensure isolation of the circuit.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Access Time

The time taken to access the hazardous machine parts after the initiation of the stop command by the interlocking device, as calculated on the basis of an approach speed chosen for each particular case, taking into account the parameters as listed in EN 999, Safety of machinery – The positioning of protective equipment in respect of approach speeds of parts of the human body".

American National Standards Institute (ANSI)

The premier private standards organization in the United States. ANSI operates as the United States National Committee to the IEC. ANSI itself does not write standards, but acts as a national clearing house.

Angle of Divergence

The angle at which the light diverges, or spreads, as it travels away from the transmitter. A small angle of divergence is more immune to interference and problems from: outside light sources, reflective surfaces, and other light curtains. Operating (sensing) ranges are generally longer on light curtains with smaller angles of divergence.

AOPD

Active Opto-Electronic Protective Device: a device whose sensing function is performed by opto-electronic emitting and receiving elements detecting the interruption of optical radiations, generated within the device, by an opaque object present in the specified detection zone.

ASEFA

Association des Stations D'essais Francaise d'Appareils electriques. This is an association of French testing stations for low voltage industrial control equipment.

Authorized Person

A person to whom the authority and responsibility to perform a specific assignment has been given by the employer. Also further defined in OSHA 1920.211 Definitions, and as Qualified Person in NFPA 79 3.3.78 and NEC 2002 Article 100 – Definitions

Blanking

Disables (other terms: blinds or masks) a fixed beam(s) in the light curtain\qs sensing field, and the light curtain ignores this beam's existence. This is used where other machine components (such as conveyors, brackets, tooling or fixtures) are required to be in the sensing field, or where material is fed into the machine at a pre-determined location.
NOTE: If material being fed into the machine will not always be at a pre-determined location, floating blanking is used. Using blanking increases the minimum safety distance. Blanking is also referred to as "deselect" and "exact channel select" or "channel select".

Brake

The mechanism used on a mechanical power press or other machinery to stop and/or hold the crankshaft, either directly or through a gear train, when the clutch is disengaged.

Brake Monitor

A sensing device or unit which is designed, constructed, and arranged to monitor the effectiveness of the braking system.

Category

A classification of the safety related parts of a control system in respect of its resistance to faults and its subsequent behavior in the fault condition, and which is achieved by the structural arrangement of the parts and/or by their reliability.

CENELEC

A major standards organization is the result of the European Union. The Commission of the European Communities issued a directive in the mid 1970\qs to harmonize standards. The CENELEC Organization was assigned this task and was directed to base their new standards on the IEC work. In addition to the Common Market countries, other Western European countries have adopted these standards. The resulting CENELEC standards are similar to IEC standards.

Clutch

The coupling mechanism used on a mechanical power press or other machinery to couple the flywheel to the crankshaft, either directly or through a gear train.

Competent Body

An accredited test laboratory or other EMC agency with the resources and expertise to help manufacturers verify their products' compliance with the EMC Directive. Competent bodies are appointed by national authorities within the member states of the EU and charged with the task of supporting manufacturers, importers, and exporters wishing to CE Mark their products by assessing Technical Construction Files.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Concurrent

Acting in conjunction with another component. Where two or more control components exist in the operated state at the same time.

Control Reliability

The control system shall be constructed so that a failure within the system does not prevent the normal stopping action from being applied to the machine when required, but does prevent initiation of a successive machine cycle until the failure is corrected. See OSHA 1910.217 (b)(13) and ANSI B11.19; 6.1.

Declaration of Conformity

A formal signed statement indicating conformity of the referenced product(s) to the listed provisions of the applicable Directive(s).

Direct Opening

See Positive Opening Operation

Directive

Legislation which is binding on all European member states that has been adopted by the Council of the European Communities. They contain essential requirements (ERs). These requirements are mandatory (part of European law)

EAA

Effective Aperture Angle: the maximum angle of deviation from the optical alignment of the emitting element(s) and the receiving element(s) within which the active opto-electronic protective device (AOPD) continues in normal operation.

EDM

External Device Monitoring – a means by which the ESPE monitors the state of the control devices which are external to the ESPE.

Energy isolating device

A mechanical device that physically prevents the transmission or release of energy, including but not limited to the following: a manually operated electrical circuit breaker, a disconnect switch, a manually operated switch by which the conductors of a circuit can be disconnected from all ungrounded supply conductors and, in addition, no pole can be operated independently; a line valve; a block; and any similar device used to block or isolate energy. Push buttons, selector switches and other control circuit type devices are not energy isolating devices.

Energy source

Any source of electrical, mechanical, hydraulic, pneumatic, chemical, thermal, or other energy.

ESPE

Electro-Sensitive Protective Equipment – An assembly of devices and/or components working together for protective tripping or presence sensing purposes and comprising: a sensing device, controlling/monitoring devices/and output signal switching devices.

European Union

The regional geographic and economic union formed by various European nations bound by treaty to form a single European Economic Community.

Exact Channel Select

Same as blanking except that any beams blanked must remain blocked. It prevents any stationary object that is intended to be in the sensing field from being removed from the machine. If the object is moved, the machine shuts down.

Factory Mutual Research Corporation

Factory Mutual Research Corporation (FM) publishes standards and guides.

Floating Blanking

Similar to blanking except that one or more beams are blanked – but the location of these blanked beams is not fixed. This allows the blanked beams to “float” up and down throughout the sensing field. This is very useful where the material is being fed into a machine can flex, making it difficult to maintain its location to one fixed beam. A typical example is where material is taken off a roll and into a machine. Floating blanking can include one or more beams. Using floating blanking increases the minimum safety distance. Floating blanking is also referred to as “floating deselect”.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Force Guided Contacts (Linked contacts)

All-or-nothing relay with at least one break contact and at least one make contact designed in such a way that it is made sure by mechanical means that make and break contacts can not be in closed position simultaneously. Also known as: forced contacts, positively activated contacts, guided contacts, and linked contacts.

FSD

Final Switching Device: the component of the machine safety related control system that interrupts the circuit to the machine primary control element when the OSSD (Output Signal Switching Device) goes to the OFF state.

Full Revolution

Full revolution machinery uses a clutch assembly that, when tripped, cannot be disengaged until the crankshaft (or machine) has completed a full revolution and returned to its initial position. It cannot be stopped in mid-stroke. Light curtains cannot be used on these types of machines.

Guard

Part of a machine specifically used to provide protection by means of physical barrier. Depending on its construction, a guard can be called casing, cover, screen, door, enclosing guard, etc.

Harmonized Standard

A standard developed and adopted by the European Union, which support and clarify the essential requirements (ERs) of the Directives. A product complying with the provisions of a harmonized standard is presumed to comply with the corresponding ERs.

Hazard

A source of possible injury or damage to health.

Hazardous Area

An area which can be a source of possible injury or damage to health. Usually associated with areas containing pinch points.

Interlock (for safeguarding)

An arrangement that interconnects guard(s) or device(s) with the control system and/or all or part of the electrical energy distributed to the machine.

Interlocking Device (interlock)

A device whose purpose is to prevent the operation of machine elements under specified conditions, generally as long as a guard is not closed.

International Electrotechnical Commission (IEC)

The major organization for worldwide electrical standards is the International Electrotechnical Commission (IEC) based in Geneva. This organization was founded in 1906 and has grown so that now there are over 40 member countries. They are responsible for electrical standardization activities.

LCIE

Laboratoire Centrale des Industries Electriques. Electrical Industries Central Laboratory, a French organization.

Linked Contacts

All-or-nothing relay with at least one break contact and at least one make contact designed in such a way that it is made sure by mechanical means that make and break contacts can not be in closed position simultaneously. Also known as: forced contacts, positively activated contacts, force guided contacts, and guided contacts.

Lockout

The placing of a lockout device on an energy isolating device to insure that the energy isolating device and the equipment being controlled cannot be operated until the lock out device is removed (See OSHA 1910.147).

LOVAG

Low Voltage Agreement Group, an association in England which approves low voltage electrical equipment.

Machinery

An assembly of linked parts or components, at least one of which moves, which have been combined to process, treat, move or package a material. Also an assembly of such machines. Machinery moved by manual effort is excluded – except for lifting equipment.

Minimum Safe Distance

The distance between the hazardous area and the light curtain, which is sufficient to stop the machine before the operator can access the hazardous area once the operator penetrates the light curtain's sensing field. This distance is based on a formula which considers many factors, including the stopping time of the machine, speed of approach of various body parts, response time of the safety controls, and braking time. Also referred to as Minimum Separation Distance.

Minimum Object Sensitivity (MOS)

Minimum Object Sensitivity of a light curtain: the minimum diameter object that a light curtain will be able to detect at any point in the sensing field.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

MPCE

Machine Primary Control Element: the electrically powered element that directly controls the normal operation of a machine in such a way that it is the last element (in time) to function when machine operation is to be initiated or stopped.
NOTE: This element can be, for example, a main contactor, a magnetic clutch or an electrically operated hydraulic valve.

MSCE

Machine Secondary Control Element: a machine control element, independent of the machine primary control element(s) (MPCE above), that is capable of removing the source power from the prime driving component(s) of the relevant hazardous parts in an emergency. The MSCE is normally controlled by the secondary switching device.
NOTE: This element can be, for example, a main contactor, a magnetic clutch or an electrically operated hydraulic valve.

Muting

Defined as “the temporary, automatic suspension of safety functions by a safety related control system during normal operation of a machine”. Muting is only permitted during the non-hazardous portion of the machine cycle. (see ANSI B11.19:8.3.2.5) It is generally used for parts ejecting and feeding of material.

National Electrical Manufacturers Association

The National Electrical Manufacturers Association (NEMA) publishes standards on the construction and performance of electrical equipment.

Notified Body

An independent testing laboratory that a Member State has determined to be qualified to perform testing and certification functions relating to specified EU Directives. The Member State “notifies” the EC and the laboratory of the laboratory’s qualified status as tester and certifier. The Notified body must reside in one of the EU countries, but it may have testing facilities outside the EU.

Object Sensitivity

See MOS.

Occupational Safety and Health Administration

The United States Occupational Safety and Health Administration (OSHA) is a federal government regulatory agency with jurisdiction in the United States.

OSSD

Output Signal Switching Device: the component of the ESPE connected to the machine control system which, when the sensing device is actuated during normal operation, responds by going to the OFF state.

Part Revolution

Part revolution machinery uses a clutch assembly that can be disengaged at any point before the crankshaft (or machine) has completed a full revolution and returned to its initial position. It can be stopped in mid-stroke.

Pinch Point

Any point other than the point of operation where it is possible for any part of the body to be caught between moving parts of a machine, between the machine and the material (being worked with), between the machine and other equipment, between the moving parts of the machine and a stationary object such as a wall or floor or other stationary part of the machine.

Point of Operation

That point where material is actually positioned and work is being performed during any process such as shearing, punching, forming, or assembling.

Positive Opening Operation (of a contact element)

The achievement of contact separation as the direct result of a specified movement of the switch actuator through non-resilient members (e.g.: not dependent on springs).The term Positive Opening is used throughout NFPA 79, and in IEC 60947-5-1, and EN 60947-5-1. Direct Opening is the term referred to in NEMA ICS-5, part 6 (direct opening action). The terms Positive Opening and Direct Opening identify the same contact action and characteristics

PSD

Presence Sensing Device: a device designed, constructed and arranged to create a sensing field or area to detect when an operator’s hand or any other part of their body is within such a field or area (i.e.: a light curtain).

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

PSDI

Presence Sensing Device Initiation: an operating mode of indirect manual initiation of a single stroke of a press or machine by a presence sensing device (such as a light curtain). When the PSD senses that the work motions of the operator related to feeding and/or removing parts are completed, and that all parts of the operator's body or hand tools are safely clear of the point of operation, the press is initiated for a single stroke.
Example: The operator reaches into machine to place a part, the light curtain beams are broken, and the machine is stopped. The operator positions part in machine, the light curtain field is still broken, machine remains stopped. When done positioning part, the operator retracts his hands to clear the light curtain. The light curtain resets, returns to a safe status, and initiates a machine start.
For more information on PSDI, refer to OSHA 29 CFR 1910.217 (h), the various appendices referenced on PSDI, and OSHA mandatory regulations requiring third party approval.

Qualified Person

A person to whom the authority and responsibility to perform a specific assignment has been given by the employer. Defined as Authorized Person in OSHA 1920.211 Definitions, and as Qualified Person in NFPA 79 3.3.78 and NEC 2002 Article 100 – Definitions

Redundancy

The application of more than one device or system, or part of a device or system, with the objective of providing that in the event of one failing to perform its function another is available to perform that function.

Risk

A combination of the probability and the degree of the possible injury or damage to health in a hazardous situation.

Safeguard

A guard or protective device used in a safety function to protect persons from a present or impending hazard.

Safeguarding

Safety measures consisting of the use of specific technical means called safeguards to protect persons from the hazards which cannot be reasonably removed or sufficiently limited by design.

SPM

Stopping Performance Monitor: a monitoring means to determine whether or not the overall system stopping performance is within the preset limit(s).

SSD

Secondary Switching Device: a device which, in a lock-out condition, performs a back-up safety function by going to the OFF state and initiating an appropriate machine control action. e.g: de-energizing the MCSE.

Stopping Time

The period between the point at which the interlocking or other safety device (such as a light curtain) initiates the stop command and the point at which the risk from hazardous machine functions has passed.

Stop Time Measurement Device

This device measures the time from when a stop signal is issued to the time the machine has come to a complete stop. Typically used on mechanical or hydraulic presses and press brakes, many devices are available with accessories so they can be used with other machinery such as lathes, mills, and drills.

Tagout

The placing of a tagout device on an energy isolating device to insure that the energy isolating device and the equipment being controlled may not be operated until the tagout device is removed (See OSHA 1910.147).

Test Object

An object (usually supplied by the light curtain manufacturer) which is the same size as the minimum object sensitivity for periodically testing the light curtain for proper operation. This test object is typically a rod of a specific diameter, and is therefore also referred to as a test rod.

Type A Standards

Fundamental safety standards giving basic concepts, principles of design, and general aspects that can be applied to all machinery.

Type B Standards

Group safety standards dealing with one aspect or one type of safety related device that can be used across a wide range of machinery.

Type C Standards

Machine safety standards giving detailed safety requirements for a particular machine or group of machines

Underwriters Laboratories Inc.

Underwriters Laboratories Inc. (UL) publishes a number of different standards providing detailed construction and performance requirements for equipment.

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Product reference index

Product reference index *10/2*

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Product reference index

#

170DTN11000 2/14 2/29 2/47
467NHP81100 2/14 2/29 2/47
490NAD91103 2/14 2/29 2/47
490NAD91104 2/14 2/29 2/47
490NAD91105 2/14 2/29 2/47
490NAE91100 2/14 2/29 2/47
490NTC00005 2/14 2/29 2/47
490NTC00015 2/14 2/29 2/47
490NTC00040 2/14 2/29 2/47
490NTC00080 2/14 2/29 2/47
490NTW00002 2/14 2/29 2/47 2/125
490NTW00002U 2/125
490NTW00005 2/14 2/29 2/47 2/125
490NTW00005U 2/125
490NTW00012 2/14 2/29 2/47 2/125
490NTW00012U 2/125
490NTW00040 2/14 2/29 2/47
490NTW00080 2/14 2/29 2/47

A

ABL1REM12050 2/13 2/28 2/46
ABL1REM24025 2/13 2/28 2/46
ABL1REM24100 2/13 2/28 2/46
ABL8RPS24030 2/13 2/28 2/46 5/40
ABL8RPS24030 2/13 2/28 2/46 5/40
ABL8RPS24050 2/13 2/28 2/46 5/40
ABL8RPS24100 2/13 2/28 2/46 2/125 5/40
ASISA01 3/118 3/122
ASISAD1 3/122
ASISAFEMON1B 3/118
ASISAFEMON2B 3/118
ASISCM 3/118
ASISCPC 3/118
ASISEA1C 3/122
ASISEK1C 3/122
ASISSLB4 3/122
ASISSLB5 3/122
ASISSLC1 3/122
ASISSLC2 3/122
ASISSLE4 3/122
ASISSLE5 3/122
ASISSLLS 3/122
ASISWIN2 3/118
ASITERV2 3/118 3/122

D

DE9RA1012 4/38 4/46 4/74
DE9RA2012 4/69
DE9RI2016 3/122
DL1AA024 6/10
DL1AA127 6/10
DL1AA220 6/10

S

SSV1XPSMFWIN 2/12 2/26 2/45 2/68
STBNDP2112 2/14 2/29 2/47

T

TSCCANTDM4 2/125
TSXCANCA100 2/125
TSXCANCA300 2/125
TSXCANCA50 2/125
TSXCANCADD03 2/125
TSXCANCADD1 2/125
TSXCANCADD3 2/125
TSXCANCADD5 2/125
TSXCSA100 2/14 2/47
TSXCSA200 2/14 2/47
TSXCSA500 2/14 2/47
TSXCUSB485 2/125
TSXPBSCA100 2/14 2/29 2/47 2/125
TSXPBSCA400 2/14 2/29 2/47 2/125
TSXPBY100 2/14 2/29 2/47
TSXPCX1031 2/125

V

VW3A8306R 2/14 2/29 2/47
VW3A8306R03 2/29
VW3A8306R10 2/29
VW3A8306R30 2/125
VW3A8306R30 2/29
VW3A8306RC 2/14 2/29 2/47

X

XBTGT2130 2/13 2/28 2/46
XBTGT2330 2/13 2/28 2/46
XBTGT4330 2/13 2/28 2/46
XBTGT5230 2/13 2/28 2/46
XBTGT5330 2/13 2/28 2/46
XBTGT6330 2/13 2/28 2/46
XBTGT7340 2/13 2/28 2/46
XBTZ938 2/14 2/29 2/47
XBTZG909 2/14 2/29 2/47
XCSA503 4/50
XCSA523 4/50
XCSA703 4/50
XCSA713 4/50
XCSA723 4/50
XCSA803 4/50
XCSB503 4/50
XCSB703 4/50
XCSB713 4/50
XCSB723 4/50
XCSB803 4/50
XCSC703 4/50
XCSC803 4/50
XCSD3702G13 4/33
XCSD3702N12 4/33
XCSD3702P20 4/33
XCSD3710G13 4/33
XCSD3710N12 4/33
XCSD3710P20 4/33
XCSD3718G13 4/33
XCSD3718N12 4/33
XCSD3718P20 4/33
XCSD3719G13 4/33
XCSD3719N12 4/33
XCSD3719P20 4/33
XCSD3902G13 4/32
XCSD3902N12 4/32
XCSD3902P20 4/32
XCSD3910G13 4/32
XCSD3910N12 4/32
XCSD3910P20 4/32
XCSD3918G13 4/32
XCSD3918N12 4/32
XCSD3918P20 4/32
XCSD3919G13 4/32
XCSD3919N12 4/32
XCSD3919P20 4/32
XCSDM379102 4/94
XCSDM379110 4/94
XCSDM3791M12 4/95
XCSDM480102 4/94
XCSDM480105 4/94
XCSDM480110 4/94
XCSDM4801M12 4/95
XCSDMC5902 4/82
XCSDMC590L01M8 4/83
XCSDMC5912 4/82
XCSDMC591L01M8 4/83
XCSDMC7902 4/82
XCSDMC790L01M8 4/83
XCSDMC7912 4/82
XCSDMC791L01M8 4/83
XCSDMP5002 4/82
XCSDMP500L01M12 4/83
XCSDMP5012 4/82
XCSDMP501L01M12 4/83
XCSDMP5902 4/82
XCSDMP590L01M12 4/83
XCSDMP5912 4/82
XCSDMP591L01M12 4/83
XCSDMP7002 4/82
XCSDMP700L01M12 4/83
XCSDMP7012 4/82
XCSDMP701L01M12 4/83
XCSDMP7902 4/82
XCSDMP790L01M12 4/83
XCSDMP7912 4/82
XCSDMP791L01M12 4/83
XCSDMR5902 4/82
XCSDMR590L01M12 4/83
XCSDMR5912 4/82
XCSDMR591L01M12 4/83
XCSDMR7902 4/82
XCSDMR790L01M12 4/83
XCSDMR7912 4/82
XCSDMR791L01M12 4/83
XCSDMT 4/96
XCSE5313 4/68
XCSE5333 4/68
XCSE7313 4/68
XCSE7333 4/68
XCSE8313 4/68
XCSE8333 4/68
XCSLE2525312 4/58
XCSLE2525332 4/58
XCSLE2525342 4/58
XCSLE2525512 4/58
XCSLE2525513 4/58
XCSLE2727312 4/58
XCSLE2727313 4/58
XCSLE2727332 4/58
XCSLE2727333 4/58
XCSLE2727512 4/58
XCSLE3535312 4/58
XCSLE3535313 4/58
XCSLE3535333 4/58
XCSLE3535342 4/58
XCSLE3535343 4/58
XCSLE3737312 4/58
XCSLE3737313 4/58
XCSLE3737333 4/58
XCSLE3737342 4/58
XCSLE3737513 4/58
XCSLE3737533 4/58
XCSLE3838312 4/58
XCSLE3838313 4/58
XCSLE3838333 4/58
XCSLE3838342 4/58
XCSLE3838513 4/58
XCSLE3838533 4/58
XCSLF2525312 4/56
XCSLF2525342 4/56
XCSLF2725312 4/56
XCSLF2725342 4/56
XCSLF2727312 4/56
XCSLF2727313 4/56
XCSLF2727333 4/56
XCSLF2727342 4/56
XCSLF3535312 4/56
XCSLF3535313 4/56
XCSLF3535332 4/56
XCSLF3535333 4/56
XCSLF3535342 4/56
XCSLF3535343 4/56
XCSLF3535412 4/57
XCSLF3535512 4/56
XCSLF3535513 4/56
XCSLF3535533 4/56
XCSLF3535612 4/57
XCSLF3737312 4/56
XCSLF3737313 4/56
XCSLF3737332 4/56
XCSLF3737333 4/56
XCSLF3737342 4/56
XCSLF3737343 4/56
XCSLF3737412 4/57
XCSLF3737413 4/57
XCSLF3737433 4/57
XCSLF3737512 4/56
XCSLF3737513 4/56
XCSLF3737533 4/56
XCSLF3737543 4/56
XCSLF3737612 4/57
XCSLF3737613 4/57
XCSLF3737633 4/57
XCSLF3838312 4/56
XCSLF3838313 4/56
XCSLF3838333 4/56
XCSLF3838513 4/56
XCSLF3838533 4/56
XCSM3702L2 4/28
XCSM3710L2 4/28
XCSM3715L2 4/28
XCSM3716L2 4/28
XCSM3902L2 4/28
XCSM3910L2 4/28
XCSM3915L2 4/28
XCSM3916L2 4/28
XCSM4102L2 4/28

Schneider Electric

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Product reference index

XCSM4110L2 4/28
XCSM4115L2 4/28
XCSM4116L2 4/28
XCSMP59L2 4/42
XCSMP70L2 4/42
XCSMP79L2 4/42
XCSMP80L2 4/42
XCSP3702G13 4/35
XCSP3702N12 4/35
XCSP3702P20 4/35
XCSP3710G13 4/35
XCSP3710N12 4/35
XCSP3710P20 4/35
XCSP3718G13 4/35
XCSP3718N12 4/35
XCSP3718P20 4/35
XCSP3719G13 4/35
XCSP3719N12 4/35
XCSP3719P20 4/35
XCSP3902G13 4/34
XCSP3902N12 4/34
XCSP3902P20 4/34
XCSP3910G13 4/34
XCSP3910N12 4/34
XCSP3910P20 4/34
XCSP3918G13 4/34
XCSP3918N12 4/34
XCSP3918P20 4/34
XCSP3919G13 4/34
XCSP3919N12 4/34
XCSP3919P20 4/34
XCSPA593 4/46
XCSPA693 4/46
XCSPA793 4/46
XCSPL553 4/38
XCSPL563 4/38
XCSPL573 4/38
XCSPL583 4/38
XCSPL593 4/38
XCSPL753 4/38
XCSPL763 4/38
XCSPL773 4/38
XCSPL783 4/38
XCSPL793 4/38
XCSPR553 4/38
XCSPR753 4/38
XCSTA593 4/46
XCSTA793 4/46
XCSTA893 4/46
XCSTE5313 4/74
XCSTE5333 4/74
XCSTE5343 4/74
XCSTE6313 4/74
XCSTE6333 4/74
XCSTE6343 4/74
XCSTE7313 4/74
XCSTE7333 4/74
XCSTE7343 4/74
XCSTL553 4/38
XCSTL563 4/38
XCSTL583 4/38
XCSTL753 4/38
XCSTL763 4/38
XCSTL773 4/38
XCSTL783 4/38
XCSTL793 4/38
XCSTL863 4/38
XCSTL873 4/38
XCSTL883 4/38
XCSTR553 4/38
XCSTR753 4/38
XCSTR853 4/38
XCSZ01 4/50 4/59 4/69
XCSZ02 4/50 4/59 4/69
XCSZ03 4/50 4/59 4/69
XCSZ05 4/50 4/59 4/69
XCSZ100 4/59 4/74
XCSZ11 4/47 4/74
XCSZ12 4/47 4/74
XCSZ13 4/47 4/74
XCSZ14 4/47 4/74
XCSZ15 4/47 4/74
XCSZ200 4/46 4/74
XCSZ21 4/47
XCSZ25 4/51 4/59 4/69
XCSZ27 4/59 4/69
XCSZ28 4/46 4/74
XCSZ29 4/42
XCSZ30 4/59
XCSZ31 4/51
XCSZ32 4/51
XCSZ43 4/69
XCSZ81 4/42
XCSZ83 4/42
XCSZ84 4/42
XCSZ85 4/42
XCSZ90 4/51 4/59 4/69
XCSZ91 4/46 4/74
XCSZC1 4/84
XCSZCC 4/84
XCSZCP 4/84
XCSZCR 4/84
XCSZP1 4/84
XCSZR1 4/84
XPSABV11330C 3/20
XPSABV11330P 3/20
XPSABV1133C 3/20
XPSABV1133P 3/20
XPSAC1321 3/15
XPSAC1321P 3/15
XPSAC3421 3/15
XPSAC3421P 3/15
XPSAC3721 3/15
XPSAC3721P 3/15
XPSAC5121 3/15
XPSAC5121P 3/15
XPSAF5130 3/33
XPSAF5130P 3/33
XPSAFL5130 3/37
XPSAFL5130P 3/37
XPSAK311144 3/47
XPSAK311144P 3/47
XPSAK351144 3/47
XPSAK351144P 3/47
XPSAK371144 3/47
XPSAK371144P 3/47
XPSAR311144 3/41
XPSAR311144P 3/41
XPSAR351144 3/41
XPSAR351144P 3/41
XPSAR371144 3/41
XPSAR371144P 3/41
XPSATE3410 3/20
XPSATE3410P 3/20
XPSATE3710 3/20
XPSATE3710P 3/20
XPSATE5110 3/20
XPSATE5110P 3/20
XPSATR11530C 3/29
XPSATR11530P 3/29
XPSATR1153C 3/29
XPSATR1153P 3/29
XPSATR39530C 3/29
XPSATR39530P 3/29
XPSATR3953C 3/29
XPSATR3953P 3/29
XPSAV11113 3/20
XPSAV11113P 3/20
XPSAXE5120C 3/15
XPSAXE5120P 3/15
XPSBAE3920C 3/55
XPSBAE3920P 3/55
XPSBAE5120C 3/55
XPSBAE5120P 3/55
XPSBCE3110C 3/55
XPSBCE3110P 3/55
XPSBCE3410C 3/55
XPSBCE3410P 3/55
XPSBCE3710C 3/55
XPSBCE3710P 3/55
XPSBF1132 3/55
XPSBF1132P 3/55
XPSCM1144 3/62 5/50
XPSCM1144P 3/62 5/50
XPSDCRM10 5/24
XPSDMB1132 3/89
XPSDMB1132P 3/89
XPSDME1132 3/89
XPSDME1132P 3/89
XPSECME5131C 3/81
XPSECME5131P 3/81
XPSECPE3910C 3/81
XPSECPE3910P 3/81
XPSECPE5131C 3/81
XPSECPE5131P 3/81
XPSLCD1141 3/69 5/57
XPSLCM1 5/14 5/24
XPSLCM1150 3/74 5/62
XPSMC16Z 2/124
XPSMC16ZC 2/124
XPSMC16ZP 2/124
XPSMC32Z 2/124
XPSMC32ZC 2/124
XPSMC32ZP 2/124
XPSMCCPC 2/125
XPSMCSCY 2/125
XPSMCSCY 2/29
XPSMCTC16 2/124
XPSMCTC32 2/124
XPSMCTS16 2/124
XPSMCTS32 2/124
XPSMCWIN 2/124
XPSMF1DI1601 2/78
XPSMF2DO1601 2/85
XPSMF2DO1602 2/85
XPSMF2DO401 2/85
XPSMF2DO801 2/85
XPSMF3022 2/26
XPSMF31222 2/26
XPSMF3502 2/26
XPSMF3522 2/26
XPSMF3542 2/26
XPSMF3AIO8401 2/97
XPSMF3DIO16801 2/97
XPSMF3DIO20802 2/97
XPSMF3DIO8801 2/97
XPSMF4000 2/12
XPSMF4002 2/12
XPSMF4020 2/12
XPSMF4022 2/12
XPSMF4040 2/12
XPSMF4042 2/12
XPSMFADAPT 2/29 2/47
XPSMFAI801 2/44 2/51
XPSMFAO801 2/44 2/53
XPSMFBLK 2/45
XPSMFCIO2401 2/44 2/55
XPSMFCPU22 2/44
XPSMFDI2401 2/44 2/57
XPSMFDI3201 2/44 2/59
XPSMFDIO241601 2/44 2/61
XPSMFDO801 2/44 2/63
XPSMFGEH01 2/44
XPSMFPS01 2/44
XPSMP11123 2/108
XPSMP11123P 2/108
XPSOT3444 3/110
XPSOT3744 3/110
XPSPVK1184 3/105
XPSPVK3484 3/105
XPSPVK3784 3/105
XPSPVT1180 3/101
XPSTSA3442P 3/85
XPSTSA3742P 3/85
XPSTSA5142P 3/85
XPSTSW3442P 3/85
XPSTSW3742P 3/85
XPSTSW5142P 3/85
XPSVNE1142HSP 3/95
XPSVNE1142P 3/95
XPSVNE3442HSP 3/95
XPSVNE3442P 3/95
XPSVNE3742HSP 3/95
XPSVNE3742P 3/95
XSZNCR03 5/37
XSZNCR10 5/37
XSZNCR30 5/37
XSZNCT03 5/37
XSZNCT10 5/37
XSZNCT30 5/37
XSZB130 4/84
XSZBCR05 5/14
XSZBCR10 5/14
XSZBCR15 5/14
XSZBCR30 5/14
XSZBCT05 5/14
XSZBCT10 5/14
XSZBCT15 5/14
XSZBCT30 5/14
XSZCM01 3/74
XSZCM01 5/24 5/62
XSZCM02 3/74 5/24 5/62
XSZDCR003 5/14
XSZDCR005 5/14
XSZDCR010 5/14
XSZDCR020 5/14
XSZDCR030 5/14
XSZDCR050 5/14
XSZDCR100 5/14
XSZDCT003 5/14
XSZDCT005 5/14
XSZDCT010 5/14
XSZDCT020 5/14
XSZDCT030 5/14
XSZDCT050 5/14
XSZDCT100 5/14
XSZPCR05 5/31
XSZPCR10 5/31
XSZPCR15 5/31
XSZPCR30 5/31
XSZPCT05 5/31
XSZPCT10 5/31
XSZPCT15 5/31
XSZPCT30 5/31
XSZSMK 5/42
XSZSMK1 5/42
XSZSMK2 5/42
XSZTBDMCR003 5/14

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Product reference index

XSZTBDMCT003 5/14
XU2S18KP340DT 3/63 5/51
XU2S18KP340L5T 3/63 5/51
XU2S18KP340WDT 3/63 5/51
XU2S18KP340WL5T 3/63 5/51
XU2S18PP340D 3/63 5/51
XU2S18PP340DR 3/63 5/51
XU2S18PP340L5 3/63 5/51
XU2S18PP340L5R 3/63 5/51
XU2S18PP340WD 3/63 5/51
XU2S18PP340WDR 3/63 5/51
XU2S18PP340WL5 3/63 5/51
XU2S18PP340WL5R 3/63 5/51
XUSLAT1 5/40
XUSLBQ6A0280 5/10 5/20
XUSLBQ6A0320 5/10 5/20
XUSLBQ6A0360 5/10 5/20
XUSLBQ6A0440 5/10 5/20
XUSLBQ6A0520 5/10 5/20
XUSLBQ6A0600 5/10 5/20
XUSLBQ6A0720 5/10 5/20
XUSLBQ6A0760 5/10 5/20
XUSLBQ6A0880 5/10 5/20
XUSLBQ6A0920 5/10 5/20
XUSLBQ6A0960 5/10 5/20
XUSLBQ6A1040 5/10 5/20
XUSLBQ6A1120 5/10 5/20
XUSLBQ6A1200 5/10 5/20
XUSLBQ6A1360 5/10 5/20
XUSLBR5A0320 5/10 5/20
XUSLBR5A0360 5/10 5/20
XUSLBR5A0440 5/10 5/20
XUSLBR5A0520 5/10 5/20
XUSLBR5A0600 5/10 5/20
XUSLBR5A0680 5/10 5/20
XUSLBR5A0760 5/10 5/20
XUSLBR5A0880 5/10 5/20
XUSLBR5A0920 5/10 5/20
XUSLBR5A1040 5/10 5/20
XUSLBR5A1200 5/10 5/20
XUSLBR5A1360 5/10 5/20
XUSLBR5A1400 5/10 5/20
XUSLBR5A1520 5/10 5/20
XUSLBR5A1560 5/10 5/20
XUSLBR5A1640 5/10 5/20
XUSLBR5A1720 5/10 5/20
XUSLBR5A1800 5/10 5/20
XUSLBR5A1920 5/10 5/20
XUSLBR5A2120 5/10 5/20
XUSLDMQ6A0280 5/11
XUSLDMQ6A0320 5/11
XUSLDMQ6A0360 5/11
XUSLDMQ6A0440 5/11
XUSLDMQ6A0520 5/11
XUSLDMQ6A0600 5/11
XUSLDMQ6A0720 5/11
XUSLDMQ6A0760 5/11
XUSLDMQ6A0880 5/11
XUSLDMQ6A0920 5/11
XUSLDMQ6A0960 5/11
XUSLDMQ6A1040 5/11
XUSLDMQ6A1120 5/11
XUSLDMQ6A1200 5/11
XUSLDMQ6A1360 5/11
XUSLDMY5A0320 5/11 5/21
XUSLDMY5A0360 5/11 5/21
XUSLDMY5A0440 5/11 5/21
XUSLDMY5A0520 5/11 5/21
XUSLDMY5A0600 5/11 5/21
XUSLDMY5A0680 5/11 5/21
XUSLDMY5A0760 5/11 5/21
XUSLDMY5A0880 5/11 5/21
XUSLDMY5A0920 5/11 5/21
XUSLDMY5A1040 5/11 5/21
XUSLDMY5A1200 5/11 5/21
XUSLDMY5A1360 5/11 5/21
XUSLDMY5A1400 5/11 5/21
XUSLDMY5A1520 5/11 5/21
XUSLDMY5A1560 5/11 5/21
XUSLDMY5A1640 5/11 5/21
XUSLDMY5A1720 5/11 5/21
XUSLDMY5A1800 5/11 5/21
XUSLDMY5A1920 5/11 5/21
XUSLDMY5A2120 5/11 5/21
XUSLDSQ6A0280 5/13
XUSLDSQ6A0320 5/13
XUSLDSQ6A0360 5/13
XUSLDSQ6A0440 5/13
XUSLDSQ6A0520 5/13
XUSLDSQ6A0600 5/13
XUSLDSQ6A0720 5/13
XUSLDSQ6A0760 5/13
XUSLDSQ6A0880 5/13
XUSLDSQ6A0920 5/13
XUSLDSQ6A0960 5/13
XUSLDSQ6A1040 5/13
XUSLDSQ6A1120 5/13
XUSLDSQ6A1200 5/13
XUSLDSY5A0320 5/13
XUSLDSY5A0360 5/13
XUSLDSY5A0440 5/13
XUSLDSY5A0520 5/13
XUSLDSY5A0600 5/13
XUSLDSY5A0680 5/13
XUSLDSY5A0760 5/13
XUSLDSY5A0880 5/13
XUSLDSY5A0920 5/13
XUSLDSY5A1040 5/13
XUSLDSY5A1200 5/13
XUSLDSY5A1360 5/13
XUSLDSY5A1400 5/13
XUSLDSY5A1520 5/13
XUSLDSY5A1560 5/13
XUSLDSY5A1640 5/13
XUSLDSY5A1720 5/13
XUSLDSY5A1800 5/13
XUSLDSY5A1920 5/13
XUSLDSY5A2120 5/13
XUSLNG5C0150 5/37
XUSLNG5C0300 5/37
XUSLNG5C0450 5/37
XUSLNG5C0600 5/37
XUSLNG5C0750 5/37
XUSLNG5C0900 5/37
XUSLNG5C1050 5/37
XUSLNG5C1200 5/37
XUSLNG5C1350 5/37
XUSLNG5C1500 5/37
XUSLNG5D0150 5/37
XUSLNG5D0300 5/37
XUSLNG5D0450 5/37
XUSLNG5D0600 5/37
XUSLNG5D0750 5/37
XUSLNG5D0900 5/37
XUSLNG5D1050 5/37
XUSLNG5D1200 5/37
XUSLNG5D1350 5/37
XUSLNG5D1500 5/37
XUSLPB2A500M 5/29
XUSLPB2A600M 5/29
XUSLPDM 5/14
XUSLPZ1AB 5/30
XUSLPZ1AM 5/29
XUSLPZ2A0500B 5/30
XUSLPZ2A0500M 5/29
XUSLPZ2A0600B 5/30
XUSLPZ2A0600M 5/29
XUSLPZ3A0400B 5/30
XUSLPZ3A0400M 5/29
XUSLPZ3A0500B 5/30
XUSLPZ3A0500M 5/29
XUSLPZ4A0300B 5/30
XUSLPZ4A0300M 5/29
XUSLPZ5A0300B 5/30
XUSLPZ5A0300M 5/29
XUSLPZ6A0300B 5/30
XUSLPZ6A0300M 5/29
XUSLZ218 5/37
XUSLZ219 5/31
XUSLZ227 5/42
XUSLZ228 5/14
XUSLZ320 5/31
XUSLZ330 5/14
XUSLZ450 5/14 5/31 5/37
XUSLZ500 4/96
XUSLZ500 5/14 5/31 5/37
XUSLZ600 5/14
XUSLZ610 5/14
XUSLZD70280 5/15
XUSLZD70320 5/15
XUSLZD70360 5/15
XUSLZD70440 5/15
XUSLZD70520 5/15
XUSLZD70600 5/15
XUSLZD70680 5/15
XUSLZD70720 5/15
XUSLZD70760 5/15
XUSLZD70880 5/15
XUSLZD70920 5/15
XUSLZD70960 5/15
XUSLZD71040 5/15
XUSLZD71120 5/15
XUSLZD71200 5/15
XUSLZD71360 5/15
XUSLZD71400 5/15
XUSLZD71520 5/15
XUSLZD71560 5/15
XUSLZD71640 5/15
XUSLZD71720 5/15
XUSLZD71800 5/15
XUSLZD71920 5/15
XUSLZD72120 5/15
XUSLZPDM 5/14
XUSLZWB0280 5/41
XUSLZWB0320 5/41
XUSLZWB0360 5/41
XUSLZWB0440 5/41
XUSLZWB0520 5/41
XUSLZWB0600 5/41
XUSLZWB0680 5/41
XUSLZWB0720 5/41
XUSLZWB0760 5/41
XUSLZWB0880 5/41
XUSLZWB0920 5/41
XUSLZWB0960 5/41
XUSLZWB1040 5/41
XUSLZWB1120 5/41
XUSLZWB1200 5/41
XUSLZWB1360 5/41
XUSLZWB1400 5/41
XUSLZWB1520 5/41
XUSLZWB1560 5/41
XUSLZWB1640 5/41
XUSLZWB1720 5/41
XUSLZWB1800 5/41
XUSLZWB1920 5/41
XUSLZWB2120 5/41
XUSZA0102 5/40
XUSZA0152 5/40
XUSZA0305 5/40
XUSZA0457 5/40
XUSZA0508 5/40
XUSZA0610 5/40
XUSZA0711 5/40
XUSZA0762 5/40
XUSZA0813 5/40
XUSZA0914 5/40
XUSZA1016 5/40
XUSZA1067 5/40
XUSZA1219 5/40
XUSZA1321 5/40
XUSZA1372 5/40
XUSZA1422 5/40
XUSZA1524 5/40
XUSZA1626 5/40
XUSZA1830 5/40
XUSZA2134 5/40
XUSZC1200 5/43
XUSZC1800 5/43
XUSZC2100 5/43
XUSZC2400 5/43
XUSZC3100 5/43
XUSZCA 5/43
XUSZCB 5/43
XUSZM0102 5/40
XUSZM0152 5/40
XUSZM0305 5/40
XUSZM0457 5/40
XUSZM0508 5/40
XUSZM0610 5/40
XUSZM0711 5/40
XUSZM0762 5/40
XUSZM0813 5/40
XUSZM0914 5/40
XUSZM1016 5/40
XUSZM1067 5/40
XUSZM1219 5/40
XUSZM1321 5/40
XUSZM1372 5/40
XUSZM1422 5/40
XUSZM1524 5/40

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Product reference index

XUSZM1626	5/40
XUSZM1830	5/40
XUSZM2134	5/40
XUSZWSP	5/41
XY2CE1A150H7	6/5
XY2CE1A190H7	6/5
XY2CE1A196H7	6/5
XY2CE1A250H7	6/5
XY2CE1A290H7	6/5
XY2CE1A296H7	6/5
XY2CE2A150H7	6/5
XY2CE2A190H7	6/5
XY2CE2A196H7	6/5
XY2CE2A250H7	6/5
XY2CE2A290H7	6/5
XY2CE2A296H7	6/5
XY2CE3A010H7	6/5
XY2CE3A020H7	6/5
XY2CE3A026H7	6/5
XY2CE4A010H7	6/5
XY2CE4A020H7	6/5
XY2CE4A026H7	6/5
XY2CH13150H7	6/6
XY2CH13190H7	6/6
XY2CH13250H7	6/6
XY2CH13290H7	6/6
XY2CH13350H7	6/6
XY2CH13390H7	6/6
XY2CH13450H7	6/6
XY2CH33010H7	6/6
XY2CJL19H7	6/7
XY2CJR19H7	6/7
XY2CJS19H7	6/7
XY2CZ0024	6/10
XY2CZ0048	6/10
XY2CZ0130	6/10
XY2CZ0230	6/10
XY2CZ1015	6/8
XY2CZ102	6/8
XY2CZ105	6/8
XY2CZ107	6/8
XY2CZ110	6/8
XY2CZ203	6/8
XY2CZ210	6/8
XY2CZ301	6/8
XY2CZ3015	6/8
XY2CZ3018	6/8
XY2CZ302	6/8
XY2CZ303	6/8
XY2CZ305	6/8
XY2CZ310	6/8
XY2CZ402	6/8
XY2CZ404	6/8
XY2CZ503	6/8
XY2CZ513	6/8
XY2CZ523	6/8
XY2CZ524	6/8
XY2CZ601	6/8
XY2CZ602	6/8
XY2CZ701	6/8
XY2CZ702	6/8
XY2CZ703	6/8
XY2CZ704	6/8
XY2CZ705	6/8
XY2CZ708	6/8
XY2CZ800	6/10
XY2CZ801	6/10
XY2CZ805	6/10
XY2CZ908	6/10
XY2CZ916	6/8
XY2CZ917	6/9
XY2CZ918	6/9
XY2CZ9310	6/9
XY2CZ9315	6/9
XY2CZ9318	6/9
XY2CZ9325	6/9
XY2CZ9330	6/9
XY2CZ9350	6/9
XY2CZ9525	6/9
XY2CZ9550	6/9
XY2CZ9570	6/9
XZCC23FCM160S	4/60
XZCC23FCM190S	4/60
XZCC23FDM160S	4/60
XZCC23FDM190S	4/60
XZCP0941L10	4/84
XZCP0941L2	4/84
XZCP0941L5	4/84
XZCP1041L10	4/84
XZCP1041L2	4/84
XZCP1041L5	4/84
XZCP1141L10	4/84
XZCP1141L2	4/84
XZCP1141L5	4/84
XZCP1241L10	4/84
XZCP1241L2	4/84
XZCP1241L5	4/84
XZCP29P11L10	4/84
XZCP29P11L2	4/84
XZCP29P11L5	4/84
XZCP29P12L10	4/96
XZCP29P12L2	4/96
XZCP29P12L5	4/96
Z	
ZALVB4	6/10
ZALVB5	6/10
ZALVG4	6/10
ZALVG5	6/10
ZALVM4	6/10
ZALVM5	6/10
ZB4BS844	3/122
ZB4BS944	3/122
ZB5AA639	6/10
ZB5AC64	6/10
ZB5AG612R26	6/10
ZB5AG6R26	6/10
ZB5AP6S	6/10
ZB5APA6	6/10
ZB5AS844	3/122
ZB5AS944	3/122
ZB5AZ901	6/10
ZB5AZ905	6/10
ZBG421E	6/10
ZBG455	6/10
ZBV0143	6/10
ZBV0153	6/10

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Product reference index

Notes

Schneider Electric
Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@stevenengineering.com - www.stevenengineering.com

Schneider Electric USA, Inc.
8001 Knightdale Blvd.
Knightdale, NC 27545

USA Customer Care Center
Tel: 888-778-2733

Schneider Electric Canada
5985 McLaughlin Rd.
Missassauga, Ontario, Canada L5R 1B8

Canada Customer Care Center
Tel: 800-565-6699

www.schneider-electric.com

© 2009–2013 Schneider Electric. All rights reserved. Schneider Electric, Advantys, AS-Interface, Harmony, Magelis, Modbus, Momentum, Phaseo, Premium, Preventa, Transparent Ready, and "Make the most of your energy" are trademarks owned by Schneider Electric Industries SAS or its affiliated companies. All other trademarks are property of their respective owners.

Design: Schneider Electric
Photos: Schneider Electric

MKTED208051EN-US Rev. 02
4/2014

Courtesy of Steven Engineering, Inc. - (800) 258-9200 - sales@steveneng.com - www.stevenengineering.com